WORKS OF PROF. I. P. CHURCH

PUBLISHED BY

JOHN WILEY & SONS.

Mechanics of Engineering.
Comprising Statics and Dynamics of Solids, the Mechanics of the Materials of Construction or Strength and Elasticity of Beams, Columns, Shafts, Arches, etc., and the Principles of Hydraulics and Pneumatics with Applications. For the Use of Technical Schools. 8vo, xxvi + 854 pages, 4 half tones, 656 figures, cloth, $6.00.

Notes and Examples in Mechanics.
With an Appendix on the Graphical Statics of Mechanism. 8vo, 167 pages, 178 figures, cloth, $2.00.

Diagrams of Mean Velocity of Water in Open Channels.
Based on the Formula of Ganguillet and Kutter. 9 × 12 inches, paper, $1.50.

Hydraulic Motors; with related subjects; including Centrifugal Pumps, Pipes, and Open Channels. 8vo, 279 pages, 125 figures, cloth, $2.00.



One of the two **"clinometers"** in use in the Testing Laboratory of the College of Civil Engineering at Cornell University (see p. 241). The main barrel or sleeve of the instrument encircles the horizontal shaft or rod (in testing machine) whose angle of torsion is to be obtained, near one extremity of the same. At each end of the barrel are four brass screws having smooth rounded ends where they bear on the shaft. These are used for centering the barrel on the shaft, but do not grip it. The four steel "gripping screws," at the middle of the barrel, are thumb-screws with flat heads and hardened sharp points. They serve to grip the shaft after the centering is completed. After the shaft has thus been gripped at a certain transverse section, the collar carrying the graduated arc is clamped upon the barrel, the plane of the arc and its vernier arm being that of the points of the gripping screws. By taking a reading of the vernier on the arc at any stage of the test (the vernier-arm being adjusted each time so that the bubble of the spirit level carried by this arm is brought to the center of its scale) and subtracting its initial reading, the angle through which the transverse section has turned from its initial position becomes known. The second clinometer is placed at another transverse section, near the other end of the shaft, and serves to measure its turning movement. The difference of these movements is the angle of torsion. The verniers read to single minutes. (The shaft in above figure is $1\frac{1}{2}$ in. in diameter).

Frontispiece.

MECHANICS OF ENGINEERING

COMPRISING

STATICS AND KINETICS OF SOLIDS; THE MECHANICS OF THE MATERIALS OF CONSTRUCTION, OR STRENGTH AND ELASTICITY OF BEAMS, COLUMNS, SHAFTS, ARCHES, ETC.; AND THE PRINCIPLES OF HYDRAULICS AND PNEUMATICS, WITH APPLICATIONS.

FOR USE IN TECHNICAL SCHOOLS.

BY

IRVING P. CHURCH, C.E.,

PROFESSOR OF APPLIED MECHANICS AND HYDRAULICS, COLLEGE OF CIVIL ENGINEERING, CORNELL UNIVERSITY.

REVISED EDITION, PARTLY REWRITTEN

TOTAL ISSUE, FIFTEEN THOUSAND.

NEW YORK:
JOHN WILEY & SONS.
LONDON: CHAPMAN & HALL, LIMITED.
1908

Copyright, 1890, 1908
BY
IRVING P. CHURCH.



The Scientific Press
Robert Drummond and Company
New York

PREFACE.

In presenting a revised edition of this work for the use of technical schools the writer would call attention to the principal changes that have been made; omissions as well as additions.

The chapter on "Continuous Girders by Graphics" has been omitted in its entirety, while the graphic treatment of the horizontal straight girder, formerly a part of the chapter on "Arch Ribs," has been removed to the appendix, in which will also be found various paragraphs involving special problems in flexure, once located in the body of the book. Former chapters V and VI in Part III, on beams under oblique forces and on columns, respectively, have been merged in one (Chapter VI), the matter having been largely rewritten and more fully illustrated, with introduction of the more modern formulæ for columns and some treatment of the problem of eccentric loading.

Chapter V in Part III of the revised book, on "Flexure of Reinforced Concrete Beams," is entirely new and presents both theory and numerical illustration; as also diagrams aiding in practical design. New matter will also be found in an analytical treatment of "Circular Ribs and Hoops," placed at the end of the chapter on "Arch Ribs." Two other new chapters in Part III, are XII, on the flexure of beams treated by a geometrical method (which, however, does not call for the use of drafting instruments) leading to a very simple and available form of the Theorem of Three Moments; and XIII, which gives the analysis of stresses in thick hollow cylinders and spheres. A few pages on the strength of plates have also been added in Chapter III.

In Part IV additional matter is presented relating to the differential manometer, gas- and oil-engines, the Cippolletti weir, losses of heads in pipes and bends, the hydraulic grade-line, the Venturi meter, current-meters, Pitot's tube, use of Kutter's formula, etc. In Parts I and II numerous additional examples and illustrations are introduced while many pages have been rewritten throughout the book, aside from the new chapters already referred to. Tables of logarithms, trigonometric functions, and hyperbolic sines and cosines, will be found in the appendix.

Grateful acknowledgment is again due to Dr. H. T. Eddy for the use of his methods * in treating arch ribs; to Prof. C. L. Crandall for the chapter on retaining-walls; and to Col. J. T. Fanning for the table of coefficients of friction of water in pipes. The writer would also extend his thanks to Messrs. Buff and Buff of Boston, for the half-tone cut of their current-meter; and to Builders Iron Foundry of Providence, R. I., for the engravings illustrating the Venturi meter.

Cornell University, Ithaca, N. Y.,
June, 1908.

Note.—Additional matter involving many examples and forming an appendix to the present work, but too bulky to be incorporated with it, was issued in a separate volume in 1892 and entitled *"Notes and Examples in Mechanics."* A second edition, revised and enlarged, was published in 1897.

* See pp. 14 and 25 of "*Researches in Graphical Statics*," by Prof. H. T. Eddy, C.E., Ph.D., published by D. Van Nostrand, New York, 1878, reprinted from Van Nostrand's Magazine for 1877; or the German translation of the same, "*Neue Constructionen aus der Graphischen Statik*," published by Teubner u. Cie., Leipsic, 1880.

11196

INTRODUCTORY NOTES.

Preparation.—Prior to the use of this book the student is supposed to have had the usual training given in technical schools in analytical geometry and in the differential and integral calculus; and also a year of college physics.

Gravitation Measure of a Force. Mass and Weight.—Since the gravitation measure of a force is the one almost exclusively used by engineers, a brief résumé of its nature is here given, aside from the paragraph of p. 835, Appendix.

The amount of matter in a certain piece of platinum, kept by the British government, is called by the physicist a pound of *mass*, but the engineer understands by the word "pound" the *force* of gravitation, or weight, exerted by the earth on this piece of metal at London; and if this piece of metal be supported, at London, by a spring balance, the scale of which is so graduated that the pointer now stands at unity, such a balance constitutes a standard instrument with which to measure forces for the purposes of the engineer. According to the indications of such an instrument the same piece of metal, if suspended on the same balance at the equator, at sea-level, would be found to weigh only 0.997 lbs. (force) on account of the diminished intensity of gravitation; the difference, however, being only about three parts in a thousand, or one-third of one per cent. For ordinary engineering problems involving the strength of structures, this difference is of no practical importance.

A unit of force based on this gravitation method is called a *gravitation measure of force*. The *mass* of the piece of platinum, has, of course, suffered no change in the transit from London to the equator, and since the fraction obtained by dividing the weight (obtained from the spring balance) by the acceleration of gravity, g, is constant, regardless of the place where the two quantities are measured, it is convenient (though not essential) for the engineer to give the name "mass" to this fraction when it occurs in the equations of kinetics. For instance, since g (for foot and second) $=32.18$ at London, and 32.09 at the equator (at sea-level), we note that $\frac{1.000}{32.18}=\frac{0.997}{32.09}$ $=0.03108$.

Arithmetic.—In arithmetical operations the student should remember that the degree of refinement attained or employed does not depend on the number of decimal places used, but upon the number of *significant figures*. Thus, each of the quantities 0.0003674 and 510.4 contains four significant figures. For instance, let us suppose that the value of x is to be obtained from the relation $x=a-b$, where $a=0.0000568$ and $b=0.0000421$. Should the student conclude that five decimal places would be accurate enough and thus write 0.00005 for a, and 0.00004 for b, he would obtain $x=0.00001$, containing only one significant figure; whereas the true result is $x=0.0000147$. Hence the former result is seen to be in error to the extent of 47 parts in 147, or 32 parts in 100, i.e., 32 per cent.; which is a very gross and totally unnecessary error. Values obtained from the ordinary 10-inch slide rule usually contain only three significant figures (four if near left of scale).

Logarithms.—The following facts and operations are not usually fresh in the student's mind. The logarithm of a number less than unity is a negative quantity but is usually expressed as the algebraic sum of a positive mantissa (or decimal part) and a negative characteristic which is a whole number; thus, the common logarithm of 0.20 is $\bar{1}.301030\ldots$, that is, log. $0.20=+0.301030-1.000000$ (or, $+9.301030-10$). This should be borne in mind in raising such a number to any power. For example: required the value of $x=\left(\frac{11}{13}\right)^{0.71}$.

Solution.—$\frac{11}{13}=0.8461$ and log. $0.8461=\bar{1}.9274$, i.e., $=0.9274-1.0000$.

Hence $0.71\times\text{log. } 0.8461=0.71(0.9274-1.0000), =0.6584-0.7100,$
$=-0.0516=\bar{1}.9484=\text{log. } 0.8880$; therefore $x=0.8880$.

Note that, according to the definition of a logarithm, the statement $e^n=m$ is equivalent to the statement $n=\log_e m$.

MATHEMATICAL DATA.

Trigonometry. $\cos^2 A + \sin^2 A = 1.$

$\cos^2 A - \sin^2 A = \cos 2A$

$\sin 2A = 2 \sin A \cos A$

$\cos 2A = \cos^2 A - \sin^2 A$

$\cot \frac{1}{2}A = \dfrac{\sin A}{1 - \cos A}$

$2 \sin^2 A = 1 - \cos 2A.$

$2 \cos^2 A = 1 + \cos 2A.$

$\sin A = \dfrac{\tan A}{\sqrt{1+\tan^2 A}} = \dfrac{1}{\operatorname{cosec} A}$

$\cos A = \dfrac{1}{\sqrt{1+\tan^2 A}} = \dfrac{1}{\sec A}$

Solution of Oblique Triangles, etc.



$$\frac{\sin A}{a} = \frac{\sin B}{b} = \frac{\sin C}{c}.$$

$d = a \sin C \qquad d = c \sin A$

$m = c \cos A \qquad n = a \cos C$

$d = m \tan A \qquad d = n \tan C$

Given a, b, B; to find A: $\quad \sin A = \dfrac{a \sin B}{b}$

" a, b, C; " A: $\quad \tan A = \dfrac{a \sin C}{b - a \cos C}$

" a, b, C; " c: $\quad c^2 = a^2 + b^2 - 2ab \cos C$

" a, b, c: " C: $\quad \cos C = \dfrac{a^2 + b^2 - c^2}{2ab}$



Mensuration. Area of a circle $= \pi r^2$; circumference $= 2\pi r$. Area of *sector* $ABCOA = \left(\dfrac{\alpha^\circ}{360^\circ}\right)\pi r^2$; $= \left(\dfrac{\alpha}{2\pi}\right)\pi r^2$; (the latter α in *radians*). Vol. of sphere $= \frac{4}{3}\pi r^3$. Area of the *segment*, $ABCDA$, of a circle,

$=$ (area of sector $ABCOA$) $-$ (area of triangle ACO).



Area of rightsegment of a *parabola* $=$ two-thirds that of circumscribing rectangle, $= \frac{2}{3}(2ha)$. Equation to curve OA is $\dfrac{y^2}{h^2} = \dfrac{x}{a}$. Distance $\overline{OC}$, of center of gravity, is $\bar{x} = \dfrac{3}{5}a$, from vertex O.

Integral Forms.—(Each integral to be taken between limits, or to have a constant added and determined). (See also p. 480.)

$$\int x^n dx = \frac{x^{n+1}}{n+1}; \qquad \int \frac{dx}{x} = \log_e x; \qquad \int e^x dx = e^x;$$

$$\int \cos x\, dx = \sin x; \qquad \int \sin x\, dx = -\cos x; \qquad \int \frac{dx}{\cos^2 x} = \tan x;$$

$$\int \frac{dx}{\sqrt{1-x^2}} = \sin^{-1} x; \qquad \int \frac{dx}{1+x^2} = \tan^{-1} x; \qquad \int \frac{dx}{\sqrt{2x-x^2}} = \text{vers}\sin^{-1} x;$$

$$\int \frac{dx}{\sqrt{x^2 \pm a^2}} = \log_e(x + \sqrt{x^2 \pm a^2}); \qquad \int \frac{dx}{\sqrt{a+bx-cx^2}} = \frac{1}{\sqrt{c}} \sin^{-1}\left(\frac{2cx-b}{\sqrt{b^2+4ac}}\right);$$

$$\int \frac{dx}{a-bx^2} = \frac{1}{2\sqrt{ab}} \log_e \frac{\sqrt{ab}+bx}{\sqrt{ab}-bx}; \qquad \int \frac{x\,dx}{a-bx^2} = -\frac{1}{2b} \log_e (a-bx^2).$$

Numerical Constants.—The acceleration of gravity, g, (for the English foot and second) is 32.16 for the latitude of Philadelphia at sea-level, and for any latitude β, and elevation h above sea-level, is

$$32.1723 - 0.0833 \cos 2\beta - 0.000003h.$$

For ordinary problems in mechanics, however, in the northern United States g may be taken as 32.2, for which value we have

$$\sqrt{2g} = 8.025; \quad \frac{1}{g} = 0.03105; \quad \text{and} \quad \frac{1}{2g} = 0.01553.$$

The ratio $\pi = 3.141592$, or approx. $3\frac{1}{7}$, i.e., $\frac{22}{7}$;

$$\frac{1}{\pi} = 0.31831; \quad \pi^2 = 9.86960; \quad \frac{1}{\pi^2} = 0.10132; \quad \sqrt{\pi} = 1.77245.$$

$1° = 0.01745$ radians. One radian $= 57° 17' 44.8''$.

If n denote any number, then

$\text{Log}_{10}(n) = 0.43429 \times \log_e(n)$; and $\log_e(n) = 2.30258 \times \log_{10}(n)$.

Base of nat. logs. $= e$, $= 2.71828$; base of Briggs system $= 10$.

GREEK ALPHABET.

Letters.	Names.	Letters.	Names.
$A\ \alpha$	Alpha	$N\ \nu$	Nu
$B\ \beta$	Bēta	$\Xi\ \xi$	Xi
$\Gamma\ \gamma$	Gamma	$O\ o$	Omicron
$\Delta\ \delta$	Delta	$\Pi\ \pi$	Pi
$E\ \epsilon$	Epsilon	$P\ \rho$	Rho
$Z\ \zeta$	Zēta	$\Sigma\ \sigma\ \varsigma$	Sigma
$H\ \eta$	Eta	$T\ \tau$	Tau
$\Theta\ \vartheta\ \theta$	Thēta	$\Upsilon\ \upsilon$	Upsilon
$I\ \iota$	Iōta	$\Phi\ \phi$	Phi
$K\ \kappa$	Kappa	$X\ \chi$	Chi
$\Lambda\ \lambda$	Lambda	$\Psi\ \psi$	Psi
$M\ \mu$	Mu	$\Omega\ \omega$	Omega

TABLE OF CONTENTS.

[*MECHANICS OF SOLIDS.*]

PRELIMINARY CHAPTER.

PAGE

§§ 1–15*a*. Definitions. Kinds of Quantity. Homogeneous Equations. Parallelogram of Forces..... 1

PART I. STATICS.

CHAPTER I. STATICS OF A MATERIAL POINT.

§§ 16–19. Composition and Equilibrium of Concurrent Forces.... 8

CHAPTER II. PARALLEL FORCES AND THE CENTRE OF GRAVITY.

§§ 20–22. Parallel Forces..... 13
§§ 23–27*b*. Centre of Gravity. Problems. Centrobaric Method... 18

CHAPTER III. STATICS OF A RIGID BODY.

§§ 28–34. Couples..... 27
§§ 35–39. Composition and Equilibrium of Non-concurrent Forces. 31

CHAPTER IV. STATICS OF FLEXIBLE CORDS.

§§ 40–48. Postulates. Suspended Weights. Parabolic Cord. Catenary..... 42

PART II. KINETICS.

CHAPTER I. RECTILINEAR MOTION OF A MATERIAL POINT.

§§ 49–55. Uniform Motion. Falling Bodies. Newton's Laws. Mass..... 49
§§ 56–60. Uniformly Accelerated Motion. Graphic Representations. Variably Accelerated Motions. Impact... 54

CHAPTER II. VIRTUAL VELOCITIES.

§§ 61–69. Definitions and Propositions. Connecting-rod. Problems..... 67

CHAPTER III. CURVILINEAR MOTION OF A MATERIAL POINT.

		PAGE
§§ 70–74.	Composition of Motions, of Velocities, etc. General Equations	72
§§ 75–84	Normal Acceleration. Centripetal and Centrifugal Forces. Simple Pendulums. Projectiles. Relative Motion	77

CHAPTER IV. MOMENT OF INERTIA.

§§ 85–94.	Plane Figures. Rigid Bodies. Reduction Formulæ. The Rectangle, Triangle, etc. Compound Plane Figures. Polar Moment of Inertia	91
§§ 95–104.	Rod. Thin Plates. Geometric Solids	98
§§ 105–107.	Numerical Substitution. Ellipsoid of Inertia	103

CHAPTER V. KINETICS OF A RIGID BODY.

§§ 108–115.	Translation. Rotation about a Fixed Axis. Centre of Percussion	105
§§ 117–121.	Compound Pendulum. The Fly-wheel	118
§§ 122–123.	Uniform Rotation. "Centrifugal Action." Free Axes.	125
§§ 124-126.	Rolling Motions. Parallel Rod of Locomotive	130

CHAPTER VI. WORK, ENERGY, AND POWER.

§§ 127–134.	Work. Power. Horse-power. Kinetic Energy	133
§§ 135–138.	Steam-hammer. Pile-driving. Inelastic Impact	138
§§ 139–141.	Rotary Motion. Equivalent Systems of Forces. Any Motion of a Rigid Body	143
§§ 142–146.	Work and Kinetic Energy in a Moving Machine of Rigid Parts	147
§§ 147–155.	Power of Motors. Potential Energy. Heat, etc. Dynamometers. Boat-rowing. Examples	153

CHAPTER VII. FRICTION.

§§ 156–164.	Sliding Friction. Its Laws. Bent Lever	164
§§ 165–171.	Axle-friction. Friction Wheels. Pivots. Belting. Transmission of Power by Belting	175
§§ 172–177.	Rolling Friction. Brakes. Friction of Car Journals; and of Well-lubricated Journals. Rigidity of Cordage. Examples	186

PART III. STRENGTH OF MATERIALS.

(OR MECHANICS OF MATERIALS.)

CHAPTER I. ELEMENTARY STRESSES AND STRAINS.

§§ 178–182. Stress and Strain; of Two Kinds. Oblique Section of Rod in Tension 195

§§ 182*a*–190. Hooke's Law. Elasticity. Safe Limit. Elastic Limit. Rupture. Modulus of Elasticity. Isotropes. Resilience. Ellipse of Stress. Classification of Cases 201

TENSION.

§§ 191–195. Hooke's Law by Experiment. Strain Diagrams. Lateral Contraction. Modulus of Tenacity 207

§§ 196–199. Resilience of Stretched Prism. Load Applied Suddenly. Prism Under Its Own Weight. Solid of Uniform Strength. Temperature Stresses .. 213

COMPRESSION OF SHORT BLOCKS.

§§ 200–202. Short and Long Columns. Remarks on Crushing .. 218

EXAMPLES IN TENSION AND COMPRESSION.

§§ 203–206. Tables. Examples. Factor of Safety. Practical Notes 220

SHEARING.

§§ 207–213. Rivets. Shearing Distortion. Table. Punching. Examples 225

CHAPTER II. TORSION.

§§ 214–220. Angle and Moment of Torsion. Torsional Strength, Stiffness, and Resilience. Non-Circular Shafts 233

§§ 221–223. Transmission of Power. Autographic Testing Machine. Torsion Clinometers. Examples 238

CHAPTER III. FLEXURE OF HOMOGENEOUS PRISMS UNDER PERPENDICULAR FORCES IN ONE PLANE.

§§ 224–232*a*. The Common Theory. Elastic Forces. Neutral Axis. The "Shear" and "Moment." Flexural Strength and Stiffness. Radius of Curvature. Resilience 244

ELASTIC CURVES.

§§ 233–238. Single Central Load; at Rest, and Applied Suddenly. Eccentric Load. Uniform Load. Cantilever .. 252

SAFE LOADS.

§§ 239–246. Maximum Moment. Shear = x-Derivative of the Moment. Simple Beams With Various Loads. Comparative Strength and Stiffness of Rectangular Beams..... 262
§§ 247–252. Moments of Inertia. Rolled Steel I-Beams, etc. Cantilevers. Tables. Numerical Examples ... 273

SHEARING STRESSES IN FLEXURE.

§§ 253–257. Shearing Stress Parallel to Neutral Surface; and in Cross Section. Web of I-Beam. Riveting of Built Beams 284

SPECIAL PROBLEMS IN FLEXURE.

§§ 258–265. Designing Sections of Built Beams. Moving Loads. Special Cases of Quiescent Loads. Hydrostatic Load..... 295
§§ 266–270. Strength of Flat Plates. Weight Falling on Beam. Crank Shaft. Other Shafts. Web of I-Beam . 310

CHAPTER IV. FLEXURE; CONTINUED.

CONTINUOUS GIRDERS.

§§ 271–276. Analytical Treatment of Symmetrical Cases of Beams on Three Supports; also, Built in; (see p. 499.). 320

THE DANGEROUS SECTION IN NON-PRISMATIC BEAMS.

§§ 277–279. Double Truncated Wedge, Pyramid, and Cone 332

NON-PRISMATIC BEAMS OF UNIFORM STRENGTH.

§§ 280–289. Parabolic and Wedge-Shaped Beams. Elliptical Beams. (See Appendix, p. 841, for Cantilevers). 335

CHAPTER V. FLEXURE OF REINFORCED CONCRETE BEAMS.

§§ 284–287. Concrete, and "Concrete-Steel" Beams. Beams of Rectangular Section. Horizontal Shearing Stresses in Latter. Examples 339
§§ 288–294. Concrete-Steel Beams of T-Form Section. Deflection of Concrete-Steel Beams. Practical Formulæ and Diagrams 346

CHAPTER VI. FLEXURE. COLUMNS AND HOOKS.- OBLIQUE LOADS.

§§ 294–300. Oblique Cantilever. Moment, Thrust and Shear. Experimental Proof. Common Theory of Crane-Hooks. Winkler-Bach Theory 352

§§ 301–314. Long Columns. End-Conditions. Euler's and Rankine's Formulæ. Examples. Radii of Gyration. Built Columns. Other Formulæ: Merriman-Ritter; "Straight-Line;" Parabolic. Wooden Posts. Eccentric Loading of Columns. Eccentric Loading Combined with Uniform Transverse Pressures. Buckling of Web of Plate Girder 360

CHAPTER VII. LINEAR ARCHES (OF BLOCKWORK.)

§§ 315–323. Inverted Catenary. Parabolic Arch. Circular Arch. Transformed Catenary as Arch..... 386

CHAPTER VIII. ELEMENTS OF GRAPHICAL STATICS

§§ 324–326. Force Polygons. Concurrent and Non-Concurrent Forces in a Plane. Force Diagrams. Equilibrium Polygons..... 397

§§ 327–332. Constructions for Resultant, Pier-Reactions, and Stresses in Roof Truss. Bow's Notation. The Special Equilibrium Polygon..... 402

CHAPTER IX. GRAPHICAL STATICS OF VERTICAL FORCES.

§§ 333–336. Jointed Rods. Centre of Gravity..... 412

§§ 337–343. Useful Relations Between Force Diagrams and Their Equilibrium Polygons..... 415

CHAPTER X. RIGHT ARCHES OF MASONRY.

§§ 344–352. Definitions. Mortar and Friction. Pressure in Joints. Conditions of Safe Equilibrium. True Linear Arch..... 421

§§ 353–357. Arrangement of Data for Graphic Treatment..... 428

§§ 358–362. Graphical Treatment of Arch. Symmetrical and Unsymmetrical Cases..... 431

CHAPTER XI. ARCH-RIBS.

§§ 364–374. Mode of Support. Special Equilibrium Polygon and its Force Diagram. Change in Angle Between Rib Tangents. Displacement of Any Point on Rib..... 438

§§ 374*a*–378*a*. Graphical Arithmetic. Summation of Products. Moment of Inertia by Graphics. Classification of Arch-Ribs..... 450

§§ 379–388. Prof. Eddy's Graphical Method for Arch-Ribs of Hinged Ends; and of Fixed Ends. Stress Diagrams. Temperature Stresses. Braced Arches 461
§§ 389–391. Circular Ribs and Hoops 479

CHAPTER XII. FLEXURE OF BEAMS, SIMPLE AND CONTINUOUS, GEOMETRICAL TREATMENT.

§§ 392–398. Geometrical Treatment Defined. Angle between End-tangents. Relative Displacement of Any Point of Elastic Curve. Deflections and Slopes by Calculus. Examples. Properties of Moment Diagrams. Deflections and Slopes by Geometric Method. Examples 485
§§ 399–405. The "Normal Moment Diagram." The Theorem of Three Moments. Values of Products of Moment-Areas by "Gravity x's." Continuous Girders Treated by the Theorem of Three Moments. Continuous Beam with "Built-in" Ends. Deflections Found by Theorem of Three Moments 494

CHAPTER XIII. THICK HOLLOW CYLINDERS AND SPHERES.

§§ 405a–405g. General Relations between Stress and Strain. The "Elongation Theory" of Safety. Thick Hollow Cylinder under Internal Fluid Pressure; also under External Fluid Pressure. Equalization of Hoop Stress in Compound Cylinder. Equation of Continuity for Cylinder and Sphere. Thick Hollow Sphere under Internal Fluid Pressure 507

[*CONTENTS OF "MECHANICS OF FLUIDS."*]

PART IV.—HYDRAULICS.

CHAPTER I.—DEFINITIONS. FLUID PRESSURE. HYDROSTATICS BEGUN.

PAGE

§§ 406–417. Perfect fluids. Liquids and Gases. Principle of "Equal Transmission of Pressure." Non-planar Pistons... 515

§§ 418–427. Hydraulic Press. Free Surface of Liquid. Barometers and Manometers. The Differential Manometer. Safety-valves. Strength of Thin Hollow Cylinders against Bursting and Collapse 526

CHAPTER II.—HYDROSTATICS CONTINUED. PRESSURE OF LIQUIDS IN TANKS AND RESERVOIRS.

§§ 428–434. Liquid in Motion, but in "Relative Equilibrium." Pressure on Bottom and Sides of Vessels. Centre of Pressure of Rectangles, Triangles, etc..... 540

§§ 435–444. Stability of Rectangular and Trapezoidal Walls against Water Pressure. High Masonry Dams. Proposed Quaker Bridge Dam. Earthwork Dam. Water Pressure on both Sides of a Gate..... 554

CHAPTER III.—EARTH PRESSURE AND RETAINING WALLS.

§§ 445–455. Angle of Repose. Wedge of Maximum Thrust. Geometrical Constructions. Resistance of Retaining Walls. Results of Experience..... 572

CHAPTER IV.—HYDROSTATICS CONTINUED. IMMERSION AND FLOTATION.

§§ 456–460. Buoyant Effort. Examples of Immersion. Specific Gravity. Equilibrium of Flotation. Hydrometer.. 586

§§ 461–465. Depth of Flotation. Draught and Angular Stability of Ships. The Metacentre..... 592

PAGE

CHAPTER V.—HYDROSTATICS CONTINUED. GASEOUS FLUIDS.

§§ 466–478. Thermometers. Absolute Temperature. Gases and Vapors. Critical Temperature. Law of Charles. Closed Air-manometer. Mariotte's Law. Mixture of Gases. Barometric Levelling. Adiabatic Change.. 604

§§ 479–489. Work Done in Steam-engine Cylinders. Expanding Steam. Graphic Representation of Change of State of Gas. Compressed-air Engine. Air-compressor. Hot-air Engines. Gas-engines. Heat-efficiency. Duty of Pumping-engines. Buoyant Effort of the Atmosphere..... 624

CHAPTER VI.—HYDROKINETICS BEGUN. STEADY FLOW OF LIQUIDS THROUGH PIPES AND ORIFICES.

§§ 489*a*–495. Phenomena of a "Steady Flow." Bernoulli's Theorem for Steady Flow without Friction, and Applications. Orifice in "Thin Plate"..... 646

§§ 496–500. Rounded Orifice. Various Problems involving Flow through Orifices. Jet from Force-pump. Velocity and Density; Relation. Efflux under Water. Efflux from Vessel in Motion. Barker's Mill..... 663

§§ 501–508. Efflux from Rectangular and Triangular Orifices. Poncelet's Experiments. Perfect and Complete Contraction, etc. Overfall Weirs. Experiments of Francis, Fteley and Stearns, and Bazin. The Cippolletti Weir. Short Pipes or Tubes..... 672

§§ 509–513. Conical Tubes. Venturi's Tube Fluid Friction. Froude's Experiments. Bernoulli's Theorem with Friction. Hydraulic Radius. Loss of Head. Problems involving Friction Heads in Pipes. Accumulator 693

§§ 513*a*–518. Loss of Head in Orifices and Short Pipes. Coefficient of Friction of Water in Pipes. Fanning's Table. Petroleum Pumping. Flow through Long Pipes.. 703

§§ 519–526. Chézy's Formula. The "Hydraulic Grade-Line." Pressure-energy. Losses of Head due to Sudden Enlargement of Section; Borda's Formula. Diaphragm in Pipe. Venturi Water-meter..... 714

§§ 527–536. Sudden Diminution of Section. Losses of Head due to Elbows, Bends, Valve-gates, and Throttle-valves. Examples, Capt. Bellinger's Experiments on Elbows. Siphons. Branching Pipes. Time of Emptying Vessels of Various Forms; Prisms, Wedges Pyramids, Cones, Paraboloids, Spheres, Obelisks, and Volumes of Irregular Form using Simpson's Rule.. 727

CHAPTER VII.—HYDROKINETICS, CONTINUED; STEADY FLOW OF WATER IN OPEN CHANNELS.

PAGE

§§ 538–542*a*. Nomenclature. Velocity Measurements and Instruments for the same. Ritchie-Haskell Direction Current-meter. Change of Velocity with Depth. Pitot's Tube and W. M. White's Experiments. Current-meters. Gauging Streams. Chézy's Formula for Uniform Motion in Open Channel. Experiments 749

§§ 543–547. Kutter's Formula. Sections of Least Resistance. Trapezoidal Section of Given Side Slope and Minimum Friction. Variable Motion in Open Channel. Bends. Formula introducing Depths at End Sections. Backwater 759

CHAPTER VIII.—KINETICS OF GASEOUS FLUIDS.

§§ 548–556. Theorem for Steady Flow of Gases without Friction. Flow through Orifices by Water-formula; with Isothermal Expansion; with Adiabatic Expansion. Maximum Flow of Weight. Experimental Coefficients for Orifices and Short Pipes. Flow considering Velocity of Approach 773

§§ 557–561*a*. Transmission of Compressed Air through Long Pipes. Experiments in St. Gothard Tunnel. Pipes of Variable Diameter. The Piping of Natural Gas 786

CHAPTER IX.—IMPULSE AND RESISTANCE OF FLUIDS.

§§ 562–569. Reaction of a Jet of Liquid. Impulse of Jet on Curved Vanes, Fixed and in Motion. Pitot's Tube. The California "Hurdy-gurdy." Impulse on Plates. Plates Moving in a Fluid. Plates in Currents of Fluid 798

§§ 570–575. Wind-pressure. Smithsonian Scale. Mechanics of the Sail-boat. Resistance of Still Water to Immersed Solids in Motion. Spinning Ball, Deviation from Vertical Plane. Robinson's Cup anemometer. Resistance of Ships. Transporting Power of a Current. Fire-streams, Hose-friction, etc 818

APPENDIX. Miscellaneous Addenda and Tables 835–854

MECHANICS OF ENGINEERING.

PRELIMINARY CHAPTER.

1. **Mechanics** treats of the mutual actions and relative motions of material bodies, solid, liquid, and gaseous; and by *Mechanics of Engineering* is meant a presentment of those principles of pure mechanics, and their applications, which are of special service in engineering problems.

2. **Kinds of Quantity.**—Mechanics involves the following fundamental kinds of quantity: **Space,** of one, two, or three dimensions, i.e., length, surface, or volume, respectively; **time,** which needs no definition here; **force** and **mass,** as defined below; and **abstract numbers,** whose values are independent of arbitrary units, as, for example, a ratio.

3. **Force.**—A force is one of a pair of equal, opposite, and simultaneous actions between two bodies, by which the state* of their motions is altered or a change of form in the bodies themselves is effected. Pressure, attraction, repulsion, and traction are instances in point. Muscular sensation conveys the idea of force, while a spring-balance gives an absolute measure of it, a beam-balance only a relative measure. In accordance with Newton's third law of motion, that action and reaction are equal, opposite, and simultaneous, forces always occur in pairs; thus, if a pressure of 40 lbs. exists between bodies A and B, if A is considered by itself (i.e., "free"), apart from all other bodies whose actions upon it are called forces, among these forces will be one of 40 lbs. directed from B toward A. Similarly, if B is under consideration, a force

* The state of motion of a small body under the action of no force, or of balanced forces, is either absolute rest, or uniform motion in a right line. If the motion is different from this, the fact is due to the action of an unbalanced force (§ 54).

of 40 lbs. directed from A toward B takes its place among the forces acting on B. This is the interpretation of Newton's third law.

[NOTE.—In some common phrases, such as "The tremendous force" of a heavy body in rapid motion, the word force is not used in a technical sense, but signifies energy (as explained in Chap. VI.). The mere fact that a body is in motion, whatever its mass and velocity, does not imply that it is under the action of any force, necessarily. For instance, at any point in the path of a cannon ball through the air, the only forces acting on it are the resistance of the air and the attraction of the earth, the latter having a vertical and downward direction.]

4. **Mass** is the quantity of matter in a body. The masses of several bodies being proportional to their weights at the same locality on the earth's surface, in physics the weight is taken as the mass, but in practical engineering another mode is used for measuring it (as explained in a subsequent chapter), viz.: the mass of a body is equal to its weight divided by the acceleration of gravity in the locality where the weight is taken, or, symbolically, $M = G \div g$. This quotient is a constant quantity, as it should be, since the mass of a body is invariable wherever the body be carried.

5. **Derived Quantities.**—All kinds of quantity besides the fundamental ones just mentioned are compounds of the latter, formed by multiplication or division, such as velocity, acceleration, momentum, work, energy, moment, power, and force-distribution. Some of these are merely names given for convenience to certain combinations of factors which come together not in dealing with first principles, but as a result of common algebraic transformations.

6. **Homogeneous Equations** are those of such a form that they are true for any arbitrary system of units, and in which all terms combined by algebraic addition are of the same kind. Thus, the equation $s = \frac{gt^2}{2}$ (in which g = the acceleration of gravity and t the time of vertical fall of a body in vacuo, from rest) will give the distance fallen through, s, whatever units be adopted for measuring time and distance. But if for

g we write the numerical value 32.2, which it assumes when time is measured in seconds and distance in feet, the equation $s = 16.1t^2$ is true for those units alone, and the equation is not of homogeneous form. Algebraic combination of homogeneous equations should always produce homogeneous equations; if not, some error has been made in the algebraic work. If any equation derived or proposed for practical use is not homogeneous, an explicit statement should be made in the context as to the proper units to be employed.

7. **Heaviness.**—By heaviness of a substance is meant the weight of a cubic unit of the substance. E.g. the heaviness of fresh water is 62.5, in case the unit of force is the pound, and the foot the unit of space; i.e., a cubic foot of fresh water weighs 62.5 lbs.* In case the substance is not uniform in composition, the heaviness varies from point to point. If the weight of a homogeneous body be denoted by G, its volume by V, and the heaviness of its substance by γ, then $G = V\gamma$.

WEIGHT IN POUNDS OF A CUBIC FOOT (i.e., THE HEAVINESS) OF VARIOUS MATERIALS.

Anthracite, solid	100	Masonry, dry rubble	138
" broken	57	" dressed granite or limestone	165
Brick, common hard	125	Mortar	100
" soft	100	Petroleum	55
Brick-work, common	112	Snow	7
Concrete	125	" wet	15 to 50
Earth, loose	72	Steel	490
" as mud	102	Timber	25 to 60
Granite	164 to 172	Water, fresh	62.5
Ice	58	" sea	64.0
Iron, cast	450		
" wrought	480		

8. **Specific Gravity** is the ratio of the heaviness of a material to that of water, and is therefore an abstract number.

9. **A Material Point** is a solid body, or small particle, whose dimensions are practically nothing, compared with its range of motion.

* Or, we may write 62.5 lbs./cub. ft.; or 62.5 lbs./ft.^{3}

10. A Rigid Body is a solid, whose distortion or change of form under any system of forces to be brought upon it in practice is, for certain purposes, insensible.

11. Equilibrium.—When a system of forces applied to a body produces the same effect as if no force acted, so far as the *state of motion* of the body is concerned, they are said to be balanced, or to be in equilibrium. [If no force acts on a material point it remains at rest if already at rest; but if already in motion it continues in motion, and *uniformly* (equal spaces in equal times), in a right line in direction of its original motion. See § 54.]

12. Division of the Subject.—*Statics* will treat of bodies at rest, i.e., of balanced forces or equilibrium; *kinetics*, of bodies in motion; *strength of materials* will treat of the effect of forces in distorting bodies; *hydraulics*, of the mechanics of liquids and gases (thus including *pneumatics*).

13. Parallelogram of Forces.—Duchayla's Proof. To fully determine a force we must have given its amount, its direction, and its point of application in the body. It is generally denoted in diagrams by an arrow. It is a matter of experience that besides the point of application already spoken of any other may be chosen in the line of action of the force. This is called the transmissibility of force; i.e., so far as the *state of motion* of the body is concerned, a force may be applied anywhere in its line of action.

The **Resultant** of two forces (called its components) applied at a point of a body is a single force applied at the same point, which will replace them. To prove that this resultant is given in amount and position by the diagonal of the parallelogram formed on the two given forces (conceived as laid off to some scale, so many pounds to the inch, say), Duchayla's method requires four postulates, viz.: (1) the resultant of two forces must lie in the same plane with them; (2) the resultant of two equal forces must bisect the angle between them; (3) if one of the two forces be increased, the angle between the other force and the resultant will be greater than before; and (4) the transmissibility of force,' already mentioned. Granting these, we proceed as follows (Fig. 1): Given the two forces P and Q =

$P' + P''$ (P' and P'' being each equal to P, so that $Q = 2P$), applied at O. Transmit P'' to A. Draw the parallelograms OB and AD; OD will also be a parallelogram. By postulate (2), since OB is a rhombus, P and P' at O may be replaced by a single force R' acting through B. Transmit R' to B and replace it by P and P'. Transmit P from B to A, P' from B to D. Similarly P and P'', at A, may be replaced by a single force R'' passing through D; transmit it there and resolve it into P and P''. P' is already at D. Hence P and $P' + P''$, acting at D, are equivalent to P and $P' + P''$ acting at O, in their respective directions. Therefore the resultant of P and $P' + P''$ must lie in the line OD, the diagonal of the parallelogram formed on P and $Q = 2P$ at O. Similarly



Fig. 1.



Fig. 2.

this may be proved (that the diagonal gives the *direction* of the resultant) for any two forces P and mP; and for any two forces nP and mP, m and n being any two whole numbers, i.e., for any two commensurable forces. When the forces are incommensurable (Fig. 2), P and Q being the given forces, we may use a *reductio ad absurdum*, thus: Form the parallelogram OD on P and Q applied at O. Suppose for an instant that R the resultant of P and Q does not follow the diagonal OD, but some other direction, as OD'. Note the intersection H, and draw HC parallel to DB. Divide P into equal parts, each less than HD; then in laying off parts equal to these from O along OB, a point of division will come at some point F between C and B. Complete the parallelogram $OFEG$. The force $Q'' = OF$ is commensurable with P, and hence their

resultant acts along OE. Now Q is greater than Q'', while R makes a less angle with P than OE, which is contrary to postulate (3); therefore R cannot lie outside of the line OD. Q. E. D.

It still remains to prove that the resultant is represented in *amount*, as well as position, by the diagonal. OD (Fig. 3) is the direction of R the resultant of P and Q; required its amount. If R' be a force equal and opposite to R it will balance P and Q; i.e, the resultant of R' and P must lie in the line QO prolonged (besides being equal to Q). We can therefore determine R' by drawing BA parallel to DO to intersect QO prolonged in A; and then complete the parallelogram BF on BO and BA as sides. Since $OFAB$ and $AODB$ are parallelograms, $\overline{OF}$ must $=\overline{BA}$ and $\overline{BA}$ must $=\overline{OD}$. Hence OF and OD are equal and lie on the same right line. Evidently if R' were any shorter or any longer than OF the resultant of it and $\overline{OB}(=P)$ would not take the direction QOA. Hence R' must $=\overline{OF}$, i.e., $=\overline{OD}$; and hence $R=\overline{OD}$ in *amount*. Q. E. D.



FIG. 3.

Corollary.—The resultant of three forces applied at the same point is the diagonal of the parallelopiped formed on the three forces.

14. Concurrent forces are those whose lines of action intersect in a common point, while **non-concurrent** forces are those which do not so intersect; results obtained for a system of concurrent forces are really derivable, as particular cases, from those pertaining to a system of non-concurrent forces.

15. Resultant.—A single force, the action of which, as regards the *state of motion* of the body acted on, is equivalent to that of a number of forces forming a system, is said to be the **Resultant** of that system, and may replace the system; and conversely a force which is equal and opposite to the resultant of a system will balance that system, or, in other words, when it is combined with that system there will result a new system in equilibrium; this (ideal) force is called the **Anti-resultant.**

In general, as will be seen, a given system of forces can al-

ways be replaced by two single forces, but these two can be combined into a single resultant only in particular cases.

15a. Equivalent Systems are those which may be replaced by the same set of two single forces—or, in other words, those which have the same effect, as to state of motion, upon the given body.

15b. Formulæ.—If in Fig. 3 the forces P and Q and the angle $\alpha = POQ$ are given, we have, for the resultant,

$$R = \overline{OD} = \sqrt{P^2 + Q^2 + 2PQ\cos\alpha}.$$

(If α is $> 90°$ its cosine is negative.) In general, given any three parts of either plane triangle ODQ, or ODB, the other three may be obtained by ordinary trigonometry. Evidently if $\alpha = 0$, $R = P + Q$; if $\alpha = 180°$, $R = P - Q$; and if $\alpha = 90°$, $R = \sqrt{P^2 + Q^2}$.

15c. Varieties of Forces.—Great care should be used in deciding what may properly be called forces. The latter may be divided into actions *by contact*, and actions *at a distance*. If pressure exists between two bodies and they are perfectly smooth at the surface of contact, the *pressure* (or *thrust*, or *compressive action*), of one against the other constitutes a force, whose direction is normal to the tangent plane at any point of contact (a matter of experience); while if those surfaces are not smooth there may also exist mutual tangential actions or *friction*. (If the bodies really form a continuous substance at the surface considered, these tangential actions are called *shearing forces*.) Again, when a rod or wire is subjected to tension, any portion of it is said to exert a *pull* or *tensile force* upon the remainder; the ability to do this depends on the property of cohesion. The foregoing are examples of actions by contact.

Actions at a distance are exemplified in the mysterious *attractions*, or *repulsions*, observable in the phenomena of gravitation electricity, and magnetism, where the bodies concerned are not necessarily in contact. By the term *weight* we shall always mean the *force* of the earth's attraction on the body in question, and not the amount of matter in it.

15d. Example 1.—If $\overline{OD}, = R$, is given, $= 40$ lbs., while the angle BOD is 110° and $QOD = 40°$ (also $= ODB$), find the components P and Q.

Solution.—From the triangle BOD, $\overline{OB} : \overline{OD} :: \sin 40° : \sin 30°$; whence

$$P, \text{ or } \overline{OB}, = (40 \times 0.6428) \div 0.5000 = 51.42 \text{ lbs.}$$

Similarly, from triangle BOD, we have $\overline{BD} : \overline{OD} :: \sin 110° : \sin 30°$,

$$\therefore\ Q, \text{ or } \overline{BD}, = (40 \times 0.9397) \div 0.05000 = 75.17 \text{ lbs.}$$

Example 2.—Given $P = 20$ lbs., $Q = 30$ lbs., and angle $\alpha (= POQ), = 115°$, find the resultant R in amount and direction. *As to amount*

$$R = \sqrt{(20)^2 + (30)\ + 2 \times 20 \times 30 \times (-0.4226)} = \sqrt{792.88} = 28.16 \text{ lbs.}$$

As to direction, let β denote the angle $ODB, = QOD$; we then have, from triangle OBD, $20 : 28.16 :: \sin\beta : \sin 65°$; whence, solving,

$$\sin\beta = (20 \times 0.9063) \div 28.16 = 0.6437;\ \textit{i.e.},\ \text{angle } \beta = 40°\ 4'.$$

PART I.—STATICS.

CHAPTER I.

STATICS OF A MATERIAL POINT.

16. Composition of Concurrent Forces.—A system of forces acting on a material point is necessarily composed of concurrent forces.

Case I.—All the forces in **One Plane.** Let O be the material point, the common point of application of all the forces; P_1, P_2, etc., the given forces, making angles α_1, α_2, etc., with the axis X. By the parallelogram of forces P_1 may be resolved into and replaced by its components, $P_1 \cos \alpha_1$ acting along X, and $P_1 \sin \alpha_1$ along Y. Similarly all the remaining forces may be replaced by their X and Y components. We have now a new system, the equivalent of that first given, consisting of a set of X forces, having the same line of application (axis X), and a set of Y forces, all acting in the line Y. The resultant of the X forces being their algebraic sum (denoted by ΣX) (since they have the same line of application) we have



Fig. 4.

$$\Sigma X = P_1 \cos \alpha_1 + P_2 \cos \alpha_2 + \text{etc.} = \Sigma(P \cos \alpha),$$

and similarly

$$\Sigma Y = P_1 \sin \alpha_1 + P_2 \sin \alpha_2 + \text{etc.} = \Sigma(P \sin \alpha).$$

These two forces, ΣX and ΣY, may be combined by the parallelogram of forces, giving $R = \sqrt{(\Sigma X)^2 + (\Sigma Y)^2}$ as the single resultant of the whole system, and its direction is determined by the angle α; thus, $\tan \alpha = \frac{\Sigma Y}{\Sigma X}$; see Fig. 5. For equilibrium to exist, R must $= 0$, which requires, *separately*,

$\Sigma X = 0$, and $\Sigma Y = 0$ (for the two squares $(\Sigma X)^2$ and $(\Sigma Y)^2$ can neither of them be negative quantities).

Case II.—The forces having any directions in space, but all applied at O, the material point. Let P_1, P_2, etc., be the given forces, P_1 making the angles α_1, β_1, and γ_1, respectively, with three arbitrary axes, X, Y, and Z (Fig. 6), at right angles to each other and intersecting at O, the origin. Similarly let α_2, β_2, γ_2, be the angles made by P_2 with these axes, and so on for all the forces. By the parallelopiped of forces, P_1 may be replaced by its components.

$X_1 = P_1 \cos \alpha_1$, $Y_1 = P_1 \cos \beta_1$, and $Z_1 = P_1 \cos \gamma_1$; and



Fig. 5.



Fig. 6.



Fig. 7.

similarly for all the forces, so that the entire system is now replaced by the three forces,

$$\Sigma X = P_1 \cos \alpha_1 + P_2 \cos \alpha_2 + \text{etc};$$
$$\Sigma Y = P_1 \cos \beta_1 + P_2 \cos \beta_2 + \text{etc};$$
$$\Sigma Z = P_1 \cos \gamma_1 + P_2 \cos \gamma_2 + \text{etc};$$

and finally by the single resultant

$$R = \sqrt{(\Sigma X)^2 + (\Sigma Y)^2 + (\Sigma Z)^2}.$$

Therefore, for equilibrium we must have **separately,**

$$\Sigma X = 0, \ \Sigma Y = 0, \text{ and } \Sigma Z = 0.$$

R's position may be determined by its direction cosines, viz.,

$$\cos \alpha = \frac{\Sigma X}{R}; \ \cos \beta = \frac{\Sigma Y}{R}; \ \cos \gamma = \frac{\Sigma Z}{R}.$$

17. Conditions of Equilibrium.—Evidently, in dealing with a system of concurrent forces, it would be a simple matter to

replace any two of the forces by their resultant (diagonal formed on them), then to combine this resultant with a third force, and so on until all the forces had been combined, the last resultant being the resultant of the whole system. The foregoing treatment, however, is useful in showing that for equilibrium of concurrent forces in a plane only two conditions are necessary, viz., $\Sigma X = 0$ and $\Sigma Y = 0$; while in space there are three, $\Sigma X = 0$, $\Sigma Y = 0$, and $\Sigma Z = 0$. In Case I., then, we have conditions enough for determining two unknown quantities; in Case II., three.

18. Problems involving equilibrium of concurrent forces. (A rigid body in equilibrium under no more than three forces may be treated as a material point, since the (two or) three forces are necessarily concurrent.)*

Problem 1.—A body weighing G lbs. rests on a horizontal table: required the pressure between it and the table. Fig. 8. Consider the body **free**, i.e., conceive all other bodies removed (the table in this instance), being replaced by the forces which they exert on the first body. Taking the axis Y vertical and positive upward, and not assuming in advance either the amount or direction of N, the pressure of the table against the body, but knowing that G, the action of the earth on the body, is vertical and downward, we have here a system of concurrent forces in equilibrium, in which the X and Y components of G are known (being 0 and $-G$ respectively), while those, N_x and N_y, of N are unknown. Putting $\Sigma X = 0$, we have $N_x + 0 = 0$; i.e., N has no horizontal component, $\therefore N$ is vertical. Putting $\Sigma Y = 0$, we have $N_y - G = 0$, $\therefore N_y = +G$; or the vertical component of N, i.e., N itself, is positive (upward in this case), and is numerically equal to G.



Fig. 8.

Problem 2.—Fig. 9. A body of weight G (lbs.) is moving in a straight line over a rough horizontal table with a uniform velocity v (feet per second) to the right. The tension in an oblique cord by which it is pulled is given, and $= P$ (lbs.),

* Three parallel forces form an exception; see §§ 20, 21, etc.

which remains constant, the cord making a given angle of elevation, α, with the path of the body. Required the vertical pressure N (lbs.) of the table, and also its horizontal action F (friction) (lbs.) against the body



Fig. 9.

Referring by anticipation to Newton's first law of motion, viz., a material point acted on by no force or by balanced forces is either at rest or moving uniformly in a straight line, we see that this problem is a case of balanced forces, i.e., of equilibrium. Since there are only two unknown quantities, N and F, we may determine them by the two equations of Case I., taking the axes X and Y as before. Here let us leave the *direction* of N as well as its amount to be determined by the analysis. As F must evidently point toward the left, treat it as negative in summing the X components; the analysis, therefore, can be expected to give only its numerical value.

$\Sigma X = 0$ gives $P \cos \alpha - F = 0$. $\therefore F = P \cos \alpha$.

$\Sigma Y = 0$ gives $N + P \sin \alpha - G = 0$. $\therefore N = G - P \sin \alpha$.

$\therefore N$ is upward or downward according as G is $>$ or $<$ $P \sin \alpha$. For N to be a downward pressure upon the body would require the surface of the table to be above it. The ratio of the friction F to the pressure N which produces it can now be obtained, and is called the "*coefficient of friction.*" It may vary somewhat with the velocity. (See p. 168.)

This problem may be looked upon as arising from an experiment made to determine the coefficient of friction between the given surfaces at the given uniform velocity.

19. The Free-Body Method.—The foregoing rather labored solutions of very simple problems have been made such to illustrate what may be called the "*free-body method*" of treating any problem involving a body acted on by a system of forces. It consists in conceiving the body isolated from all others which act * on it in any way, those actions being introduced as so many forces known or unknown, in amount and position. The system of forces thus formed may be made to yield certain equations, whose character and number depend on circumstances, such as the behavior of the body, whether the forces are confined to

* That is, in any "*force*-able" way.

a plane or not, etc., and which are therefore theoretically available for determining an equal number of unknown quantities.

19a. Examples.—1. A cast-iron cylinder, with axis horizontal, rests against two *smooth* inclined surfaces, as shown in Fig. 9*a*. Its length, l, is 4 ft., diameter, d, is 10 in., and "*heaviness*" (p. 3) 480 lbs./cub. ft. Required the pressures (or "*reactions*," or "*supporting forces*"), P and Q at the two points of contact A and B. (Points, in the end view.) These pressures on the cylinder are shown pointing normal to the surfaces (*smooth* surfaces) and hence pass through the center of the body,



FIG. 9*a*.



FIG. 9*b*.

C, where we may consider the resultant weight, G, of the body to act. These three forces, then, form a concurrent system, and the body is in equilibrium under their action.

Solution.—The weight $G=\frac{\pi d^2 l}{4}\gamma=\frac{\pi}{4}\left(\frac{10}{12}\right)^2\times 4\times 480=1047.6$ lbs.

$\Sigma X=0$ gives: $+P\cos 40°-Q\cos 20°+0=0$; . . . . . (1)

$\Sigma Y=0$ " $+P\sin 40°+Q\sin 20°-G=0$; . . . . . (2)

that is, numerically, $0.7660P-0.9396Q=0$; . . . . . (3)

and $0.6428P+0.3420Q=0.1047.6$ lbs. . . . . (4)

From (3) we have $P=1.227Q$, which in (4) gives

$(0.7887+0.3420)Q=1047.6$ lbs.; and hence $Q=926.4$ lbs. } Ans.

Therefore P, $=1.227Q$, $=1127.6$ lbs.

Example 2.—Fig. 9*b*. The 4-ton weight is suspended on the bolt C, which passes through the ends of boom OC and tie-rod DC. Bolt C is also subjected to a horizontal pull toward the left, due to the 2-ton weight, suspended as shown. Find the pull P in the tie and the thrust Q in the boom. Note that the boom is pivoted at both ends and hence (if we neglect its weight) is under only *two* pressures; both of which, therefore (for the equilibrium of the boom), *must point along its length*. Hence the thrust Q on bolt C makes an angle of 41° with the horizontal. Similarly, P, the action of tie-rod on C, is at 15°.

Solution.—At (*b*) we see the bolt as a "*free body*"; in equilibrium under the four concurrent forces.

$\Sigma X=0$ . . . . . $Q\cos 41°-P\cos 15°-G_2-0=0$; . . . . . (5)

$\Sigma Y=0$ . . . . . $Q\sin 41°-P\sin 15°-G_1-0=0$; . . . . . (6)

or, numerically, $0.7547Q-0.9659P-2=0$, ... (7)

and $0.6560Q-0.2588P-4=0$ . . . . . (8)

From (7), $Q=2.651+1.279P$, which in (8) gives

$0.6560(2.651+1.279P)-0.2588P=4$;

that is, $1.740+0.8390P-0.2588P=4$; and hence, finally,

$P=2.260\div 0.5802=3.896$ tons, and $\therefore\ Q=7.633$ tons. Ans.

CHAPTER II.

PARALLEL FORCES AND THE CENTRE OF GRAVITY.

20. Preliminary Remarks.—Although by its title this section should be restricted to a treatment of the equilibrium of forces, certain propositions involving the composition and resolution of forces, without reference to the behavior of the body under their action, will be found necessary as preliminary to the principal object in view.

As a rigid body possesses extension in three dimensions, to deal with a system of forces acting on it we require three coordinate axes: in other words, the system consists of "forces in space," and in general the forces are *non-concurrent.* In most problems in statics, however, the forces acting are in one plane: we accordingly begin by considering non-concurrent forces in a plane, of which the simplest case is that of two parallel forces. For the present the body on which the forces act will not be shown in the figure, but must be understood to be there (since we have no conception of forces independently of material bodies). The device will frequently be adopted of introducing into the given system two opposite and equal forces acting in the same line: evidently this will not alter the effect of the given system, as regards the rest or motion of the body.

21. Resultant of two Parallel Forces.

Case I.—The two forces have the *same direction.* Fig. 10. Let P and Q be the given forces, and AB a line perpendicular to them (P and Q are supposed to have been transferred to the intersections A and B). Put in at A and B two equal and opposite forces S and S, combining them with P and Q to form P'



Fig. 10.

and Q'. Transfer P' and Q' to their intersection at C, and there resolve them again into S and P, S and Q. S and S annul each other at C; therefore P and Q, acting along a common line CD, replace the P and Q first given; i.e., the resultant of the original two forces is a force $R = P + Q$, acting parallel to them through the point D, whose position must now be determined. The triangle CAD is similar to the triangle shaded by lines, $\therefore P : S :: \overline{CD} : x$; and CDB being similar to the triangle shaded by dots, $\therefore S : Q :: a - x : \overline{CD}$. Combining these, we have* $\frac{P}{Q} = \frac{a-x}{x}$ and $\therefore x = \frac{Qa}{P+Q} = \frac{Qa}{R}$. Now write this $Rx = Qa$, and add Rc, i.e., $Pc + Qc$, to each member, c being the distance of O (Fig. 10), any point in AB produced, from A. This will give $R(x + c) = Pc + Q(a + c)$, in which c, $a + c$, and $x + c$ are respectively the lengths of perpendiculars let fall from O upon P, Q, and their resultant R. Any one of these products, such as Pc, is for convenience (since products of this form occur so frequently in Mechanics as a result of algebraic transformation) called the **Moment** of the force about the arbitrary point O. Hence the resultant of two parallel forces of the same direction is equal to their sum, acts in their plane, in a line parallel to them, and at such a distance from any arbitrary point O in their plane as may be determined by writing its moment about O equal to the sum of the moments of the two forces about O. O is called a *centre of moments*, and each of the perpendiculars a *lever-arm*.

Case II.—Two parallel forces P and Q of opposite directions. Fig. 11. By a process similar to the foregoing, we obtain $R = P - Q$ and $(P - Q)x = Qa$, i.e., $Rx = Qa$. Subtract each member of the last equation from Rc (i.e., $Pc - Qc$), in which c is the distance, from A, of any arbitrary point O in AB produced. This gives $R(c - x) = Pc - Q(a + c)$. But $(c - x)$, c, and $(a + c)$ are respectively the perpendiculars, from



Fig. 11.

* That is, the resultant of two parallel forces pointing in the same direction *divides the distance between them in the inverse ratio of those forces.*

O, upon R, P, and Q. That is, $R(c - x)$ is the moment of R about O; Pc, that of P about O; and $Q(a + c)$, that of Q about O. But the moment of Q is subtracted from that of P, which corresponds with the fact that Q in this figure would produce a rotation about O opposite in direction to that of P. Having in view, then, this imaginary rotation, we may define the moment of a force as *positive* when the indicated direction about the given point is against the hands of a watch; as *negative* when with the hands of a watch.*

Hence, in general, the resultant of any two parallel forces is, in amount, equal to their algebraic sum, acts in a parallel direction in the same plane, while its moment, about any arbitrary point in the plane, is equal to the algebraic sum of the moments of the two forces about the same point.

Corollary.—If each term in the preceding moment equations be multiplied by the secant of an angle (α, Fig. 12) thus:



Fig. 12.



Fig. 13.

(using the notation of Fig. 12), we have

$$Pa \sec \alpha = P_1 a_1 \sec \alpha + P_2 a_2 \sec \alpha, \text{ i.e., } Pb = P_1 b_1 + P_2 b_2,$$

in which b, b_1 and b_2 are the *oblique* distances of the three lines of action from any point O in their plane, and lie on the same straight line; P is the resultant of the parallel forces P_1 and P_2.

22. Resultant of any System of Parallel Forces in Space.—Let P_1, P_2, P_3, etc., be the forces of the system, and x_1, y_1, z_1, x_2, y_2, z_2, etc., the co-ordinates of their points of application as referred to an arbitrary set of three co-ordinate axes X, Y, and Z, perpendicular to each other. Each force is here re-

* These two directions of rotation are often called *counter clockwise*, and *clockwise*, respectively.

stricted to a definite point of application in its line of action (with reference to establishing more directly the fundamental equations for the co-ordinates of the centre of gravity of a body). The resultant P' of any two of the forces, as P_1 and P_2, is $= P_1 + P_2$, and may be applied at C, the intersection of its own line of action with a line BD joining the points of application of P_1 and P_2, its components. Produce the latter line to A, where it pierces the plane XY, and let b_1, b', and b_2, respectively, be the distances of B, C, D, from A; then from the corollary of the last article we have

$$P'b' = P_1b_1 + P_2b_2;$$

but from similar triangles

$$b' : b_1 : b_2 :: z' : z_1 : z_2, \qquad \therefore P'z' = P_1z_1 + P_2z_2.$$

Now combine P', applied at C, with P_3, applied at E, calling their resultant P'' and its vertical co-ordinate z'', and we obtain

$$P''z'' = P'z' + P_3z_3, \text{ i.e., } P''z'' = P_1z_1 + P_2z_2 + P_3z_3,$$

also

$$P'' = P' + P_3 = P_1 + P_2 + P_3.$$

Proceeding thus until all the forces have been considered, we shall have finally, for the resultant of the whole system,

$$R = P_1 + P_2 + P_3 + \text{etc.};$$

and for the vertical co-ordinate of its point of application, which we may write $\bar{z}$,

$$R\bar{z} = P_1z_1 + P_2z_2 + P_3z_3 + \text{etc};$$

$$\text{i.e., } \bar{z} = \frac{P_1z_1 + P_2z_2 + P_3z_3 \ldots}{P_1 + P_2 + P_3 + \ldots} = \frac{\Sigma(Pz)}{\Sigma P};$$

and similarly for the other co-ordinates.

$$\bar{x} = \frac{\Sigma(Px)}{\Sigma P} \text{ and } \bar{y} = \frac{\Sigma(Py)}{\Sigma P}.$$

In these equations, in the general case, such products as P_1z_1, etc., cannot strictly be called moments. The point whose co-

ordinates are the $\bar{x}$, $\bar{y}$, and $\bar{z}$, just obtained, is called the *Centre of Parallel Forces*, and its position is *independent of the* (*common*) *direction* of the forces concerned.

Example.—If the parallel forces are contained in one plane, and the axis Y be assumed parallel to the direction of the forces, then each product like P_1x_1 will be a *moment*, as defined in § 21; and it will be noticed in the accompanying numerical example, Fig. 14, that a detailed substitution in the equation

$$R\bar{x} = P_1x_1 + P_2x_2 + \text{etc.}, \quad . \quad . \quad . \quad (1)$$



Fig. 14.

having regard to the proper sign of each force and of each abscissa, gives the same result as if each product Px were first obtained numerically, and a sign affixed to the product considered as a moment about the point O. Let $P_1 = -1$ lb.; $P_2 = +2$ lbs.; $P_3 = +3$ lbs.; $P_4 = -6$ lbs.; $x_1 = +1$ ft.; $x_2 = +3$ ft.; $x_3 = -2$ ft.; and $x_4 = -1$ ft. Required the amount and position of the resultant R. In amount $R = \Sigma P = -1+2+3-6 = -2$ lbs.; i.e., it is a *downward* force of 2 lbs. As to its position, $R\bar{x} = \Sigma(Px)$ gives $(-2)\bar{x} = (-1)\times(+1) + 2\times 3 + 3\times(-2) + (-6)\times(-1) = -1+6-6+6$. Now from the figure, by inspection, it is evident that the moment of P_1 about O is negative (*with* the hands of a watch), and is numerically $= 1$, i.e., its moment $= -1$; similarly, by inspection, that of P_2 is seen to be positive, that of P_3 negative, that of P_4 positive; which agree with the results just found, that $(-2)\bar{x} = -1+6-6+6 = +5$ ft. lbs. (Since a moment is a product of a force (lbs.) by a length (ft.), it may be called so many foot-pounds.) Next, solving for $\bar{x}$, we obtain $\bar{x} = (+5) \div (-2) = -2.5$ ft.; i.e., the resultant of the given forces is a downward force of 2 lbs. acting in a vertical line 2.5 ft. to the left of the origin. Hence, if the body in question be a horizontal rod whose weight has been already included in the statement of forces, a support placed 2.5 ft. to the left of O and capable of resisting at least 2 lbs. downward pressure will preserve equilibrium; and the pressure which it exerts

against the rod must be an upward force, P_5, of 2 lbs., i e. the equal and opposite of the resultant of P_1, P_2, P_3, P_4.

Fig. 15 shows the rod as a free body in equilibrium under the five forces. $P_5 = +2$ lbs. = the *reaction* of the support.



FIG. 15.

Of course P_5 is one of a pair of equal and opposite forces; the other one is the pressure of the rod against the support, and would take its place among the forces acting on the support.

23. Centre of Gravity.—Among the forces acting on any rigid body at the surface of the earth is the so-called attraction of the latter (i.e., gravitation), as shown by a spring-balance, which indicates the *weight* of the body hung upon it. The weights of the different particles of any rigid body constitute a system of parallel forces (practically so, though actually slightly convergent). The point of application of the resultant of these forces is called the *centre of gravity* of the body, and may also be considered the *centre of mass*, the body being of very small dimensions compared with the earth's radius.

If $\bar{x}$, $\bar{y}$, and $\bar{z}$ denote the co-ordinates of the centre of gravity of a body referred to three co-ordinate axes, the equations derived for them in § 22 are directly applicable, with slight changes in notation.

Denote the weight of any particle * of the body by dG, its volume by dV, by γ its *heaviness* (rate of weight, see § 7) and its co-ordinates by x, y, and z; then, using the integral sign as indicating a summation of like terms for all the particles of the body, we have, for heterogeneous bodies (see also p. 119, *Notes*).

$$\bar{x} = \frac{\int \gamma x dV}{\int \gamma dV}; \quad \bar{y} = \frac{\int \gamma y dV}{\int \gamma dV}; \quad \bar{z} = \frac{\int \gamma z dV}{\int \gamma dV}; \quad . \quad . \quad (1)$$

while, if the body is homogeneous, γ is the same for all its elements, and being therefore placed outside the sign of summation, is cancelled out, leaving for *homogeneous* bodies (V denoting the total volume)

$$\bar{x} = \frac{\int x dV}{V}; \quad \bar{y} = \frac{\int y dV}{V}; \quad \text{and } \bar{z} = \frac{\int z dV}{V}; \quad . \quad . \quad (2)$$

* Any subdivision of the body may be adopted for use of equations (1) and (2), etc.; but it must be remembered that the x (or y, or z) in each term of the summations, or integrals, is the co-ordinate of the *center of gravity of the subdivision employed.*

Corollary.—It is also evident that if a homogeneous body is for convenience considered as made up of several finite parts, whose volumes are V_1, V_2, etc., and whose gravity co-ordinates are $\bar{x}_1, \bar{y}_1, \bar{z}_1$; $\bar{x}_2, \bar{y}_2, \bar{z}_2$; etc., we may write

$$\bar{x} = \frac{V_1\bar{x}_1 + V_2\bar{x}_2 + \dots}{V_1 + V_2 + \dots} \quad \dots \quad (3)$$

If the body is heterogeneous, put G_1 (weights), etc., instead of V_1, etc., in equation (3).

If the body is an infinitely thin *homogeneous shell* of uniform thickness $= h$, then $dV = hdF$ (dF denoting an element, and F the whole area of one surface) and equations (2) become, after cancellation,

$$\bar{x} = \frac{\int x dF}{F}; \quad \bar{y} = \frac{\int y dF}{F}; \quad \bar{z} = \frac{\int z dF}{F}. \quad \dots \quad (4)$$

For a thin homogeneous plate, or shell, of uniform thickness, and composed of several finite parts, of area F_1, F_2, etc., with gravity co-ordinates $\bar{x}_1$, $\bar{x}_2$, etc., we may write

$$\bar{x} = \frac{F_1\bar{x}_1 + F_2\bar{x}_2 + \dots}{F_1 + F_2 + \dots} \quad \dots \quad (4a)$$

Similarly, for a *homogeneous wire* of constant small cross-section (i.e., a geometrical line, having weight), its length being s, and an element of length ds, we obtain

$$\bar{x} = \frac{\int x ds}{s}; \quad \bar{y} = \frac{\int y ds}{s}; \quad \bar{z} = \frac{\int z ds}{s}. \quad \dots \quad (5)$$

24. Symmetry.—Considerations of symmetry of form often determine the centre of gravity of homogeneous solids without analysis, or limit it to a certain line or plane. Thus the centre of gravity of a sphere, or any regular polyedron, is at its centre of figure; of a right cylinder, in the middle of its axis; of a thin plate of the form of a circle or regular polygon, in the centre of figure; of a straight wire of uniform cross-section, in the middle of its length.

Again, if a homogeneous body is symmetrical about a plane, the centre of gravity must lie in that plane, called a plane of

gravity; if about a line, in that line called a line of gravity; if about a point, in that point.

25. By considering certain modes of subdivision of a homogeneous body, lines or planes of gravity are often made apparent. E.g., a line joining the middle of the bases of a trapezoidal plate is a line of gravity, since it bisects all the strips of uniform width determined by drawing parallels to the bases; similarly, a line joining the apex of a triangular plate to the middle of the opposite side is a line of gravity. Other cases can easily be suggested by the student.

26. Problems.—(1) Required the position of the centre of gravity of a *fine homogeneous wire of the form of a circular arc, AB*, Fig. 16. Take the origin O at the centre of the circle, and the axis X bisecting the wire. Let the length of the wire, s, $= 2s_1$; ds = element of arc. We need determine only the $\bar{x}$, since evidently $\bar{y} = 0$. Equations (5), § 23, are applicable here, i.e., $\bar{x} = \dfrac{\int x ds}{s}$.



FIG. 16.

From similar triangles we have *

$$ds : dy :: r : x; \therefore ds = \frac{r dy}{x};$$

$$\therefore \bar{x} = \frac{r}{2s_1}\int_{y=-a}^{y=+a} dy = \frac{2ra}{2s_1}, \text{ i.e., } = \text{chord} \times \text{radius} \div \text{length of}$$

wire. For a semicircular wire, this reduces to $\bar{x} = 2r \div \pi$.

PROBLEM 2. *Centre of gravity of trapezoidal (and triangular) thin plates, homogeneous, etc.*—Prolong the non-parallel sides of the trapezoid to intersect at O, which take as an origin, making the axis X perpendicular to the bases b and b_1. We may here use equations (4), § 23, and may take a vertical strip for our element of area, dF, in determining $\bar{x}$; for each point of such a strip has the same x. Now $dF = (y + y')dx$, and

* The two triangles meant (m being *any* point of the wire) are the finite triangle Omc, and the infinitely small one at m formed by the infinitesimal lengths dy, dx, and ds.

from similar triangles $y + y' = \frac{b}{h}x$. Now $F, = \frac{1}{2}(bh - b_1h_1)$,*

can be written $\frac{1}{2}\frac{b}{h}(h^2 - h_1^2)$, and $\bar{x} = \frac{\int x dF}{F}$ becomes

$$= \left[\frac{b}{h}\int_{h_1}^{h} x^2 dx\right] \div \frac{1}{2}\frac{b}{h}(h^2 - h_1^2) = \frac{2}{3}\frac{h^3 - h_1^3}{h^2 - h_1^2}$$

for the trapezoid.

For a triangle $h_1 = 0$, and we have $\bar{x} = \frac{2}{3}h$; that is, the centre of gravity of a triangle is one third the altitude from the base. The centre of gravity is finally determined by knowing



FIG. 17.



FIG. 18.

that a line joining the middles of b and b_1 is a line of gravity; or joining O and the middle of b in the case of a triangle.

PROBLEM 3. *Sector of a circle. Thin plate*, etc.—Let the notation, axes, etc., be as in Fig. 18. Angle of sector $= 2\alpha$; $\bar{x} = ?$ Using polar co-ordinates, the element of area dF (a small rectangle) $= \rho d\varphi \,.\, d\rho$, and its $x = \rho \cos \varphi$; hence the total area $=$

$$F = \int_{-a}^{+a}\left[\int_0^r \rho d\rho\right] d\varphi = \int_{-a}^{+a}\frac{1}{2}r^2 d\varphi = \frac{r^2}{2}\left[\varphi\right]_{-a}^{+a};$$

i.e., $F = r^2\alpha$. From equations (4), § 23, we have

$$\bar{x} = \frac{1}{F}\int x dF$$

$$= \frac{1}{F}\int\int \cos\varphi \rho^2 d\rho d\varphi = \frac{1}{F}\int_{-a}^{+a}\left[\cos\varphi \int_0^r \rho^2 d\rho\right] d\varphi.$$

*Note that $b_1 : h_1 :: b : h$, so that $b_1h_1 = (b \div h)h_1^2$.

(*Note on double integration.*—The quantity

$$\left[\cos\varphi \int_0^r \rho^2\, d\rho\right] d\varphi,$$

is that portion of the summation $\int\int \cos\varphi\rho^2 d\rho d\varphi$ which belongs to a single elementary sector (triangle), since all its elements (rectangles), from centre to circumference, have the same φ and $d\varphi$.)

That is,

$$\bar{x} = \frac{1}{F}\cdot\frac{r^3}{3}\int_{-\alpha}^{+\alpha}\cos\varphi d\varphi = \frac{r^3}{3r^2\alpha}\left[\sin\varphi\right]_{-\alpha}^{+\alpha} = \frac{2}{3}\cdot\frac{r\sin\alpha}{\alpha};$$

or, putting $\beta = 2\alpha$ = total angle of sector, $\bar{x} = \frac{4}{3}\frac{r\sin\frac{1}{2}\beta}{\beta}$.

For a semicircular plate this reduces to $\bar{x} = \frac{4r}{3\pi}$.

[*Note.*—In numerical substitution the arcs α and β used above (unless sin or cos is prefixed) are understood to be expressed in circular measure (π-measure); e.g., for a quadrant, $\beta = \frac{\pi}{2} = 1.5707$*+; for 30°, $\beta = \frac{\pi}{6}$; or, in general, if β in degrees $= \frac{180°}{n}$, then β in π-measure $= \frac{\pi}{n}$.]



FIG. 19.

PROBLEM 4. *Sector of a flat ring*; thin plate, etc.—Treatment similar to that of Problem 3, the difference being that the limits of the interior integrations are $\left[\begin{smallmatrix}r_1\\r_2\end{smallmatrix}\right.$ instead of $\left[\begin{smallmatrix}r\\0\end{smallmatrix}\right.$. Result,

$$\bar{x} = \frac{4}{3}\cdot\frac{r_1^3 - r_2^3}{r_1^2 - r_2^2}\cdot\frac{\sin\frac{1}{2}\beta}{\beta}.$$

* "Radians."

PROBLEM 5.—*Segment of a circle;* thin plate, etc.—Fig. 20. Since each rectangular element of any vertical strip has the same x, we may take the strip as dF in finding $\bar{x}$, and use y as the half-height of the strip. $dF = 2ydx$, and from similar triangles $x : y :: (-dy) : dx$,* i.e., $xdx = -ydy$. Hence from eq. (4), § 23,



FIG. 20.

$$\bar{x} = \frac{\int x dF}{F} = \frac{\int x 2y dx}{F} = \frac{-2\int_a^0 y^2 dy}{F} = \frac{2}{3F}\left[\,\right]_a^0 (-y^3) = \frac{2}{3}\cdot\frac{a^3}{F};$$

but a = the half-chord, hence, finally, $\bar{x} = \dfrac{(chord)^3}{12F}$.



FIG. 21.

PROBLEM 6.—*Trapezoid;* thin plate, etc., by the method in the corollary of § 23; equation (4a). Required the distance $\bar{x}$ from the base AB. Join DB, thus dividing the trapezoid $ABCD$ into two triangles $ADB = F_1$ and $DBC = F_2$, whose gravity x's are, respectively, $x_1 = \frac{1}{3}h$ and $x_2 = \frac{2}{3}h$. Also, $F_1 = \frac{1}{2}hb_1$, $F_2 = \frac{1}{2}hb_2$, and F (area of trapezoid) $= \frac{1}{2}h(b_1 + b_2)$. Eq. (4$a$) of § 23 gives $F\bar{x} = F_1x_1 + F_2x_2$; hence, substituting,

$$(b_1 + b_2)\bar{x} = \tfrac{1}{3}b_1h + \tfrac{2}{3}b_2h.$$

$$\therefore\ \bar{x} = \frac{h}{3}\cdot\frac{(b_1 + 2b_2)}{b_1 + b_2}.$$

The line joining the middles of b_1 and b_2 is a line of gravity, and is divided in such a ratio by the centre of gravity that the following construction for finding the latter holds good: Prolong each base, in opposite directions, an amount equal to the other base; join the two points thus found: the intersection with the other line of gravity is the centre of gravity of the trapezoid. Thus, Fig. 21, with $BE = b_1$ and $DF = b_2$, join FE, etc.

* The minus sign is used for dy since, as we progress from left to right in bringing into account all the various strips, x increases while y diminishes; i.e., dx is an increment and dy a *decrement*. At the point of beginning of the summation, on left, $y = +a$; while at the extreme right, $y = 0$.

PROBLEM 7. *Homogeneous oblique cone or pyramid.*—Take the origin at the vertex, and the axis X perpendicular to the base (or bases, if a frustum). In finding $\bar{x}$ we may put $dV =$ volume of any lamina parallel to YZ, F being the base of such a lamina, each point of the lamina having the same x. Hence, (equations (2), § 23), (see also Fig. 22).

$$\bar{x} = \frac{1}{V}\int x dV, \quad V = \int dV = \int F dx;$$

but, from the geometry of *similar* plane figures,

$$F : F_2 :: x^2 : h_2^2, \quad \therefore F = \frac{F_2}{h_2^2}x^2,$$

and

$$V = \frac{F_2}{h_2^2}\int x^2 dx = \frac{F_2}{h_2^2}\left[\frac{x^3}{3}\right]; \int x dV = \frac{F_2}{h_2^2}\int x^3 dx = \frac{F_2}{h_2^2}\left[\frac{x^4}{4}\right].$$

For a frustum, $\bar{x} = \frac{3}{4}\cdot\frac{h_2^4 - h_1^4}{h_2^3 - h_1^3}$; while for a pyramid, h_1, being $= 0$, $\bar{x} = \frac{3}{4}h$. Hence the centre of gravity of a pyramid is one fourth the altitude from the base. It also lies in the line joining the vertex to the centre of gravity of the base.



FIG. 22.

PROBLEM 8.—If the heaviness of the material of the above cone or pyramid varied directly as x, γ_2 being its heaviness at the base F_2, we should use equations (1), § 23, putting $\gamma = \frac{\gamma_2}{h_2}x$; and finally, for the frustum,

$$\bar{x} = \frac{4}{5}\cdot\frac{h_2^5 - h_1^5}{h_2^4 - h_1^4},$$

and for a complete cone $\bar{x} = \frac{4}{5}h_2$.

27. The Centrobaric Method.—If an elementary area dF be revolved about an axis in its plane, through an angle $\alpha < 2\pi$,

the distance from the axis being $= x$, the volume generated is $dV = \alpha x dF$, and the total volume generated by all the dF's of a finite plane figure whose plane contains the axis and which lies entirely on one side of the axis, will be $V = \int dV = \alpha \int x dF$. But from § 23, $\alpha \int x dF = \alpha F \bar{x}$; $\alpha \bar{x}$ being the length of path described by the centre of gravity of the plane figure, we may write: *The volume of a solid of revolution generated by a plane figure, lying on one side of the axis, equals the area of the figure multiplied by the length of curve described by the centre of gravity of the figure.*



FIG. 23.

A corresponding statement may be made for the surface generated by the revolution of a line. The arc α must be expressed in π measure in numerical work.

27a. Centre of Gravity of any Quadrilateral.—Fig. 23*a*. *Construction;* $ABGD$ being any quadrilateral. Draw the diagonals. On the long segment DK of DB lay off $DE = BK$, the shorter, to determine E; similarly, determine N on the other diagonal, by making $GN = AK$. Bisect EK in H and KN in M. The intersection of EM and NH is the centre of gravity, C.



FIG. 23*a*.

Proof.—H being the middle of DB, and AH and HG having been joined, I the centre of gravity of the triangle ABD is found on AH, by making $HI = \frac{1}{3}AH$; similarly, by making $HL = \frac{1}{3}HG$, L is the centre of gravity of triangle BDG. $\therefore$ IL is parallel to AG and is a gravity-line of the whole figure; and the centre of gravity C may be found on it if we can make $CL : CI ::$ area ABD : area BDG (§ 21). But since these triangles have a common base DB, their areas are proportional to the slant heights (equally inclined to DB) AK and KG, i.e., to GN and NA. Hence HN, which divides IL in the required ratio, contains C, and *is* $\therefore$ *a gravity-line.* By similar reasoning, using the other diagonal, AG, and

the two triangles into which it divides the whole figure, we may prove EM to be a gravity-line also. Hence the construction is proved.

27b. EXAMPLES.—1. Required the volume of a sphere by the centrobaric method.

A sphere may be generated by a semicircle revolving about its diameter through an arc $\alpha = 2\pi$. The length of the path described by its centre of gravity is $= 2\pi \frac{4r}{3\pi}$ (see Prob. 3, § 26), while the area of the semicircle is $\frac{1}{2}\pi r^2$. Hence by § 27,

$$\text{Volume generated} = 2\pi \cdot \frac{4r}{3\pi} \cdot \tfrac{1}{2}\pi r^2 = \frac{4}{3}\pi r^3.$$

2. Required the position of the centre of gravity of the sector of a flat ring in which $r_1 = 21$ feet, $r_2 = 20$ feet, and $\beta = 80°$ (see Fig. 19, and § 26, Prob. 4).

$\sin \frac{\beta}{2} = \sin 40° = 0.64279$, and β in *circular measure* $= \frac{80}{180}\pi = \frac{4}{9}\pi = 1.3962$ *radians*. By using r_1 and r_2 in feet, $\bar{x}$ will be obtained in feet.

$$\therefore \bar{x} = \frac{4}{3} \cdot \frac{r_1^3 - r_2^3}{r_1^2 - r_2^2} \cdot \frac{\sin \frac{\beta}{2}}{\beta} = \frac{4}{3} \cdot \frac{1261}{41} \cdot \frac{0.64279}{1.3962} = 18.87 \text{ feet.}$$

3. Find the height ($\bar{z}$, $= \overline{OC}$) of the center of gravity of the plane figure in Fig. 23*b* above its base OX.



FIG. 23*b*.

This figure is bounded by straight lines and is an approximation to the shape of the cross-section of a steel "channel" (see p. 275).

Dividing it into three rectangles and two triangles (see dotted lines in figure) and applying eq. (4a) of p. 19, we have

$$\bar{z} = \frac{15\times.6\times.3 + 2[3.4\times.6\times2.3] + 2\left[1.7\times.5\times\frac{1.7}{3}\right]}{15\times0.6 + 2[3.4\times0.6] + 2[1.7\times0.5]} = 0.882 \text{ in.}$$

(The student should carefully verify these numerical details.)

CHAPTER III.

STATICS OF A RIGID BODY.

28. Couples.—On account of the peculiar properties and utility of a system of two equal forces acting in parallel lines and in opposite directions, it is specially considered, and called a **Couple.** The *arm* of a couple is the perpendicular distance between the forces; its *moment*, the product of this arm, by one of the forces. The axis of a couple is an imaginary line drawn perpendicular to its plane on that side from which the rotation appears *positive* (against the hands of a watch). (An ideal rotation is meant, suggested by the position of the arrows; any actual rotation of the rigid body is a subject for future consideration.) In dealing with two or more couples the lengths of their axes are made proportional to their moments; in fact, by selecting a proper scale, numerically equal to these moments. E.g., in Fig. 24, the moments of the two couples there shown are Pa and Qb; their axes p and q so laid off that $Pa : Qb :: p : q$, and that the ideal rotation may appear positive, viewed from the outer end of the axis.



FIG. 24.

For example, if each force P of a couple is 60 lbs., and the arm is $a = 6$ ft., its moment is 360 *foot-pounds;* or 0.180 *foot-tons;* or 4320 *inch-pounds;* or 2.16 *inch-tons.*

29. *No single force can balance a couple.*—For suppose the couple P, P, could be balanced by a force R', then this, acting at some point C, ought to hold the couple in equilibrium. Draw CO through O, the centre of symmetry of the couple, and make $OD = OC$. At D put in two opposite and equal forces, S and T, equal and parallel to R'. The supposed equilibrium is undisturbed. But if R', P, and



FIG. 25.

P are in equilibrium, so ought (by symmetry about O) S, P, and P to be in equilibrium, and they may be removed without disturbing equilibrium. But we have left T and R', which are evidently not in equilibrium; $\therefore$ the proposition is proved by this *reductio ad absurdum*. Conversely a couple has no single resultant.

30. *A couple may be transferred anywhere in its own plane.*—First, it may be turned through any angle α, about any point of its arm, or of its arm produced. Let (P, P') be a couple, G any point of its arm (produced), and α any angle. Make $GC = GA$, $CD = AB$, and put in at C, P_1 and P_2 equal to P (or P'), opposite to each other and perpendicular to GC; and P_3 and P_4 similarly at D. Now apply and combine P and P_1 at O, P' and P_4 at O'; then evidently R and R' neutralize each other, leaving P_3 and P_2 equivalent to the original couple (P, P'). The arm $\overline{CD} = AB$. Secondly, if G be at infinity, and $\alpha = 0$, the same proof applies, i.e., a couple may be moved parallel to itself in its own plane. Therefore, by a combination of the two transferrals, the proposition is established for any transferral in the plane.



FIG. 26.

31. *A couple may be replaced by another of equal moment in a parallel plane.*—Let (P, P') be a couple.* Let CD, in a parallel plane, be parallel to AB. At D put in a pair of equal and opposite forces, S_3 and S_4, parallel to P and each $= \frac{\overline{AE}}{\overline{ED}}P$. Similarly at C, S_1 and S_2 parallel to P and each $= \frac{\overline{BE}}{\overline{EC}}P$. But, from similar triangles,

$$\frac{\overline{AE}}{\overline{ED}} = \frac{\overline{BE}}{\overline{EC}}; \quad \therefore S_1 = S_2 = S_3 = S_4.$$

* See Fig. 27, which is a *perspective view*. The arm of the couple (P, P') is AB, in the background. The length of CD, which is in the foreground, may be anything whatever.

[NOTE.—The above values are so chosen that the intersection point E may be the point of application of $(P' + S_2)$, the resultant of P' and S_2; and also of $(P + S_3)$, the resultant of P and S_3, as follows from § 21; thus (Fig. 28), R, the resultant of the two parallel forces P and S_3, is $= P + S_3$, and its moment about any centre of moments, as E, its own point of application, should equal the (algebraic) sum of the moments of its components about E; i.e., $R \times \text{zero} = P \cdot \overline{AE} - S_3 \cdot \overline{DE}$; $\therefore S_3 = \frac{\overline{AE}}{\overline{DE}} \cdot P$.]



FIG. 27.

FIG. 28.

Replacing P' and S_2 by $(P' + S_2)$, and P and S_3 by $(P + S_3)$, the latter resultants cancel each other at E, leaving the couple (S_1, S_4) with an arm CD, equivalent to the original couple P, P' with an arm AB. But, since $S_1 = \frac{\overline{BE}}{\overline{EC}} \cdot P = \frac{\overline{AB}}{\overline{CD}} \cdot P$, we have $S_1 \times \overline{CD} = P \times \overline{AB}$; that is, their moments are equal.

32. Transferral and Transformation of Couples.—In view of the foregoing, we may state, in general, that a couple acting on a rigid body may be transferred to any position in any parallel plane, and may have the values of its forces and arm changed in any way so long as its moment is kept unchanged, and still have the same effect on the rigid body (as to rest or motion, not in distorting it).

Corollaries.—A couple may be replaced by another in any position so long as their axes are equal and parallel and similarly situated with respect to their planes.

A couple can be balanced only by another couple whose axis is equal and parallel to that of the first, and dissimilarly situated. For example, Fig. 29, Pa being $= Qb$, the rigid body AB (here supposed without weight) is in equilibrium in each

case shown. By "reduction of a couple to a certain arm a" is meant that for the original couple whose arm is a', with forces each $= P'$, a new couple is substituted whose arm shall be $= a$, and the value of whose forces P and P must be computed from the condition

$$Pa = P'a', \quad \text{i.e.,} \quad P = P'a' \div a.$$



FIG. 29.



FIG. 30.

33. Composition of Couples.—Let (P, P') and (Q, Q') be two couples in different planes *reduced to the same arm* $\overline{AB} = a$, which is a portion of the line of intersection of their planes. That is, whatever the original values of the individual forces and arms of the two couples were, they have been transferred and replaced in accordance with § 32, so that $P \cdot \overline{AB}$, the moment of the first couple, and the direction of its axis, p, have remained unchanged; similarly for the other couple. Combining P with Q and P' with Q', we have a resultant couple (R, R') whose arm is also $\overline{AB}$. The axes p and q of the component couples are proportional to $P \cdot \overline{AB}$ and $Q \cdot AB$, i.e., to P and Q, and contain the same angle as P and Q. Therefore the parallelogram $p \ldots q$ is similar to the parallelogram $P \ldots Q$; whence $p : q : r :: P : Q : R$, or $p : q : r :: Pa : Qa : Ra$. Also r is evidently perpendicular to the plane of the resultant couple (R, R'), whose moment is Ra. Hence r, the diagonal of the parallelogram on p and q, is the axis of the resultant couple. To combine two couples, therefore, we have only to combine their axes, as if they were forces, by a parallelogram, the diagonal being the axis of the resultant couple; the plane of this couple will be perpendicular to the

axis just found, and its moment bears the same relation to the moments of the component couples as the diagonal axis to the two component axes. Thus, if two couples, of moments Pa and Qb, lie in planes perpendicular to each other, their resultant couple has a moment $Rc = \sqrt{(Pa)^2 + (Qb)^2}$.

If three couples in different planes are to be combined, the axis of their resultant couple is the diagonal of the parallelopiped formed on the axes, laid off to the same scale and *pointing in the proper directions*, the proper *direction* of an axis being *away* from the plane of its couple, on the side from which the couple appears of positive rotation.

34. If several couples lie in the same plane their axes are parallel and the axis of the resultant couple is their algebraic sum; and a similar relation holds for the moments: thus, in Fig. 24, the resultant of the two couples has a moment $= Qb - Pa$, which shows us that a convenient way of combining couples, when all in one plane, is to call the moments positive or negative, according as the ideal rotations are against, or with, the hands of a watch, as seen from the *same* side of the plane; the sign of the algebraic sum will then show the ideal rotation of the resultant couple.

35. Composition of Non-concurrent Forces in a Plane.—Let P_1, P_2, etc., be the forces of the system; x_1, y_1, x_2, y_2, etc., the



FIG. 31.



FIG. 32.

co-ordinates of their points of application; and α_1, α_2, . . . etc., their angles with the axis X. Replace P_1 by its components X_1 and Y_1, parallel to the arbitrary axes of reference. At the origin put in two forces, opposite to each other and equal and parallel to X_1; similarly for Y_1. (Of course $X_1 = P_1 \cos \alpha$ and $Y_1 = P_1 \sin \alpha$.) We now have P_1 replaced by two forces X_1

and Y_1 *at the origin*, and two couples, in the same plane, whose moments are respectively $-X_1y_1$ and $+Y_1x_1$, and are therefore (§ 34) equivalent to a single couple, in the same plane with a moment $= (Y_1x_1 - X_1y_1)$.

Treating all the remaining forces in the same way, the whole system of forces is replaced by

the force $\Sigma(X) = X_1 + X_2 + \ldots$ at the origin, along the axis X;
the force $\Sigma(Y) = Y_1 + Y_2 + \ldots$ at the origin, along the axis Y;

and the couple whose mom. $G = \Sigma(Yx - Xy)$, which may be called the couple C (see Fig. 32), and may be placed anywhere in the plane. Now $\Sigma(X)$ and $\Sigma(Y)$ may be combined into a force R; i.e.,

$R = \sqrt{(\Sigma X)^2 + \Sigma Y)^2}$ and its direction-cosine is $\cos \alpha = \dfrac{\Sigma X}{R}$.

Since, then, the whole system reduces to C and R, we must have for equilibrium $R = 0$, and $G = 0$; i.e., **for equilibrium**

$$\Sigma X = 0,\ \Sigma Y = 0, \text{ and } \Sigma(Yx - Xy) = 0. \quad \text{eq. (1)}$$

If R alone $= 0$, the system reduces to a couple whose moment is $G = \Sigma(Yx - Xy)$; and if G alone $= 0$ the system reduces to a single force R, applied at the origin. If, in general, neither R nor $G = 0$, the system is still equivalent to a single force, but not applied at the origin (as could hardly be expected, since the origin is arbitrary); as follows (see Fig. 33):

Replace the couple C by one of equal moment, G, with each force $= R$. Its arm will therefore be $\dfrac{G}{R}$. Move this couple in the plane so that one of its forces R may cancel the R already at the origin, thus leaving a **single resultant** R for the whole system, applied in a line at a perpendicular distance, $c = \dfrac{G}{R}$, from the origin, and making an angle α whose cosine $= \dfrac{\Sigma X}{R}$, with the axis X. It is easily proved that the "*moment*," Rc, of the single resultant, about the origin O, *is equal to the algebraic sum of those of its "components"* (i.e., the forces of the system.

36. More convenient form for the equations of equilibrium of non-concurrent forces in a plane.—In (I.), Fig. 34, O being

any point and a its perpendicular distance from a force P; put in at O two equal and opposite forces P and $P' =$ and $\parallel$ to P, and we have P replaced by an equal single force P' at O, and a couple whose moment is $+ Pa$. (II.) shows a similar construction, dealing with the X and Y components of P, so that in (II.) P is replaced by single forces X' and Y' at O



Fig. 33.



Fig. 34.

(and they are equivalent to a resultant P', at O, as in (I.), and two couples whose moments are $+ Yx$ and $- Xy$.

Hence, O being the same point in both cases, the couple Pa is equivalent to the two last mentioned, and, their axes being parallel, we must have $Pa = Yx - Xy$. Equations (1), § 35, for equilibrium, may now be written*

$$\Sigma X = 0, \ \Sigma Y = 0, \text{ and } \Sigma(Pa) = 0. \quad . \quad . \quad (2)$$

In problems involving the equilibrium of non-concurrent forces in a plane, we have *three independent conditions*, or *equations*, and can determine at most three unknown quantities. For practical solution, then, the rigid body having been made *free* (by conceiving the actions of all other bodies as represented by forces), and being in equilibrium (which it must be if at rest), we apply equations (2) literally; i.e., assuming an origin and two axes, equate the sum of the X components of all the forces to zero; similarly for the Y components; and then for the "moment-equation," having dropped a perpendicular from the origin upon each force, write the algebraic sum of the products (*moments*) obtained by multiplying each force by its perpendicular, or "*lever-arm*," equal to zero, calling each product $+$ or $-$ according as the ideal rotation appears against, or with, the hands of a watch, as seen from the same side of the plane. (The converse convention would do as well.)

* Another proof is given on p. 15 of the "*Notes and Examples in Mechanics.*"

Sometimes it is convenient to use three moment equations, taking a new origin each time, and then the $\Sigma X = 0$ and $\Sigma Y = 0$ are superfluous, as they would not be independent equations.

37. Problems involving Non-concurrent Forces in a Plane.—*Remarks.* The weight of a rigid body is a vertical force through its centre of gravity, downwards.

If the surface of contact of two bodies is *smooth* the action (pressure, or force) of one on the other is perpendicular to the surface at the point of contact. If a cord must be imagined cut, to make a body free, its tension must be inserted in the line of the cord, and in such a direction as to keep *taut* the small portion still fastened to the body. In case the pin of a hinge must be removed, to make the body free, its pressure against the ring being unknown in *direction* and *amount*, it is most convenient to represent it by its unknown components X and Y, in *known* directions. In the following problems there is supposed to be no friction. If the line of action of an unknown force is known, but not its direction (forward or backward), *assume a direction for it* and adhere to it in all the three equations, and if the assumption is correct the value of the force, after elimination, will be positive; if incorrect, negative.*

Problem 1.—Fig. 35. Given an oblique rigid rod, with two loads G_1 (its own weight) and G_2; required the reaction of the *smooth* vertical wall at A, and the direction and amount of the *hinge*-pressure at O. The reaction at A must be horizontal; call it X'. The pressure at O, being unknown in direction, will have both its X and Y components unknown. The three unknowns, then, are X_0, X', and Y_0, while G_1, G_2, a_1, a_2, and h are known. The figure shows the rod as a *free body*, all the forces acting on it have been put in, and, since the rod is at rest, constitute a system of non-concurrent forces in a plane, ready for the conditions of equilibrium. Taking origin and axes as in the figure.



FIG. 35.

* That is, the force must point in a direction opposite to that first assumed for it.

$\Sigma X = 0$ gives $+ X_0 - X' = 0$; $\Sigma Y = 0$ gives $+ Y_0 - G_1 - G_2 = 0$; while $\Sigma(Pa) = 0$, about O, gives $+ X'h - G_1a_1 - G_2a_2 = 0$. (The moments of X_0 and Y_0 about O are, each, = zero.) By elimination we obtain $Y_0 = G_1 + G_2$; $X_0 = X' = [G_1a_1 + G_2a_2] \div h$; while the pressure at $O = \sqrt{X_0^2 + Y_0^2}$, and makes with the horizontal an angle whose tan $= Y_0 \div X_0$.

[N.B. A special solution for this problem consists in this, that the resultant of the two known forces G_1 and G_2 intersects the line of X' in a point which is easily found by § 21. The hinge-pressure must pass through this point, since three forces in equilibrium must be concurrent.]

Note that the line of action of the pressure at 0, i.e., of the resultant of X_0 and Y_0, *does not coincide with the axis of the rod;* the rod being subjected to more than the two forces at its extremities. The case therefore differs from that presented by the boom in Ex. 2 of p. 12.

Problem 2.—Given two rods with loads, three hinges (or "pin-joints"), and all dimensions: required the three hinge-



FIG. 36.



FIG. 37.

pressures; i.e., there are six unknowns, viz., three X and three Y components. We obtain three equations from each of the two free bodies in Fig. 37. The student may fill out the details. Notice the application of the principle of action and reaction at B (see § 3).

Problem 3.—A Warren bridge-truss rests on the horizontal *smooth* abutment-surfaces in Fig. 38. It is composed of equal isosceles triangles; no piece is continuous beyond a joint, each of which is a *pin connection.* All loads are considered as acting at the joints, so that each piece will be subjected to a simple tension or compression. ("*Two-force* pieces; see p. 18, *Notes.*)



FIG. 38.

First, required the reactions of the supports V_1 and V_2; these and the loads are called the *external* forces. $\Sigma(Pa)$ about $O = 0$ gives (the whole truss is the free body)

$$V_2 3a - P_1 \cdot \tfrac{1}{2}a - P_2 \cdot \tfrac{3}{2}a - P_3 \cdot \tfrac{5}{2}a = 0;$$

while $\Sigma(Pa)$ about $K = 0$ gives

$$- V_1 \cdot 3a + P_3 \cdot \tfrac{1}{2}a + P_2 \tfrac{3}{2}a + P_1 \tfrac{5}{2}a = 0;$$

$$\therefore V_1 = \tfrac{1}{6}[5P_1 + 3P_2 + P_3];$$

and $$V_2 = \tfrac{1}{6}[P_1 + 3P_2 + 5P_3].$$

Secondly, required the stress (thrust or pull, compression or tension) in each of the pieces A, B, and C cut by the imaginary line DE. The stresses in the pieces are called *internal* forces. These appear in a system of forces acting on a free body only when a portion of the truss or frame is conceived separated from the remainder in such a way as to expose an internal plane of one or more pieces. Consider as a free body the portion on the left of DE (that on the right would serve as well, but the pulls or thrusts in A, B, and C would be found to act in directions opposite to those they have on the other portion; see § 3). Fig. 39. The arrows (forces) A, B, and C, are assumed to point, respectively, in the directions shown in the figure. They, with V_1, P_1, and P_2, form a system holding the body in equilibrim.



Fig. 39.

For this system, $\Sigma(Pa)$ about $O=0$ gives

$$0+Ah-V_1 2a+P_1 \cdot \tfrac{3}{2}a+P_2 \cdot \tfrac{1}{2}a=0;$$

and hence $$A=(\tfrac{1}{2}a \div h)[4V_1-3P_1-P_2],$$

which is *positive;* since, (see above), $4V_1$ is $>3P_1+P_2$.

Therefore the assumption that A points to the left is confirmed and A is a thrust, or compression; (its value as above.)

Again, taking moments about O_1 (intersection of A and B), we have an equation in which the only unknown is C, viz.,

$$Ch-V_1\tfrac{3}{2}a+P_1a=0; \quad \therefore C=(\tfrac{1}{2}a \div h)[3V_1-2P_1],$$

a positive value since $3V_1$ is $>2P_1$; $\therefore C$ must point to the right as assumed; i.e., is a tension, and $=\frac{a}{2h}[3V_1-2P_1]$.

Finally, to obtain B, put Σ(vert. comps.)$=0$; i.e.

$$B\cos\phi+V_1-P_1-P_2=0.$$

$\therefore B\cos\phi=P_1+P_2-V_1$; but, (see foregoing value of V_1) we may write

$$V_1=(P_1+P_2)-(\tfrac{1}{6}P_1+\tfrac{1}{2}P_2)+\tfrac{1}{6}P_3.$$

$\therefore B\cos\varphi$ will be $+$ (upward) or $-$ (downward), and B will be compression or tension, as $\frac{1}{6}P_3$ is $<$ or $>$ $[\frac{1}{6}P_1+\frac{1}{2}P_2]$.

$$B=[P_1+P_2-V_1]\div\cos\varphi=\frac{\sqrt{h^2+\frac{1}{4}a^2}}{h}[P_1+P_2-V_1].$$

Problem 4.—Given the weight G_1 of rod, the weight G_2, and all the geometrical elements (the student will assume a convenient notation); required the tension in the cord, and the amount and direction of pressure on hinge-pin. Fig. 41.



Fig. 40.



Fig. 41.

Problem 5.—Roof-truss; pin-connection; all loads at joints; wind-pressures W and W_1 normal to OA; required the three reactions or supporting forces (of the two horizontal surfaces and one vertical surface), and the stress in each piece. All geometrical elements are given; also P, P_1, P_2, W (Fig. 40).



Fig. 42.

38. Composition of Non-concurrent Forces in Space.—Let P_1, P_2, etc., be the given forces, and x_1, y_1, z_1, x_2, y_2, z_2, etc., their points of application referred to an arbitrary origin and axes; α_1, β_1, γ_1, etc., the angles made by their lines of application with X, Y, and Z.

Considering the first force* P_1, replace it by its three components parallel to the axes, $X_1 = P_1 \cos \alpha_1$; $Y_1 = P_1 \cos \beta_1$; and $Z_1 = P_1 \cos \gamma_1$ (P_1 itself is not shown in the figure). At O, and also at A, put a pair of equal and opposite forces, each equal and parallel to Z_1; Z_1 is now replaced by a single force Z_1 acting upward at the origin, and two couples, one in a plane parallel to YZ and having a moment $= -Z_1 y_1$ (as we see it looking toward O from a remote point on the axis $+X$), the other in a plane parallel to XZ and having a moment $= +Z_1 x_1$ (seen from a remote point on the axis $+Y$). Similarly at O and C put in pairs of forces equal and parallel to X_1, and we have X_1, at B, replaced by the single force X_1 at the origin, and the couples, one in a plane parallel to XY and having a moment $+X_1 y_1$, seen from a remote point on the axis $+Z$, the other in a plane parallel to XZ, and of a moment $= -X_1 z_1$, seen from a remote point on the axis $+Y$; and finally, by a similar device, Y_1 at B is replaced by a force Y_1 at the origin and two couples, parallel to the planes XY and YZ, and having moments $-Y_1 x_1$ and $+Y_1 z_1$, respectively. (In Fig. 42 the single forces at the origin are broken lines, while the two forces constituting any one of the six couples may be recognized as being equal and parallel, of opposite directions, and both continuous, or both dotted.) We have, therefore, replaced the force P_1 by three forces X_1, Y_1, Z_1, at O, and six couples (shown more clearly in Fig. 43; the couples have been transferred to symmetrical positions). Combining each two couples whose axes are parallel to X, Y, or Z, they can be reduced to three, viz.,



FIG. 43.

one with an X axis and a moment $= Y_1 z_1 - Z_1 y_1$;
one with a Y axis and a moment $= Z_1 x_1 - X_1 z_1$;
one with a Z axis and a moment $= X_1 y_1 - Y_1 x_1$.

* This "first force," P_1, is applied at the point B, whose co-ordinates are x_1, y_1, and z_1, and is typical of all the other forces of the system.

Dealing with each of the other forces P_2, P_3, etc., in the same manner, the whole system may finally be replaced by three forces ΣX, ΣY, and ΣZ, at the origin and three couples whose moments are, respectively, (ft-lbs., for example)

$$L = \Sigma(Yz - Zy) \text{ with its axis parallel to } X;$$
$$M = \Sigma(Zx - Xz) \text{ with its axis parallel to } Y;$$
$$N = \Sigma(Xy - Yx) \text{ with its axis parallel to } Z.$$

The "axes" of these couples, being parallel to the respective co-ordinate axes X, Y, and Z, and proportional to the moments L, M, and N, respectively, the axis of their resultant C, whose moment is G, must be the diagonal of a parallelopipedon constructed on the three component axes (proportional to) L, M, and N. Therefore, $G = \sqrt{L^2 + M^2 + N^2}$, while the resultant of ΣX, ΣY, and ΣZ is

$$R = \sqrt{(\Sigma X)^2 + (\Sigma Y)^2 + (\Sigma Z)^2}$$

acting at the origin. If α, β, and γ are the direction-angles of R, we have $\cos \alpha = \frac{\Sigma X}{R}$, $\cos \beta = \frac{\Sigma Y}{R}$, and $\cos \gamma = \frac{\Sigma Z}{R}$; while if λ, μ, and ν are those of the *axis* of the couple C, we have $\cos \lambda = \frac{L}{G}$, $\cos \mu = \frac{M}{G}$, and $\cos \nu = \frac{N}{G}$.

For equilibrium we have both $G = 0$ and $R = 0$; i.e., separately, *six conditions*, viz.,

$$\Sigma X = 0,\ \Sigma Y = 0,\ \Sigma Z = 0; \quad \text{and} \quad L = 0,\ M = 0,\ N = 0 \quad . \quad (1)$$

Now, noting that $\Sigma X = 0$, $\Sigma Y = 0$, and $\Sigma(Xy - Yx) = 0$ are the conditions for equilibrium of the system of non-concurrent forces which would be formed by projecting each force of our actual system upon the plane XY, and similar relations for the planes YZ and XZ, we may restate equations (1) in another form, more serviceable in practical problems, viz.:

Note.—*If a system of non-concurrent forces in space is in equilibrium, the plane systems formed by projecting the given system upon each of three arbitrary co-ordinate planes will each be in equilibrium.* But we can obtain *only six independent*

equations in any case, available for six unknowns. If R alone $= 0$, we have the system equivalent to a couple C, whose moment $= G$; if G alone $= 0$, the system has a single resultant R applied at the origin. In general, neither R nor G being $= 0$, we cannot further combine R and C (as was done with non-concurrent forces in a plane) to produce a single resultant unless R and C happen to be in parallel planes; in which case the system may be reduced to a single resultant by use of the device explained near foot of p. 32.

Remark.—In general, R and C not being in parallel planes, the system may be reduced to *two single forces* not in the same plane, by assigning any value we please to P, one of the forces of the couple C, computing the corresponding arm $a = G \div P$, transferring C until one of the P's has the same point of application as R, and then combining these two forces into a single resultant. This last force and the second P are, then, the equivalent of the original system, but are not in the same plane. (See §§ 15 and 15*a*.)

Again, if a reference plane be chosen at right angles to R, and the couple C be decomposed into two couples, one in the reference plane and the other in a plane at right angles to it, this second couple and R may be replaced by a single force (as on p. 32) and we then have the whole system replaced by a *single force* and *a couple situated in a plane perpendicular to that force;* (and this may be called a "screwdriver action.")

Example.—A shaft, with crank and drum attached and supported horizontally on two *smooth* cylindrical bearings, constitutes a hoisting device. See Fig. 43*a*. A force P is to be applied to the crank handle at 30° with the horizontal (and ⊥ to the crank), and acting in a plane at right angles to the shaft; and is to be of such value as to preserve equilibrium when the weight of 800 lbs. is sustained, as shown. The weight of the shaft, etc., is 200 lbs., and its center of gravity is at C in the axis of the shaft. (Counterpoise for crank not shown.) The reactions at the two bearings will lie in planes ⊥ to the axis of the shaft (*smooth* cylindrical surfaces), making unknown angles with the vertical; and will be represented by their X and Z components,



FIG. 43*a*.

as shown. It is required to find the proper value for P and the amount and position of the two reactions.

Solution.—The seven forces shown in the figure (of which five are unknown) constitute a non-concurrent system of forces in space; in equilibrium. Since there are no Y-components the condition $\Sigma Y = 0$ is already satisfied. Let us now apply the statement of the "note" on p. 39, first projecting the forces on the plane ZX (vertical plane ⊥ to the shaft). (That is, we take an "*end-view*" of the system.) Each of the seven forces projects in full length, or value, since they are all parallel to that plane. Treating the plane system so formed as in equilibrium and taking moments about the point O, we find (feet and lbs.)

$$+P\times 1.5 - 800\times\tfrac{1}{3} + 0 = 0; \quad \therefore\ P = 177.77 \text{ lbs.} \quad . \quad . \quad . \quad (1)$$

Next projecting on the vertical plane ZY, containing axis of shaft (i.e., taking a "*side-view*" of the system) we note that the projection of P is $P \sin 30°$ and those of X_0 and X_1 each zero, while Z_0, Z_1, and the 200 and 800 lbs., project in full length; hence taking moments about O we have

$$+200\times 1\tfrac{2}{3} + 800\times 2 - Z_1\times 3 - P\times 0.50\times 4 + 0 = 0 \quad . \quad . \quad . \quad (2)$$

while moms. about O_1 gives $+Z_0\times 3 - P\times 0.5\times 1 - 200\times 1\tfrac{1}{3} - 800 - 1 = 0$ (3)

Finally, projecting on the horizontal plane XZ ("top-view"), the forces in this projection are $P \cos 30°$, X_0, and X_1; so taking moms. about point O_1,

$$+X_0\times 3 - P\times 0.8660\times 1 = 0; \quad \therefore\ X_0 = +51.34 \text{ lbs.}; \quad . \quad (4)$$

while from $\Sigma X = 0$, $X_1 - X_0 = 0$, or $X_1 = X_0$; i.e., $X_1 = +51.34$ lbs. . (5)

From (2) and (3) we have $Z_1 = +525.93$ lbs., and $Z_0 = +385.18$ lbs. All these + signs show that the arrows for X_0, X_1, Z_0, and Z_1 have been correctly assumed (Fig. 43*a*) as to direction. Combining results, we find that the pressure or reaction at O is $R_0 = \sqrt{X_0^2 + Z_0^2} = 388.6$ lbs. and makes an angle whose tang. is $X_0 \div Z_0$, (i.e., 0.1333), viz., 7° 36′, on the *left* of the vertical; also that the pressure or reaction at O_1 is $R_1 = \sqrt{X_1^2 + Z_1^2} = 528.4$ lbs., at an angle on the *right* of the vertical whose tang., $= X_1 \div Z_1$, $(= 0.09763)$; i.e., 5° 34′.

39. Problem (Somewhat similar to the foregoing.)—Given all geometrical elements (including α, β, γ, angles of P), also the weight of Q, and weight of apparatus G; A being a hinge whose pin is in the axis Y, O a *ball-and-socket* joint: required the *amount* of P (lbs.) to preserve equilibrium, also the pressures (*amount* and *direction*) at A and O; no friction. Replace P by its X, Y, and Z components. The pressure at A will have Z and X components; that at O, X, Y, and Z components. [Evidently there are six unknowns; Y_0 will come out negative.



FIG. 44.

CHAPTER IV.

STATICS OF FLEXIBLE CORDS.

40. Postulate and Principles.—The cords are perfectly flexible and inextensible. All problems will be restricted to one plane. Solutions of problems are based on two principles, viz.:

PRIN. I.—The strain or tension, in a cord at any point can act only along the cord, or along the tangent if it be curved.

PRIN. II.—We may apply to flexible cords in equilibrium all the conditions for the equilibrium of rigid bodies; since, if the system of cords became rigid, it would still, with greater reason, be in equilibrium.

41. The Simple Pulley.—A "simple pulley" is one that is acted on by only *one* cord (or belt) and the reaction of the bearing supporting its axle (or "journal").

A cord in equilibrium over a simple pulley whose axle is smooth is under equal tensions on both sides; for, Fig. 46,



FIG. 46.



FIG. 47.

considering the pulley and its portion of cord free $\Sigma(Pa) = 0$ about the centre of axle gives $P'r = Pr$, i.e., $P' = P =$ tension in the cord. Hence the pressure R at the axle *bisects the angle* α, and therefore if a weighted pulley rides upon a cord ABC, Fig. 47, its position of equilibrium, B, may be found by cutting the vertical through A by an arc of radius $CD =$ length of cord, and centre at C, and drawing a horizontal through the middle of AD to cut CD in B. A smooth ring would serve as well as the pulley; this would be a *slip-knot.* From Fig. 46, $R = 2P \cos \frac{1}{2}\alpha$.

42. If three cords meet at a *fixed knot*, and are in equilibrium, the tension in any one is the equal and opposite of the resultant of those in the other two.



FIG. 48.

FIG. 49.

43. Tackle.—If a cord is continuous over a number of sheaves in blocks forming a tackle, neglecting the weight of the cord and blocks and friction of any sort, we may easily find the ratio between the cord-tension P and the weight to be sustained. E.g., Fig. 48, regarding all the straight cords as vertical and considering the block B free, we have, Fig. 49 (from $\Sigma Y = 0$), $4P - G = 0$, $\therefore P = \frac{G}{4}$. The stress on the support C will $= 5P$.



FIG. 49*a*. FIG. 49*b*. FIG. 49*c*. FIG. 49*d*.

Other designs of tackle are presented in Figs. 49*a*, 49*b*, 49*c*, and 49*d*, and should be worked out as exercises by the student. In each case the weight G is supposed to be given and a value of the smaller weight (or pull) P must be determined for the equilibrium of the tackle. Friction, and the weights of the pulleys and cords, are neglected and all straight parts of cords (or chains) are considered vertical.

All of the pulleys shown are "simple pulleys," *except the one at A* in Fig. 49*d*, which represents a "*differential pulley*" tackle. Pulley A consists of two ordinary pulleys fastened together, the groove in each being so rough, or furnished with "sprocket-teeth" in case a chain is used, that *slipping of the cord or chain is prevented.* The chain or cord is endless, the loop C being slack. B is a simple pulley. In this case, for equilibrium the pull P must $= \frac{1}{2}G(r_1 - r) \div r_1$. The other results are $p = \frac{1}{5}G$ for Fig. 49*a*; $\frac{1}{4}G$ for 49*b*; and $\frac{1}{3}G$ for 49*c*.

44. Weights Suspended at Fixed Knots.—Given all the geometrical elements in Fig. 50, and one weight, G_1; required the remaining weights and the forces H_0, V_0, H_n and V_n, at the points of support, that equilibrium may obtain. H_0 and V_0 are the horizontal and vertical components of the tension in the cord at O; similarly H_n and V_n those at n. There are $n+2$ unknowns.



FIG. 50.

(The solution of this problem is deferred. See p. 420.)



FIG. 50a.



FIG. 50b.

45. Example.—The boom OD, tie-rod RD, with four simple pulleys and a cable, form a crane as shown in Fig. 50*a*. Find the necessary vertical force P to be exerted on the piston at H, that the load of 800 lbs. may be sustained. Also find the pressure of pulley B on its bearing, the pull T in the tie-rod and the pressure P_0 (amount and position) at pin O; neglecting all friction and rigidity (p. 192) and the weights of the members. Dimensions as in figure. Since all pulleys are "simple" the tension in cable is the same at all points; and is $=400$ lbs. since the straight parts of cable adjoining pulley A are parallel. For a similar reason $P=800$ lbs.

Pressure at B bisects the angle (50°) between adjoining straight parts of cable; i.e., is 25° with vertical, and $=2\times400\times\cos 25°=725$ lbs., (§ 41).

Next take the free body in Fig. 50*b* (boom and pulley B together with a part of cable.) Three unknowns and three equations.

$\Sigma(\text{moms.})_0=0$; $\therefore +T\times9\times\tan 40°+400\times1-400\times9-400\times7=0$ (1)

i.e., $T\times9\times0.8391=6000$ ft.-lbs.; $\therefore T=794.3$ lbs., (tension in tie-rod.)

$\Sigma X=0$, $\therefore X_0-400\cos 40°-T=0$; $\therefore X_0=794.3+400\times.766=1100.7$ lbs.

$\Sigma Y=0$, $\therefore Y_0-400\sin 40°-400-400=0$;

$\therefore Y_0=400\times.6428+800=1057.12$ lbs.

Hence P_0, $=\sqrt{X_0^2+Y_0^2}$, $=1526$ lbs. at $\tan^{-1}Y_0/X_0$, or 43° 50′, with horiz.

Note.—If the weight 800 lbs. were attached directly to cable on right of pulley B, the value of P would need to be 1600 lbs.

46. Loaded Cord as Parabola.—If the weights are equal and infinitely small, and are intended to be uniformly spaced *along the horizontal*, when equilibrium obtains, the cord having no weight, it will form a parabola. Let q = weight of loads per horizontal linear unit, O be the vertex of the curve in which the cord hangs, and m any point. We may consider the portion Om as a **free body**, if the reactions of the contiguous portions of the cord are put in, H_0 and T, and these (from Prin. I.) must act along the tangents to the curve at O and m, respectively; i.e., H_0 is horizontal, and T makes some angle φ (whose tangent $= \frac{dy}{dx}$, etc.) with the axis X. Applying Prin. II.,



Fig. 51.

$$\Sigma X = 0 \text{ gives } T\cos\varphi - H_0 = 0;\ \text{i.e., } T\frac{dx}{ds} = H_0; \quad . \quad . \quad (1)$$

$$\Sigma Y = 0 \text{ gives } T\sin\varphi - qx = 0;\ \text{i.e., } T\frac{dy}{ds} = qx. \quad . \quad . \quad (2)$$

Dividing (2) by (1), member by member, we have $\frac{dy}{dx} = \frac{qx}{H_0}$;

$\therefore dy = \frac{q}{H_0}x\,dx$, the differential equation of the curve;

$y = \frac{q}{H_0}\int_0^x x\,dx = \frac{q}{H_0}\cdot\frac{x^2}{2}$; or $x^2 = \frac{2H_0}{q}y$, the equation of a **parabola** whose vertex is at O and axis vertical.

Note.—The same result, $\frac{dy}{dx} = \frac{qx}{H_0}$, may be obtained by considering that we have here (Prin. II.) a *free rigid body* acted on by three forces, T, H_0, and $R = qx$, acting vertically through the middle of the abscissa x; the resultant of H_0 and R must be equal and opposite to T, Fig. 52. $\therefore \tan\varphi = \frac{R}{H_0}$, or $\frac{dy}{dx} = \frac{qx}{H_0}$. Evidently also the tangent-line bisects the abscissa x. (Try moments about m.)



Fig. 52.

Example.—Let $q = 800$ lbs. "per foot run" and $x = 100$ ft., with $y = 20$ ft. Then we have, for the value of the tension at the vertex O of the parabola,

$$H_0 = qx^2 \div 2y = 800 \times (100)^2 \div 40 = 200{,}000 \text{ lbs.}$$

47. Problem under § 46. [Case of a suspension-bridge in which the suspension-rods are vertical, the weight of roadway is uniform per horizontal foot, and large compared with that of the cable and rods. Here the roadway is the only load: it is generally furnished with a stiffening truss to avoid deformation under passing loads.]—Given the span $= 2b$, Fig. 53, the deflection $= a$, and the rate of loading $= q$ lbs. per horizontal foot; required the tension in the cable at O, also at m; and the length of cable needed. From the equation of the parabola $qx^2 = 2H_0y$, putting $x = b$ and $y = a$, we have $H_0 = qb^2 \div 2a =$ the tension at O. From $\Sigma Y = 0$ we have $V_1 = qb$, while $\Sigma X = 0$ gives $H_1 = H_0$; $\therefore$ the tension at $m = \sqrt{H_1^2 + V_1^2} = \frac{1}{2a}[qb\sqrt{4a^2 + b^2}]$.



Fig. 53.

The semi-length, Om, of cable (from p. 88, Todhunter's Integral Calculus) is (letting n denote $H_0 \div 2q$, $= b^2 \div 4a$)

$$Om = \sqrt{na + a^2} + n \cdot \log_e [(\sqrt{a} + \sqrt{n + a}) \div \sqrt{n}].$$

48. The Catenary.*—A flexible, inextensible cord or chain, of uniform weight per unit of length, hung at two points, and supporting *its own weight alone*, forms a curve called the **catenary**. Let the tension H_0 at the lowest point or vertex be represented (for algebraic convenience) by the weight of an imaginary length, c, of similar cord weighing q lbs. per unit of length, i.e., $H_0 = qc$; an actual portion of the cord, of length s, weighs qs lbs. Fig. 54 shows as *free* and in equilibrium a portion of the curve of any length s, reckoning from O the vertex. Required the equation of the curve. The load is uniformly spaced *along the curve*, and not horizontally, as in §§ 46 and 47.



Fig. 54.

$\Sigma Y = 0$ gives $T\frac{dy}{ds} = qs$; while $\Sigma X = 0$ gives $T\frac{dx}{ds} = qc$. Hence, by division, $cdy = sdx$, and squaring, $c^2dy^2 = s^2dx^2$. . . . . (1)

* For the "transformed catenary," see p. 395.

Put $dy^2 = ds^2 - dx^2$, and we have, after solving for dx

$$dx = \frac{c\,ds}{\sqrt{s^2 + c^2}}. \quad \therefore x = c\int_0^s \frac{ds}{\sqrt{s^2 + c^2}} = c\Big[\log_e (s + \sqrt{s^2 + c^2})$$

and $$x = c \cdot \log_e [(s + \sqrt{s^2 + c^2}) \div c], \quad . \quad . \quad . \quad (2)$$

a relation between the horizontal abscissa and length of curve

Again, in eq. (1) put $dx^2 = ds^2 - dy^2$, and solve for dy.

This gives $dy = \dfrac{s\,ds}{\sqrt{c^2 + s^2}} = \dfrac{1}{2} \cdot \dfrac{d(c^2 + s^2)}{(c^2 + s^2)^{\frac{1}{2}}}$. Therefore

$$y = \tfrac{1}{2}\int_0^s (c^2 + s^2)^{-\frac{1}{2}} d(c^2 + s^2) = \tfrac{1}{2}\Big[_0^s 2(c^2 + s^2)^{\frac{1}{2}}, \text{ and finally}$$

$$y = \sqrt{s^2 + c^2} - c. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

Clearing of radicals and solving for c, we have

$$c = (s^2 - y^2) \div 2y. \quad . \quad . \quad . \quad . \quad . \quad (4)$$

Now T, the tension at any point, $= \sqrt{(qs)^2 + (qc)^2}$, and from (3) we obtain

$$T = q(y + c). \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4a)$$

Example.—A 40-foot chain weighs 240 lbs., and is so hung from two points at the same level that the deflection is 10 feet. Here, for $s = 20$ ft., $y = 10$; hence eq. (4) gives the *parameter*, $c = (400 - 100) \div 20 = 15$ feet. $q = 240 \div 40 = 6$ lbs. per foot. $\therefore$ the tension at the middle is $H_0 = qc = 6 \times 15 = 90$ lbs.; while the greatest tension is at either support and $= \sqrt{90^2 + 120^2} = 150$ lbs.

Knowing $c = 15$ feet, and putting $s = 20$ feet = half length of chain, we may compute the corresponding value of x from eq. (2); this will be the half-span. That is,

$$x = 15 \cdot \log_e 3 = 15 \times 2.303 \times 0.4771 = 16.48 \text{ ft.}$$

To derive s in terms of x, transform eq. (2) in the way that $n = \log_e m$ may be transformed into $e^n = m$, clear of radicals and solve for s, obtaining *

$$s = \tfrac{1}{2}c\Big[e^{\frac{x}{c}} - e^{-\frac{x}{c}}\Big]; \text{ or, } \quad s = c \cdot \sinh\left(\frac{x}{c}\right). \quad . \quad . \quad (5)$$

Again, eliminate s from (2) by substitution from (3), transform as above, clear of radials, and solve for $y + c$, whence

$$y + c = \tfrac{1}{2}c\Big[e^{\frac{x}{c}} + e^{-\frac{x}{c}}\Big]; \text{ or, } \quad y + c = c \cdot \cosh\left(\frac{x}{c}\right). \quad (6)$$

which is the equation of a catenary with axes as in Fig. 54. If the horizontal axis be taken a distance $= c$ below the vertex,

* sinh and cosh denote "*hyperbolic*" sine and cosine; see table, appendix.

the new ordinate $z=y+c$, while x remains the same; the last equation is simplified. See figure below.

If the span and length of chain are given, or if the span and deflection are given, c can be determined from (5) or (6) only by successive assumptions and approximations.

48a. Catenary (Chain or Cable) with Supports at Different Levels.—Given the span k, the difference of elevation d of the two supports, and the whole length of chain, l; it is required to find x' and y' (see Fig. 54*a*) and thus determine the position of the vertex, or lowest point, O, of the catenary. By applying the equations of p. 47 to parts $A'O$ and $B'O$, in turn, and combining, we may finally deduce (see p. 179 of Rankine's Applied Mechanics)



FIG. 54*a*.

$$\sqrt{l^2-d^2}=c\left[e^{\frac{k}{2c}}-e^{-\frac{k}{2c}}\right]; \quad \text{i.e.,} \quad \sqrt{l^2-d^2}=2c\cdot\sinh\left(\frac{k}{2c}\right). \quad . \quad (7)$$

and also the relation $$x'-x''=c\cdot\log_e\left[\frac{l+d}{l-d}\right]. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (8)$$

From (7) we find the "*parameter*," c, by trial; then the value of $x'-x''$ from (8); whence, finally, we obtain x' and x'' separately (since $x'+x''=k$). With x' known y' is found from (6); i.e.,

$$y'+c=\tfrac{1}{2}c\left[e^{\frac{x'}{c}}+e^{-\frac{x'}{c}}\right]; \quad \text{or,} \quad y'+c=c\cdot\cosh\left(\frac{x'}{c}\right). \quad . \quad . \quad . \quad (9)$$

Thus the position of the vertex is located. The greatest tension will be at the highest point A', viz., $T_{A'}=q(y'+c)$. . . . . (10)

[The expression $\frac{1}{2}[e^u-e^{-u}]$ is called the "*hyperbolic sine*" of the number u, or sinh (u); and $\frac{1}{2}[e^u+e^{-u}]$ the "*hyperbolic cosine*" of u, or cosh (u); e being the Naperian base 2.71828 . . . Tables of sinh u and cosh u will be found in the appendix.]

Example.—A chain 100 ft. long is supported at two points 80 ft. apart horizontally and 30 ft. vertically; find the position of its lowest point. That is, (Fig. 54*a*) given $l=100$ ft., $k=80$ ft., $d=30$ ft.

Solution.—$\sqrt{l^2-d^2}=\sqrt{9100}=95.4$ ft., the left-hand member of (7). Assuming $c=20$ ft. as a first trial, we find $k\div 2c=2.00$ and sinh (2.00) $=3.6269$, so that $2c$ sinh (2.00) is 145.176, which is much larger than 95.4. Next, with c assumed as 40, 39, and 38.3 ft., we find $2c$ sinh $(k\div 2c)$ to be $2\times 40\times 1.1745=93.96$; $2\times 39\times 1.2153=94.8$; and $2\times 38.3\times 1.2444=95.3$, respectively; and hence conclude that $c=38.2$ ft. will satisfy eq. (7) with sufficient accuracy. Eq. (8) now becomes

$$x'-x''=38.2\times 2.303\times 0.2689=23.66 \text{ ft.};$$

and finally we obtain $x'=51.83$ and $x''=28.17$ ft. From eq. (9) we now have $y'+38.2=38.2\times 2.0713=79.10$ ft. and $\therefore\ y'=40.9$ ft. With $q=1.5$ lbs. per foot, the tension at $A'=1.5\times 79.1=118.6$ lbs.

PART II.—KINETICS.

CHAPTER I.

RECTILINEAR MOTION OF A MATERIAL POINT.

49. Uniform Motion implies that the moving point passes over equal distances in equal times; **variable motion**, that unequal distances are passed over in equal times. In uniform motion the distance passed over in a unit of time, as one second, is called the **velocity** ($= v$), which may also be obtained by dividing the length of *any portion* ($= s$) of the path by the time ($= t$) taken to describe that portion, however small or great; in variable motion, however, the velocity varies from point to point, its value at any point being expressed as the quotient of ds (an infinitely small distance containing the given point) by dt (the infinitely small portion of time in which ds is described).

49*a*. By **acceleration** is meant the rate at which the velocity of a variable motion is changing at any point, and may be a *uniform acceleration*, in which case it equals the total change of velocity between any two points, however far apart, divided by the time of passage; or a *variable acceleration*, having a different value at every point, this value then being obtained by dividing the velocity-increment, dv, or gain of velocity in passing from the given point to one infinitely near to it, by dt, the time occupied in acquiring the gain.* (Acceleration must be understood in an algebraic sense, a negative acceleration implying a decreasing velocity, or else that the velocity in a negative direction is increasing.) The foregoing applies to motion in a path or line of any form whatever, the distances mentioned being portions of the path, and therefore measured along the path. (See p. 43 in the "Notes," etc.

* See addendum on p. 836.

50. Rectilinear Motion, or motion in a straight line.—The general relations of the quantities involved may be thus stated (see Fig. 55): Let v = velocity of the body at any instant; then dv = gain of velocity in an instant of time dt. Let t = time elapsed since the body left a given fixed point, which will be taken as an origin, O. Let s = distance (+ or −) of the body, at any instant, from the origin O; then ds = distance traversed in a time dt. Let p = acceleration = *rate at which v is increasing* at any instant. All these may be variable; and t is taken as the **independent variable**, i.e., time is conceived to elapse by *equal* small increments, each $= dt$; hence two consecutive ds's will not in general be equal, their difference being called d^2s. Evidently d^2t is = zero, i.e., dt is constant.

FIG. 55.

Since $\frac{1}{dt}$ = number of instants in one second, the velocity at any instant (i.e., the distance which *would* be described *at that rate* in one second) is $v = ds \cdot \frac{1}{dt}$; $\therefore v = \frac{ds}{dt}$ . . . . . (I.)

Similarly, $p = dv \cdot \frac{1}{dt}$, and $\left(\text{since } dv = d\left(\frac{ds}{dt}\right) = \frac{d^2s}{dt}\right)$.

$$\therefore p = \frac{dv}{dt} = \frac{d^2s}{dt^2} \quad . \quad . \quad . \quad . \quad . \quad . \quad \text{(II.)}$$

Eliminating dt, we have also $vdv = pds$. . . . . (III.)

These are the fundamental differential formulæ of rectilinear motion (for curvilinear motion we have these and some in addition) as far as kinematics, i.e., as far as space and time, is concerned. The consideration of the mass of the material point and the forces acting upon it will give still another relation (see § 55).

Example.—If we have given $s = [6t^3 + 3t^2 + 2t]$ *ft.*, for a certain motion, then the velocity, v, at any time, $= ds \div dt$, $= [18t + 6t + 2]$ *ft. per sec.*; and the acceleration, p, $= dv \div dt$, $= [36t + 6]$ *ft. per sec. per sec.*

51. Rectilinear Motion due to Gravity.—If a material point fall freely in vacuo, no initial direction other than vertical having been given to its motion, many experiments have

shown that this is a uniformly accelerated rectilinear motion in a vertical line having an acceleration (called the *acceleration of gravity*) equal to 32.2 feet per square second,* or 9.81 metres per square second; i.e., the velocity increases at this constant rate in a downward direction, or decreases in an upward direction.

[NOTE.—By "square second" it is meant to lay stress on the fact that an acceleration (being $= d^2s \div dt^2$) is in quality equal to one dimension of length divided by two dimensions of time. E.g., if instead of using the foot and second as units of space and time we use the foot and the minute, g will $= 32.2 \times 3600$; whereas a velocity of say six feet per second would $= 6 \times 60$ feet per minute. The value of $g = 32.2$ implies the units foot and second, and is sufficiently exact for practical purposes.]

52. Free Fall in Vacuo.—Fig. 56. Let the body start at O with an initial downward velocity $= c$. The acceleration is constant and $= +g$. Reckoning both time and distance (+ downwards) from O, required the values of the variables s and v after any time t. From eq. (II.), § 50, we have $+g = dv \div dt$; $\therefore dv = gdt$, in which the two variables are separated.



FIG. 56.

Hence $\int_c^v dv = g\int_0^t dt$; i.e., $\Big[_c^v v = g\Big[_0^t t$; or $v - c = gt - 0$; and finally, $v = c + gt$. . . . . (1)

(Notice the correspondence of the limits in the foregoing operation; when $t = 0$, $v = +c$.)

From eq. (I.), § 50, $v = ds \div dt$; $\therefore$ substituting from (1), $ds = (c + gt)dt$, in which the two variables s and t are separated.

$$\therefore \int_0^s ds = c\int_0^t dt + g\int_0^t tdt; \text{ i.e., } \Big[_0^s s = c\Big[_0^t t + g\Big[_0^t \frac{t^2}{2},$$

or
$$s = ct + \tfrac{1}{2}gt^2. \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

Again, eq. (III.), § 50, $vdv = gds$, in which the variables v and s are already separated.

$$\therefore \int_c^v vdv = g\int_0^s ds; \text{ or } \Big[_c^v \tfrac{1}{2}v^2 = g\Big[_0^s s; \text{ i.e., } \tfrac{1}{2}(v^2 - c^2) = gs,$$

or
$$s = \frac{v^2 - c^2}{2g}. \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

* Or, 32.2 "feet per second per second."

If the initial velocity = zero, i.e., if the body falls from rest, eq. (3) gives $s = \frac{v^2}{2g}$ and $v = \sqrt{2gs}$. [From the frequent recurrence of these forms, especially in hydraulics, $\frac{v^2}{2g}$ is called the "height due to the velocity v," i.e., the vertical height through which the body must fall from rest to acquire the velocity v; while, conversely, $\sqrt{2gs}$ is called the velocity due to the height or "*head*" s.]

By eliminating g between (1) and (3), we may derive another formula between three variables, s, v, and t, viz.,

$$s = \tfrac{1}{2}(c + v)t. \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

Example.—A leaden ball occupies 4.6 seconds in falling from the eaves of a tall building to the sidewalk; initial velocity zero. Find the height fallen through, $= s'$. We have from eq. (2)

$$s' = 0 + \tfrac{1}{2}(32.2)(4.6)^2 = 341 \text{ ft.}$$

53. Upward Throw.—If the initial velocity were in an upward direction in Fig. 56 we might call it $-c$, and introduce it with a negative sign in equations (1) to (4), just derived; but for variety let us call the upward direction $+$, in which case an upward initial velocity would $= +c$, while the acceleration $= -g$, constant, as before. (The motion is supposed confined within such a small range that g does not sensibly vary.) Fig. 57. From $p = dv \div dt$ we have $dv = -gdt$ and

Fig. 57.

$$\int_c^v dv = -g\int_0^t dt; \therefore v - c = -gt; \text{ or } v = c - gt. \quad (1)a$$

From $v = ds \div dt$, $ds = cdt - gtdt$,

$$\text{i.e., } \int_0^s ds = c\int_0^t dt - g\int_0^t tdt; \text{ or } s = ct - \tfrac{1}{2}gt^2. \quad (2)a$$

$vdv = pds$ gives $\int_c^v vdv = -g\int_0^s ds$, whence

$$\tfrac{1}{2}(v^2 - c^2) = -gs, \text{ or finally, } s = \frac{c^2 - v^2}{2g}. \quad . \quad (3)a$$

And by eliminating g from (1)a and (3)a,

$$s = \tfrac{1}{2}(c + v)t. \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)a$$

The following is now easily verified from these equations: the body passes the origin again ($s = 0$) with a velocity $= -c$, after a lapse of time $= 2c \div g$. The body comes to rest (for

an instant) (put $v = 0$) after a time $= c \div g$, and at a distance $s = c^2 \div 2g$ ("height due to velocity c") from O. For $t > c \div g$, v is negative, showing a downward motion; for $t > 2c \div g$, s is negative, i.e., the body is below the starting-point while the rate of change of v is constant and $= -g$ at all points.

Example.—Let c be 40 ft./sec. Then in a time $= 40 \div 32.2$, $= 1.24$ sec., the body will reach its maximum height, $(40)^2 \div 2 \times 32.2 = 24.84$ ft. above the start. After 3 sec. the body will be found a distance $s_3 = 40 \times 3 - \frac{1}{2}(32.2)(3)^2 = -24.9$ ft. from the origin, i.e., *below* it.

54. Newton's Laws.—As showing the relations existing in general between the motion of a material point and the actions (forces) of other bodies upon it, experience furnishes the following three laws or statements as a basis for kinetics:

(1) A material point under no forces, or under balanced forces, remains in a state of rest or of uniform motion in a right line. (This property is often called *Inertia*.)

(2) If the forces acting on a material point are unbalanced, an acceleration of motion is produced, proportional to the resultant force and in its direction.

(3) Every action (force) of one body on another is always accompanied by an equal, opposite, and simultaneous reaction. (This was interpreted in § 3.)

As all bodies are made up of material points, the results obtained in Kinetics of a Material Point serve as a basis for the Kinetics of a Rigid Body, of Liquids, and of Gases.

55. Mass.—If a body is to continue moving in a right line, the resultant force P at all instants must be directed along that line (otherwise it would have a component deflecting the body from its straight course). (See addendum on p. 835.)

In accordance with Newton's second law, denoting by p the acceleration produced by the resultant force (G being the body's weight), we must have the proportion $P : G :: p : g$; i.e.,

$$P = \frac{G}{g} \cdot p \ldots\ldots, \quad \text{or } P = Mp. \quad . \quad . \quad \text{(IV.)}$$

Eq. IV. and (I.), (II.), (III.) of § 50 are the fundamental equations of Dynamics. Since the quotient $G \div g$ is invaria-

ble, wherever the body be moved on the earth's surface (G and g changing in the same ratio), it will be used as the measure of the mass M or quantity of matter in the body. In this way it will frequently happen that the quantities G and g will appear in problems where the weight of the body, i.e., the force of the earth's attraction upon it, and the acceleration of gravity have no direct connection with the circumstances. No name will be given to the unit of mass, it being always understood that the fraction $G \div g$ will be put for M before any numerical substitution is made. From (IV.) we have, in words,

$$\left\{\begin{array}{ll} & \textit{accelerating force} = \textit{mass} \times \textit{acceleration;} \\ \text{also,} & \textit{acceleration} = \textit{accelerating force} \div \textit{mass.} \end{array}\right.$$

56. Uniformly Accelerated Motion.—If the resultant force is constant as time elapses, the acceleration must be constant (from eq. (IV.), since of course M is constant) and $= P \div M$. The motion therefore will be uniformly accelerated, and we have only to substitute $+ p_1$, (*constant*), for g in eqs. (1) to (4) of § 52 for the equations of this motion, the initial velocity being $= c$ (in the line of the force).

$$v = c + p_1 t \quad . \quad . \quad . \quad (1); \qquad s = ct + \tfrac{1}{2} p_1 t^2; \quad . \quad . \quad . \quad (2)$$

$$s = \frac{(v^2 - c^2)}{2p_1}; \quad . \quad . \quad . \quad (3), \quad \text{and } s = \tfrac{1}{2}(c + v)t \quad . \quad . \quad . \quad (4)$$

If the force is in a negative direction, the acceleration will be negative, and may be called a *retardation;* the initial velocity should be made negative if its direction requires it.

57. Examples of Unif. Acc. Motion.—*Example* 1. Fig. 58. A small block whose weight is $\frac{1}{2}$ lb. has already described a distance $Ao = 48$ inches over a smooth portion of a horizontal table in two seconds; at O it encounters a rough portion, and a consequent constant friction of 2 oz. Required the distance described beyond O, and the time occupied in coming to rest. Since we shall use 32.2 for g, times must be in seconds, and distances in feet; as to the unit



FIG. 58.

f force, as that is still arbitrary, say ounces. Since AO was smooth, it must have been described with a uniform motion (the resistance of the air being neglected); hence with a velocity = 4 ft. ÷ 2 sec. = 2 ft. per sec. The initial velocity for the retarded motion, then, is $c = +2$ at O. At any point beyond O the acceleration = force ÷ mass = (− 2 oz.) ÷ (8 oz. ÷ 32.2) = − 8.05 ft. per square second, i.e., $p = -8.05$ = constant; hence the motion is uniformly accelerated (retarded here), and we may use the formulæ of § 56 with $c = +2$, $p_1 = -8.05$. At the end of the motion v must be zero, and the corresponding values of s and t may be found by putting $v = 0$ in equations (3) and (1), and solving for s and t respectively: thus from (3), $s = \frac{1}{2}(-4) \div (-8.05)$, i.e., $s = 0.248+$, which must be feet; while from (1), $t = (-2) \div (-8.05) = 0.248+$, which must be seconds.

Example 2. (Algebraic.)—Fig. 59. The two masses $M_1 = G_1 \div g$ and $M = G \div g$ are connected by a flexible, inextensible cord. Table smooth. Required the acceleration common to the two rectilinear motions, and the tension in the string S,



FIG. 59.



FIG. 60.

there being no friction under G_1, none at the pulley, and *no mass* in the latter or in the cord. At any instant of the motion consider G_1 free (Fig. 60), N being the pressure of the table against G_1. Since the motion is in a horizontal right line Σ(vert. compons.) = 0, i.e., $N - G_1 = 0$, which determines N. S, the only horizontal force (and resultant of all the forces) = $M_1 p$, i.e.,

$$S = G_1 p \div g. \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

At the same instant of the motion consider G free (Fig. 61); the tension in the cord is the same value as above = S. The accelerating force is $G - S$, and

$$\therefore = \text{mass} \times \text{acc.}, \text{ or } G - S = (G \div g)p. \quad . \quad (2)$$

FIG. 61.

From equations (1) and (2) we obtain $p = (Gq) \div (G + G_1) =$ a constant; hence each motion is *uniformly accelerated*, and we may employ equations (1) to (4) of § 56 to find the velocity and distance from the starting-points, at the end of any assigned time t, or *vice versâ*. The initial velocity must be known, and may be zero. Also, from (1) and (2) of this article,

$$S = (GG_1) \div (G + G_1) = \text{constant}.$$

Example 3.—A body of $2\frac{3}{4}$ (short) tons weight is acted on during $\frac{1}{2}$ minute by a constant force P. It had previously described $316\frac{2}{3}$ yards in 180 seconds under no force; and subsequently, under no force, describes 9900 inches in $\frac{1}{40}$ of an hour. Required the value of P. Ans. $P = 22.1$ lbs.

Example 4.—A body of 1 ton weight, having an initial velocity of 48 inches per second, is acted on for $\frac{1}{4}$ minute by a force of 400 avoirdupois ounces. Required the final velocity.

Ans. 10.037 ft. per sec.

Example 5.—Initial velocity, 60 feet per second; body weighs 0.30 of a ton. A resistance of $112\frac{1}{2}$ lbs. retards it for $\frac{2}{15}$ of a minute. Required the distance passed over during this time.

Ans. 286.8 feet.

Example 6.—Required the time in which a force of 600 avoirdupois ounces will increase the velocity of a body weighing $1\frac{1}{2}$ tons from 480 feet per minute to 240 inches per second.

Ans. 30 seconds.

Example 7.—What distance is passed over by a body of (0.6) tons weight during the overcoming of a constant resistance (friction), if its velocity, initially 144 inches per sec., is reduced to zero in 8 seconds. Required, also, the friction.

Ans. 48 ft. and 55 lbs.

Example 8.—Before the action of a force (value required) a body of 11 tons had described uniformly 950 ft. in 12 minutes. Afterwards it describes 1650 feet uniformly in 180 seconds. The force acts 30 seconds. $P = ?$ Ans. $P = 178$ lbs.

58. Graphic Representations. Unif. Acc. Motion.—With the initial velocity = 0, the equations of § 56 become

$$v = p_1 t, \quad . \quad . \quad . \quad . \quad (1) \qquad s = \tfrac{1}{2} p_1 t^2, \quad . \quad . \quad . \quad . \quad . \quad (2)$$

$$s = v^2 \div 2p_1, \quad . \quad . \quad (3) \quad \text{and} \quad s = \tfrac{1}{2} vt. \quad . \quad . \quad . \quad . \quad . \quad (4)$$

Eqs. (1). (2), and (3) contain each two variables, which may graphically be laid off to scale as co-ordinates and thus give a curve corresponding to the equation. Thus, Fig. 62, in (I.), we



Fig. 62.

have a right line representing eq. (I.); in (II.), a parabola with axis parallel to s, and vertex at the origin for eq. (2); also a parabola similarly situated for eq. (3). Eq. (4) contains three variables, s, v, and t. This relation can be shown in (I.), s being represented by the *area* of the shaded triangle $= \frac{1}{2}vt$. (II.) and (III.) have this advantage, that the axis OS may be made the actual path of the body. [Let the student determine how the origin shall be moved in each case to meet the supposition of an initial velocity $= +c$ or $-c$.] (See Notes, p. 120.)

59. Variably Accelerated Motions.—We here restate the equations (differential)

$$v = \frac{ds}{dt} \; . \; . \; (\text{I.}); \quad p = \frac{dv}{dt} = \frac{d^2s}{dt^2} \; . \; . \; (\text{II.}); \quad vdv = pds \; . \; . \; (\text{III.});$$

and resultant force

$$= P = Mp, \quad . \quad . \quad . \quad . \quad . \quad . \quad (\text{IV.});$$

which are the only ones for *general use* in rectilinear motion and involve the *five variables*, s, t, v, p, and P.

Problem 1.—In pulling a mass M along a smooth, horizontal table, by a horizontal cord, the tension is so varied that $s = 4t^3$ (*not a homogeneous equation;* the units are, say, the foot and second). Required by what law the tension varies.

From (I.) $v = \frac{ds}{dt} = \frac{d(4t^3)}{dt} = 12t^2$; from (II.), $p = \frac{d(12t^2)}{dt} = 24t$; and (IV.) the tension $= P = Mp = 24Mt$, i.e., varies directly as the time.

PROBLEM 2. "Harmonic Motion," Fig. 63.—A small block



FIG. 63

on a smooth horizontal table is attached to two horizontal elastic cords (and they to pegs) in such a way that when the block is at O, each cord is straight but not tense; in any other position, as m, one cord is tense, the other slack. The cords are alike in every respect, and, as with springs, the tension varies directly with the elongation ($= s$ in figure). If for an elongation s_1 the tension is T_1, then for any elongation s it is $T = T_1 s \div s_1$. If the block be given an initial velocity $= c$ at O, it begins to execute an oscillatory motion on both sides of O; m is any point of its motion. The tension T is the accelerating force; *variable* and always pointing toward O. The acceleration at any point m, then, is $p = -(T \div M) = -(T_1 s \div Ms_1)$, which for brevity put $p = -as$, a being a constant. Required the equations of motion, the initial velocity being $= +c$, at O. From eq. (III.)

$$vdv = -asds\,; \quad \therefore \int_c^v vdv = -a\int_0^s sds,$$

$$\text{i.e., } \tfrac{1}{2}(v^2 - c^2) = -\tfrac{1}{2}as^2\,; \quad \text{or, } v^2 = c^2 - as^2. \quad . \quad (1)$$

From (I.), $dt = ds \div v$; hence from (1), $\left.\right\} \int_0^t dt = \int_0^s [ds \div \sqrt{c^2 - as^2}]$; or,

$$t = \frac{1}{\sqrt{a}}\int_0^s \frac{d[s\sqrt{a} \div c]}{\sqrt{1 - (s\sqrt{a} \div c)^2}} = \frac{1}{\sqrt{a}}\left[\sin^{-1}\left(\frac{s\sqrt{a}}{c}\right)\right]_0^s$$

$$= \frac{1}{\sqrt{a}}\sin^{-1}\left(\frac{s\sqrt{a}}{c}\right). \quad . \quad . \quad . \quad . \quad . \quad (2)$$

Inverting (2), we have $s = (c \div \sqrt{a}) \sin (t\sqrt{a})$, . . . (3)

Again, by differentiating (3), see (I.), $v = c \cos (t\sqrt{a})$ (4)

Differentiating (4), see (II.), $p = -c\sqrt{a} \sin (t\sqrt{a})$. . . (5)

These are the relations required, each between *two* of the four variables, s, t, v, and p; but the peculiar property of the motion is made apparent by inquiring the time of passing from O to a state of rest; i.e., put $v = 0$ in equation (4), we obtain $t = \frac{1}{2}\pi \div \sqrt{a}$, or $\frac{3}{2}\pi \div \sqrt{a}$, or $\frac{5}{2}\pi \div \sqrt{a}$, and so on, while the corresponding values of s (from equation (3)), are $+(c \div \sqrt{a})$, $-(c \div \sqrt{a})$, $+(c \div \sqrt{a})$, and so on. This shows that the body vibrates equally on both sides of O in a cycle or period whose duration $= 2\pi \div \sqrt{a}$, and is *independent of the initial velocity given it at O*. Each time it passes O the velocity is either $+c$, or $-c$, the acceleration $= 0$, and the time since the start is $= n\pi \div \sqrt{a}$, in which n is any whole number. At the extreme point $p = \mp c\sqrt{a}$, from eq. (5). If then a different amplitude be given to the oscillation by changing c, the duration of the period is still the same, i.e., the vibration is *isochronal*.* The motion of an ordinary pendulum is nearly, that of a cycloidal pendulum exactly, harmonic.

If the crank-pin of a reciprocating engine moved uniformly in its circular path, the piston would have a harmonic motion if the connecting-rod were infinitely long, or if the design in



FIG. 64.

Fig. 64 were used. (Let the student prove this from eq. (3).) Let $2r$ = length of stroke, and c = the uniform velocity of the crank-pin, and M = mass of the piston and rod AB. Then the velocity of M at mid-stroke must $= c$, at the dead-points, zero; its acceleration at mid-stroke zero; at the dead-points the acc. $= c\sqrt{a}$, and $s = r = c \div \sqrt{a}$ (from eq. (3)); $\therefore \sqrt{a} = c \div r$, and the acc. at a dead point (the maximum acc.)

* See illustrations and example on pp. 47, 48, of the "*Notes.*"

$= c^2 \div r$. Hence on account of the acceleration (or retardation) of M in the neighborhood of a dead-point a pressure will be exerted on the crank-pin, equal to mass $\times$ acc. $= Mc^2 \div r$ at those points, independently of the force transmitted due to steam-pressure on the piston-head, and makes the resultant pressure on the pin at C smaller, and at D larger than it would be if the "*inertia*" of the piston and rod were not thus taken into account. We may prove this also by the free-body method, considering *AB free* immediately after passing the dead-point



Fig. 65.

C, neglecting all friction. See Fig. 65. The forces acting are: G, the weight; N, the pressures of the guides; P, the known effective steam-pressure on piston-head; and P', the unknown pressure of crank-pin on side of slot. There is no change of motion vertically; $\therefore N' + N - G = 0$, and the resultant force is $P - P'$ = mass $\times$ accel. $= Mc^2 \div r$, hence $P' = P - Mc^2 \div r$. Similarly at the other dead-point we would obtain $P' = P + Mc^2 \div r$. In high-speed engines with heavy pistons, etc., $Mc^2 \div r$ is no small item. [The upper half-revol., alone, is here considered.] (See example on p. 68, "*Notes.*")

Problem 3.—Supposing the earth at rest and *the resistance of the air to be null*, a body is given an initial upward vertical velocity $= c$. Required the velocity at any distance s from the centre of the earth, whose attraction varies inversely as the square of the distance s.



Fig. 66.

See Fig. 66.—The attraction on the body at the surface of the earth where $s = r$, the radius, is its weight G; at any point m it will be $P = G(r^2 \div s^2)$,* while its mass $= G \div g$.

Hence the acceleration at $m = p = (-P) \div M = -g(r^2 \div s^2)$. Take equation III., $vdv = pds$, and we have

$$vdv = -gr^2 s^{-2} ds; \quad \therefore$$

$$\int_c^v vdv = -gr^2 \int_r^s s^{-2} ds; \text{ or, } \left[\frac{1}{2}v^2\right]_c^v = -gr^2 \left[-\frac{1}{s}\right]_r^s,$$

$$\text{i.e., } \tfrac{1}{2}(v^2 - c^2) = -gr^2 \left(\frac{1}{r} - \frac{1}{s}\right). \quad . \quad . \quad . \quad (1)$$

* That is, the force of attraction, (P, lbs.) at any distance, s, from O is to the force at the surface (viz., G lbs.) as r^2 is to s^2.

Evidently v decreases, as it should. Now inquire how small a value c may have that the body shall *never return*; i.e., that v shall not $= 0$ until $s = \infty$. Put $v = 0$ and $s = \infty$ in (1) and solve for c; and we have

$$c = \sqrt{2gr} = \sqrt{2 \times 32.2 \times 21000000},$$

= about 36800 ft. per sec. or nearly 7 miles per sec. Conversely, if a body be allowed to fall, from rest, toward the earth, the velocity with which it would strike the surface would be less than seven miles per second through whatever distance it may have fallen.

If a body were allowed to fall through a straight opening in the earth passing through the centre, the motion would be harmonic, since the attraction and consequent acceleration now vary directly with the distance from the centre. See Prob. 2. This supposes the earth homogeneous.

Problem 4.—Steam working expansively and raising a weight. Fig. 67.—A piston works without friction in a vertical cylinder. Let S = total steam-pressure on the underside of the piston; the weight G, of the mass $G \div g$ (which includes the piston itself) and an atmospheric pressure $= A$, constitute a constant back-pressure. Through the portion $OB = s_1$, of the stroke, S is constant $= S_1$, while beyond B, boiler communication being "cut off," S diminishes with Boyle's law, i.e., in this case, for any point above B, we have, neglecting the "clearance", F being the cross-section of the cylinder,*



Fig. 67.

$$S : S_1 :: Fs_1 : Fs; \quad \text{or} \quad S = S_1 s_1 \div s.$$

(Which gives S as a function of s at any point *above* B.)

Full length of stroke $= ON = s_n$. Given, then, the forces S_1 and A, the distances s_1 and s_n, and the velocities at O and at N both $= 0$ (i.e., the mass $M = G \div g$ is to start from rest at O, and to *come to rest at* N), required the proper weight G to

* See p. 627 for meaning of "clearance."

fulfil these conditions, S varying as already stated. The acceleration at any point will be

$$p = [S - A - G] \div M. \quad . \quad . \quad . \quad . \quad (1)$$

Hence (eq. III.) $Mvdv = [S - A - G]ds$, and $\therefore$ for the whole stroke

$$M\int_0^0 vdv = \int_0^N [S - A - G]ds; \text{ i.e.,}$$

$$0 = S_1\int_0^{s_1} ds + S_1s_1\int_{s_1}^{s_n}\frac{ds}{s} - A\int_0^{s_n} ds - G\int_0^{s_n} ds,$$

or
$$S_1s_1\left[1 + \log_e\frac{s_n}{s_1}\right] = As_n + Gs_n. \quad . \quad . \quad . \quad (2)$$

Since $S = S_1 =$ constant, from O to B, and variable, $= S_1s_1 \div s$, from B to N, we have had to write the summation $\int_0^N Sds$ in two parts.

From (2), G becomes known, and $\therefore$ M also $(= G \div g)$.

Required, further, the time occupied in this upward stroke. From O to B (the point of cut-off) the motion is uniformly accelerated, since p is constant (S being $= S_1$ in eq. (1)), with the initial velocity zero; hence, from eq. (3), § 56, the velocity at $B = v_1 = \sqrt{2\,[S_1 - A - G]s_1 \div M}$ is known; $\therefore$ the time $t_1 = 2s_1 \div v_1$ becomes known (eq. (4), § 56) of describing OB. At any point beyond B the velocity v may be obtained thus: From (III.) $vdv = pds$, and eq. (1) we have, summing between B and any point above,

$$M\int_{v_1}^{v} vdv = S_1s_1\int_{s_1}^{s}\frac{ds}{s} - (A + G)\int_{s_1}^{s} ds; \text{ i.e.,}$$

$$\frac{G}{g}\frac{(v^2 - v_1^2)}{2} = S_1s_1\log_e\frac{s}{s_1} - (A + G)(s - s_1).$$

This gives the relation between the two variables v and s anywhere between B and N; if we solve for v and insert its value in $dt = ds \div v$, we shall have $dt =$ a function of s and ds, which is not integrable. Hence we may resort to approxi-

mate methods for the time from B to N. Divide the space BN into an uneven number of equal parts, say five; the distances of the points of division from O will be s_1, s_2, s_3, s_4, s_5, and s_n. For these values of s compute (from above equation) v_1 (already known), v_2, v_3, v_4, v_5, and v_n (known to be zero). To the first four spaces apply Simpson's Rule,* and we have the time from B to the end of s_5,

$$\left[{}_1^5 t = \int_1^5 \frac{ds}{v}; \text{ approx.} = \frac{s_5 - s_1}{12}\left[\frac{1}{v_1} + \frac{4}{v_2} + \frac{2}{v_3} + \frac{4}{v_4} + \frac{1}{v_5}\right];\right.$$

while regarding the motion from 5 to N as uniformly retarded (approximately) with initial velocity $= v_5$ and the final = zero, we have (eq. (4), § 56),

$$\left[{}_5^N t = 2(s_n - s_5) \div v_5.\right.$$

By adding the three times now found we have the whole time of ascent. In Fig. 67 the dotted curve on the left shows by horizontal ordinates the variation in the velocity as the distance s increases; similarly on the right are ordinates showing the variation of S. The point E, where the velocity is a maximum $= v_m$, may be found by putting $p = 0$, i.e., for $S = A + G$, the accelerating force being $= 0$, see eq. (1). Below E the accelerating force, and consequently the acceleration, is positive; above, negative (i.e., the back-pressure exceeds the steam-pressure). The horizontal ordinates between the line $HE'KL$ and the right line RT are proportional to the accelerating force. If by condensation of the steam a vacuum is produced below the piston on its arrival at N, the accelerating force is downward and $= A + G$. [Let the student determine how the detail of this problem would be changed, if the cylinder were horizontal instead of vertical.]

60. Direct Central Impact.—Suppose two masses M_1 and M_2 to be moving in the same right line so that their distance apart continually diminishes, and that when the collision or impact takes place the line of action of the mutual pressure coincides with the line joining their centres of gravity, or centres of

* See p. 13 of the "*Notes and Examples.*"

mass, as they may be called in this connection. This is called a direct central impact, and the motion of each mass is variably accelerated and rectilinear during their contact, the only force being the pressure of the other body. The whole mass of each body will be considered concentrated in the centre of mass, on the supposition that all its particles undergo simultaneously the same change of motion in parallel directions. (This is not strictly true; the effect of the pressure being gradually felt, and transmitted in vibrations. These vibrations endure to some extent after the impact.) When the centres of mass cease to approach each other the pressure between the bodies is a maximum and the bodies have a common velocity; after this, if any capacity for restitution of form (elasticity) exists in either body, the pressure still continues, but diminishes in value gradually to zero, when contact ceases and the bodies separate with different velocities. Reckoning the time from the first instant of contact, let t' = duration of the first period, just mentioned; t'' that of the first + the second (restitution). Fig. 68. Let M_1 and M_2 be the masses, and at *any instant during the contact* let v_1 and v_2 be simultaneous values of the velocities of the mass-centres respectively (reckoning velocities positive toward the right), and P the pressure (variable). At any instant the acceleration of M_1 is $p_1 = -(P \div M_1)$, while at the same instant that of M_2 is $p_2 = +(P \div M_2)$; M_1 being retarded, M_2 accelerated, in velocity. Hence (eq. II., $p = dv \div dt$) we have



Fig. 68.

$$M_1 dv_1 = -Pdt; \quad \text{and} \quad M_2 dv_2 = +Pdt. \quad . \quad . \quad (1)$$

Summing all similar terms for the first period of the impact, we have (calling the velocities before impact c_1 and c_2, and the common velocity at instant of maximum pressure C)

$$M_1 \int_{c_1}^{C} dv_1 = -\int_0^{t'} Pdt, \text{ i.e., } M_1(C - c_1) = -\int_0^{t'} Pdt; \quad (2)$$

$$M_2 \int_{c_2}^{C} dv_2 = +\int_0^{t'} Pdt, \text{ i.e., } M_2(C - c_2) = +\int_0^{t'} Pdt. \quad . \quad (3)$$

The two integrals* are identical, numerically, term by term, since the pressure which at any instant accelerates M_2 is numerically equal to that which retards M_1; hence, though we do not know how P varies with the time, we can eliminate the definite integral between (2) and (3) and solve for C. If the impact is *inelastic* (i.e., no power of restitution in either body, either on account of their total inelasticity or damaging effect of the pressure at the surfaces of contact), they continue to move with this common velocity, which is therefore their final velocity. Solving, we have

$$C = \frac{M_1 c_1 + M_2 c_2}{M_1 + M_2}. \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

Next, supposing that the impact is *partially elastic*, that the bodies are of the same material, and that the summation $\int_{t'}^{t''} P dt$ for the second period of the impact bears a ratio, e, to that $\int_0^{t'} P dt$, already used, a ratio peculiar to the material, if the impact is not too severe, we have, summing equations (1) for the second period (letting V_1 and V_2 = the velocities after impact),

$$M_1 \int_C^{V_1} dv_1 = -\int_{t'}^{t''} P dt, \text{ i.e., } M_1(V_1 - C) = -e\int_0^{t'} P dt; \quad (5)$$

$$M_2 \int_C^{V_2} dv_2 = +\int_{t'}^{t''} P dt, \text{ i.e., } M_2(V_2 - C) = +e\int_0^{t'} P dt. \quad (6)$$

e is called the coefficient of restitution.

Having determined the value of $\int_0^t P dt$ from (2) and (3) in terms of the masses and initial velocities, substitute it and that of C, from (4), in (5), and we have (for the final velocities)

$$V_1 = [M_1 c_1 + M_2 c_2 - e M_2(c_1 - c_2)] \div [M_1 + M_2]; \quad . \quad (7)$$

and similarly

$$V_2 = [M_1 c_1 + M_2 c_2 + e M_1(c_1 - c_2)] \div [M_1 + M_2]. \quad . \quad (8)$$

For $e = 0$, i.e., for *inelastic impact*, $V_1 = V_2 = C$ in eq. (4); for

* That is, the right-hand members of eqs. (2) and (3).

$e = 1$, or *elastic impact*, (7) and (8) become somewhat simplified.

To determine e experimentally, let a ball (M_1) of the substance fall upon a very large slab (M_2) of *the same substance*, noting both the height of fall h_1, and the height of rebound H_1. Considering M_2 as $= \infty$, with

$$c_1 = \sqrt{2gh_1},\ V_1 = -\sqrt{2gH_1}, \text{ and } c_2 = 0,$$

eq. (7) gives

$$-\sqrt{2gH_1} = -e\sqrt{2gh_1};\ \therefore e = \sqrt{H_1 \div h_1}.$$

Let the student prove the following from equations (2), (3), (5), and (6):

(*a*) For any direct central impact whatever,

$$M_1c_1 + M_2c_2 = M_1V_1 + M_2V_2.$$

[The product of a mass by its velocity being sometimes called its *momentum*, this result may be stated thus:

In any direct central impact the sum of the momenta before impact is equal to that after impact (or at any instant during impact). This principle is called the *Conservation of Momentum*. The present is only a particular case of a more general proposition.

It can be proved that C, eq. (4), is the velocity of the centre of gravity of the two masses before impact; the conservation of momentum, then, asserts that this velocity is unchanged by the impact, i.e., by the mutual actions of the two bodies.]

(*b*) The loss of velocity of M_1, and the gain of velocity of M_2, are twice as great when the impact is elastic as when inelastic.

(*c*) If $e = 1$, and $M_1 = M_2$, then $V_1 = +c_2$, and $V_2 = c_1$.

Example.—Let M_1 and M_2 be perfectly elastic, having weights $= 4$ and 5 lbs. respectively, and let $c_1 = 10$ ft. per sec. and $c_2 = -6$ ft. per sec. (i. e., before impact M_2 *is moving in a direction contrary to that of* M_1). By substituting in eqs. (7) and (8), with $e = 1$, $M_1 = 4 \div g$, and $M_2 = 5 \div g$, we have

$$V_1 = \frac{1}{9}\Big[4 \times 10 + 5 \times (-6) - 5\Big(10 - (-6)\Big)\Big] = -7.7 \text{ ft. per sec.}$$

$$V_2 = \frac{1}{9}\Big[4 \times 10 + 5 \times (-6) + 4\Big(10 - (-6)\Big)\Big] = +8.2 \text{ ft. per sec.}$$

as the velocities after impact. Notice their directions, as indicated by their signs

CHAPTER II.

"VIRTUAL VELOCITIES."

61. Definitions.—If a material point is moving in a direction not coincident with that of the resultant force acting (as in curvilinear motion in the next chapter), and any element of its path, ds, projected upon this force;* the length of this projection, du, Fig. 69, is called the "VIRTUAL VELOCITY" of the force, since $du \div dt$ may be considered the velocity of the force at this instant, just as $ds \div dt$ is that of the point. The product of the force by its du will be called its *virtual moment*, reckoned $+$ or $-$ according as the direction from O to D is the same as that of the force or opposite.



FIG. 69.

62. Prop. I.—*The virtual moment of a force equals the algebraic sum of those of its components.* Fig. 70. Take the direction of ds as an axis X; let P_1 and P_2 be components of P; α_1, α_2, and α their angles with X. Then (§ 16) $P \cos \alpha = P_1 \cos \alpha_1 + P_2 \cos \alpha_2$. Hence $P(ds \cos \alpha) = P_1(ds \cos \alpha_1) + P_2(ds \cos \alpha_2)$. But $ds \cos \alpha$ = the projection of ds upon P, i.e., $= du$; $ds \cos \alpha_1 = du_1$, etc.; $\therefore Pdu = P_1 du_1 + P_2 du_2$. If in Fig. 70 α_1 were $> 90°$, evidently we would have $Pdu = -P_1 du_1 + P_2 du_2$, i.e., $P_1 du_1$ would then be negative, and OD_1 would fall behind O; hence the definition of $+$ and $-$ in § 61. For any number of components the proof would be similar, and is equally applicable whether they are in one plane or not.



FIG. 70.

63. Prop. II.—*The sum of the virtual moments equals zero, for concurrent forces in equilibrium.*

* We should rather say "projected on the line of action of the force;" but the phrase used may be allowed, for brevity.

(If the forces are balanced, the material point is moving in a straight line if moving at all.) The resultant force is zero. Hence, from § 62, $P_1du_1 + P_2du_2 + \text{etc.} = 0$, having proper regard to sign, i.e., $\Sigma(Pdu) = 0$.

64. Prop. III.—*The sum of the virtual moments equals zero for any small displacement or motion of a rigid body in equilibrium under non-concurrent forces in a plane; all points of the body moving parallel to this plane.* (Although the kinds of motion of a given rigid body which are consistent with balanced non-concurrent forces have not yet been investigated, we may imagine any slight motion for the sake of the algebraic relations between the different du's and forces.)



FIG. 71.

First, let the motion be a *translation*, all points of the body describing equal parallel lengths $= ds$. Take X parallel to ds; let α_1, etc., be the angles of the forces with X. Then (§ 35) $\Sigma(P\cos\alpha) = 0$; $\therefore ds\Sigma(P\cos\alpha) = 0$; but $ds\cos\alpha_1 = du_1$; $ds\cos\alpha_2 = du_2$; etc.; $\therefore \Sigma(Pdu) = 0$. Q. E. D.

Secondly, let the motion be a *rotation* through a small angle $d\theta$ in the plane of the forces about any point O in that plane, Fig. 72. With O as a pole let ρ_1 be the radius-vector of the point of application of P_1, and a_1 its lever-arm from O; similarly for the other forces. In the rotation each point of application describes a small arc, ds_1, ds_2, etc., proportional to ρ_1, ρ_2, etc., since $ds_1 = \rho_1 d\theta$, $ds_2 = \rho_2 d\theta$, etc. From § 36, $P_1a_1 + \text{etc.} = 0$; but from similar triangles $ds_1 : du_1 :: \rho_1 : a_1$; $\therefore a_1 = \rho_1 du_1 \div ds_1 = du_1 \div d\theta$; similarly $a_2 = du_2 \div d\theta$, etc.



FIG. 72.

Hence we must have $[P_1du_1 + P_2du_2 + \ldots] \div d\theta = 0$, i.e., $\Sigma(Pdu) = 0$. Q. E. D.

Now since any slight displacement or motion of a body may be conceived to be accomplished by a small translation followed by a rotation through a small angle, and since the fore-

going deals only with projections of paths, the proposition is established and is called the *Principle of Virtual Velocities.*

[A similar proof may be used for any slight motion whatever in space when a system of non-concurrent forces is balanced.] Evidently if the path (ds) of a point of application is perpendicular to the force, the virtual velocity (du), and consequently the virtual moment (Pdu) of the force are zero. Hence we may frequently make the displacement of such a character in a problem that one or more of the forces may be excluded from the summation of virtual moments.

65. Connecting-Rod by Virtual Velocities.—Let the effective steam-pressure P be the means, through the connecting-rod and crank (i.e., two links), of raising the weight G *very slowly;* neglect friction and the weight of the links themselves. Consider AB as *free* (see (*b*) in Fig. 73), BC also, at (*c*); let the



FIG. 73.

"small displacements" of both be *simultaneous* small portions of their ordinary motion in the apparatus. A has moved to A_1 through dx; B to B_1, through ds, a small arc; C has not moved. The forces acting on AB are P (steam-pressure), N (vertical reaction of guide), and N' and T (the tangential and normal components of the crank-pin pressure). Those on BC are N' and T (reversed), the weight G, and the oblique pressure of bearing P'. The motion being slow (or rather the acceleration being small), each of these two systems will be considered as balanced. Now put $\Sigma(Pdu) = 0$ for AB, and we have

$$Pdx + N \times 0 + N' \times 0 - Tds = 0. \quad . \quad . \quad (1)$$

For the simultaneous and corresponding motion of BC, $\Sigma(Pdu) = 0$ gives

$$N' \times 0 + Tds - Gdh + P' \times 0 = 0, \quad . \quad . \quad (2)$$

dh being the vertical projection of G's motion.

From (1) and (2) we have, easily, $Pdx - Gdh = 0$, . (3)



Fig. 74.

which is the same as we might have obtained by putting $\Sigma(Pdu) = 0$ *for the two links together, regarded collectively as a free body*, and describing a small portion of the motion they really have in the mechanism, viz., (Fig. 74,)

$$Pdx + N \times 0 - Gdh + P' \times 0 = 0. \quad . \quad . \quad (4)$$

We may therefore announce the—

66. Generality of the Principle of Virtual Velocities.—*If any mechanism of flexible inextensible cords, or of rigid bodies jointed together, or both, at rest, or in motion with very small accelerations, be considered free collectively* (*or any portion of it*), *and all the external forces put in; then* (*disregarding mutual frictions*) *for a small portion of its prescribed motion,* $\Sigma(Pdu)$ *must* $= 0$, *in which the* du, *or virtual velocity, of each force,* P, *is the projection of the path of the point of application upon the force* (the product, Pdu, being $+$ or $-$ according to § 61).

67. *Example.*—In the problem of § 65, having given the weight G, required the proper steam-pressure (effective) P to hold G in equilibrium, or to raise it uniformly, if already in motion, for a *given position of the links*. That is, Fig. 75, given a, r, c, α, and β, required the ratio $dh : dx$; for, from equation (3), § 65, $P = G(dh : dx)$. The projections of dx and ds upon AB will be equal, since $AB = A_1B_1$, and makes an (infinitely) small angle with A_1B_1, i.e., $dx \cos \alpha = ds \cos (\beta - \alpha)$. Also, $dh = (c : r)ds \sin \beta$.



Fig. 75.

Eliminating ds, we have,

$$\frac{dh}{dx} = \frac{c \sin \beta \cos \alpha}{r \cos (\beta - \alpha)}; \quad \therefore P = G \frac{c \sin \beta \cos \alpha}{r \cos (\beta - \alpha)}.$$

68. When the acceleration of the parts of the mechanism is not practically zero, $\Sigma(Pdu)$ will not $= 0$, but a function of the masses and velocities to be explained in the chapter on Work, Energy, and Power. If friction occurs at moving joints, enough "free bodies" should be considered that no free body extend beyond such a joint; it will be found that this friction cannot be eliminated in the way T and N' were, in § 65.

69. Additional Problems; to be solved by "virtual velocities." PROBLEM 1.—Find relations between the forces acting on a straight lever in equilibrium; also, on a bent lever.

PROBLEM 2.—When an ordinary copying-press is in equilibrium, find the relation between the force applied horizontally and tangentially at the circumference of the wheel, and the vertical resistance under the screw-shaft. See Fig. 75*a*.

Solution.—Considering free the rigid body consisting of the wheel and screw-shaft, let R be the resistance at the point of the shaft (pointing along the axis of the shaft), and P the required horizontal tangential force at edge of wheel. Let radius of wheel be r. Besides R and P there are also acting on this body certain pressures, or "supporting forces," consisting of the reactions of the collars, and reactions of the threads of nut against the threads of screw. Denote by s the "*pitch*" of the screw, i.e., the distance the shaft would advance for a full turn of the wheel. Then if we imagine the wheel to turn through a small angle $d\theta$, the corresponding advance, ds, of the shaft would be $\frac{s d\theta}{2\pi}$, from the proportion $s : ds :: 2\pi : d\theta$.

The path of the point of application of P is AB, a small portion of a helix, the projection of which on the line of P is $rd\theta$, while ds projects in its full length on the line of the force R. In the case of each of the other forces, however, the path of the point of application is *perpendicular* to the line of the force (which is normal to the rubbing surfaces, friction being disregarded). Hence, substituting in $\Sigma(Pdu) = 0$, we have

$$+P \,.\, rd\theta - R \,.\, ds + 0 + 0 = 0;$$

whence

$$P = \frac{ds}{rd\theta} \,.\, R = \frac{s}{2\pi r} \,.\, R.$$



FIG. 75*a*.

CHAPTER III.

CURVILINEAR MOTION OF A MATERIAL POINT.

[Motion in a plane, only, will be considered in this chapter.]

70. Parallelogram of Motions.—It is convenient to regard the curvilinear motion of a point in a plane as compounded, or made up, of two independent rectilinear motions parallel respectively to two co-ordinate axes X and Y, as may be explained thus: Fig. 76. Consider the drawing-board CD as fixed, and let the head of a T-square move from A toward B along the edge according to any law whatever, while a pencil moves from M toward Q along the blade. The result is a curved line on the board, whose form depends on the character of the two X and Y *component motions*, as they may be called. If in a time t_1 the T-square head has moved an X distance $= MN$, and the pencil simultaneously a Y distance $= MP$, by completing the parallelogram on these lines, we obtain R, the position of the point on the board at the end of the time t_1. Similarly, at the end of the time t_1' we find the point at R'.



Fig. 76.

71. Parallelogram of Velocities.—Let the X and Y motions be *uniform*, required the resulting motion. Fig. 77. Let c_x and c_y be the constant uniform X and Y velocities. Then in any time, t, we have $x = c_x t$ and $y = c_y t$; whence we have, eliminating t, $x \div y = c_x \div c_y =$ constant, i.e., x is proportional to y, i.e., the path is a straight line. Laying off $OA = c_x$, and $AB = c_y$, B is a point of the path, and OB is the distance described by the point in the first



Fig. 77.

second. Since by similar triangles $\overline{OR} : x :: \overline{OB} : c_x$, we have also $\overline{OR} = \overline{OB} \cdot t$; hence the resultant motion is uniform, and its velocity, $\overline{OB} = c$, *is the diagonal of the parallelogram formed on the two component velocities.*

Corollary.—If the resultant motion is curved, the direction and velocity of the motion at any point will be given by the diagonal formed on the component velocities at that instant. The direction of motion is, of course, a tangent to the curve.

72. Uniformly Accelerated X and Y Motions.—The *initial velocities of both being zero.* Required the resultant motion. Fig. 78. From § 56, eq. (2) (both c_x and c_y being = 0), we have $x = \frac{1}{2}p_x t^2$ and $y = \frac{1}{2}p_y t^2$, whence $x \div y = p_x \div p_y =$ constant, and the resultant motion is in a straight line. Conceive lines laid off from O on X and Y to represent p_x and p_y to scale, and form a parallelogram on them. From similar triangles (OR being the distance described in the resultant motion in any time t), $\overline{OR} : x :: \overline{OB} : p_x$; $\therefore \overline{OR} = \frac{1}{2}\overline{OB}t^2$. Hence, from the form of this last equation, the resultant motion is uniformly accelerated, and its acceleration is $\overline{OB} = p_1$, (on the same scale as p_x and p_y).



FIG. 78.

This might be called the parallelogram of accelerations, but is really a parallelogram of forces, if we consider that a free material point, initially at rest at O, and acted on simultaneously by constant forces P_x and P_y (so that $p_x = P_x \div M$ and $p_y = P_y \div M$), must begin a uniformly accelerated rectilinear motion in the direction of the resultant force, (*having no initial velocity* in any direction.)

73. In general, considering the point hitherto spoken of as a *free material point*, under the action of one or more forces, in view of the foregoing, and of Newton's second law, given the initial velocity in amount and direction, the starting-point, the initial amounts and directions of the acting forces and the

laws of their variation if they are not constant, we can resolve them into a single X and a single Y force at any instant, determine the X and Y motions independently, and afterwards the resultant motion.

Note.—The resultant force *is never in the direction of the tangent to the path* (except at a point of inflection). The relations which its amount and position at any instant bear to the velocity, rates of change of that velocity (i.e., accelerations), both as to amount and position, and the radius of curvature of the path, will now be treated (§ 74).

In Fig. 79, A, B, and C are three "consecutive" positions of the moving point, AB and BC being two short chords of the curve. When dt is taken smaller and smaller (position B remaining unchanged) and finally becomes zero, the points A and C merge into B and the chords AB and BC becomes tangents at B; and hence the results to be obtained *only apply to a single point, B.* But note that before dt becomes zero each equation [except (7)] is divided through by dt (or dt^2) and therefore the individual terms do not necessarily become zero also.

74. General Equations for the curvilinear motion of a material point in a plane.—The motion will be considered resulting from the composition of independent X and Y motions, X and Y being perpendicular to each other. Fig. 79. In two consecutive **equal** times (each $= dt$), let dx and $dx' =$ small spaces due to the X motion; and dy and $CK = dy'$, due to the Y motion. Then ds and ds' are two consecutive elements of the curvilinear motion. Prolong ds, making $BE = ds$; then $EF = d^2x$, $CF = d^2y$, and $CO = d^2s$ (EO being perpendicular to BE). Also draw CL perpendicular to BG and call CL d^2n. Call the velocity of the X motion v_x, its acceleration p_x; those of the Y motion, v_y and p_y. Then,



FIG. 79.

$$v_x = \frac{dx}{dt}; \quad v_y = \frac{dy}{dt}; \quad p_x = \frac{dv_x}{dt} = \frac{d^2x}{dt^2}; \quad \text{and } p_y = \frac{dv_y}{dt} = \frac{d^2y}{dt^2}.$$

For the velocity along the curve (i.e., tangent) $v = ds \div dt$, we shall have, since $ds^2 = dx^2 + dy^2$,

$$v^2 = \left(\frac{ds}{dt}\right)^2 = \left(\frac{dx}{dt}\right)^2 + \left(\frac{dy}{dt}\right)^2 = v_x^2 + v_y^2. \quad . \quad . \quad (1)$$

Hence v is the diagonal formed on v_x and v_y (as in § 71). Let p_t = the acceleration of v, i.e., the *tangential acceleration.* then $p_t = d^2s \div dt^2$, and, since d^2s = the sum of the projections of EF and CF on BC, i.e., $d^2s = d^2x \cos \alpha + d^2y \sin \alpha$, we have

$$\frac{d^2s}{dt^2} = \frac{d^2x}{dt^2} \cos \alpha + \frac{d^2y}{dt^2} \sin \alpha; \text{ i.e., } p_t = p_x \cos \alpha + p_y \sin \alpha. \quad (2)$$

By **Normal Acceleration** we mean the rate of change of the velocity in the direction of the normal. In describing the element $AB = ds$, no progress has been made in the direction of the normal BH i.e., there is *no velocity* in the direction of the normal; but in describing BC (on account of the new direction of path) the point has progressed a distance CL (call it d^2n) in the direction of the old normal BH (though none in that of the new normal CI). Hence, just as the tang. acc. $= \dfrac{ds' - ds}{dt^2} = \dfrac{d^2s}{dt^2}$, so the normal accel. $= \dfrac{CL - \text{zero}}{dt^2} = \dfrac{d^2n}{dt^2}$.

It now remains to express this normal acceleration ($= p_n$) in terms of the X and Y accelerations. From the figure, $\overline{CL} = \overline{CM} - ML$, i.e.,

$$d^2n = d^2y \cos \alpha - d^2x \sin \alpha \{\text{since } EF = d^2x\};$$

$$\therefore \frac{d^2n}{dt^2} = \frac{d^2y}{dt^2} \cos \alpha - \frac{d^2x}{dt^2} \sin \alpha.$$

Hence $$p_n = p_y \cos \alpha - p_x \sin \alpha. \quad . \quad . \quad . \quad . \quad . \quad (3)$$

The norm. acc. may also be expressed in terms of the tang. velocity v, and the radius of curvature r, as follows:

$ds' = r d\alpha$, or $d\alpha = ds' \div r$; also $d^2n = ds' d\alpha, = ds'^2 \div r$,

$$\text{i.e., } \frac{d^2n}{dt^2} = \left(\frac{ds'}{dt}\right)^2 \frac{1}{r}, \quad \text{or} \quad p_n = \frac{v^2}{r}. \quad . \quad . \quad . \quad . \quad (4)$$

If now, Fig. 80, we resolve the forces $X = Mp_x$ and $Y = Mp_y$, which at this instant account for the X and Y accelerations (M = mass of the material point), into components along the tangent and normal to the curved path, we shall have, as *their equivalent*, a tangential force



FIG. 80.

$$T = Mp_x \cos \alpha + Mp_y \sin \alpha,$$

and a normal force

$$N = Mp_y \cos \alpha - Mp_x \sin \alpha.$$

But [see equations (2), (3), and (4)] we may also write

$$T = Mp_t = M\frac{dv}{dt}; \quad \text{and} \quad N = Mp_n = M\frac{v^2}{r}. \quad . \quad (5)$$

Hence, if a free material point is moving in a curved path, the sum of the tangential components of the acting forces must equal (the mass) × tang. accel.; *that of the normal components,* = (the mass) × normal accel. = (mass) × (square of veloc. in path) ÷ (rad. curv.).

It is evident, therefore, that the resultant force (= diagonal on T and N or on X and Y, Fig. 80) *does not act along the tangent* at any point, but toward the concave side of the path; unless $r = \infty$.

Radius of curvature.—From the line above eq. (4) we have $d^2n = ds'^2 \div r$; hence (line above eq. (3)), $ds'^2 \div r = d^2y \cos \alpha - d^2x \sin \alpha$; but $\cos \alpha = dx \div ds$, and $\sin \alpha = dy \div ds$,

$$\therefore \frac{ds'^2}{r} = d^2y\frac{dx}{ds} - d^2x\frac{dy}{ds}; \text{ or } \frac{ds'^2 ds}{r} = dx^2\left[\frac{dxd^2y - dyd^2x}{dx^2}\right];$$

$$\text{i.e., } \frac{ds'^2 ds}{r} = dx^2 d\left[\frac{dy}{dx}\right] = dx^2 d(\tan \alpha),$$

$$\therefore r = \left(\frac{ds'^2 ds}{dt^3}\right) \div \left[\left(\frac{dx}{dt}\right)^2 \frac{d \tan \alpha}{dt}\right];$$

$$\text{or,} \qquad r = v^3 \div \left[v_x^2 \frac{d \tan \alpha}{dt}\right]. \quad . \quad . \quad . \quad . \quad . \quad (6)$$

which is equally true if, for v_x and tan α, we put v_y and tan $(90° - \alpha)$, respectively.

Change in the velocity square.—Since the tangential acceleration $\frac{dv}{dt} = p_t$, we have $ds\frac{dv}{dt} = p_t ds$; i.e.,

$$\frac{ds}{dt}dv = p_t ds, \quad \text{or} \quad vdv = p_t ds \quad \text{and} \quad \therefore \frac{v^2 - c^2}{2} = \int p_t ds. \quad (7)$$

having integrated between any initial point of the curve where $v = c$, and any other point where $v = v$. This is nothing more than equation (III.), of § 50.

75. Normal Acceleration. Another Method.—Fig. 81. Consider a material point m describing a circular path ABC, with constant velocity $=v$; the center of the curve being at O and the radius $=r$. The velocity v is always tangent to the curve. Let the linear arc BC be described in the small time dt, the angle at the center being $d\alpha$. At B the velocity is directed along the tangent BT, while at C it is ⌝ to OC and makes an angle $d\alpha$ with a line parallel to BT. As m moves along the curve from B to C, the point n, which is the foot of the ⌝ dropped from any position of m upon the normal BO, moves from B toward D; while the foot, a, of the ⌝ let fall from m upon the tangent BT, moves along BT with an average velocity $=v'$, a little less than v. Now the motion of m may be regarded as compounded of these two motions, viz., that of n and that of a. The motion of n is called the "motion of *m along the normal.*" The velocity of n is zero at B, where v is ⌝ to the normal, and is $v \sin d\alpha$ at the point D; hence in the time dt the gain of n's velocity is $v \sin d\alpha - 0$, and the *rate* of gain, or acceleration, is $p_n = v \sin d\alpha \div dt$. But $\sin d\alpha = CD \div r$ and $\overline{CD} = BC' = v'dt$. Substituting, we have $p_n = vv' \div r$.



FIG. 81.

Now make dt equal to zero and we have $v' = v$; and finally $p_n = v^2 \div r$, as the value of the normal acceleration, just at the point B.

76. Uniform Circular Motion. Centripetal Force.—The velocity being constant, p_t must be $= 0$, and $\therefore$ T (or ΣT if there are several forces) must $= 0$. The resultant of all the forces, therefore, must be a normal force $= (Mc^2 \div r) =$ a constant (eq. 5, § 74). This is called the "deviating force," or "centripetal force;" without it the body would continue in a straight line. Since forces always occur in pairs (§ 3), a "centrifugal force," equal and opposite to the "centripetal" (one being the reaction of the other), will be found among the forces acting on the body to whose constraint the deviation of the first body from its natural straight course is due. For example, the attraction of the earth on the moon acts as a centripetal or deviating force on the latter, while the equal and opposite force *acting on the earth* may be called the centrifugal. If a small block moving on a smooth horizontal table is gradually turned from its straight course AB by a fixed circular guide, tangent to AB at B, the pressure of the guide against the block is the centripetal force $Mc^2 \div r$ directed *toward* the centre of curvature, while



FIG. 82.

the centrifugal force $Mc^2 \div r$ is the pressure of the block against the *guide*, directed *away* from that centre.

Note.—One is not justified, therefore, in saying that a body describing a circular path is under the action of a "centrifugal force."

The Conical Pendulum, or governor-ball.—Fig. 83. If a material point of mass $= M = G \div g$, suspended on a cord of length $= l$, is to maintain a uniform circular motion in a horizontal plane, with a given radius r, under the action of gravity and the cord, required the velocity c to be given it. At B we have the body free. The only forces acting are G and the cord-tension P. The sum of their normal components, i.e., ΣN, must $= Mc^2 \div r$, i.e., $P \sin \alpha = Mc^2 \div r$; but, since Σ (vert. comps.) $= 0$, $P \cos \alpha = G$. Hence $G \tan \alpha = Gc^2 \div gr$; $\therefore c = \sqrt{gr \tan \alpha}$. Let $u =$ number of revolutions per unit of time, then $u = c \div 2\pi r = \sqrt{g} \div 2\pi \sqrt{h}$; i.e., is inversely proportional to the square root of the vertical projection of the length of cord. The time of executing one revolution is $= 1 \div u$.



Fig. 83.

Elevation of the outer rail on railroad curves (considerations of traction disregarded).—Consider a single car as a material point, and *free*, having a given velocity $= c$. P is the rail-pressure against the wheels. So long as the car follows the track the resultant R of P and G must point toward the centre of curvature and have a value $= Mc^2 \div r$. But $R = G \tan \alpha$, whence $\tan \alpha = c^2 \div gr$. If therefore the ties are placed at this angle α with the horizontal, the pressure will come upon the tread and not on the flanges of the wheels; in other words, the car will not leave the track. (This is really the same problem as the preceding.)



Fig. 84.

Apparent weight of a body at the equator.—This is less than the true weight or attraction of the earth, on account of the uniform circular motion of the body with the earth in its diurnal rotation. If the body hangs from a spring-balance,

whose indication is G lbs. (apparent weight), while the true attraction is G' lbs., we have $G' - G = Mc^2 \div r$. For M we may use $G \div g$ (apparent values); for r about 20,000,000 ft.; for c, 25,000 miles in 24 hrs., reduced to feet per second. It results from this that G is $< G'$ by $\frac{1}{289}G'$ nearly, and (since $17^2 = 289$) hence if the earth revolved on its axis seventeen times as fast as at present, G would $= 0$, i.e., bodies would apparently have no weight, the earth's attraction on them being just equal to the necessary centripetal or deviating force necessary to keep the body in its orbit.

Centripetal force at any latitude.—If the earth were a homogeneous liquid, and at rest, its form would be spherical; but when revolving uniformly about the polar diameter, its form of relative equilibrium (i.e., no motion of the particles relatively to each other) is nearly ellipsoidal, the polar diameter being an axis of symmetry.

Lines of attraction on bodies at its surface do not intersect in a common point, and the centripetal force requisite to keep a suspended body in its orbit (a small circle of the ellipsoid), at any latitude β is the resultant, N, of the attraction or true weight G' directed (nearly) toward the centre, and of G the tension of the string. Fig. 85. G = the apparent weight, indicated by a spring-balance and MA is its line of action (plumb-line) normal to the ocean surface. Evidently the apparent weight, and consequently g, are less than the true values, since N must be perpendicular to the polar axis, while the true values themselves, varying inversely as the square of MC, *decrease* toward the equator, hence the apparent values decrease still more rapidly as the latitude diminishes. The apparent g for any latitude β, at h ft. above sea-level, is (Chwolson, 1901), for foot-second units,*



FIG. 85.

$$g = 32.1723 - 0.083315 \cos 2\beta - 0.000003h.$$

(The value 32.2 is accurate enough for practical purposes.) Since the earth's axis is really not at rest, but moving about

* At the equator, $g = 32.09$ at sea-level but decreases to 32.06 at an elevation of 10,000 ft. above the sea.

the sun, and also about the centre of gravity of the moon and earth, the form of the ocean surface is periodically varied, i.e., the phenomena of the tides are produced.

77. Cycloidal Pendulum.—This consists of a material point at the extremity of an imponderable, flexible, and inextensible cord of length $= l$, confined to the arc of a cycloid in a vertical plane by the cycloidal evolutes shown in Fig. 86. Let the oscillation begin (from rest) at A, a height $= h$ above O



FIG. 86.



FIG. 87.

the vertex. On reaching any lower point, as B (height $= z$ above O), the point has acquired some velocity v, which is at this instant increasing at some rate $= p_t$. Now consider the point free, Fig. 87; the forces acting are P the cord-tension, normal to path, and G the weight, at an angle φ with the path. From § 74, eq. (5), $\Sigma T = Mp_t$ gives

$$G \cos \varphi + P \cos 90° = (G \div g)p_t; \quad \therefore p_t = g \cos \varphi$$

Hence (eq. (7), § 74), $vdv = p_t ds$ gives

$$vdv = g \cos \varphi ds; \quad \text{but } ds \cos \varphi = -dz; \quad \therefore vdv = -gdz.$$

Summing between A and B, we have

$$\left[\begin{matrix} v \\ 0 \end{matrix}\right. \tfrac{1}{2}v^2 = -g \int_h^z dz; \quad \text{or} \quad v^2 = 2g(h - z);$$

the same as if it had fallen freely from rest through the height $h - z$. (*This result evidently applies to any form of path when, besides the weight G, there is but one other force, and that always normal to the path.*)*

From $\Sigma N = Mv^2 \div r_1$, we have $P - G \sin \varphi = Mv^2 \div r_1$,

* Compare with lower part of p. 83.

whence P, the cord-tension at any point, may be found (here r_1 = the radius of curvature at any point = length of straight portion of the cord).

To find the time of passing from A to O, a half-oscillation, substitute the above value of v^2 in $v = ds \div dt$, putting $ds^2 = dx^2 + dz^2$, and we have $dt^2 = (dx^2 + dz^2) \div [2g(h - z)]$. To find dx in terms of dz, differentiate the equation of the curve, which in this position is

$$x = r \text{ ver. sin.}^{-1}(z \div r) + \sqrt{2rz - z^2};$$

whence

$$dx = \frac{rdz}{\sqrt{2rz - z^2}} + \frac{(r - z)dz}{\sqrt{2rz - z^2}} = \frac{(2r - z)dz}{\sqrt{2rz - z^2}};$$

$$\therefore dx^2 = \left[\frac{2r}{z} - 1\right]dz^2$$

(r = radius of the generating circle). Substituting, we have

$$dt = \sqrt{\frac{r}{g}} \cdot \frac{(-dz)}{\sqrt{hz - z^2}};$$

$$\therefore \Big[_A^O t = \sqrt{\frac{r}{g}} \int_0^h \frac{dz}{\sqrt{hz - z^2}} = \sqrt{\frac{r}{g}} \Big[_0^h \text{ver. sin.}^{-1} \frac{z}{\frac{1}{2}h} = \pi\sqrt{\frac{r}{g}}.$$

Hence the whole oscillation occupies a time $= \pi\sqrt{l \div g}$ (since $l = 4r$). This is independent of h, i.e., the oscillations are *isochronal*. This might have been proved by showing that p_t is proportional to OB *measured along the curve;* i.e., that the motion is *harmonic*. (§ 59, Prob. 2.)

78. Simple Circular Pendulum.—If the material point oscillates in the arc of a circle, Fig. 88, proceeding as in the preceding problem, we have finally, after integration by series, as the time of a full oscillation, in one direction,*

$$\left(= \sqrt{\frac{l}{g}}\right)\left[1 + \frac{1}{8} \cdot \frac{h}{l} + \frac{9}{256} \cdot \frac{h^2}{l^2} + \frac{225}{18432} \cdot \frac{h^3}{l^3} + \ldots\right].$$



FIG. 88.

Hence for a small h the time is nearly $\pi\sqrt{l \div g}$, and the os-

* See p. 651 of Coxe's translation of Weisbach's *Mechanics*.

cillations nearly isochronal. (For the Compound Pendulum, see § 117.)

[**Note.**—While the simple pendulum is purely ideal, the conception is a very useful one. A sphere of lead an inch in diameter and suspended by a silk thread, or very fine wire, more than 2 ft. in length, makes a close approximation to a simple pendulum; the length l being measured from the point of suspension to the middle of the sphere (strictly it should be a little greater). The length of the simple pendulum beating seconds (small amplitude) is about 3.26 ft.; (see p. 120)].

79. Change in the Velocity Square.—From eq. (7), § 74, we have $\frac{1}{2}(v^2 - c^2) = \int p_t ds$. But, from similar triangles, du being the projection of any ds of the path upon the resultant force R at that instant, $Rdu = Tds$ (or, Prin. of Virt. Vels. § 62, $Rdu = Tds + N \times 0$). T and N are the tangential and normal components of R. Fig. 89. Hence, finally,

$$\tfrac{1}{2}Mv^2 - \tfrac{1}{2}Mc^2 = \int Rdu, \quad . \quad . \quad . \quad . \quad . \quad (a)$$

for all elements of the curve between any two points. In general R is different in amount and direction for each ds of the path, but du is the distance through which R acts, **in its own direction**, while the body describes any ds; Rdu is called the **work done** by R when ds is described by the body. The above equation is read: *The difference between the initial and final kinetic energy of a body = the work done by the resultant force in that portion of the path.*



Fig. 89.

(These phrases will be further spoken of in Chap. VI.)

Application of equation (a) to a planet in its orbit about the sun.—Fig. 90. Here the only force at any instant is the attraction of the sun $R = C \div u^2$ (see Prob. 3, § 59), where C is a constant and u the variable radius vector. As u diminishes, v increases, therefore dv and du have contrary signs; hence equation (a) gives (c being the velocity at some initial point O)

$$\frac{1}{2}Mv_1^2 - \frac{1}{2}Mc^2 = -C\int_{u_0}^{u_1}\frac{du}{u^2} = C\left[\frac{1}{u_1} - \frac{1}{u_0}\right]; \quad (b)$$

$$\therefore v_1 = \sqrt{c^2 + \frac{2C}{M}\left[\frac{1}{u_1} - \frac{1}{u_0}\right]},$$ which is independent of the direction of the initial velocity c.



Fig. 90.

Application of eq. (*a*) *to a projectile in vacuo.*—G, the body's weight, is the only force acting, and therefore $= R$, while $M = G \div g$. Therefore equation (*a*) gives



Fig. 91

$$\frac{G}{g} \cdot \frac{v_1^2 - c^2}{2} = G\int_0^{y_1} dy = Gy_1;$$

$\therefore v_1 = \sqrt{c^2 + 2gy_1}$, which is independent of the angle, α, of projection.

Application of equation (*a*) to a body sliding, *without friction*, on a fixed curved guide in a vertical plane; initial velocity $= c$ at O.—Since there is some pressure at each point between the body and the guide, to consider the body *free* in space, we must consider the guide removed and that the body describes the given curve as a result of the action of the two forces, its weight G, and the pressure P, of the guide against the body. G is constant, while P varies from point to point, though always (since there is no friction) *normal to curve*. At any point, R being the resultant of G and P, project ds upon R, thus obtaining du; on G, thus obtaining dy; on P, thus obtaining zero. But by the *principle of virtual velocities* (see § 62) we have $Rdu = Gdy + P \times \text{zero}^* = Gdy$, which substituted in eq. (*a*) gives



Fig. 92.

$$\frac{G}{g}\frac{1}{2}(v_1^2 - c^2) = \int_0^{y_1} Gdy = G\int_0^{y_1} dy = Gy_1; \quad \therefore v_1 = \sqrt{c^2 + 2gy_1},$$

and therefore depends only on the *vertical distance* fallen through and the initial velocity, i.e., is *independent of the form of the guide.*

As to the value of P, the mutual pressure between the guide and body at any point, since ΣN must equal $Mv^2 \div r$, r being the variable radius of curvature, we have, as in § 77,

$$P - G\sin\varphi = Mv^2 \div r; \quad \therefore P = G[\sin\varphi + (v^2 \div gr)].$$

As, in general, φ and r are different from point to point of

* It is quite essential that the guide be *fixed*, as well as smooth, in order that this projection be zero; since if the guide were in motion, the force P, although $\perp$ to the guide, would not be $\perp$ to the ds or element of the path of the body, for that path would then be different from the curve of the guide.

the path, P is not constant. Should the curve at the point in question be *convex* upward (instead of concave upward as in Fig. 92) we must write $G \sin \phi - P = Mv^2 \div r$; etc.

80. Projectiles in Vacuo.—A ball is projected into the air (whose resistance is neglected, hence the phrase *in vacuo*) at an angle $= \alpha_0$ with the horizontal;* required its path; assuming it confined to a vertical plane. Resolve the motion into independent horizontal (X) and vertical (Y) motions, G, the weight, the only force acting, being correspondingly replaced by its horizontal component = zero, and its vertical component $= -G$. Similarly the initial velocity along $X = c_x = c \cos \alpha_0$, along Y, $= c_y = c \sin \alpha_0$. The X acceleration $= p_x = 0 \div M = 0$, i.e., the X motion is uniform, the velocity v_x remains $= c_x = c \cos \alpha_0$ at all points, hence, reckoning the time from O, at the end of any time t we have



FIG. 93.

$$x = c(\cos \alpha_0)t \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

In the Y motion, $p_y = (-G) \div M = -g$, i.e., it is uniformly retarded, the initial velocity being $c_y = c \sin \alpha_0$; hence, after any time t, the Y velocity will be (see § 56) $v_y = c \sin \alpha_0 - gt$, while the distance

$$y = c(\sin \alpha_0)t - \tfrac{1}{2}gt^2. \quad . \quad . \quad . \quad . \quad . \quad (2)$$

Between (1) and (2) we may eliminate t, and obtain as the equation of the trajectory or path

$$y = x \tan \alpha_0 - \frac{gx^2}{2c^2 \cos^2 \alpha_0}.$$

For brevity put $c^2 = 2gh$, h being the ideal *height due to the velocity* c, i.e., $c^2 \div 2g$ (see § 53; if the ball were directed vertically upward, a height $h = c^2 \div 2g$ would be actually attained, α_0 being $= 90°$), and we have

$$y = x \tan \alpha_0 - \frac{x^2}{4h \cos^2 \alpha_0}. \quad . \quad . \quad . \quad . \quad (3)$$

This is easily shown to be the equation of a parabola, with its axis vertical.

* And with a velocity of c ft. per sec.

The horizontal range.—Fig. 94. Putting $y = 0$ in equation (3), we obtain

$$x\left[\tan \alpha_0 - \frac{x}{4h \cos^2 \alpha_0}\right] = 0,$$

which is satisfied both by $x = 0$ (i.e., at the origin), and by $x = 4h \cos \alpha_0 \sin \alpha_0$. Hence the horizontal range for a given c and α_0 is $x_r = 4h \cos \alpha_0 \sin \alpha_0 = 2h \sin 2\alpha_0$.



FIG. 94.

For $\alpha_0 = 45°$ this is a maximum (c remaining the same), being then $= 2h$. Also, since $\sin 2\alpha_0 = \sin (180° - 2\alpha_0) = \sin 2(90° - \alpha_0)$, therefore any two complementary angles of projection give the same horizontal range.

Greatest height of ascent; that is, the value of y maximum, $= y_m$.—Fig. 94. Differentiate (3), obtaining

$$\frac{dy}{dx} = \tan \alpha_0 - \frac{x}{2h \cos^2 \alpha_0},$$

which, put $= 0$, gives $x = 2h \sin \alpha_0 \cos \alpha_0$, and this value of x in (3) gives $y_m = h \sin^2 \alpha_0$.

(Let the student obtain this more simply by considering the Y motion separately.)

81. Actual Path of Projectiles.—Small jets of water, so long as they remain unbroken, give close approximations to parabolic paths, as also any small dense object, e.g., a ball of metal, having a moderate initial velocity. The course of a cannon-ball, however, with a velocity of 1200 to 1400 feet per second is much affected by the resistance of the air, the descending branch of the curve being much steeper than the ascending; see Fig. 96*a*. The equation of this curve has not yet been determined, but only the expression for the slope (i.e., $dy : dx$) at any point. See Professor Bartlett's Mechanics, § 151 (in which the body is a sphere having no motion of rotation). Swift rotation about an axis, as well as an unsymmetrical form with reference to the direction of motion, alters the trajectory still further, and may deviate it from a vertical plane. The presence of wind would occasion increased irregularity. See Johnson's Encyclopædia, article "Gunnery." (See p. 823.)



FIG. 96*a*.

82. Special Problem (imaginary; from Weisbach's Mechanics. *The equations are not homogeneous*).—Suppose a material point, mass $= M$, to start from the point O, Fig. 97, with a velocity $= 9$ feet per second along the $-Y$ axis, being subjected thereafter to a constant attractive X force, of a value $X = 12M$, and to a variable Y force increasing with the time (in seconds, reckoned from O), viz., $Y = 8Mt$. Required the path, etc. For the X motion we have $p_x = X \div M = 12$, and hence



FIG. 97.

$$\int_0^{v_x} dv_x = \int_0^t p_x dt = 12\int_0^t dt\,;\ \text{i.e.,}\ v_x = 12t\,;$$

$$\text{and}\ \int_0^x dx = \int_0^t v_x dt\,;\ \text{i.e.,}\ x = 12\int_0^t t dt = 6t^2. \quad . \quad (1)$$

For the Y motion $p_y = Y \div M = 8t$, $\therefore \int_{-9}^{v_y} dv_y = 8\int_0^t t dt$;

$$\text{i.e.,}\ v_y + 9 = 4t^2,\ \text{and}\ \int_0^y dy = \int_0^t v_y dt;$$

$$\therefore\ y = 4\int_0^t t^2 dt - 9\int_0^t dt,\ \text{or}\ y = \tfrac{4}{3}t^3 - 9t. \quad . \quad . \quad (2)$$

Eliminate t between (1) and (2), and we have, as the *equation of the path*,

$$y = \pm\frac{4}{3}\left(\frac{x}{6}\right)^{\frac{3}{2}} \mp 9\left(\frac{x}{6}\right)^{\frac{1}{2}}, \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

which indicates a curve of the third order.

The velocity at any point is (see § 74, eq. (1))

$$v = \sqrt{v_x^2 + v_y^2} = 4t^2 + 9. \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

The length of curve measured from O will be (since $v = ds \div dt$)

$$s = \int_0^s ds = \int_0^t v dt = 4\int_0^t t^2 dt + 9\int_0^t dt = \tfrac{4}{3}t^3 + 9t. \quad (5)$$

The *slope*, tan α, at any point $= v_y \div v_x = (4t^2 - 9) \div 12t$,

$$\text{and}\ \therefore \frac{d\tan\alpha}{dt} = \frac{4t^2 + 9}{12t^2}. \quad . \quad . \quad . \quad . \quad . \quad (6)$$

CHAPTER IV.

MOMENT OF INERTIA.

[NOTE.—For the propriety of this term and its use in Mechanics, see §§ 114, 216, and 229; for the present we deal only with the geometrical nature of these two kinds of quantity.]

85. Plane Figures.—Just as in dealing with the centre of gravity of a plane figure (§ 23), we had occasion to sum the series $\int z dF$, z being the distance of any element of area, dF, from an axis; so in subsequent chapters it will be necessary to know the value of the series $\int z^2 dF$ for plane figures of various shapes referred to various axes. This summation $\int z^2 dF$ of the products arising from multiplying each elementary area of the figure by the *square* of its distance from an axis is called the **moment of inertia** *of the plane figure with respect to the axis in question;* its symbol will be I. If the axis is perpendicular to the plane of the figure, it may be named the *polar mom. of inertia* (§ 94); if the axis lies in the plane, the *rectangular* mom. of inertia (§§ 90–93). Since the I of a plane figure evidently consists of *four dimensions of length*, it may always be resolved into two factors, thus $I = Fk^2$, in which F = total area of the figure, while $k = \sqrt{I \div F}$, is called the **radius of gyration**, because if all the elements of area were situated at the *same* radial distance, k, from the axis, the moment of inertia would still be the same, viz.,

$$I = \int k^2 dF = k^2 \int dF = Fk^2.$$

For example, if the moment of inertia of a certain plane figure about a specified axis is 248 biquadratic inches (i.e., four-dimension inches; or in.^{4}), while its area is 12 sq. in. (or in.^{2}), the corresponding radius of gyration is

$$k = \sqrt{248 \div 12} = 4.55 \text{ in.}$$

86. Rigid Bodies.—Similarly, in dealing with the rotary motion of a rigid body, we shall need the sum of the series $\int \rho^2 dM$, meaning the summation of the products arising from multiplying the mass dM of each elementary volume dV of a

rigid body by the square of its distance from a specified axis. This will be called the *moment of inertia of the body with respect to the particular axis mentioned* (often indicated by a subscript), and will be denoted by I. As before, it can often be conveniently written Mk^2, in which M is the whole mass, and k its "radius of gyration" for the axis used, k being $= \sqrt{I \div M}$. If the body is *homogeneous*, the heaviness, γ, of all its particles will be the same, and we may write

$$I = \int \rho^2 dM = (\gamma \div g) \int \rho^2 d\,V = (\gamma \div g)\, V k^2.$$

87. If the body is a homogeneous plate of an *infinitely small thickness* $= \tau$, and of area $= F$, we have $I = (\gamma \div g) \int \rho^2 d\,V = (\gamma \div g) \tau \int \rho^2 dF$; i.e., $= (\gamma \div g) \times$ *thickness* $\times$ *mom. inertia of the plane figure.*

88. Two Parallel Axes. Reduction Formula.*—Fig. 99. Let Z and Z' be two parallel axes. Then $I_z = \int \rho^2 dM$, and $I_{z'} = \int \rho'^2 dM$. But d being the distance between the axes, so that $a^2 + b^2 = d^2$, we have $\rho'^2 = (x-a)^2 + (y-b)^2 = (x^2 + y^2) + d^2 - 2ax - 2by$, and $\therefore$

$$I_{z'} = \int \rho^2 dM + d^2 \int dM - 2a \int x dM - 2b \int y dM. \quad . \quad (1)$$



FIG. 99.

But $\int \rho^2 dM = I_z$, $\int dM = M$, and from the theory of the centre of gravity (see § 23, eq. (1), knowing that $dM = \gamma d\,V \div g$, and $\therefore$ that $[\int \gamma d\,V] \div g = M$) we have $\int x dM = M\bar{x}$ and $\int y dM = M\bar{y}$; hence (1) becomes

$$I_{z'} = I_z + M(d^2 - 2a\bar{x} - 2b\bar{y}), \quad . \quad . \quad . \quad . \quad (2)$$

in which a and b are the x and y of the axis Z'; $\bar{x}$ and $\bar{y}$ refer to the centre of gravity of the body. If Z is a gravity-axis (call it g), both $\bar{x}$ and $\bar{y} = 0$, and (2) becomes

$$I_{z'} = I_g + Md^2. \ . \ . \ . \quad \text{or} \quad k_{z'}^2 = k_g^2 + d^2. \quad . \quad . \quad (3)$$

It is therefore evident that the mom. of inertia about a gravity-axis is smaller than about any other *parallel* axis.

Eq. (3) includes the particular case of a *plane figure*, by

* The particle of mass $= dM$, shown in Fig. 99, is typical of the *vast number* of particles which form the rigid body. That is, a, b, and d are *constants*, but x, y, z, ρ, and ρ' are *variables*.

writing area instead of mass, i.e., when Z (now g) is a gravity-axis,

$$I_{z'} = I_g + Fd^2. \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

89. Other Reduction Formulæ; for Plane Figures.—(The axes here mentioned lie in the plane of the figure.) For *two sets of rectangular axes*, having the *same* origin, the following holds good. Fig. 100. Since

$$I_X = \int y^2 dF, \quad \text{and} \quad I_Y = \int x^2 dF,$$

we have $$I_X + I_Y = \int (x^2 + y^2) dF.$$

Similarly, $$I_U + I_V = \int (v^2 + u^2) dF.$$

But since the x and y of any dF have the same hypothenuse as the u and v, we have $v^2 + u^2 = x^2 + y^2$; $\therefore I_X + I_Y = I_U + I_V$.



FIG. 100.



FIG. 100*a*.

Let X be an axis of symmetry; then, given I_X and I_Y (O is anywhere on X), required I_U, *U being an axis through O and making any angle α with X.* See Fig. 100*a*.

$I_U = \int v^2 dF = \int (y \cos \alpha - x \sin \alpha)^2 dF$; i.e.,

$I_U = \cos^2 \alpha \int y^2 dF - 2 \sin \alpha \cos \alpha \int xy dF + \sin^2 \alpha \int x^2 dF.$

But since the area is symmetrical about X, in summing up the products $xy dF$, for every term $x(+y)dF$, there is also a term $x(-y)dF$ to cancel it; which gives $\int xy dF = 0$. Hence

$$I_U = \cos^2 \alpha I_X + \sin^2 \alpha I_Y.$$

The student may easily prove that if two distances a and b be set off from O on X and Y respectively, made inversely proportional to $\sqrt{I_X}$ and $\sqrt{I_Y}$, and an ellipse described on a and b as semi-axes; then the moments of inertia of the figure about

any axes through O are inversely proportional to the squares of the corresponding semi-diameters of this ellipse; called therefore the *Ellipse of Inertia*. It follows therefore that the moments of inertia about *all gravity-axes* of a circle, or a regular polygon, are equal; since their ellipse of inertia must be a circle. Even if the plane figure is not symmetrical, an "ellipse of inertia" can be located at any point, and has the properties already mentioned; its axes are called the *principal axes* for that point.

90. The Rectangle.—*First, about its base.* Fig. 101. Since all points of a strip parallel to the base have the same co-ordinate, z, we may take the area of such a strip for $dF = bdz$;



FIG. 101.



FIG. 102.

$$\therefore I_B = \int_0^h z^2 dF = b\int_0^h z^2 dz$$

$$= \tfrac{1}{3}b\Big[_0^h z^3 = \tfrac{1}{3}bh^3; \text{ and } k = h \div \sqrt{3}.$$

Secondly, about a *gravity-axis parallel to base.*

$$dF = bdz \therefore I_g = \int z^2 dF = b\int_{-\frac{1}{2}h}^{\frac{1}{2}h} z^2 dz = \tfrac{1}{12}bh^3.$$

Hence the radius of gyration $= k = h \div \sqrt{12}$.

Thirdly, about *any other axis in its plane.* Use the results already obtained in connection with the reduction-formulæ of §§ 88, 89.

90a. The Triangle.—*First*, about an axis through the vertex and parallel to the base; i.e., I_V in Fig. 103. Here the length of the strip is variable; call it y. From similar triangles

$$y = (b \div h)z;$$



FIG. 103.



FIG. 104.

$$\therefore I_V = \int z^2 dF = \int z^2 y dz = (b \div h)\int_0^h z^3 dz = \tfrac{1}{4}bh^3.$$

Secondly, about g, a gravity-axis parallel to the base. Fig 104. From § 88, eq. (4), we have, since $F = \frac{1}{2}bh$ and

$$d = \tfrac{2}{3}h,\ I_g = I_V - Fd^2 = \tfrac{1}{4}bh^3 - \tfrac{1}{2}bh \cdot \tfrac{4}{9}h^2 = \tfrac{1}{36}bh^3.$$

Thirdly, Fig. 104, *about the base*; $I_B = ?$ From § 88, eq. (4), $I_B = I_g + Fd^2$, with $d = \frac{1}{3}h$; hence

$$I_B = \tfrac{1}{36}bh^3 + \tfrac{1}{2}bh \cdot \tfrac{1}{9}h^2 = \tfrac{1}{12}bh^3.$$

91. The Circle.—About any diameter, as g, Fig. 105. Polar co-ordinates, $I_g = \int z^2 dF$. Here we take dF = area of an elementary rectangle $= \rho d\varphi \cdot d\rho$, while $z = \rho \sin \varphi$.



Fig. 105.



Fig. 106.

$$I_g = \int\int (\rho \sin \varphi)^2 \rho d\varphi d\rho = \int_0^{2\pi} \left[\sin^2 \varphi d\varphi \int_0^r \rho^3 d\rho \right]$$

$$= \frac{r^4}{4} \int_0^{2\pi} \sin^2 \varphi d\varphi = \frac{r^4}{4} \int_0^{2\pi} \tfrac{1}{2}(1 - \cos 2\varphi) d\varphi$$

$$= \frac{r^4}{4} \int_0^{2\pi} \left[\frac{1}{2} d\varphi - \frac{1}{4} \cdot \cos 2\varphi d(2\varphi) \right]$$

$$= \frac{1}{4} r^4 \left[\left(\frac{1}{2}\varphi - \frac{1}{4} \sin 2\varphi \right) \right]_0^{2\pi}$$

$$= \frac{1}{4} r^4 \left[\left(\frac{2\pi}{2} - 0 \right) - (0 - 0) \right]. \quad \text{i.e., } I_g = \frac{1}{4}\pi r^4.$$

Hence the radius of gyration $= \frac{1}{2}r$.

92. Compound Plane Figures.—Since $I = \int z^2 dF$ is an infinite series, it may be considered as made up of separate groups or subordinate series, combined by algebraic addition, corresponding to the subdivision of the compound figure into component figures, each subordinate series being the moment of inertia of one of these component figures; but these separate moments *must all be referred to the same axis.* It is convenient to remember that the (*rectangular*) I of a plane figure remains unchanged if we conceive some or all of its elements shifted any distance parallel to the axis of reference. E.g., in Fig. 106, the sum of the I_B of the rectangle CE, and that of FD is = to the I_B of the imaginary rectangle

formed by shifting one of them parallel to B, until it touches the other; i.e., I_B of CE + I_B of $FD = \frac{1}{3}b_1h_1^3$ (§ 90). Hence the I_B of the ⊤ shape in Fig. 106 will be = I_B of rectangle $AD - I_B$ of rect. $CE - I_B$ of rect. FD.

That is, I_B of ⊤ $= \frac{1}{3}[bh^3 - b_1h_1^3]$. . . . (§ 90). . . (1)

About the gravity-axis, g, Fig. 106. To find the distance d from the base to the centre of gravity, we may make use of eq. (3) of § 23, writing areas instead of volumes, or, experimentally, having cut the given shape out of sheet-metal or card-board, we may balance it on a knife-edge. Supposing d to be known by some such method, we have, from eq. (4) of § 88, since the area $F = bh - b_1h_1$, $I_g = I_B - Fd^2$;

i.e., $I_g = \frac{1}{3}[bh^3 - b_1h_1^3] - (bh - b_1h_1)d^2$. . . (2)



Fig. 106a.

The double-⊤ (*or* ⌶), and the *box* forms of Fig. 106*a*, *if symmetrical about the gravity-axis* g, have moments of inertia alike in form. Here the gravity-axis (parallel to base) of the compound figure is also a gravity axis (parallel to base) of each of the two component rectangles, of dimensions b and h, b_1 and h_1, respectively.

Hence by algebraic addition we have (§ 90), for either compound figure,

$$I_g = \tfrac{1}{12}[bh^3 - b_1h_1^3]. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

(If there is no axis of symmetry parallel to the base we must proceed as in dealing with the ⊤-form.) Similarly for the ring,



Fig. 107.



Fig. 108.

Fig. 107, or space between two *concentric* circumferences, we have, about any diameter or g (§ 91),

$$I_g = \tfrac{1}{4}\pi(r_1^4 - r_2^4). \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

The rhombus about a gravity-axis, g, perpendicular to a diagonal, Fig. 108.—This axis divides the figure into two equal triangles, *symmetrically placed*, hence the I_g of the rhombus equals double the moment of inertia of one triangle about its base; hence (§ 90*a*)

$$I_g = 2 \cdot \tfrac{1}{12} b(\tfrac{1}{2}h)^3 = \tfrac{1}{48} bh^3. \quad . \quad . \quad . \quad . \quad . \quad (5)$$

(The result is the same, if either vertex, or both, be shifted any distance parallel to AB.)

For practice, the student may derive results for the *trapezoid;* for the forms in Fig. 106, when the inner corners are rounded into equal quadrants of circles; for the double-$\top$, when the lower flanges are shorter than the upper; for the regular polygons, etc. (See table in the Cambria Steel Co.'s hand-book.)

93. If the plane figure be bounded, wholly or partially, by curves, it may be subdivided into an infinite number of strips, and the moments of inertia of these (referred to the desired axis) added by integration, *if the equations of the curves are known;* if not, Simpson's Rule,* for a finite even number of strips, of equal width, may be employed for an approximate result. If these strips are parallel to the axis, the I of any one strip = its length × its width × square of distance from axis; while if perpendicular to, and *terminating in,* the axis, its $I = \frac{1}{3}$ its width × cube of its length (see § 90).

A graphic method of determining the moment of inertia of any irregular figure will be given in a subsequent chapter.*

94. Polar Moment of Inertia of Plane Figures (§ 85).—Since the axis is now perpendicular to the plane of the figure, intersecting it in a point, O, the distances of the elements of area will all *radiate* from this point, and would better be denoted by ρ instead of z; hence, Fig. 109, $\int \rho^2 dF$ is the polar moment of inertia of any plane figure about a specified point O; this may be denoted by I_p. But $\rho^2 = x^2 + y^2$, for each dF; hence



FIG. 109.

$$I_p = \int (x^2 + y^2) dF = \int x^2 dF + \int y^2 dF = I_Y + I_X.$$

7

* See pp. 13, 79, 80, and 81 of the author's "*Notes and Examples in Mechanics,*" and p. 454 of this book.

i.e., *the polar moment of inertia about any given point in the plane equals the sum of the rectangular moments of inertia about any two axes of the plane figure, which intersect at right angles in the given point.* We have therefore for the *circle about its centre*

$$I_p = \tfrac{1}{4}\pi r^4 + \tfrac{1}{4}\pi r^4 = \tfrac{1}{2}\pi r^4;$$

For a *ring* of radii r_1 and r_2,

$$I_p = \tfrac{1}{2}\pi(r_1^4 - r_2^4);$$

For the *rectangle about its centre*,

$$I_p = \tfrac{1}{12}bh^3 + \tfrac{1}{12}hb^3 = \tfrac{1}{12}bh(b^2 + h^2);$$

For the *square*, this reduces to

$$I_p = \tfrac{1}{6}b^4.$$

(See §§ 90 and 91.)

95. Slender, Prismatic, Homogeneous Rod.—Returning to the moment of inertia of rigid bodies, or solids, we begin with that of a *material line*, as it might be called, about an axis through its extremity making some angle α with the rod. Let l = length of the rod, F its cross-section (very small, the result being strictly true only when $F = 0$). Subdivide the rod into an infinite number of small prisms, each having F as a base, and an altitude $= ds$. Let γ = the heaviness of the material; then the mass of an elementary prism, or $dM = (\gamma \div g)Fds$, while its distance from the axis Z is $\rho = s \sin \alpha$. Hence the moment of inertia of the rod with respect to Z as an axis is



Fig. 110.

$$I_Z = \int \rho^2 dM = (\gamma \div g)F \sin^2\alpha \int_0^l s^2 ds = \tfrac{1}{3}(\gamma \div g)Fl^3 \sin^2\alpha.$$

But $\gamma Fl \div g$ = mass of rod and $l \sin \alpha = a$, the distance of the further extremity from the axis; hence $I_Z = \frac{1}{3}Ma^2$ and the *radius of gyration*, or k, is found by writing $\frac{1}{3}Ma^2 = Mk^2$; $\therefore k^2 = \frac{1}{3}a^2$, or $k = \sqrt{\frac{1}{3}}a$ (see § 86). If $\alpha = 90°$, $a = l$.

96. Thin Plates. Axis in the Plate.—Let the plates be homogeneous and of small constant thickness $= \tau$. If the surface of

the plate be $= F$, and its heaviness γ, then its mass $= \gamma F\tau \div g$. From § 87 we have for the plate, about any axis,

$I = (\gamma \div g)\tau \times$ *mom. of inertia of the plane figure formed by the shape of the plate.* . . . . . (1)

Rectangular plate. Gravity-axis parallel to base.—Dimensions b and h. From eq. (1) and § 90 we have

$$I_g = (\gamma \div g)\tau \cdot \tfrac{1}{12}bh^3 = (\gamma bh\tau \div g)\tfrac{1}{12}h^2 = \tfrac{1}{12}Mh^2;\ \therefore k^2 = \tfrac{1}{12}h^2.$$

Similarly, if *the base is the axis*, $I_B = \frac{1}{3}Mh^2$, $\therefore k^2 = \frac{1}{3}h^2$.

Triangular plate. Axis through vertex parallel to base.—From eq. (1) and § 90*a*, dimensions being b and h,

$$I_V = (\gamma \div g)\tau\tfrac{1}{4}bh^3 = (\gamma\tfrac{1}{2}bh\tau \div g)\tfrac{1}{2}h^2 = \tfrac{1}{2}Mh^2;\ \therefore k^2 = \tfrac{1}{2}h^2.$$

Circular plate, with any diameter as axis.—From eq. (1) and § 91 we have

$$I_g = (\gamma \div g)\tau\tfrac{1}{4}\pi r^4 = (\gamma\pi r^2\tau \div g)\tfrac{1}{4}r^2 = \tfrac{1}{4}Mr^2;\ \therefore k^2 = \tfrac{1}{4}r^2.$$

97. Plates or Right Prisms of any Thickness (or Altitude). Axis Perpendicular to Surface (or Base).—As before, the solid is homogeneous, i.e., of constant heaviness γ; let the altitude $= h$. Consider an elementary prism, Fig. 111, whose length is parallel to the axis of reference Z. Its altitude $= h =$ that of the whole solid; its base $= dF =$ an element of F the area of the base of solid; and each point of it has the same ρ. Hence we may take its mass, $= \gamma h dF \div g$, as the dM in summing the series



Fig. 111.

$$I_Z = \int \rho^2 dM;$$
$$\therefore I_Z = (\gamma h \div g)\int \rho^2 dF$$
$$= (\gamma h \div g) \times \text{polar mom. of inertia of base. . . (2)}$$

By the use of eq. (2) and the results in § 94 we obtain the following:

Circular plate, or *right circular cylinder*, about the geometrical axis. $r =$ radius, $h =$ altitude.

$$I_g = (\gamma h \div g)\tfrac{1}{2}\pi r^4 = (\gamma h\pi r^2 \div g)\tfrac{1}{2}r^2 = \tfrac{1}{2}Mr^2;\ \therefore k^2 = \tfrac{1}{2}r^2.$$

Right parallelopiped or *rectangular plate.*—Fig. 112,

$$I_g = (\gamma h \div g)\tfrac{1}{12}bb_1(b_1^2 + b^2) = M\tfrac{1}{12}d^2;\ \therefore k^2 = \tfrac{1}{12}d^2.$$

For a *hollow cylinder*, about its geometric axis,

$$I_g = (\gamma h \div g)\tfrac{1}{2}\pi(r_1^4 - r_2^4) = \tfrac{1}{2}M(r_2^2 + r_1^2); \quad \therefore k^2 = \tfrac{1}{2}(r_2^2 + r_1^2).$$



Fig. 112.



Fig. 113.

98. Circular Wire.—Fig. 113 (perspective). Let Z be a gravity-axis perpendicular to the plane of the wire; X and Y lie in this plane, intersecting at right angles in the centre O. The wire is homogeneous and of constant (small) cross-section. Since, referred to Z, each dM has the same $\rho = r$, we have $I_Z = \int r^2 dM = Mr^2$. Now I_X must equal I_Y, and (§ 94) their sum $= I_Z$,

$$\therefore I_X, \text{ or } I_Y, = \tfrac{1}{2}Mr^2, \qquad \text{and} \qquad k_X^2, \text{ or } k_Y^2 = \tfrac{1}{2}r^2.$$

99. Homogeneous Solid Cylinder, *about a diameter of its base.* —Fig. 114. $I_X = ?$ Divide the cylinder into an infinite number of laminæ, or thin plates, parallel to the base. Each is some distance z from X, of thickness dz, and of radius r (constant). In each draw a gravity-axis (of its own) parallel to X. We may now obtain the I_X of the whole cylinder by adding the I_X's of all the laminæ. The I_g of *any one lamina* (§ 96, circular plate) = its mass $\times \tfrac{1}{4}r^2$; hence its I_X (eq. (3), § 88) = its I_g + (its mass) $\times z^2$. Hence for the whole cylinder



Fig. 114.

$$I_X = \int_0^h [(\gamma dz \pi r^2 \div g)(\tfrac{1}{4}r^2 + z^2)]$$

$$= (\pi r^2 \gamma \div g)\left[\tfrac{1}{4}r^2 \int_0^h dz + \int_0^h z^2 dz\right];$$

$$\text{i.e., } I_X = (\pi r^2 h\gamma \div g)(\tfrac{1}{4}r^2 + \tfrac{1}{3}h^2) = M(\tfrac{1}{4}r^2 + \tfrac{1}{3}h^2).$$

100. Let the student prove (1) that if Fig. 114 represent **any right prism,** and k_F denote the radius of gyration of any one lamina, referred to its gravity-axis parallel to X, then the I_X of whole prism $= M(k_F^2 + \tfrac{1}{3}h^2)$; and (2) that the moment

CHAPTER V.

KINETICS OF A RIGID BODY.

108. General Method.—Among the possible* motions of a rigid body the most important for practical purposes (and fortunately the most simple to treat) are: a *motion of translation*, in which the particles move in parallel right lines with equal accelerations and velocities at any given instant; and *rotation about a fixed axis*, in which the particles describe circles in parallel planes with velocities and accelerations proportional (at any given instant) to their distances from the axis. Other motions will be mentioned later. To determine relations, or equations, between the elements of the motion, the mass and form of the body, and the forces acting (which do not necessarily form an unbalanced system), the most direct method to be employed is that of two *equivalent systems* of forces (§ 15), one consisting of the actual forces acting on the body, *considered free*, the other imaginary, consisting of the infinite number of forces which, applied to the separate material points composing the body, would account for their individual motions, as if they were an assemblage of particles without mutual actions or coherence. If the body were at rest, then considered *free*, and the forces referred to three co-ordinate axes, they would constitute a balanced system, for which the six summations ΣX, ΣY, ΣZ, $\Sigma(\text{mom.})_X$, $\Sigma(\text{mom.})_Y$, and $\Sigma(\text{mom.})_Z$, would each $= 0$; but in most cases of motion some or all of these sums are equal (at any given instant), not to zero, but to the corresponding summation of the imaginary equivalent system, i.e., to expressions involving the masses of the particles (or material points), their distribution in the body, and the elements of the motion. That is, we obtain six equations by putting the ΣX of the actual system equal to the ΣX of the imaginary, and so on; for a definite instant of time (since some of the quantities may be variable).

* Motions of such character that the particles of the body do not change their relative positions. In other words, the body remains *rigid*.

108a. The "Imaginary System."—In conceiving the imaginary equivalent system in § 108, applied to the material points or particles (supposed destitute of mutual action, and not exposed to gravitation), which make up the rigid body, we employ the simplest system of forces that is capable, by the Mechanics of a Material Point, of producing the motion, which the particles actually have. If now the mutual actions, coherence, etc., were suddenly re-established, there would evidently be no change in the motion of the assemblage of particles; that is, in what is now a rigid body again, hence the imaginary system is equivalent to the actual system.

In applying this logic to the motion of translation of a rigid body (see § 109 and Fig. 122,) we reason as follows:

If the particles or elementary masses did not cohere together, being altogether without mutual action and not subjected to gravitation, their actual rectilinear motion in parallel lines, each having at a given instant the same velocity and also the *same acceleration*, p, as any other, could be maintained only by the application, to *each* particle, of a force having a value $=$ *its mass* $\times p$, directed in the line of motion. In this way system (II.) is conceived to be formed and is evidently composed of parallel forces all pointing one way, whose resultant must be equal to their sum, viz. $\int dM \times p$. But since at this instant p is common to the motion of all the particles, this sum can be written $p \int dM$, $=$ the whole mass $M \times p$.

If now the mutual coherence of contiguous particles were suddenly to be restored, system (II.) still acting, the motion of the assemblage of particles *would not be affected* (precisely as the falling motion *in vacuo* of two wooden blocks in contact is just the same whether they are glued together or not) and consequently we argue that the imaginary system (II.) is the equivalent of whatever system of forces the body is actually subjected to, viz. system (I.), (in which the body's own weight belongs) producing the actual motion.

Since the resultant of system (II.) is a single force, $= Mp$, parallel to the direction of the acceleration, and in a line passing through the center of gravity of the body, it follows that the resultant of the actual system is the same.

109. Translation.—Fig. 122. At a given instant all the particles have the same velocity $= v$, in parallel right lines (parallel to the axis X, say), and the same acceleration p. Required the ΣX of the acting forces, shown at (I.). (II.) shows the imaginary equivalent system, consisting of a force = mass × acc. $= dMp$ applied parallel to X to each particle, since such a force would be necessary (from eq. (IV.) § 55) to account for the accelerated rectilinear motion of the particle, independently of the others. Putting $(\Sigma X)_I = (\Sigma X)_{II}$, we have



Fig. 122.

$$(\Sigma X)_I = \int p dM = p \int dM = Mp. \quad . \quad . \quad . \quad (V.)$$

It is evident that the resultant of system (II.) must be parallel to X; hence* that of (I.), which $= (\Sigma X)_I$ and may be denoted by R, must also be parallel to X; let a = perpendicular distance from R to the plane YX; a will be parallel to Z. Now put $[\Sigma(\text{mom.})_Y]_I = [\Sigma(\text{mom.}_Y)]_{II}$, ($Y$ is an axis perpendicular to paper through O) and we have $-Ra = -\int dMpz = -p\int dMz = -pM\bar{z}$ (§ 88), i.e., $a = \bar{z}$. A similar result may be proved as regards $\bar{y}$. Hence, *if a rigid body has a motion of translation, the resultant force must act in a line through the centre of gravity* (here more properly called the centre of mass), *and parallel to the direction of motion.* Or, practically, in dealing with a rigid body having a motion of translation, we may consider it concentrated at its centre of mass. If the velocity of translation is uniform, $R = M \times 0 = 0$, i.e., the forces are balanced.

109a. Example.—The symmetrical rigid body in Fig. 122*a* weighs ($G=$) 4 tons, and touches a smooth horizontal floor at the two points O and B, symmetrically situated. Its center of gravity, C, is 6 ft. above the floor; and it is required to find the effect of applying a horizontal orce of $P=1$ ton, pointing to the right and 4 ft. below the level of the center of gravity C. Evidently a motion of translation will ensue from left to right, with some acceleration p, unless the body should begin to overturn about O or B as a pivot. The latter would be proved to

* The forces of system (I.) *cannot form a couple;* since those of system (II.) do not reduce to a couple, *all pointing one way.*

be the case if either reaction, V_0 or V, of the floor against the body at O and B, is found to be negative as the result of an analysis which assumes translation to occur. The actual forces acting on the body are only four, viz.: G and P, and the unknown vertical reactions V and V_0. A special device (very convenient for the present case) will now be used as a means of solution. The resultant of the "equivalent system," II, in this case of translation (see Fig. 122), is $R, = Mp$, lbs., acting through the center of gravity in a line parallel to that of the motion and in the direction of the acceleration, and hence is also the resultant of the actual system (just described). If, therefore, we annex to the actual system *its anti-resultant* (which is a force, R', of the same value, Mp, as R, and in same line, but pointing in the *opposite direction*) we thereby form a system under which the body would be in equilibrium; which would justify our writing $\Sigma X = 0$, $\Sigma Y = 0$, Σ(moms.) $= 0$, etc. (R' is called the "reversed inertia force" and is, of course, fictitious). With this system, then, in view, putting $\Sigma X = 0$ we obtain $P - R' = 0$; i.e., R', $= Mp$, $= 1$ ton; whence the acceleration $p = 1 \div (G \div g)$ $= 1 \div (4 \div 32.2) = 8.05$ ft./sec.^{2}



FIG. 122a.

By Σ(moms. about point A) $= 0$ we find $R' \times 4' + G \times 2' - V \times 4' = 0$ or $V = 2.5$ tons; and, by $\Sigma Z = 0$, $V + V_0 - G = 0$, or $V_0 = 4 - 2.5 = 1.5$ tons.

Since neither V nor V_0 is found to be negative the body does not tend to overturn but moves parallel to itself (i.e., translation) with a uniformly accelerated motion, the value of the acceleration being $p = 8.05$ ft./sec.^{2}; so that at the end of the first second the body would be 4.025 ft. from the start (no initial velocity); at the end of the second second, 16.1 ft.

If P were zero, or if P were applied horizontally through the center of gravity, V and V_0 would each be one half of G, i.e. 2 tons. It appears, therefore, that the effect of the eccentric application of P (viz. 4 ft. below the center of gravity C) is to increase V by 0.5 ton and diminish V_0 by an equal amount. If P acted 4 ft. *above* C, V and V_0 would change places in this respect. For V to be just zero, P (in its present position) would need to have a value of 2 tons, and the body would be on the point of overturning toward the left. Or, again, with $P = 1$ ton, its line of application would have to be 8 ft. below or above C, for one of the reactions to be just zero. In fact, in the fictitious equilibrated system which includes R', since $P = R'$ (in this simple case) they form a couple; and hence the three forces G, V, and V_0 are equivalent to a couple of equal and opposite moment (viz. 4 ft.-tons in Fig. 122a).

From the above it is seen that in the case of the last car of a railroad train, when it has an accelerated motion (just leaving a station), the pressures under the front and rear trucks will be slightly different from their values when the motion is uniform or zero, if the pull in the coupling does not pass through the center of gravity of the car.

110. Rotation about a Fixed Axis.—First, as to the elements of space and time involved. Fig. 123. Let O be the axis of rotation (perpendicular to paper), OY a fixed line of reference, and OA a convenient line of the rotating body, passing through the axis and perpendicular to it, accompanying the body in its angular motion, which is the same as that of OA. Just as in linear motion we dealt with linear space (s), linear velocity (v), and linear acceleration (p), so here we distinguish at any instant;



Fig. 123.

α, the *angular space* between OY and OA, (radians; or degrees, or revolutions);

$\omega = \frac{d\alpha}{dt}$, the *angular velocity,* or rate at which α is changing, (such as radians per sec., or revolutions per minute, etc.); and

$\theta = \frac{d\omega}{dt} = \frac{d^2\alpha}{dt^2}$, the *angular acceleration*, or rate at which ω is changing (radians per sec. per sec., e.g.)

These are all in angular measure and may be + or −, according to their direction against or with the hands of a watch. $d\alpha$ is a small increment of α, while $d^2\alpha$ is the difference between two $d\alpha$'s described in two consecutive small and *equal* time-intervals, each $= dt$.

(Let the student interpret the following cases: (1) at a certain instant ω is +, and θ −; (2) ω is −, and θ +; (3) α is −, ω and θ both +; (4) α +, ω and θ both −.) For rotary motion we have therefore, *in general,*

$$\omega = \frac{d\alpha}{dt}; \quad . \quad . \quad . \quad . \quad . \quad \text{(VI.)} \qquad \theta = \frac{d\omega}{dt} = \frac{d^2\alpha}{dt^2}; \quad . \quad . \quad \text{(VII.)}$$

and $\therefore$ (by elimination) $\omega d\omega = \theta d\alpha$; . . . . . (VIII.)

corresponding to eqs. (I.), (II.), and (III.) in § 50, for rectilinear motion.

Hence, for *uniform rotary motion*, ω being constant and $\theta = 0$, we have $\alpha = \omega t$, t being reckoned from the instant when $\alpha = 0$.

* See pp. 132, 133, of the "*Notes,*" etc, for further illustration.

For *uniformly accelerated rotary motion* θ is constant, and if ω_0 denote the *initial* angular velocity (when α and $t=0$) we may derive, as in § 56, denoting the constant θ by θ_1,

$$\omega = \omega_0 + \theta_1 t; \quad . \quad . \quad (1) \qquad \alpha = \omega_0 t + \tfrac{1}{2}\theta_1 t^2; \quad . \quad . \quad (2)$$

$$\alpha = \frac{\omega^2 - \omega_0^2}{2\theta_1}; \quad . \quad . \quad (3) \quad \text{and} \quad \alpha = \tfrac{1}{2}(\omega_0 + \omega)t. \quad . \quad . \quad (4)$$

If in any problem in rotary motion θ, ω, and α have been determined for any instant, the corresponding *linear* values for any point of the body whose radial distance from the axis is ρ, will be $s = \alpha\rho$ (= distance described by the point measured along its circular path from its initial position), $v = \omega\rho$ = its velocity, and $p_t = \theta\rho$ its tangential acceleration, at the instant in question, if α, ω and θ, *are expressed in radians.*

Example.—(1) What value of ω, the angular velocity, is implied in the statement that a pulley is revolving at the rate of 100 revolutions per minute if the radian is unit angle?

100 revolutions per minute is at the rate of $2\pi \times 100 = 628.32$ radian units of angular space per minute $= 10.472$ per second. $\therefore$ $\omega = 628.32$ radians per minute or 10.472 radians per second.

(2) A grindstone whose initial speed of rotation is 90 revolutions per minute is brought to rest in 30 seconds, the angular retardation (or negative angular acceleration) being constant; required the angular acceleration, θ_1, and the angular space α described. Use the second and radian as units.

$\omega_0 = 2\pi\frac{9}{6}\frac{0}{0} = 9.4248$ radians per second; $\therefore$ from eq. (1)

$$\theta_1 = \frac{\omega - \omega_0}{t} = -9.424 \div 30 = -0.3141 \text{ radians per sec. per sec.}$$

The angular space, from eq. (2) is

$$\alpha = \omega_0 t + \tfrac{1}{2}\theta_1 t^2 = 30 \times 9.42 - \tfrac{1}{2}(0.314)900 = 141.3$$

radians; that is, the stone has made 22.4 revolutions in coming to rest and a point 2 ft. from the axis has described a distance $s = \alpha\rho = 141.3 \times 2 = 282.6$ ft. in its circular path.

111. Rotation. Preliminary Problems. Axis Fixed.—For clearness in subsequent matter we now consider the following

problem. Fig. 124 shows a rigid homogeneous right cylinder A of weight $G=200$ lbs. and radius $r=2$ ft., mounted on a horizontal axle and concentric with the same. The center of gravity of the cylinder is in the axis of rotation (Z). The axle carries a light and concentric drum, of 10 in. radius, from which a light *inextensible* cord may unwind as the attached weight B descends, thus imparting an accelerated rotary motion to the cylinder. The weights and masses of the drum, cord, and axle, and all friction, will be neglected; and the two journals will be considered as one. The cylinder being originally at rest we wish to determine its motion as produced by a constant downward pull or tension of 80 lbs. in the vertical cord. (The necessary weight, G', of the body to be used at B*, to secure this 80 lbs. tension in the cord, will be found later.) During this motion the real system of forces (system (I)) acting on a body A consists of the weight 200 lbs., always acting through Z, the *fixed* axis of rotation; the downward pull of 80 lbs. at 10 in. from the axis; the vertical component V of the reaction of the bearing; and the horizontal component (if any), H. At (II), Fig. 124, is shown an imaginary *equivalent system* capable of producing the same motion in the particles, each of mass $=dM$, if they were independent. Since each particle is moving in a circle of some radius ρ with some linear (tangential) acceleration p_t at any instant, the cylinder having at that same instant some angular velocity ω and some angular acceleration θ, we have $v=\omega\rho$ and $p_t=\theta\rho$. (ω and θ in *radians*.)



Fig. 124.

This circular motion of each particle could be produced (see eq. (5), p. 76) by a tangential force dT lbs., $=dMp_t$, $=\theta dM\rho$, accompanied by a normal force dN lbs., $=dMv^2\div\rho$, $=\omega^2 dM\rho$. Our equivalent system, then, in (II), consists of a dT and a dN of proper value applied to each particle of body A at a given instant. Axes X and Y are shown in Fig. 124,

* The body B is not shown in the figure.

axis Z, the axis of rotation, being ⊥ to the paper through origin O. Let us now, for any instant of the motion, equate Σ (moms.)$_z$ of the actual system, (I), to Σ (moms.)$_z$ in system (II); using the integral sign to denote a summation which extends over all the particles of body A (for this instant; the integral might therefore be called an *instantaneous* integral). This gives, if we note that each of the normal forces dN of system (II) has no moment about axis Z, and that θ is common to all the particles at this instant, (with ft.-lb.-sec. units),

$$+80\times 10/12 = +\int dT\,.\,\rho = +\theta\int dM\rho^2 = +\theta I_z. \quad . \quad (1)$$

The summation (instantaneous) $\int dM\rho^2$ is seen to be the quantity called "*moment of inertia*," about axis Z, of the body A and remains constant, since the ρ's do not change in value as the motion proceeds. For a solid homogeneous cylinder $I_z = \frac{1}{2}Mr^2$ (p. 99), and hence

$$800 = 6\theta[200 \div 32.2](2)^2; \quad \text{i.e.,} \quad \theta = 7.376 \text{ rads./sec.}^2$$

That is, θ is *constant* and the rotary motion of the cylinder is *uniformly accelerated.*

(**N. B.**—From eq. (1) we note that, in general, in order to obtain the angular acceleration, θ, of the rotary motion of a rigid body about a fixed axis Z we have only to treat the body as a "free body" and write Σ (moms.) *about axis of rotation = angul. accel.* $\times$ *mom. of inertia about* Z.)

112. Further Results in Preceding Problem. — As to the *necessary weight, G', of body B* (suspended on the cord and causing the motion of both bodies), in order to produce the 80 lbs. tension in the cord, we note that body B has the same motion (only in a right line), as a point in the circumference of the drum, where the acceleration is $p' = \theta \times \frac{10}{12}$ $= 4.48$ ft./sec. That is, the motion of B will be *uniformly accelerated*, with an acceleration of 4.48 ft./sec.^{2} Hence the weight of B must not only produce the 80 lbs. tension in the cord but also accelerate the mass of B, $(M' = G' \div g)$ with an acceleration of 4.48 ft./sec.^{2} I.e., we have $G' = 80 + (G' \div g)p'$; which is nothing more than saying that the net accelerating force, $G' - 80$, = mass $\times$ accel.; whence we find, on solving, $G' = 92.9$ lbs. for the weight of the body to be used at B.

For example, in the first 3 sec. of time, starting from rest, B will descend a distance (see p. 54), $s_3 = \frac{1}{2}p'(3)^2 = 20.16$ ft. and will have acquired a (linear) velocity of $v_3 = p' \times 3 = 13.44$ ft./sec.; while body A will have turned through an angle of $\alpha_3 = \frac{1}{2}\theta(3)^2 = 33.19$ radians, (or 5.283 revolutions) and will possess an angular velocity of $\omega_3 = \theta \times 3 = 72.13$ rads./sec. or, $(33.19 \div 2\pi =)$, 3.525 revs./sec.

Reaction of the bearing; (two journals considered as one). To find the two components H and V of this reaction, we again have recourse to the two equivalent systems of Fig. 124, acting on body A. (N.B.—The *upward* 80 lbs. and the force G' do not belong to system (I), since they act on body B.) During the motion, the coordinates x and y of each particle (of mass $= dM$) are continually changing, as also the angle ϕ

between the ρ of the particle and axis Y (but not ρ itself). At any given instant we note that $x=\rho \sin \phi$ and $y=\rho \cos \phi$, for each particle. Let us now put ΣY of system (I) equal to ΣY of system (II). This gives us

$$V-200-80=\int dT \sin \phi - \int dN \cos \phi \quad . \quad . \quad . \quad . \quad . \quad (2)$$

As before, these integrals are "*instantaneous integrals*," being extended over all the particles of the body at a *given instant* of time, [so that in general the value of each may change with the progress of the motion.

Substituting for dT and dN, etc., this may be written

$$V-200-80=\theta \int dM\rho \sin \phi - \omega^2 \int dM\rho \cos \phi \quad . \quad . \quad . \quad (3)$$

or,
$$V-200-80=\theta \int dMx - \omega^2 \int dMy, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

Note that the value of θ, and also of ω, at this single instant are common to all the particles and have been factored out, as shown.

But the summation of $\int dMx$ is nothing more than $M\bar{x}$; where M is the mass of the whole cylinder A $(=200 \div g)$ [see p. 18, eq. (1)], and $\bar{x}$ is the x coordinate of its center of gravity; and, similarly, $\int dMy = M\bar{y}$. We may therefore write

$$V-200-80=\theta M\bar{x} - \omega^2 M\bar{y} \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

But in the present case, since the center of gravity of body A is in the axis of rotation at all times, we have both $\bar{x}$ and $\bar{y}$ = zero at all times; and hence finally $V-200-80=0$; or $V=280$ lbs.

As to the horizontal component, H, of the bearing reaction, we place ΣX of system (I) equal to ΣX of system (II) and obtain

$$H=-\int dT \cos \phi - \int dN \sin \phi = -\theta \int dM\rho \cos \phi - \omega^2 \int dM\rho \sin \phi, \quad (6)$$

i.e., $$H=-\theta \int dMy - \omega^2 \int dMx, = -\theta M\bar{y} - \omega^2 M\bar{x}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (7)$$

But since $\bar{x}$ and $\bar{y}$ are zero at all times, H must be zero, from (7); and we therefore conclude that in this case the reaction of the bearing is purely vertical at all times and is V, $=280$ lbs.

113. Centre of Percussion of a Rod suspended from one End.—Fig. 126. The rod is initially at rest (see (I.) in figure), is straight, homogeneous, and of constant (small) cross-section. Neglect its weight. A horizontal force or pressure, P, due to a blow (and varying in amount during the blow), now acts upon it from the left, perpendicularly to the axis, Z, of suspension. An accelerated rotary motion begins about the fixed axis Z. (II.) shows the rod *free*, at a certain instant, with the reactions X_0 and Y_0 put in at O_0. (III.) shows an imaginary system which would produce the same effect at this instant, and consisting of a $dT = dM\theta\rho$, and a $dN = \omega^2 dM\rho$ applied to each dM, the rod being composed of an infinite number of dM's, each at some distance ρ from the axis. Considering that *the rotation has just begun*, ω, the



FIG. 126.

angular velocity is as yet small, and will be neglected. Required Y_0 the horizontal reaction of the support at O in terms of P. By putting $\Sigma Y_{II} = \Sigma Y_{III}$, we have

$$P - Y_0 = \int dT = \theta \int \rho dM = \theta M \bar{\rho}.$$

$\therefore\ Y_0 = P - \theta M\bar{\rho}$; $\bar{\rho}$ is the distance of the centre of gravity from the axis (N.B. $\int \rho dM = M\bar{\rho}$ is only true when all the ρ's are parallel to each other). But the value of the angular acceleration θ at this instant depends on P and a, for Σ (mom.)$_Z$ in (II.) $=$ Σ (mom.)$_Z$ in (III.), whence $Pa = \theta \int \rho^2 dM = \theta I_Z$, where I_Z is the *moment of inertia* of the rod about Z, and from § 95 $= \frac{1}{3}Ml^2$. Now $\bar{\rho} = \frac{1}{2}l$; hence, finally,

$$Y_0 = P\left[1 - \frac{3}{2} \cdot \frac{a}{l}\right].$$

If now Y_0 is to $= 0$, i.e., if there is to be *no shock between the rod and axis*, we need only apply P at a point whose distance $a = \frac{2}{3}l$ from the axis; for then $Y_0 = 0$. This point is called the **centre of percussion** for the given rod and axis. It and the point of suspension O are interchangeable (see § 118). (Lay a pencil on a table; tap it at a point distant one third of the length from one end; it will *begin to rotate* about a vertical axis through the farther end. Tap it at one end; it will begin to rotate about a vertical axis through the point first mentioned. Such an axis of rotation is called an *axis of instantaneous rotation*, and is different for each point of impact—just as the point of contact of a wheel and rail is the one point of the wheel which is momentarily at rest, and about which, therefore, all the others are turning *for the instant*. Tap the pencil at its centre of gravity, and a motion of translation begins; see § 109.)

114. Rotation. Axis Fixed. General Formulæ.—Consider



Fig. 127.



Fig. 128.

ing now a rigid body of any shape whatever, let Fig. 127 indicate the system of forces acting *at any given instant*, Z being

the fixed axis of rotation, ω and θ the angular velocity and angular acceleration, *at the given instant.* X and Y are two axes, at right angles to each other and to Z, fixed in space. At this instant each dM of the body has a definite x, y, and φ (see Fig. 128), which will change, and also a ρ, and z, which will not change, as the motion progresses, and is pursuing a circular path with a velocity $= \omega\rho$ and a tangential acceleration $= \theta\rho$. Hence, if to each dM of the body (see Fig. 128) we imagine a tangential force $dT = dM\theta\rho$ and a normal force $= dM(\omega\rho)^2 \div \rho = \omega^2 dM\rho$ to be applied (eq. (5), § 74), and these alone, we have a system comprising an infinite number of forces, all parallel to XY, and equivalent to the actual system in Fig. 127. Let ΣX, etc., represent the sums (six) for Fig. 127. whatever they may be in any particular case, while for 128 we shall write the corresponding sums in detail. Noting that

$$\int dN \cos\varphi = \omega^2 \int dM\rho \cos\varphi = \omega^2 \int dMy = \omega^2 M\bar{y}, (\S\ 88);$$

that $\int dN \sin\varphi = \omega^2 \int dM\rho \sin\varphi = \omega^2 \int dMx = \omega^2 M\bar{x}$;

and similarly, that $\int dT \cos\varphi = \theta \int dM\rho \cos\varphi = \theta M\bar{y}$, and $\int dT \sin\varphi = \theta M\bar{x}$; while in the moment sums (the moment of $dT \cos\varphi$ about Y, for example, being $-dT \cos\varphi \,.\, z = -\theta dM\rho\,(\cos\varphi)z = -\theta dMyz$, the sum of the moms.$_Y$ of all the $(dT\cos\varphi)$'s $= -\theta \int dMyz$)

$$\int dT\cos\varphi z = \theta \int dMyz, \int dN \sin\varphi z = \omega^2 \int dMxz, \text{ etc.,}$$

we have, since the systems are equivalent,

$$\Sigma X = +\theta M\bar{y} - \omega^2 M\bar{x}; \quad . \quad . \quad . \quad . \quad \text{(IX.)}$$

$$\Sigma Y = -\theta M\bar{x} - \omega^2 M\bar{y}; \quad . \quad . \quad . \quad . \quad \text{(X.)}$$

$$\Sigma Z = \quad 0; \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad \text{(XI.)}$$

$$\Sigma \text{ moms.}_X = -\theta \int dMxz - \omega^2 \int dMyz; \quad . \quad \text{(XII.)}$$

$$\Sigma \text{ moms.}_Y = -\theta \int dMyz + \omega^2 \int dMxz; \quad . \quad \text{(XIII.)}$$

$$\Sigma \text{ moms.}_Z = \quad \theta \int dM\rho^2 = \theta I_Z. \quad . \quad . \quad . \quad \text{(XIV.)}$$

These hold good for any instant. As the motion proceeds $\bar{x}$ and $\bar{y}$ change, as also the sums $\int dMxz$ and $\int dMyz$. If the body, however, is homogeneous, and *symmetrical about the plane* XY, $\int dMxz$ and $\int dMyz$ would always = zero; since

the z of any dM does not change, and for every term $dMy(+z)$, there would be a term $dMy(-z)$ to cancel it; similarly for $\int dMxz$. The eq. (XIV.), Σ(moms. about axis of rotat.) $= \int dT\rho = \theta \int dM\rho^2 =$ (*angular accel.*) $\times$ (*mom. of inertia of body about axis of rotat.*), shows how the sum $\int dM\rho^2$ arises in problems of this chapter. That a force $dT = dM\theta\rho$ should be necessary to account for the acceleration (tangential) $\theta\rho$ of the mass dM, is due to the so-called *inertia* of the mass (§ 54), and its moment $dT\rho$, or $\theta dM\rho^2$, might, with some reason, be called the *moment of inertia* of the dM, and $\int \theta dM\rho^2 = \theta \int dM\rho^2$ that of the whole body. But custom has restricted the name to the sum $\int dM\rho^2$, which, being without the θ, has no term to suggest the idea of inertia. For want of a better the name is still retained, and is generally denoted by I. (See §§ 86, etc.)

115. Example of the Preceding.—A homogeneous right parallelopiped is mounted on a vertical axle (no friction), as in figure. O is at its centre of gravity, *hence both* $\bar{x}$ *and* $\bar{y}$ *are zero.* Let its heaviness be γ, its dimensions h, b_1, and b (see § 97). XY is a plane of symmetry, hence both $\int dMxz$ and $\int dMyz$ are zero at all times (see above). The tension P in the (inextensible) cord is caused by the hanging weight P_1 (but is not $= P_1$, unless the rotation is uniform). The figure shows both rigid bodies *free*. P_1 will have a motion of translation; the parallelopiped, one of rotation about a fixed axis. No masses are considered except $P_1 \div g$, and $bhb_1\gamma \div g$. The $I_Z = Mk_Z^2$ of the latter $=$ its mass $\times \frac{1}{12}(b_1^2 + b^2)$, § 97. At any instant, the cord being taut, if $p =$ linear acceleration of P_1, we have $p = \theta a$. . . . . eq. (α)



FIG. 129.

From (XIV.), $Pa = \theta I_Z$; $\therefore P = \theta I_Z \div a$. . . . (1)

For the free mass $P_1 \div g$ we have (§ 109) $P_1 - P =$ mass $\times$ acc.,

$= (P_1 \div g)p = (P_1 \div g)\theta a$; $\therefore P = P_1(1 - \theta a \div g)$. (2)

Equate these two values of P and solve for θ, whence

$$\theta = \frac{P_1 a}{Mk_z^2 + (P_1 \div g)a^2} \quad . \quad . \quad . \quad . \quad . \quad (3)$$

All the terms here are *constant*, hence θ is constant; therefore the rotary motion is *uniformly accelerated*, as also the translation of P_1. The formulæ of § 56, and (1), (2), (3), and (4) of § 110, are applicable. The tension P is also constant; see eq. (1). As for the five unknown reactions (components) at O_1 and O_2, the bearings, we shall find that they too are constant; for

from	(IX.) we have	$X_1+X_2=0$; (4)
from	(X.) we have	$P+Y_1+Y_2=0$; (5)
from	(XI.) we have	$Z_2-G=0$; (6)
from	(XII.) we have	$P\,.\,\overline{AO}+Y_1\,.\,\overline{O_1O}-Y_2\,.\,\overline{O_2O}=0$; (7)
from	(XIII.) we have	$-X_1\,.\,\overline{O_1O}+X_2\,.\,\overline{O_2O}=0$. (8)

Numerical substitution in the above problem.—Let the parallelopiped be of wrought-iron; let $P_1=48$ lbs.; $a=6$ in. $=\frac{1}{2}$ ft.; $b=3$ in. $=\frac{1}{4}$ ft. (see Fig. 112); $b_1=2$ ft. 3 in. $=\frac{9}{4}$ ft.; and $h=4$ in. $=\frac{1}{3}$ ft. Also let $\overline{O_1O}=\overline{O_2O}=18$ in. $=\frac{3}{2}$ ft., and $\overline{AO}=3$ in. $=\frac{1}{4}$ ft. Selecting the *foot-pound second* system of units, in which $g=32.2$, the linear dimensions must be used in feet, the heaviness, γ, of the iron must be used in *lbs. per cubic foot*, i.e., $\gamma=480$ (see § 7), and all forces in lbs., times in seconds.

The weight of the iron will be $G=V\gamma=bb_1h\gamma=\frac{1}{4}\,.\,\frac{9}{4}\,.\,\frac{1}{3}\times480=90$ lbs.; its mass $=90\div32.2=2.79$; and its moment of inertia about $Z=I_z=Mk_z^2=M\frac{1}{12}(b_1^2+b^2)=2.79\times0.426=1.191$. (That is, the *radius of gyration*, k_z, $=\sqrt{0.426}=0.653$ ft.; or the moment of inertia, or any result depending solely upon it, is just the same as if the mass were concentrated in a thin shell, or a line, or a point, at a distance of 0.653 feet from the axis.) We can now compute the angular acceleration, θ, from eq. (3);

$$\theta=\frac{48\times\frac{1}{2}}{1.191+(48\div32.2)\times\frac{1}{4}}=\frac{24}{1.191+0.372}=15.36$$

radians per sec. per sec. The linear acceleration of P_1 is $p=\theta a=7.68$ feet per sec. per sec. for the uniformly accelerated translation.

Nothing has yet been said of the velocities and initial conditions of the motions; for what we have derived so far applies to any point of time. Suppose, then, that the angular velocity $\omega=$ zero when the time, $t=0$; and correspondingly the velocity, $v=\omega a$, of translation of P_1, be also $=0$ when $t=0$. At the end of any time t, $\omega=\theta t$ (§§ 56 and 110) and $v=pt=\theta at$; also the angular space, $\alpha=\frac{1}{2}\theta t^2$, described by the parallelopiped during the time t, and the linear space $s=\frac{1}{2}pt^2=\frac{1}{2}\theta at^2$, through which the weight P_1 has sunk vertically. For example, during the first second the parallelopiped has rotated through an angle $\alpha=\frac{1}{2}\theta t^2=\frac{1}{2}\times15.36\times1=7.68$ radians, i.e., $(7.68\div2\pi)=1.22$ revolutions, while P_1 has sunk through $s=\frac{1}{2}\theta at^2=3.84$ ft., vertically.

The tension in the cord, from (2), is

$$P = 48(1 - 15.36 \times \tfrac{1}{2} \div g) = 48(1 - 0.24) = 36.48 \text{ lbs.}$$

The pressures at the bearings will be as follows, *at any instant:* from (4) and (8), X_1 and X_2 must individually be zero; from (6) $Z_2 = G = V\gamma = 90$ lbs.; while from (5) and (7), $Y_1 = -21.28$ lbs., and $Y_2 = -15.20$ lbs., and should point in a direction opposite to that in which they were assumed in Fig. 129 (see last lines of § 39).

117. The Compound Pendulum is any rigid body allowed to oscillate without friction under the action of gravity when mounted on a horizontal axis. Fig. 131 shows the body *free*, in any position during the progress of the oscillation. C is the centre of gravity; let $\overline{OC} = s$. From (XIV.), § 114, we have Σ (mom. about fixed axis)



FIG. 131.

$$= \text{angul. acc.} \times \text{mom. of inertia.}$$

$$\therefore -Gs \sin \alpha = \theta I_0,$$

$$\text{and } \theta = -Gs \sin \alpha \div I_0 = -Mgs \sin \alpha \div Mk_0^2,$$

$$\text{i.e., } \theta = -gs \sin \alpha \div k_0^2 \quad . \quad . \quad . \quad . \quad . \quad (1)$$

Hence θ is variable, proportional to sin α. Let us see what the length $l = \overline{OK}$, of a simple circular pendulum, must be, to have at this instant (i.e., for this value of α) the same angular acceleration as the rigid body. The linear (tangential) accelerations of K, the extremity of the required simple pendulum would be (§ 77) $p_t = -g \sin \alpha$, and hence its angular acceleration* would $= -g \sin \alpha \div l$. Writing this equal to θ in eq. (1), we obtain

$$l = k_0^2 \div s. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

But this is *independent of* α; therefore the length of the simple pendulum having an angular acceleration equal to that of the oscillating body is *the same in all positions of the latter*, and if the two begin to oscillate simultaneously from a position of rest at any given angle α_1 with the vertical, they will keep abreast of each other during the whole motion, and hence have

* Most easily obtained by considering that if the body shrinks into a mere point at K, and thus becomes a simple pendulum, we have both k_0 and s equal to l; which in (1) gives $\theta = -g \sin \alpha \div l$.

the same duration of oscillation; which is $\therefore$, *for small amplitudes* (§ 78),

$$t' = \pi\sqrt{l \div g} = \pi\sqrt{k_0^2 \div gs}, \quad . \quad . \quad . \quad . \quad (3)$$

K is called the *centre of oscillation* corresponding to the given *centre of suspension* O, and is identical with the *centre of percussion* (§ 113).

Example.—Required the time of oscillation of a cast-iron cylinder, whose diameter is 2 in. and length 10 in., if the axis of suspension is taken 4 in. above its centre. If we use 32.2 for g, all linear dimensions should be in feet and times in seconds. From § 100, we have

$$I_C = M(\tfrac{1}{4}r^2 + \tfrac{1}{12}h^2) = M(\tfrac{1}{4}\cdot\tfrac{1}{144} + \tfrac{1}{12}\cdot\tfrac{100}{144}) = M\tfrac{1}{144}\cdot\tfrac{103}{12}.$$

From eq. (3), § 88,

$$I_0 = I_C + Ms^2 = M[\tfrac{1}{144}\cdot\tfrac{103}{12} + \tfrac{1}{9}] = M \times 0.170;$$

$\therefore k_0^2 = 0.170$ sq. ft.; $\therefore t' = \pi\sqrt{0.170 \div (32.2 \times \tfrac{1}{3})} = 0.395$ sec.

118. The Centres of Oscillation and Suspension are Interchangeable.—(Strictly speaking, these centres are points in the line through the centre of gravity perpendicular to the axis of suspension.) Refer the centre of oscillation K to the centre of gravity, thus (Fig. 132, at (I.)):

$$s_1 = l - s = \frac{Mk_0^2}{Ms} - s = \frac{Mk_C^2 + Ms^2}{Ms} - s = \frac{k_C^2}{s}. \quad (1)$$

Now invert the body and suspend it at K; required CK_1, or s_2, to find the centre of oscillation corresponding to K as centre of suspension. By analogy from (1) we have $s_2 = k_C^2 \div s_1$; but from (1). $k_C^2 \div s_1 = s$ $\therefore$ $s_2 = s$: in other words, K_1 is identical with O. Hence the proposition is proved.



FIG. 132.

Advantage may be taken of this to determine the length L of the theoretical simple pendulum vibrating seconds, and thus finally the acceleration of gravity from formula (3), § 117, viz.,

when $t' = 1.0$ and l (now $= L$) has been determined experimentally, we have

$$g \text{ (in ft. per sq. second)} = L \text{ (in ft.)} \times \pi^2. \quad . \quad . \quad (2)$$

This most accurate method of determining g at any locality requires the use of a bar of metal, furnished with a sliding weight for shifting the centre of gravity, and with two projecting blocks provided with knife-edges. These blocks can also be shifted and clamped. By suspending the bar by one knife-edge on a proper support, the duration of an oscillation is computed by counting the total number in as long a period of time as possible; it is then reversed and suspended on the other with like observations. By shifting the blocks between successive experiments, the duration of the oscillation in one position is made the same as in the other, i.e., the distance between the knife-edges is the length, l, of the simple pendulum vibrating in the computed time (if the knife-edges are not equidistant from the centre of gravity), and is carefully measured. The l and t' of eq. (3), § 117, being thus known, g may be computed. The length, in *feet*, of the simple pendulum vibrating seconds, at any latitude β, and at a height of h *ft.* above sea-level, is (Chwolson, 1902).

$$L = 3.25974 - 0.008441 \cos 2\beta - 0.0000003h.$$

119. Isochronal Axes of Suspension.—*In any compound pendulum, for any axis of suspension, there are always three others, parallel to it in the same gravity-plane, for which the oscillations are made in the same time as for the first.* For any assigned time of oscillation t', eq. (3), § 117, compute the corresponding distance $\overline{CO} = s$ of O from C;

i.e., from $$t'^2 = \pi^2 \frac{Mk_o^2}{Mgs} = \frac{\pi^2(Mk_C^2 + Ms^2}{Mgs},$$

we have $$s = (gt'^2 \div 2\pi^2) \pm \sqrt{(g^2t'^4 \div 4\pi^4) - k_C^2}. \quad . \quad . \quad (1)$$

Hence for a given t', there are two positions for the axis O parallel to any axis through C, in any gravity-plane, on both sides; i.e., *four parallel axes of suspension*, in any gravity-plane, giving equal times of vibration; for two of these axes

we must reverse the body. E.g., if a slender, homogeneous, prismatic rod be marked off into thirds, the (small) vibrations will be of the same duration, if the centre of suspension is taken at either extremity, or at either point of division.

Example.—Required the positions of the axes of suspension, parallel to the base, of a right cone of brass, whose altitude is six inches, radius of base, 1.20 inches, and weight per cubic inch is 0.304 lbs., so that the time of oscillation may be a half-second. (N.B. For variety, use the inch-pound-second system of units, first consulting § 51.)

120. The Fly-Wheel in Fig. 133 at any instant experiences a pressure P' against its crank-pin from the connecting-rod and a resisting pressure P'' from the teeth of a spur-wheel with



FIG 133.

which it gears.* Its weight G acts through C (nearly), and there are pressures at the bearings, but these latter and G have no moments about the axis C (perpendicular to paper). The figure shows it *free*, P'' being assumed constant (in practice this depends on the resistances met by the machines which D drives, and the fluctuation of velocity of their moving parts). P', and therefore T its tangential component, are variable, depending on the effective steam-pressure on the piston at any instant, on the obliquity of the connecting-rod, and in high-speed engines on the masses and motions of the piston and connecting-rod. Let r = radius of crank-pin circle, and a the perpendicular from C on P''. From eq. (XIV.), § 114, we have

$$Tr - P''a = \theta I_C, \ \therefore \theta = (Tr - P''a) \div I_C, \quad . \quad (1$$

*Bearings at C not shown. P is the thrust in the piston-rod due to steam pressure on piston.

as the angular acceleration at any instant; substituting which in the general equation (VIII.), § 110, we obtain

$$I_C \omega d\omega = Tr d\alpha - P'' a d\alpha. \quad . \quad . \quad . \quad . \quad (2)$$

From (1) it is evident that if at any position of the crank-pin the variable Tr is equal to the constant $P''a$, θ is zero, and consequently the angular velocity ω is either a maximum or a minimum. Suppose this is known to be the case both at m and n; i.e., suppose T, which was zero at the dead-point A, has been gradually increasing, till at n, $Tr = P''a$; and thereafter increases still further, then begins to diminish, until at m Tr again $= P''a$, and continues to diminish toward the dead-point B. The angular velocity ω, whatever it may have been on passing the dead-point A, diminishes, since θ is negative, from A to n, where it is ω_n, a minimum; increases from n to m, where it reaches a maximum value, ω_m. n and m being known points, and supposing ω_n known, let us inquire what ω_m will be. From eq. (2) we have

$$I_C \int_{\omega_n}^{\omega_m} \omega d\omega = \int_n^m Tr d\alpha - P'' \int_n^m a d\alpha. \quad . \quad . \quad (3)$$

But $r d\alpha = ds =$ an element of the path of the crank-pin, and also the "virtual velocity" of the force T, and $a d\alpha = ds''$, an element of the path of a point in the pitch-circle of the fly-wheel, the small space through which P'' is overcome in dt. Hence (3) becomes

$$I_C \tfrac{1}{2}(\omega_m^2 - \omega_n^2) = \int_n^m T ds - P'' \times \text{linear arc } \overline{EF}. \quad (4)$$

To determine $\int_n^m T ds$ we might, by a knowledge of the varying steam-pressure, the varying obliquity of the connecting-rod, etc., determine T for a number of points equally spaced along the curve nm, and obtain an approximate value of this sum by Simpson's Rule; but a simpler method is possible by noting (see eq. (1), § 65) that each term $T ds$ of this sum = the corresponding term $P dx$ in the series $\int_{n'}^{m'} P dx$, in which $P =$ the

effective steam-pressure on the piston in the cylinder at any instant, dx the small distance described by the piston while the crank-pin describes any ds, and n' and m' the positions of the piston (or of cross-head, as in Fig. 133) when the crank-pin is at n and m respectively. (4) may now be written

$$I_C \tfrac{1}{2}(\omega_m^2 - \omega_n^2) = \int_{n'}^{m'} P dx - P'' \times \text{linear arc } \overline{EF}, \quad (5)$$

from which ω_m may be found as proposed. More generally, it is available, alone (or with other equations), to determine any one (or more, according to the number of equations) unknown quantity. This problem, in rotary motion, is analogous to that in § 59 (Prob. 4) for rectilinear motion. Friction and the inertia of piston and connecting-rod have been neglected. As to the time of describing the arc nm, from equations similar to (5), we may determine values of ω for points along nm, dividing it into an even number of equal parts, calling them ω_1, ω_2, etc., and then employ Simpson's Rule* for an approximate value of the sum $\left[_n^m t = \int_n^m \frac{d\alpha}{\omega}\right.$ (from eq. (VI.), § 110); e.g., with four parts, we would have

$$\left[_n^m t = \frac{1}{12}(\text{angle } nCm, \text{in rads.})\left[\frac{1}{\omega_n} + \frac{4}{\omega_1} + \frac{2}{\omega_2} + \frac{4}{\omega_3} + \frac{1}{\omega_m}\right]\right. . \quad (6)$$

121. Numerical Example. Fly-Wheel.—(See Fig. 133 and the equations of § 120.) Suppose the engine is non-condensing and non-expansive (i.e., that P is constant), and that

$$P = 5500 \text{ lbs.}, \quad r = 6 \text{ in.} = \tfrac{1}{2} \text{ ft.}, \quad a = 2 \text{ ft.},$$

and also that the wheel is to make 120 revolutions per minute, i.e., that its *mean angular velocity* is to be

$$\omega' = \tfrac{120}{60} \times 2\pi, \text{ i.e., } \omega' = 4\pi \text{ "radians" per sec.}$$

First, required the amount of the resistance P'' (constant) that there shall be no permanent change of speed, i.e., that the angular velocity shall have the same value at the end of a complete revolution as at the beginning. Since an equation of the form of eq. (5) holds good for any range of the motion, let

* See p. 13 of the "*Notes and Examples in Mechanics.*"

that range be a complete revolution, and we shall have zero as the left-hand member; $\int P dx = P \times 2$ ft. $= 5500$ lbs. $\times 2$ ft., or 11,000 foot-pounds (as it may be called); while P'' is unknown, and instead of lin. arc $\overline{EF}$ we have a whole circumference of 2 ft. radius, i.e., 4π ft.;

$\therefore 0 = 11{,}000 - P'' \times 4 \times 3.1416$; whence $P'' = 875$ lbs.

Secondly, required the proper mass to be given to the fly-wheel of 2 ft. radius that in the forward stroke (i.e., while the crank-pin is describing its *upper* semicircle) the max. angular velocity ω_m shall exceed the minimum ω_n by only $\frac{1}{10}\omega'$, assuming (which is nearly true) that $\frac{1}{2}(\omega_m + \omega_n) = \omega'$. There being now three unknowns, we require three equations, which are, including eq. (5) of § 120, viz.:

$$M k_C^2 \tfrac{1}{2}(\omega_m + \omega_n)(\omega_m - \omega_n) = \int_{n'}^{m'} P dx - P'' \times \text{linear arc } \overline{EF}; \quad (5)$$

$$\tfrac{1}{2}(\omega_m + \omega_n) = \omega' = 4\pi; \quad (7) \quad \text{and} \quad \omega_m - \omega_n = \tfrac{1}{10}\omega' = \tfrac{2}{5}\pi. \quad (8)$$

The points n and m are found most easily and with sufficient accuracy by a graphic process.* Laying off the dimensions to scale, by trial such positions of the crank-pin are found that T, the tangential component of the thrust P' produced in the connecting-rod by the steam-pressure P (which may be resolved into two components, along the connecting-rod and a normal to itself) is $= (a \div r)P''$, i.e., is $= 3500$ lbs. These points will be n and m (and two others on the lower semicircle). The positions of the piston n' and m', corresponding to n and m of the crank-pin, are also found graphically in an obvious manner. We thus determine the angle nCm to be 100°, so that linear arc $EF = \frac{100}{180}\pi \times 2$ ft. $= \frac{10}{9}\pi$ ft., while

$$\int_{n'}^{m'} P dx = 5500 \text{ lbs.} \times \int_{n'}^{m'} dx = 5500 \times \overline{n'm'} = 5500 \times 0.77 \text{ ft.},$$

$n'm'$ being scaled from the draft.

Now substitute from (7) and (8) in (5), and we have, with $k_C = 2$ ft. (which assumes that the mass of the fly-wheel is concentrated in the rim),

* See p. 85, "*Notes and Examples*," etc.

$(G \div g) \times 4 \times 4\pi \times \frac{2}{5}\pi = 5500 \times 0.77 - 875 \times \frac{10}{9}\pi$,

which being solved for G (with $g = 32.2$; since we have used the foot and second), gives $G = 600.7$ lbs.

The points of max. and min. angular velocity on the back-stroke may be found similarly, and their values for the fly-wheel as now determined; they will differ but slightly from the ω_m and ω_n of the forward stroke. Professor Cotterill says that the rim of a fly-wheel should never have a max. velocity > 80 ft. per sec.; and that if made in segments, not more than 40 to 50 feet per second. In the present example we have for the forward stroke, from eqs. (7) and (8), $\omega_m = 13.2$ (π-measure units) per second; i.e., the corresponding velocity of the wheel-rim is $v_m = \omega_m a = 26.4$ feet per second.

122. Angular Velocity Constant. Fixed Axis.—If ω is constant, the angular acceleration, θ, must be = zero at all times, which requires Σ (mom.) about the axis of rotation to be = 0 (eq. (XIV.), § 114). An instance of this occurs when the only forces acting are the reactions at the bearings on the axis, and the body's weight, parallel to or intersecting the axis; the values of these reactions are now to be determined for different forms of bodies, in various positions relatively to the axis. (The opposites and equals of these reactions, i.e., the forces with which the axis acts upon the bearings, are sometimes stated to be due to the "*centrifugal forces*," or "centrifugal action," of the revolving body.)



FIG. 134.

Take the axis of rotation for Z, then, with $\theta = 0$, the equations of § 114 reduce to

$$\Sigma X = -\omega^2 M\bar{x}; \quad . \quad . \quad . \quad . \quad \text{(IX}a\text{.)}$$

$$\Sigma Y = -\omega^2 M\bar{y}; \quad . \quad . \quad . \quad . \quad \text{(X}a\text{.)}$$

$$\Sigma Z = 0; \quad . \quad . \quad . \quad . \quad . \quad . \quad \text{(XI}a\text{.)}$$

$$\Sigma \text{ moms.}_X = -\omega^2 \int dM yz; \quad . \quad . \quad . \quad \text{(XII}a\text{.)}$$

$$\Sigma \text{ moms.}_Y = +\omega^2 \int dM xz; \quad . \quad . \quad . \quad \text{(XIII}a\text{.)}$$

$$\Sigma \text{ moms.}_Z = 0. \quad . \quad . \quad . \quad . \quad . \quad . \quad \text{(XIV}a\text{.)}$$

For greater convenience, let us suppose the axes X and Y (since their position is arbitrary so long as they are perpendicular to each other and to Z) *to revolve with the body* in its uniform rotation.

122a. *If a homogeneous body have a plane of symmetry and rotate uniformly about any axis Z perpendicular to that plane (intersecting it at O), then the acting forces are equivalent to a single force, $= \omega^2 M\bar{\rho}$, applied at O and acting in a gravity-line, but directed away from the centre of gravity.* It is evident that such a force $P = \omega^2 M\bar{\rho}$, applied as stated (see Fig. 135), will satisfy all six conditions expressed in the foregoing equations, taking X through the centre of gravity, so that $\bar{x} = \bar{\rho}$. For, from (IX*a*.), P must $= \omega^2 M\bar{\rho}$, while in each of the other summations the left-hand member will be zero, since P lies in the axis of X; and as their right-hand members will also be zero for the present body ($\bar{y} = 0$; and each of the sums $\int dMyz$ and $\int dMxz$ is zero, since for each term $dMy(+z)$ there is another $dMy(-z)$ to cancel it; and similarly, for $\int dMxz$), they also are satisfied; Q.E.D. Hence a single point of support at O will suffice to maintain the uniform motion of the body, and the pressure against it will be equal and opposite to P.*



Fig. 135.

First Example.—Fig. 136. Supposing (for greater safety) that the uniform rotation of 210 revolutions per minute of each segment of a fly-wheel is maintained solely by the tension in the corresponding arm, P; required the value of P if the segment and arm together weigh $\frac{1}{30}$ of a ton, and the distance of their centre of gravity from the axis is $\bar{\rho} = 20$ in., i.e., $= \frac{5}{3}$ ft. With the *foot-ton-second* system of units, with $g = 32.2$, we have



Fig. 136.

$$P = \omega^2 M\bar{\rho} = \left[\tfrac{210}{60} \times 2\pi\right]^2 \times \left[\tfrac{1}{30} \div 32.2\right] \times \tfrac{5}{3} = 0.83 \text{ tons},$$

or 1660 lbs.

* That is, neglecting gravity. The body's weight, if considered, will take its place among the *actual* forces acting on the body.

Second Example.—Fig. 137. Suppose the uniform rotation of the same fly-wheel depends solely on the tension in the rim, required its amount. The figure shows the half-rim free, with the two equal tensions, P', put in at the surfaces exposed. Here it is assumed that the arms exert no tension on the rim. From § 122*a* we have $2P' = \omega^2 M\bar{\rho}$, where M is the mass of the half-rim, and $\bar{\rho}$ its gravity co-ordinate, which may be obtained approximately by § 26, Problem 1, considering the rim as a circular wire, viz., $\bar{\rho} = 2r \div \pi$.



FIG. 137.

Let $M = (180 \text{ lbs.}) \div g$, with $r = 2$ ft. We have then

$$P' = \tfrac{1}{2}(22)^2(180 \div 32.2)(4 \div \pi) = 1718.0 \text{ lbs.}$$

(In reality neither the arms nor the rim sustain the tensions just computed; in treating the arms we have supposed no duty done by the rim, and *vice versâ*. The actual stresses are less, and depend on the yielding of the parts. Then, too, we have supposed the wheel to take no part in the transmission of motion by belting or gearing, which would cause a bending of the arms, and have neglected its weight.)

122b. *If a homogeneous body have a line of symmetry and rotate uniformly about an axis parallel to it (O being the foot of the perpendicular from the centre of gravity on the axis), then the acting forces are equivalent to a single force* $P = \omega^2 M\bar{\rho}$, *applied at O and acting in a gravity-line away from the centre of gravity.* Taking the axis X through the centre of gravity, Z being the axis of rotation, Fig. 138, while Z' is the line of symmetry, pass an auxiliary plane $Z'Y'$ parallel to ZY. Then the sum $\int dMxz$ may be written $\int dM(\bar{\rho} + x')z$ which $= \bar{\rho}\int dMz + \int dMx'z$. But $\int dMz = M\bar{z} = 0$, since $\bar{z} = 0$, and every term $dM(+x')z$ is cancelled by a numerically



FIG. 138.

equal term $dM(-x')z$ of opposite sign. Hence $\int dMxz = 0$. Also $\int dMyz = 0$, since each positive product is annulled by an equal negative one (from symmetry about Z'). Since, also, $\bar{y} = 0$, all six conditions in § 122 are satisfied. Q. E. D.

If the homogeneous body is any solid of revolution *whose geometrical axis is parallel to the axis of rotation*, the foregoing is directly applicable.

122c. *If a homogeneous body revolve uniformly about any axis lying in a plane of symmetry, the acting forces are equivalent to a single force* $P = \omega^2 M\bar{\rho}$, *acting parallel to the gravity-line which is perpendicular to the axis* (Z), *and away from the centre of gravity, its distance from any origin* O *in the axis* Z *being* $= [\int dMxz] \div M\bar{\rho}$ (*the plane* ZX *being a gravity-plane*).—Fig. 139. From the position of the body we have $\bar{\rho} = \bar{x}$, and $\bar{y} = 0$; hence if a value $\omega^2 M\bar{\rho}$ be given to P and it be made to act through Z and parallel to X, and away from the centre of gravity, all the conditions of § 122 are satisfied except (XII*a*.) and (XIII*a*.). But symmetry about the plane XZ makes $\int dMyz = 0$, and satisfies (XII*a*.), and by placing P at a distance $a = \int dMxz \div M\bar{\rho}$ from O along Z we satisfy (XIII*a*.). Q. E. D.



Fig. 139.

Example.—A *slender*, homogeneous, prismatic rod, of length $= l$, is to have a uniform motion, about a vertical axis passing through one extremity, maintained by a cord-connection with a fixed point in this axis. Fig. 140. Given ω, φ, l, ($\bar{\rho} = \frac{1}{2}l \cos \varphi$), and F the cross-section of the rod, let s = the distance from O to any dM of the rod, dM being $= F\gamma ds \div g$. The x of any $dM = s \cos \varphi$; its $z = s \sin \varphi$;



Fig. 140.

$$\therefore \int dMxz = (F\gamma \div g) \sin \varphi \cos \varphi \int_0^l s^2 ds$$

$$= \tfrac{1}{3}(F\gamma l \div g) l^2 \sin \varphi \cos \varphi = \tfrac{1}{3} M l^2 \sin \varphi \cos \varphi.$$

Hence $a, = \int dMxz \div M\bar{\rho}$, is $= \frac{2}{3}l \sin \varphi$, and the line of action of $P\,(= \omega^2 M\bar{\rho} = \omega^2 (F\gamma l \div g)\frac{1}{2}l \cos \varphi)$ is therefore *higher up than the middle of the rod.* Find the intersection D of G and the horizontal drawn through Z at distance a from O. Determine P' by completing the parallelogram GP', attaching the cord so as to make it coincide with P'; for this will satisfy the condition of maintaining the motion, when once begun, viz., that the acting forces G, and the cord-tension P', shall be equivalent to a force $P = \omega^2 M\bar{\rho}$, applied horizontally through Z at a distance a from O.

123. Free Axes. Uniform Rotation.—Referring again to § 122 and Fig. 134, let us inquire under what circumstances the lateral forces, X_1, Y_1, X_0, Y_0, with which the bearings press the axis, to maintain the motion, are individually zero, i.e., *that the bearings are not needed, and may therefore be removed* (except a smooth horizontal plane to sustain the body's weight), leaving the motion undisturbed like that of a top "asleep." For this, not only must ΣX and ΣY both be zero, but also (since otherwise X_1 and X_0 might form a *couple*, or Y_1 and Y_0 similarly) $\Sigma\,(\text{moms.})_X$ and $\Sigma\,(\text{moms.})_Y$ must each $=$ zero. The necessary peculiar distribution of the body's mass about the axis of rotation, then, must be as follows (see the equations of § 122):

First, $\bar{x}$ and $\bar{y}$ each $= 0$, i.e., *the axis must be a gravity-axis.*

Secondly, $\int dMyz = 0$, and $\int dMxz = 0$, the origin being anywhere on Z, the axis of rotation.

An axis (Z) (of a body) fulfilling these conditions is called a **Free Axis**, and since, if either one of the three *Principal Axes* for the centre of gravity (see § 107) be made an axis of rotation (the other two being taken for X and Y), the conditions $\bar{x} = 0$, $\bar{y} = 0$, $\int dMxz = 0$, and $\int dMyz = 0$, are all satisfied, *it follows that every rigid body has at least three free axes, which are the Principal Axes* of Inertia of the centre of gravity at right angles to each other.*

In the case of *homogeneous bodies* free axes can often be determined by inspection: e.g., any diameter of a sphere; any

* See § 107. p. 104.

transverse diameter of a right circular cylinder through its centre of gravity, as well as its geometrical axis; the geometrical axis of any solid of revolution; etc.

124. Rotation about an Axis which has a Motion of Translation.—*Take only the particular case where the moving axis is a gravity-axis.* At any instant, let the velocity and acceleration of axis Z be v and p; the angular velocity and acceleration about that axis, ω and θ. Then, since the actual motion of a dM in any dt is compounded of its motion of rotation about the gravity-axis and the motion of translation in common with that axis, we may, in forming the imaginary equivalent system in Fig. 141, consider each dM as subjected to the simultaneous action of $dP = dMp$ parallel to X, of the tangential $dT = dM\theta\rho$, and of the normal $dN = dM(\omega\rho)^2 \div \rho = \omega^2 dM\rho$. Take X in the direction of translation, Z (perpendicular to paper through O) is the moving gravity-axis; Y perpendicular to both. At any instant we shall have, then, the following conditions for the acting forces (remembering that $\rho \sin \varphi = y$, $\int dMy = M\bar{y} = 0$; etc.):



Fig. 141.

$$\Sigma X = \int dP - \int dT \sin\varphi - \int dN \cos\varphi = Mp; \quad . \quad (1)$$

$$\Sigma Y = \int dT \cos\varphi - \int dN \sin\varphi \qquad = 0; \quad . \quad . \quad (2)$$

$$\Sigma \text{ moms.}_Z = \int dT\rho - \int dPy = \theta \int dM\rho^2 = \theta I_Z = \theta M k_Z^2, \quad (3)$$

and three other equations not needed in the following example.

Example.—A homogeneous solid of revolution rolls (without slipping) down a rough inclined plane. Investigate the motion. Considering the body *free*, the acting forces are G (known) and N and P, the unknown normal and tangential components of the action of the plane on the roller. If slipping occurs, then P is the sliding friction due to the pressure N (§ 156); here, however, it is less by hypothesis (perfect rolling). At any instant the four unknowns are found by the equations



Fig. 142.

$$\Sigma X, \text{ i.e., } G \sin\beta - P, = (G \div g)p; \quad . \quad (1)$$

$$\Sigma Y, \text{ i.e., } G \cos\beta - N, = 0; \quad . \quad . \quad . \quad . \quad (2)$$

$$\Sigma \text{ moms.}_Z, \text{ i.e., } \quad Pa, = \theta M k_Z^2; \quad . \quad . \quad (3)$$

while on account of the perfect rolling, $\theta a = p$ . . . (4)

Solving, we have, for the acceleration of translation,

$$p = g \sin\beta \div [1 + (k_Z^2 \div a^2)].$$

(If the body slid without friction, p would $= g \sin\beta$.) Hence for a cylinder (§ 97), k_Z^2 being $= \frac{1}{2}a^2$, we have $p = \frac{2}{3}g \sin\beta$; and for a sphere (§ 103) $p = \frac{5}{7}g \sin\beta$.

(If the plane is so steep or so smooth that both rolling and slipping occur, then θa no longer $= p$, but the ratio of P to N is known from experiments on sliding friction; hence there are still four equations.)

The motion of translation being thus found to be uniformly accelerated, we may use the equations of § 56.

Numerically, if a homogeneous solid sphere took 1.20 sec. to descend (from rest() 10 ft. along a rough inclined plane, with $\beta = 30°$, did any slipping occur, or was the motion perfect rolling? From p. 54 we have $s = \frac{1}{2}pt^2$, that is, $10 = \frac{1}{2} \cdot \frac{5}{7} \cdot g \sin 30° \cdot t^2$, for perfect rolling; from which we obtain $t = 1.32$ seconds, which is > 1.20 sec. Hence some slipping must have occurred. (The time of descent would have been only $t = \sqrt{2s \div \frac{1}{2}g} = 1.114$ sec., if the surfaces had been perfectly smooth; and the sphere would have had simply a motion of translation, the force P being zero).

N.B.—A hollow sphere would occupy a *longer time* than a solid one in descending the plane (if rough); since the ratio $k_z \div a$ is greater for the former.

125. Parallel-Rod of a Locomotive.—When the locomotive moves uniformly, each dM of the rod between the two (or three) driving-wheels rotates with uniform velocity about a centre of its own on the line BD, Fig. 143, and with a velocity v* and radius r common to all, and likewise has a horizontal *uniform* motion of translation. Hence if we inquire what are the reactions P



FIG. 143.

* This velocity is that which the dM has *relatively to the frame of the locomotive*, in a circular path. E.g., if the locomotive (frame) has a velocity of 60 miles per hour and the radius r is one-third of the radius of the driver, then v is 20 miles per hour.

of its supports, as induced *solely by its weight and motion*, when in its lowest position (independently of any thrust along the rod), we put ΣY of (I.) $= \Sigma Y$ of (II.) (II. shows the imaginary equivalent system), and obtain

$$2P - G = \int dN = \int dM v^2 \div r = (v^2 \div r) \int dM = Mv^2 \div r.$$

Example.—Let the velocity of translation $= 50$ miles per hour, the radius* of the pins be 18 in. $= \frac{3}{2}$ ft., and $=$ *half that of the driving-wheels*, while the weight of the rod is 200 lbs. With $g = 32.2$, we must use the foot and second, and obtain

$$v = \tfrac{1}{2}[50 \times 5280 \div 3600] \text{ ft. per second} = 36.6;$$

while $M = 200 \div 32.2 = 200 \times .0310 = 6.20$;

and finally $P = \frac{1}{2}[200 + 6.2(36.6)^2 \div \frac{3}{2}] = 2868.3$ lbs.,

or nearly $1\frac{1}{2}$ tons, *about thirty times that due to the weight alone.*

126. So far in this chapter the motion has been prescribed, and the necessary conditions determined, to be fulfilled by the acting forces at any instant. Problems of a converse nature, i.e., where the initial state of the body and the acting forces are given while the resulting motion is required, are of much greater complexity, but of rare occurrence in practice.

For further study in this direction the reader is referred to Routh's "*Rigid Dynamics*," Rankine's "*Applied Mechanics*," Schell's "*Theorie der Bewegung und der Kraefte*," and Worthington's "*Dynamics of Rotation*" (this last being a small but clearly written and practical book).

In Wood's "Analytical Mechanics" will be found the proof of "Euler's Equations," which are the basis of the treatment of the gyroscope in the book of that name by Gen. J. G. Barnard (Van Nostrand's *Science Series*, No. 90). The article on the gyroscope in Johnson's Cyclopædia is by Gen. Barnard. Perry's "*Spinning Tops*" is an interesting popular book.

The Brennan "Monorail Car" (model) is described in the *Engineering Record* for Aug. 31, 1907, p. 226, and depends for its stability (there being but one rail under the car) upon two gyroscope wheels revolving at 7000 revs. per min. in a vertical plane parallel to the rail. See also *McClure's Magazine* for Dec., 1907, p. 163.

* Or, rather, the radius of the circular path of the pin-centre, whose velocity in this path is 25 miles per hour.

CHAPTER VI.

WORK, ENERGY, AND POWER.

127. Remark.—These quantities as defined and developed in this chapter, though compounded of the fundamental ideas of matter, force, space, and time, enter into theorems of such wide application and practical use as to more than justify their consideration as separate kinds of quantity.

128. Work in a Uniform Translation. Definition of Work.—Let Fig. 144 represent a rigid body having a motion of translation parallel to X, acted on by a system of forces P_1, P_2, R_3, and R_4, which remain constant.*



FIG. 144.

Let s be any distance described by the body during its motion; then ΣX must be zero (§ 109), i.e., noting that R_3 and R_4 have negative X components (the supplements of their angles with X are used),

$$P_1 \cos \alpha_1 + P_2 \cos \alpha_2 - R_3 \cos \alpha_3 - R_4 \cos \alpha_4 = 0;$$

or, multiplying by s and transposing, we have (noting that $s \cos \alpha_1 = s_1$ the *projection* of s on P_1, that $s \cos \alpha_2 = s_2$, the *projection* of s on P_2, and so on),

$$P_1 s_1 + P_2 s_2 = R_3 s_3 + R_4 s_4. \quad . \quad . \quad . \quad . \quad (a)$$

The projections s_1, s_2, etc., may be called the *distances described in their respective directions* by the forces P_1, P_2, etc.; P_1 and P_2 having moved *forward*, since s_1 and s_2 fall *in front* of the initial position of their points of application; R_3 and R_4 *backward*, since s_3 and s_4 fall *behind* the initial positions in their case. (By forward and backward we refer to the direc-

* Constant in *direction* as well as amount.

tion of each force in turn.) The name **Work** is given to the *product of a force by the distance described in the direction of the force by the point of application.* If the force moves *forward* (see above), it is called a *working-force*, and is said *to do* the work (e.g., $P_1 s_1$) expressed by this product; while if *backward*, it is called a *resistance*, and is then said *to have the work* (e.g., $R_3 s_3$), *done upon it*, in *overcoming it* through the distance mentioned (it might also be said to have done negative work).

Eq. (*a*) above, then, proves the theorem that: *In a uniform translation, the working forces do an amount of work which is entirely applied to overcoming the resistances.*

129. Unit of Work.—Since the work of a force is a product of force by distance, it may logically be expressed as so many foot-pounds, inch-pounds, kilogram-meters, according to the system of units employed. The ordinary English unit is the foot-pound, or ft.-lb. It is of the same quality as a force-moment.

130. Power.—Work as already defined does not depend on the time occupied, i.e., the work $P_1 s_1$ is the same whether performed in a long or short time; but the element of time is of so great importance in all the applications of dynamics, as well as in such practical commercial matters as water-supply, consumption of fuel, fatigue of animals, etc., that the *rate of work* is a consideration both of interest and necessity.

Power is the rate at which work is done, and one of its units is one foot-pound per second in English practice; a larger one will be mentioned presently.

The *power exerted* by a *working force*, or *expended* upon a *resistance*, may be expressed symbolically as

$$L = P_1 s_1 \div t, \quad \text{or} \quad R_3 s_3 \div t,$$

in which t is the time occupied in doing the work $P_1 s_1$ or $R_3 s_3$ (see Fig. 144); or if v_1 is the component in the direction of the force P_1 of the velocity v of the body, we may also write

$$L = P_1 v_1, \text{ ft.-lbs. per sec.} \quad . \quad . \quad . \quad . \quad (b)$$

131. *Example.*—Fig. 145, shows as a *free body* a sledge which is being drawn *uniformly* up a rough inclined plane by a cord parallel to the plane. Required the total power exerted (and expended), if the tension in the cord is $P_1 = 100$ lbs., the weight of sledge $R_3 = 160$ lbs., $\beta = 30°$, and the sledge moves 240 ft. each minute. N and R_4 are the normal and parallel (i.e., R_4 = friction) components of the reaction of the plane on the sledge. From eq. (1), § 128, the work done while the sledge advances through $s = 240$ ft. may be obtained either from the working forces, which in this case are represented by P_1 alone, or from the resistances R_3 and R_4. Take the former method first. Projecting s upon P_1 we have $s_1 = s$.



FIG. 145.

Hence $P_1 s_1$ or 100 lbs. $\times$ 240 ft. = 24,000 ft.-lbs.

of work done in 60 seconds. That is, the *power exerted by the working forces* is

$$L = P_1 s_1 \div t = 400 \text{ ft.-lbs. per second.}$$

As to the other method, we notice that R_3 and R_4 are resistances, since the projections $s_3 = s \sin \beta$, and $s_4 = s$, would fall back of their points of application in the initial position, while N is *neutral*, i.e., is neither a working force nor a resistance, since the projection of s upon it is zero.

From $\Sigma X = 0$ we have $-R_4 - R_3 \sin \beta + P_1 = 0$,
and from $\Sigma Y = 0$ (§ 109) $N - R_3 \cos \beta = 0$;

whence R_4 the friction = 20 lbs., and $N = 138.5$ lbs. Also, since $s_3 = s \sin \beta = 240 \times \frac{1}{2} = 120$ ft., and $s_4 = s$, = 240 ft., we have for the work done upon the resistances (i.e., in overcoming them) in 60 seconds

$$R_3 s_3 + R_4 s_4 = 160 \times 120 + 20 \times 240 = 24{,}000 \text{ ft.-lbs.,}$$

and the *power expended in overcoming resistances*,

$$L = 24{,}000 \div 60 = 400 \text{ ft.-lbs. per second,}$$

as already derived. Or, in words the power exerted by the tension in the cord is expended entirely in raising the weight a vertical height of 2 feet, and overcoming the friction through

a distance of 4 feet along the plane, every second; *the motion being a uniform translation.*

132. Horse-Power.—As an average, a horse can exerts a tractive effort or pull of 100 lbs., at a uniform pace of 4 ft. per second, for ten hours a day without too great fatigue. This gives a power of 400 ft.-lbs. per second; but Boulton & Watt in rating their engines, and experimenting with the strong dray-horses of London, fixed upon 550 ft.-lbs. per second, or 33,000 ft.-lbs. per minute, as a convenient large unit of power. (The French horse-power, or *cheval-vapeur*, is slightly less than the English, being 75 kilogrammeters per second, or 32,550 ft.-lbs. per minute.) This value for the horse-power is in common use. In the example in § 131, then, the power of 400 ft.-lbs. per second exerted in raising the weight and overcoming friction may be expressed as $(400 \div 550 =) \frac{8}{11}$ of a horse-power. A man can work at a rate equal to about $\frac{1}{12}$ of a horse-power, with proper intervals for eating and sleeping.

133. Kinetic Energy. Retarded Translation.—In a retarded translation of a rigid body whose mass $= M$, suppose there are no working-forces, and that the resistances are constant and their resultant is R. (E.g., Fig. 146 shows such a case; a sledge, having an initial velocity c and sliding on a rough horizontal plane, is gradually retarded by the friction R.) R is parallel to the direction of translation (§ 109) and the acceleration is $p = -R \div M$; hence from $vdv = pds$ we have



FIG. 146.

$$\int vdv = -(1 \div M) \int Rds. \quad . \quad . \quad . \quad . \quad (1)$$

But the projection of each ds of the motion upon R is $= ds$ itself; i.e. (§ 128), Rds is the *work done upon* R, in overcoming it through the small distance ds, and $\int Rds$ is the sum of all such amounts of work throughout any definite portion of the motion. Let the range of motion be between the points where the velocity $= c$, and where it $=$ zero (i.e., the mass has come to rest). With these limits in eq. (1), (0 and s' being the corresponding limits for s), we have

$$\frac{Mc^2}{2} = \int_0^{s'} Rds. \quad . \quad . \quad . \quad . \quad . \quad . \quad (c)$$

That is, *in giving up all its velocity c the body has been able to do the work* $\int Rds$ (this, if R remains constant, reduces to Rs') or its equal $\frac{Mc^2}{2}$. If, then, by **energy** we designate the *ability to perform work*, we give the name **kinetic energy** of a moving body to *the product of its mass by half the square of its velocity* $\left(\frac{Mv^2}{2}\right)$; i.e., energy due to motion.

Example.—If the sledge in Fig. 146 has initially a velocity of $c=10$ ft./sec. and its weight is $G=322$ lbs. (so that its mass in the ft.-lb.-sec. system is $M=10$) its initial kinetic energy is $Mc^2 \div 2=500$ ft.-lbs. If the friction or resistance, R, is constant and has a value of 20 lbs., we compute $s'=25$ ft. (from $500=Rs'$) as the distance the sledge will go in overcoming this resistance; i.e., in giving up all its kinetic energy. If the sledge goes 40 ft. we conclude the average resistance to have been only 12.5 lbs.; since $500 \div 40=12.5$. Now suppose R variable, say $=(20+4s)$ lbs., (s in ft.), and we have $500=\int_0^{s'}[20+4s]ds=20s'+2s'^2$; $\therefore\ s'=11.6$ ft.

134. Work and Kinetic Energy in any Translation.—Let P be the resultant of the working forces at any instant, R that of the resistances; they (§ 109) will both act in a gravity-line * parallel to the direction of translation. The acceleration at any instant is $p=(\Sigma X \div M)$ $=(P-R) \div M$; hence from $vdv=pds$ we have



FIG. 147.

$$Mvdv=Pds-Rds. \quad . \quad . \quad . \quad . \quad . \quad (1)$$

Integrating between any two points of the motion as O and O' where the velocities are v_0 and v', we have after transposition

$$\int_0^{s'} Pds=\int_0^{s'} Rds+\left[\frac{Mv'^2}{2}-\frac{Mv_0^2}{2}\right]. \quad . \quad . \quad (d)$$

But P being the resultant of P_1, P_2, etc., and R that of R_1, R_2, etc., we may prove, as in § 62, that if du_1, du_2, etc., be the respective projections of any ds upon P_1, P_2, etc., while dw_1, dw_2, etc., are those upon R_1, R_2, etc., then

$Pds=P_1du_1+P_2du_2+\ldots$. and $Rds=R_1dw_1+R_2dw_2\ldots$.;

and (*d*) may be rewritten

* That is, a line passing through the centre of gravity.

$$\int_0^{s'} P_1 du_1 + \int_0^{s'} P_2 du_2 + \ldots .$$
$$= \int_0^{s'} R_1 dw_1 + \int_0^{s'} R_2 dw_2 + \ldots . + \left[\frac{Mv'^2}{2} - \frac{Mv_0^2}{2}\right]; \quad (e)$$

or, in words: *In any translation, a portion of the work done by the working forces is applied in overcoming the resistances while the remainder equals the change in the kinetic energy of the body.*

It will be noted that the bracket in (*e*) depends only on the initial and final velocities, and not upon any intermediate values; hence, if the initial state is one of rest, and also the final, the total change in kinetic energy is zero, and the work of the working forces has been entirely expended in the work of overcoming the resistances; but at intermediate stages the former exceeds the work so far needed to overcome resistances, and this excess is said to be *stored* in the moving mass; and as the velocity gradually becomes zero, this stored energy becomes available for aiding the working forces (which of themselves are then insufficient) in overcoming the resistances, and is then said to be *restored*. (The function of a fly-wheel might be stated in similar terms, but as that involves rotary motion it will be deferred.)

Work applied in increasing the kinetic energy of a body is sometimes called "work of inertia," as also the work done by a moving body in overcoming resistances, and thereby losing speed.

135. Example of Steam-Hammer.—Let us apply eq. (*e*) to determine the velocity v' attained by a steam-hammer at the lower end of its stroke (the initial velocity being $= 0$), just before delivering its blow upon a forging, supposing that the steam-pressure P_2 at all stages of the downward stroke is given by an *indicator*. Fig. 148. Weight of moving mass is 322 lbs.; $\therefore M = 10$ (foot-pound-second system), $l = 1$ foot. The *working forces* at any instant are $P_1 = G = 322$ lbs.; P_2, which is variable, but whose values at the seven *equally spaced*

points a, b, c, d, e, f, g, are 800, 900, 900, 800, 600, 500, 450 lbs., respectively. R_1 the exhaust-pressure (16 lbs. per sq. inch $\times$ 20 sq. inches piston-area) = 320 lbs., is the only resistance, and is constant. Hence from eq. (e), since here the projections du_1, etc., of any ds upon the respective forces are equal to each other and $= ds$,



FIG. 148.

$$P_1\int_0^l ds + \int_0^l P_2 ds = R_1\int_0^l ds + \frac{Mv'^2}{2}. \quad (1)$$

The term $\int P_2 ds$ can be obtained approximately* by Simpson's Rule, using the above values for six equal divisions, which gives

$$\tfrac{1}{18}[800 + 4(900 + 800 + 500) + 2(900 + 600) + 450]$$

$= 725$ ft.-lbs. of work. Hence, making all the substitutions, we have, since $\int_0^l ds = 1$ ft.,

$$322 \times 1 + 725 = 320 \times 1 + \tfrac{1}{2}Mv'^2; \quad \therefore \tfrac{1}{2}Mv'^2 = 727 \text{ ft.-lbs.}$$

of energy to be expended on the forging. (Energy is evidently expressed in the same kind of unit as work.) We may then say that the forging receives a blow of 727 ft.-lbs. energy. The pressure actually felt at the surface of the hammer varies from instant to instant during the compression of the forging and the gradual stopping of the hammer, and depends on the readiness with which the hot metal yields.

If the *mean resistance* encountered is R_m, and the depth of compression s'', we would have (neglecting the force of gravity, and noting that now the initial velocity is v', and the final zero), from eq. (c),

$$\tfrac{1}{2}Mv'^2 = R_m s''; \text{ i.e., } R_m = [727 \div s'' \text{ (ft.)}] \text{ lbs.}$$

E.g., if $s'' = \frac{1}{5}$ of an inch $= \frac{1}{60}$ of a foot, $R_m = 43620$ lbs., and the maximum value of R would probably be about double this near the end of the impact. If the anvil also sinks during the impact a distance s''', we must substitute $s''' + s''$ instead of s''; this will give a smaller value for R_m.

* See p. 13 of "*Notes and Examples in Mechanics.*"

By mean value for R is meant [eq. (*c*)] that value, R_m, which satisfies the relation

$$R_m s' = \int_0^{s'} R ds.$$

This may be called more explicitly a *space-average*, to distinguish it from a *time-average*, which might appear in some problems, viz., a value R_{tm}, to satisfy the relation (t' being the duration of the impact)

$$R_{tm} t' = \int_0^{t'} R dt,$$

and is different from R_m.

From $\frac{1}{2}Mv'^2 = 727$ ft.-lbs., we have $v' = 12.06$ ft. per sec., whereas for a free fall it would have been $\sqrt{2 \times 32.2 \times 1} = 8.03$. (This example is virtually of the same kind as Prob. 4, § 59, differing chiefly in phraseology.)

136. Pile-Driving.*—The safe load to be placed upon a pile after the driving is finished is generally taken as a fraction (from $\frac{1}{6}$ to $\frac{1}{8}$) of the resistance of the earth to the passage of the pile as indicated by the effect of the last few blows of the ram, in accordance with the following approximate theory: Toward the end of the driving the resistance R encountered by the pile is nearly constant, and is assumed to be that met by the ram at the head of the pile; the distance s' through which the head of the pile sinks as an effect of the last blow is observed. If G, then, is the weight of the ram, $= Mg$, and h the height of free fall, the velocity due to h, on striking the pile, is $c = \sqrt{2gh}$ (§ 52), and we have, from eq. (*c*),



FIG. 149.

$$\tfrac{1}{2}Mc^2, \text{ i.e., } Gh, = \int_0^{s'} R ds = Rs' \quad . \quad . \quad (1)$$

(R being considered constant); hence $R = Gh \div s'$, and the *safe load* (for ordinary wooden piles),

$$P = \text{from } \tfrac{1}{6} \text{ to } \tfrac{1}{8} \text{ of } Gh \div s'. \quad . \quad . \quad . \quad . \quad (2)$$

Maj. Sanders recommends $\frac{1}{8}$ from experiments made at Fort

* See also p. 87 of the author's *Notes and Examples in Mechanics.*

Delaware in 1851; Molesworth, $\frac{1}{8}$; General Barnard, $\frac{1}{6}$, from extensive experiments made in Holland.

Of course from eq. (2), given P, we can compute s'.

(Owing to the uncertainty as to how much of the resistance R is due to friction of the soil on the sides of the pile, and how much to the inertia of the soil around the shoe, the more elaborate theories of Weisbach and Rankine seem of little practical account.)

137. *Example.*—In preparing the foundation of a bridge-pier it is desired that each pile (placing them 4 ft. apart) shall bear safely a load of 72 tons. If the ram weighs one ton, and falls 12 ft., what should be the effect of the last blow on each pile? Using the foot-ton-second system of units, and Molesworth factor $\frac{1}{8}$, eq. (2) gives

$$s' = \tfrac{1}{8}(1 \times 12 \div 72) = \tfrac{1}{48} \text{ of a foot} = \tfrac{1}{4} \text{ of an inch.}$$

That is, the pile should be driven until it sinks only $\frac{1}{4}$ inch under each of the last few blows.

138. Kinetic Energy Lost in Inelastic Direct Central Impact.—Referring to § 60, and using the same notation as there given, we find that if the united kinetic energy possessed by two inelastic bodies after their impact, viz., $\frac{1}{2}M_1C^2 + \frac{1}{2}M_2C^2$, C having the value $(M_1c_1 + M_2c_2) \div (M_1 + M_2)$, be deducted from the amount before impact, viz., $\frac{1}{2}M_1c_1^2 + \frac{1}{2}M_2c_2^2$, the *loss of kinetic energy during impact of two inelastic bodies* is *

$$W = \frac{\frac{1}{2}M_1M_2}{M_1 + M_2}(c_1 - c_2)^2. \quad . \quad . \quad . \quad . \quad . \quad (1)$$

An equal amount of energy is also lost by partially elastic bodies during the first period of the impact, but is partly regained in the second. If the bodies were perfectly elastic, we would find it wholly regained and the resultant loss zero, from the equations of § 60; but this is not quite the reality, on account of internal vibrations.

The *kinetic energy still remaining in two inelastic bodies* after impact (they move together as one mass) is

* See *Eng. News*, July, 1888, pp. 33 and 34.

$\frac{1}{2}(M_1 + M_2)C^2$, or, after inserting the value of $C = (M_1c_1 + M_2c_2) \div (M_1 + M_2)$, we have

$$W = \frac{1}{2} \cdot \frac{[M_1c_1 + M_2c_2]^2}{M_1 + M_2} \quad \ldots \ldots \quad (2)$$



FIG. 150.

Example 1.—The weight $G_1 = M_1g$ falls freely through a height h, impinging upon a weight $G_2 = M_2g$, which was initially at rest. After their (*inelastic*) impact they move on together with the combined kinetic energy just given in (2), which, since c_1 and c_2, the velocities before impact, are respectively $\sqrt{2gh}$ and 0, may be reduced to a simpler form. This energy is soon absorbed in overcoming the flange-pressure R, which is proportional (so long as the elasticity of the rod is not impaired) to the elongation s, as with an ordinary spring. If from previous experiment it is known that a force R_0 produces an elongation s_0, then the variable $R = (R_0 \div s_0)s$. Neglecting the weight of the two bodies as a working force, we now have, from eq. (*d*),

$$0 = \frac{R_0}{s_0}\int_0^{s'} s\,ds + 0 - \frac{M_1^2gh}{M_1 + M_2};$$

$$\text{i.e.,} \quad \frac{R_0}{s_0} \cdot \frac{s'^2}{2} = \frac{M_1^2gh}{M_1 + M_2} \quad \ldots \ldots \quad (3)$$

When $s = s'$, i.e., when the masses are (momentarily) at rest in the lowest position, the flange-pressure or tensile stress in the rod is a maximum, $R' = (R_0 \div s_0)s'$, whence $s' = R's_0 \div R_0$; and (3) may be written

$$\frac{R'}{2}s' = \frac{M_1^2gh}{M_1 + M_2}, \quad \ldots \ldots \quad (4)$$

or

$$\frac{R'^2s_0}{2R_0} = \frac{M_1^2gh}{M_1 + M_2} \quad \ldots \ldots \quad (5)$$

Eq. (3) gives the final elongation of the rod, and (5) the greatest tensile force upon it, provided the elasticity of the rod is not

impaired. The form $\frac{1}{2}R's'$ in (4) may be looked upon as a direct integration of $\int_0^{s'} Rds$, viz., the mean resistance $(\frac{1}{2}R')$ multiplied by the whole distance (s') gives the work done in overcoming the variable R through the successive ds's.

If the elongation is considerable, the working-forces G_1 and G_2 cannot be neglected, and would appear in the term $+(G_1 + G_2)s'$ in the right-hand members of (3), (4), and (5). The upper end of the rod is firmly fixed, and the rod itself is of small mass compared with M_1 and M_2.

Example 2.—Two cars, Fig. 151, are connected by an elastic chain on a horizontal track. Velocities before impact (i.e., before the stretching of the chain begins, by means of which they are brought to a common velocity at the instant of greatest tension R', and elongation s' of the chain) are $c_1 = c_1$, and $c_2 = 0$.



FIG. 151.

During the stretching, i.e., the first period of the impact, the kinetic energy lost by the masses has been expended in stretching the chain, i.e., in doing the work $\frac{1}{2}R's'$; hence we may write (the elasticity of the chain not being impaired) (see eq. (1))

$$\tfrac{1}{2}\frac{M_1M_2c_1^2}{M_1+M_2} = \frac{1}{2}R's' = \frac{R_0}{s_0}\cdot\frac{s'^2}{2} = \frac{R'^2s_0}{2R_0}, \quad . \quad . \quad (6)$$

in which the different symbols have the same meaning as in Example 1, in which the rod corresponds to the chain of this example.

In this case the mutual accommodation of velocities is due to the presence of the chain, whose *stretching* corresponds to the *compression* (of the parts in contact) in an ordinary impact.

In numerical substitution, 32.2 for g requires the use of the units foot and second for space and time, while the unit of force may be anything convenient.

139. Work and Energy in Rotary Motion. Axis Fixed.—The rigid body being considered free, let an axis through O perpendicular to the paper be the axis of rotation, and resolve all forces not intersecting the axis into components parallel and perpendicular to the axis, and the latter again into components tangent and normal to the circular path of the point



FIG. 152.

of application. These tangential components are evidently the only ones of the three sets mentioned which have moments about the axis, those having moments of the same sign as ω (the angular velocity at any instant) being called *working forces*, T_1, T_2, etc.; those of opposite sign, *resistances*, T_1', T_2', etc.; for when in time dt the point of application B_1, of T_1, describes the small arc $ds_1 = a_1 d\alpha$, whose projection on T_1 is $= ds_1$, this projection falls *ahead* (i.e., in direction of force) of the position of the point at the beginning of dt, while the reverse is true for T_1'.

From eq. (XIV.), § 114, we have for θ (angul. accel.)

$$\theta = \frac{(T_1 a_1 + T_2 a_2 + \dots) - (T_1' a_1' + T_2' a_2' + \dots)}{I}, \quad (1)$$

which substituted in $\omega d\omega = \theta d\alpha$ (from § 110) gives (remembering that $a_1 d\alpha = ds_1$, etc.), after integration and transposition,

$$\int_0^n T_1 ds_1 + \int_0^n T_2 ds_2 + \text{etc.}$$
$$= \int_0^n T_1' ds_1' + \int_0^n T_2' ds_2' + \text{etc.} + [\tfrac{1}{2}\omega_n^2 I - \tfrac{1}{2}\omega_0^2 I], \quad (2)$$

where 0 and n refer to any two (initial and final) positions of the rotating body. Eq. (4), § 120, is an example of this.

Now $\frac{1}{2}\omega_n^2 I = \frac{1}{2}\omega_n^2 \int dM\rho^2 = \int \frac{1}{2} dM(\omega_n \rho)^2$, which, since $\omega_n \rho$ is the actual velocity of any dM at this (final) instant, is nothing more than the sum of the amounts of kinetic energy possessed at this instant by all the particles of the body; a similar statement may be made for $\frac{1}{2}\omega_0^2 I$. (ω_0 and ω_n in *radians*.)

Eq. (2) therefore may be put into words as follows:

Between any two positions of a rigid body rotating about a fixed axis, the work done by the working forces is partly used in overcoming the resistances, and the remainder in changing the kinetic energy of the individual particles. If in any case this remainder is negative, the final kinetic energy is less than the initial, i.e., the work done by the working forces is less than that necessary to overcome the resistances through their respective spaces, and the deficiency is made up by the *restoring* of

some of the initial kinetic energy of the rotating body. A moving fly-wheel, then, is a reservoir of kinetic energy.

Example.—The 668-lb. pulley of p. 104 was found to have a radius of gyration of $\sqrt{7.91}$ ft., and a moment of inertia about its axis, Z, of $Mk^2 = (668 \div g)\, 7.91$. Let us suppose it mounted on a short shaft of ($r_0 =$) 2 in. radius (whose I_z may be neglected) supported in proper bearings. The pulley and shaft are in contact with nothing except the bearings, which offer a friction T_1', tangent to outer surface of shaft of 120 lbs. If the pulley has an initial rotary speed of 300 revs./min., in how many turns, n, will it be brought to rest? Evidently $\omega_n = 0$, while $\omega_0 = 2\pi 300 \div 60$, $= 31.41$ *rads./sec.* That is, the initial kinetic energy is $\frac{1}{2}\omega_0^2 Mk^2$, $= \frac{1}{2}(31.41)^2(668 \div 32.2)\, 7.91$, $= 80{,}810$ ft.-lbs.: and the final, *zero*. $T_1' = 120$ lbs., *constant*, and the work done on T_1' is $T_1' \int_0^{s_n} ds_1' = 120 \,.\, n(2\pi) \,.\, \frac{1}{6} = 125.6n$ ft.-lbs. Hence from eq. (2) we have $0 = 125.6n + [0 - 80{,}810]$; i.e., $n = 643$ turns. *Ans.*

140. Work of Equivalent Systems the Same.—*If two plane systems of forces acting on a rigid body are equivalent* (§ 15*a*), *the aggregate work done by either of them during a given slight displacement or motion of the body parallel to their plane is the same.* By aggregate work is meant what has already been defined as the sum of the "virtual moments" (§§ 61 to 64), in any small displacement of the body, viz., the algebraic sum of the products, $\Sigma(Pdu)$, obtained by multiplying each force by the projection (du) of the displacement of (or small space described by) its point of application upon the force. (We here class resistances as negative working forces.)

Call the systems A and B; then, if all the forces of B were *reversed in direction* and applied to the body along with those of A, the compound system would be a *balanced system*, and hence we should have (§ 64), for a small motion parallel to the plane of the forces,

$$\Sigma(Pdu) = 0, \text{ i.e., } \Sigma(Pdu) \text{ for } A - \Sigma(Pdu) \text{ for } B = 0,$$

or
$$+ \Sigma(Pdu) \text{ for } A = + \Sigma(Pdu) \text{ for } B.$$

But $+ \Sigma(Pdu)$ for A is the aggregate work done by the forces of A during the given motion, and $+ \Sigma(Pdu)$ for B is a similar quantity for the forces of B (not reversed) during the same small motion if B acted alone. Hence the theorem is proved, and could easily be extended to space of three dimensions.

141. Relation of Work and Kinetic Energy for any Extended Motion of a Rigid Body Parallel to a Plane.—(If at any instant any of the forces acting are not parallel to the plane mentioned, their components lying in or parallel to that plane, will be used instead, since the other components obviously would be neither working forces nor resistances.)



FIG. 153.

Fig. 153 shows an initial position, o, of the body; a final, n; and any intermediate, as q. The forces of the system acting may vary in any manner during the motion.

In this motion each dM describes a curve of its own with varying velocity v, tangential acceleration p_t, and radius of curvature r; hence in any position q, an imaginary system B (see Fig. 154), equivalent to the actual system A (at q in Fig. 153), would be formed by applying to each dM a tangential force $dT = dMp_t$, and a normal force $dN = dMv^2 \div r$. By an infinite number of consecutive small displacements, the body passes from o to n. In the small displacement of which q is the initial position, each dM describes a space ds, and dT does the work $dTds = dMvdv$, while dN does the work $dN \times 0 = 0$. Hence the total work done by B in the small displacement at q would be



FIG. 154.

$$= dM'v'dv' + dM''v''dv'' + \text{etc.}, \quad . \quad . \quad . \quad (1)$$

including all the dM's of the body and their respective velocities at this instant.

But the work at q in Fig. 153 by the actual forces (i.e., of system A) during the same small displacement must (by § 140) be equal to that done by B, hence

$$P_1du_1 + P_2du_2 + \text{etc.} = dM'v'dv' + dM''v''dv'' + \text{etc.} \quad (q)$$

Now conceive an equation like (q) written out for each of

the small consecutive displacements between positions o and n and corresponding terms to be added; this will give

$$\int_0^n P_1 du_1 + \int_0^n P_2 du_2 + \text{etc.}$$
$$= dM' \int_0^n v' dv' + dM'' \int_0^n v'' dv'' + \text{etc.}$$
$$= \tfrac{1}{2} dM' (v_n'^2 - v_0'^2) + \tfrac{1}{2} dM'' (v_n''^2 - v_0''^2) + \text{etc.}$$

The second member may be rewritten so as to give, finally,

$$\int_0^n P_1 du_1 + \int_0^n P_2 du_2 + \text{etc.} = \Sigma(\tfrac{1}{2} dM v_n^2) - \Sigma(\tfrac{1}{2} dM v_0^2), \quad \text{(XV.)}$$

or, in words, *the work done by the acting forces* (*treating a resistance as a negative working force*) *between any two positions is equal to the gain* (*or loss*) *in the aggregate kinetic energy of the particles of the body between the two positions.* To avoid confusion, Σ has been used instead of the sign $\int$ in one member of (XV.), in which v_n is the final velocity of any dM (not the same for all necessarily) and v_0 the initial.

(The same method of proof can be extended to three dimensions.)

Since kinetic energy is always essentially positive, if an expression for it comes out negative as the solution of a problem, some impossible conditions have been imposed.

142. Work and Kinetic Energy in a Moving Machine.— Defining a *mechanism* or *machine* as a series of rigid bodies jointed or connected together, so that working-forces applied to one or more may be the means of overcoming resistances occurring anywhere in the system, and also of changing the amount of kinetic energy of the moving masses, let us for simplicity consider a machine the motions of whose parts are all parallel to a plane, and let all the forces acting on any one piece, considered free, at any instant be parallel to the same plane.

Now consider each piece of the machine, or of any series of its pieces, as a free body, and write out eq. (XV.) for it between any two positions (whatever initial and final positions are selected for the first piece, those of the others must be corresponding initial and corresponding final positions), and it will

be found, on adding up corresponding members of these equations, that the terms involving those components of the mutual pressures (between the pieces considered) which are *normal* to the rubbing surfaces at any instant will cancel out, while their components tangential to the rubbing surfaces (i.e., *friction*, since if the surfaces are perfectly smooth there can be no tangential action) will appear in the algebraic addition as resistances multiplied by the distances rubbed through, *measured on the rubbing surfaces.* For example, Fig. 155, where one rotating piece both presses and rubs on another. Let the normal pressure between them at A be $R_2 = P_2$; it is a working force for the body of mass M'', but a resistance for M', hence the separate symbols for the numerically equal forces (action and reaction).

Similarly, the friction at A is $R_3 = P_3$; a resistance for M', a working-force for M''. (In some cases, of course, friction may be a resistance for both bodies.) For a small motion, A describes the small arc AA' about O' in dealing with M', but for M'' it describes the arc AA'' about O'', $A'A''$ being parallel to the surface of contact AD, while AB is perpen-



FIG. 155.



FIG. 156.



FIG. 157.

dicular to $A'A''$. In Figs. 156 and 157 we see M' and M'' free, and their corresponding small rotations indicated. During these motions the kinetic energy (K. E.) of each mass has changed by amounts $d(\text{K. E.})_{M'}$ and $d(\text{K. E.})_{M''}$ respectively, and hence eq. (XV.) gives, for each free body in turn,

$$P_1\overline{aa'} - R_2\overline{AB} - R_3\overline{A'B} = d(\text{K. E.})_{M'} \quad . \quad (1)$$

$$-R_4\overline{bb''} + P_2\overline{AB} + P_3\overline{A''B} = d(\text{K. E.})_{M''}. \quad . \quad (2)$$

Now add (1) and (2), member to member, remembering that $P_2 = R_2$ and $P_3 = R_3 = F_3 =$ friction, and we have

$$P_1\overline{aa'} - F_3\overline{A'A''} - R_4\overline{bb''} = d(\text{K. E.})_{M'} + d(\text{K. E.})_{M''}, \quad (3)$$

in which the mutual actions of M' and M'' do not appear, except the friction, *the work done in overcoming which, when the two bodies are thus considered collectively, is the product of the friction by the distance $A'A''$ of actual rubbing measured on the rubbing surface.* For any number of pieces, then, *considered free collectively*, the assertion made at the beginning of this article is true, since any finite motion consists of an infinite number of small motions to each one of which an equation like (3) is applicable.

Summing the corresponding terms of all such equations, we have

$$\int_0^n P_1 du_1 + \int_0^n P_2 du_2 + \text{etc.} = \Sigma(\text{K. E.})_n - \Sigma(\text{K. E.})_0. \quad \text{(XVI.)}$$

This is of the same form as (XV.), but instead of applying to a single rigid body, deals with any assemblage of rigid parts forming a machine, or any part of a machine (a similar proof will apply to three dimensions of space); but it must be remembered that it excludes all the *mutual* actions* of the pieces considered except friction, which is to be introduced in the manner just illustrated. A flexible inextensible cord may be considered as made up of a great number of short rigid bodies jointed without friction, and hence may form part of a machine without vitiating the truth of (XVI.).

$\Sigma(\text{K. E.})_n$ signifies the sum obtained by adding the amounts of kinetic energy ($\frac{1}{2}dMv_n^2$ for each elementary mass) possessed by all the particles of all the rigid bodies at their final positions; $\Sigma(\text{K. E.})_0$, a similar sum at their initial positions. For example, the K. E. of a rigid body having a motion of translation of velocity v, $= \frac{1}{2}v^2 \int dM = \frac{1}{2}Mv^2$; that of a rigid body having an angular velocity ω about a fixed axis Z, $= \frac{1}{2}\omega^2 I_Z$ (§ 139); while, if it has an angular velocity ω about a gravity-axis Z, which has a velocity v_z of translation at right angles to itself, the (K. E.) at this instant may be proved to be (§ 143)

$$\tfrac{1}{2}Mv_z^2 + \tfrac{1}{2}\omega^2 I_z,$$

the sum of the amounts *due to the two motions separately.*

* These *mutual actions* consist only of *actions by contact* (pressure, rub, etc.). No magnetic or electrical attractions or repulsions are here considered.

143. K. E. of Combined Rotation and Translation.—The last statement may be thus proved. Fig. 158. At a given instant the velocity of any dM is v, the diagonal formed on the velocity v_Z of translation, and the rotary velocity $\omega\rho$ relatively to the moving gravity-axis Z (perpendicular to paper) (see § 71),



FIG. 158.

$$\text{i.e., } v^2 = v_Z^2 + (\omega\rho)^2 - 2(\omega\rho)v_Z \cos\varphi;$$

hence we have K. E., at this instant,

$$= \int \tfrac{1}{2} dM v^2 = \tfrac{1}{2} v_Z^2 \int dM + \tfrac{1}{2}\omega^2 \int dM \rho^2 - \omega v_Z \int dM \rho \cos\varphi,$$

but $\rho \cos\varphi = y$, and $\int dM y = M\bar{y} = 0$, since Z is a gravity-axis,

$$\therefore \text{K. E.} = \tfrac{1}{2} M v_Z^2 + \tfrac{1}{2}\omega^2 I_Z. \quad \text{Q. E. D.}$$

It is interesting to notice that the K. E. due to rotation, viz., $\frac{1}{2}\omega^2 I_Z = \frac{1}{2} M(\omega k)^2$, is the same as if the whole mass were concentrated in a point, line, or thin shell, at a distance k, the radius of gyration, from the axis.

Example.—A solid homogeneous sphere of radius $r = 6$ in. and weight $= 322$ lbs. is rolling down an incline. At a certain instant the velocity of its centre is 10 ft. per sec. and hence, *if no slipping occurs*, its angular velocity about its centre is ω, $= v_z \div r$, $= 10 \div \frac{1}{2}$, $= 20$ radians/sec. Consequently, at this instant (see § 103, p. 102) its *total kinetic energy* is $\frac{1}{2}(322 \div 32.2)[(10)^2 + (20)^2 \cdot \frac{2}{5}(\frac{1}{2})^2] = 700$ ft.-lbs.

144. Example of a Machine in Operation.—Fig. 159. Consider the four consecutive moving masses, M', M'', M''', and M^{iv} (being the piston; connecting-rod; fly-wheel, crank, drum, and chain; and weight on inclined plane) as *free*, collectively. Let us apply eq. (XVI.), the initial and final positions being taken when the crank-pin is at its dead-points o and n; i.e., we deal with the progress of the pieces made while the crank-pin describes its upper semicircle. Remembering that the mutual actions between any two of these four masses can be left out of account (except friction), the only forces to be put in are the actions of other bodies on each one of these four, and are

shown in the figure. The only *mutual* friction considered will be at the crank-pin, and if this as an average $= F''$, the work done on it between o and $n = F''\pi r''$, where $r'' =$ radius of crank-pin. The work done by P_1 the effective steam-pressure (let it be constant) during this period is $= P_1 l'$; that done in overcoming F_1, the friction between piston and cylinder, $= F_1 l'$; that done *upon* the weight G'' of connecting-rod is cancelled by the work done *by it* in the descent following; the work done



Fig. 159.

upon G^{IV}, $= G^{\text{IV}}\pi a \sin \beta$, where $a =$ radius of drum; that upon the friction F_4, $= F_4\pi a$. The pressures N, N', N^{IV}, and N''', and weights G' and G''', are neutral, i.e., do no work either positive or negative. Hence the left-hand member of (XVI.) becomes, between o and n,

$$P_1 l' - F_1 l' - F''\pi r'' - G^{\text{IV}}\pi a \sin \beta - F_4\pi a, \quad . \quad . \quad (1)$$

provided the respective distances are *actually described* by these forces, i.e., if the masses have sufficient initial kinetic energy to carry the crank-pin beyond the point of minimum velocity, with the aid of the working force P_1, whose effect is small up to that instant.

As for the total initial kinetic energy, i.e., $\Sigma(\text{K. E.})_0$, let us express it in terms of the velocity of crank-pin at o, viz., V_0. The $(\text{K.E.})_0$ of M' is nothing; that of M'', which at this instant is rotating about its right extremity (*fixed* for the instant) with angular velocity $\omega'' = V_0 \div l''$, is $\frac{1}{2}\omega''^2 I_0''$; that of M''' $= \frac{1}{2}\omega'''^2 I_C'''$, in which $\omega''' = V_0 \div r$; that of M^{IV} (translation) $= \frac{1}{2}M^{\text{IV}} v_0^{\text{IV}^2}$, in which $v_0^{\text{IV}} = (a \div r)\, V_0$. $\Sigma(\text{K. E.})_n$ is expressed

in a corresponding manner with V_n (final velocity of crank-pin) instead of V_0. Hence the right-hand member of (XVI.) will give (putting the radius of gyration of M'' about $O'' = k''$, and that of M''' about $C = k$)

$$\tfrac{1}{2}(V_n^2 - V_0^2)\left[M''\frac{k''^2}{l''^2} + M'''\frac{k^2}{r^2} + M^{\text{iv}}\frac{a^2}{r^2}\right]. \quad . \quad . \quad (2)$$

By writing (1)=(2), we have an equation of condition, capable of solution for any one unknown quantity, to be satisfied for the extent of motion considered. It is understood that the chain is always taut, and that its weight and mass are neglected.

145. Numerical Case of the Foregoing.—(Foot-pound-second system of units for space, force, and time; this requires $g = 32.2$.)

Suppose the following data:

Feet.	Lbs.	Lbs.	Mass Units.
			(and ∴)
$l' = 2.0$	$P_1 = 6000$	$G' = 60$	$M' = 1.86$
$l'' = 4.0$	$F_1 = 200$	$G'' = 50$	$M'' = 1.55$
$a = 1.5$	F' (av'ge) $= 400$	$G''' = 400$	$M''' = 12.4$
$r = 1.0$	$F_4 = 300$	$G^{\text{iv}} = 3220$	$M^{\text{iv}} = 100.0$
$k = 1.8$			
$k' = 2.3$		Also let $V_0 = 4$ ft. per sec.; $\beta = 30°$	
$r'' = 0.1$			

Denote (1) by W and the large bracket in (2) by $\overline{M}$ (this by some is called the total mass "*reduced*" to the crank-pin). Putting (1) = (2) we have, solving for the unknown V_n,

$$V_n = \sqrt{\frac{2W}{\overline{M}} + V_0^2}. \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

For above values,

$$W = 12{,}000 - 400 - 125.7 - 7590.0 - 1417.3$$
$$= 2467 \text{ foot-pounds};$$

while $\overline{M} = 0.5 + 40.3 + 225.0 = 265.8$ mass-units;

whence $V_n = \sqrt{18.56 + 16} = \sqrt{34.56} = 5.88$ ft. per second.

As to whether the crank-pin actually reaches the dead-point n, requires separate investigations to see whether V becomes zero or negative between o and n (a negative value is inad-

missible, since a reversal of direction implies a different value for W), i.e., whether the proposed extent of motion is realized; and these are made by assigning some other intermediate position m, as a final one, and computing V_m, remembering that when m is not a dead-point the $(\text{K. E.})_m$ of M' is not zero, and must be expressed in terms of V_m, and that the $(\text{K. E.})_m$ of the connecting-rod M'' must be obtained from § 143.

146. Regulation of Machines.—As already illustrated in several examples (§ 121), a fly-wheel of sufficient weight and radius may prevent too great fluctuation of speed in a single stroke of an engine; but to prevent a permanent change, which must occur if the work of the working force or forces (such as the steam-pressure on a piston, or water-impulse in a turbine) exceeds for several successive strokes or revolutions the work required to overcome resistances (such as friction, gravity, resistance at the teeth of saws, etc., etc.) through their respective spaces, automatic governors are employed to diminish the working force, or the distance through which it acts per stroke, until the normal speed is restored; or *vice versâ*, if the speed slackens, as when new resistances are temporarily brought into play. Hence when several successive periods, strokes (or other cycle), are considered, the kinetic energy of the moving parts will disappear from eq. (XVI.), leaving it in this form:

work of working-forces = work done upon resistances.

147. Power of Motors.—In a mill where the same number of machines are run continuously at a constant speed proper for their work, turning out per hour the same number of barrels of flour, feet of lumber, or other commodity, the motor (e.g., a steam-engine, or turbine) works at a constant rate, i.e., develops a definite horse-power (H.P.), which is thus found in the case of *reciprocating steam-engines* (double-acting),

$$\text{H.P.} = \left.\begin{array}{l}\text{total mean effective}\\ \text{steam-pressure on}\\ \text{piston in lbs.}\end{array}\right\} \times \left\{\begin{array}{l}\text{distance in feet}\\ \text{travelled by pis-}\\ \text{ton per second.}\end{array}\right\} \div 550,$$

i.e., the work (in ft.-lbs) done per second by the working force

divided by 550 (see § 132). The total effective pressure at any instant is the excess of the forward over the back-pressure, and by its mean value (since steam is usually used expansively) is meant such a value P' as, multiplied by the length of stroke l, shall give

$$P'l = \int_0^l P dx,$$

where P is the variable effective pressure and dx an element of its path. If u is the number of strokes per second, we may also write (*foot-pound-second system*)

$$\text{H.P.} = P'lu \div 550 = \left[\int_0^l P dx\right] u \div 550. \quad \text{(XVII.)}$$

Very often the number of revolutions *per minute*, m, of the crank is given, and then

$$\text{H.P.} = P' \text{ (lbs.)} \times 2l \text{ (feet)} \times m \div 33{,}000.$$

If F = area of piston we may also write $P' = Fp'$, where p' is the mean effective steam-pressure per unit of area. Evidently, to obtain P' in lbs., we multiply F in sq. in. by p' in lbs. per sq. in., or F in sq. ft. by p' in lbs. per sq. foot; the former is customary. p' in practice is obtained by measurements and computations from "indicator-cards" (see § 152, p. 159, where the value of P' is found by Simpson's Rule); or $P'l$, i.e., $\int_0^l P dx$, may be computed theoretically as in § 59, Problem 4.

The power as thus found is expended in overcoming the friction of all moving parts (which is sometimes a large item), and the resistances peculiar to the kind of work done by the machines. The work periodically *stored* in the increased kinetic energy of the moving masses is *restored* as they periodically resume their minimum velocities.

Example.—In the steady running of a (reciprocating) steam-engine operating a mill, the value of the mean total effective pressure on the piston is $P' = 16{,}800$ lbs. and the radius of the circle described by the crank-pin is 10 in. (so that the length of stroke is $l = 20$ inches). The fly-wheel turns at rate of 330 revs./min. Find the horse-power developed. Substituting, we find $\text{H.P.} = [16{,}800 \times 2 \times \frac{20}{12} \times 330] \div 33{,}000 = 560$ H.P.

148. Potential Energy.—There are other ways in which work or energy is stored and then restored, as follows:

First. In raising a weight G through a height h, an amount of work $= Gh$ is done *upon* G, as a *resistance*, and if at any subsequent time the weight is allowed to descend through the same vertical distance h (the form of path is of no account), G, now a *working force*, *does* the work Gh, and thus in aiding the motor repays, or restores, the Gh expended by the motor in raising it. If h is the vertical height through which the centre of gravity rises and sinks periodically in the motion of the machine, the force G may be left out of account in reckoning the expenditure of the motor's work, and the body when at its highest point is said to possess an amount Gh of **potential energy**, i.e., *energy of position*, since it is capable of doing the work Gh in sinking through its vertical range of motion.

Second. So far, all bodies considered have been by express stipulation *rigid*, i.e., incapable of changing shape. To see the effect of a lack of rigidity as affecting the principle of work and energy in machines, take the simple case in Fig. 160. A helical spring at a given instant is acted on at each end by a force P in an axial direction (they are equal, supposing the mass of the spring small).



FIG. 160.

As the machine operates of which it is a member, it moves to a new consecutive position B, suffering a further elongation $d\lambda$ in its length (if P is increasing). P on the right, a working force, does the work Pdx'; how is this expended? P on the left has the work Pdx done upon it, and the mass is too small to absorb kinetic energy or to bring its weight into consideration. The remainder, $Pdx' - Pdx = Pd\lambda$, is expended in stretching the spring an additional amount $d\lambda$, and is capable of restoration if the spring retains its elasticity. Hence the work done in changing the form of bodies *if they are elastic* is said to be stored in the form of **potential energy.** That is, in the operation of machines, the name *potential energy* is also given to the energy stored and restored periodically in the changing and regaining of form of elastic bodies.

Example.—A given helical spring, when held stretched $s' = \frac{1}{2}$ ft. beyond its "natural" (or unstrained) length, exerts a pull of $R' = 1200$ lbs. at its two ends; and the "potential energy" residing in it is $=$ *mean force* $\times$ *distance*, $= \frac{1}{2}R's'$, $= (\frac{1}{2})\ 1200\ (\frac{1}{2})$, $= 300$ ft.-lbs. If such a stretched spring be placed on a car of 644 lbs. weight on a level track and properly connected with a driving-wheel, which does not slip on the track, its recovery of natural length may be made the means of starting the car into motion and causing it to attain a final velocity of $v = 5.47$ ft./sec. (if no friction is met with); from $\frac{1}{2}(644 \div 32.2)v^2 = 300$.

149. Other Forms of Energy.—Numerous experiments with various kinds of apparatus have proved that for every 778 (about) ft.-lbs. of work spent in overcoming friction, one British unit of heat is produced (viz., the quantity of heat necessary to raise the temperature of one pound of water from 32° to 33° Fahrenheit); while from converse experiments, in which the amount of heat used in operating a steam-engine was all carefully estimated, the disappearance of a certain portion of it could only be accounted for by assuming that it had been converted into work at the same rate of (about) 778 ft.-lbs. of work to each unit of heat (or 427 kilogrammetres to each French unit of heat). This number 778 or 427, according to the system of units employed, is called the *Mechanical Equivalent of Heat*.

Heat then is energy, and is supposed to be of the kinetic form due to the rapid motion or vibration of the molecules of a substance. A similar agitation among the molecules of the (hypothetical) ether diffused through space is supposed to produce the phenomena of light, electricity, and magnetism. Chemical action being also considered a method of transforming energy (its possible future occurrence as in the case of coal and oxygen being called potential energy), the well-known doctrine of the *Conservation of Energy*, in accordance with which energy is indestructible, and the doing of work is simply the conversion of one or more kinds of energy into equivalent amounts of others, is now an accepted hypothesis of physics.

Work consumed in friction, though practically lost, still remains in the universe as heat, electricity, or some other subtile form of energy.

150. Power Required for Individual Machines. Dynamometers of Transmission.—If a machine is driven by an endless belt from the main-shaft, A, Fig. 161, being the driving-pulley

on the machine, the working force which drives the machine, in other words the "grip" with which the belt takes hold of the pulley tangentially, $= P - P'$, P and P' being the tensions in the "driving" and "following" sides of the belt respectively. The belt is supposed not to slip on the pulley. If v is the velocity of the pulley-circumference, the work expended on the machine per second, i.e., the *power*, is



Fig. 161.

$$L = (P - P')v, \text{ ft.-lbs. per sec.} \quad . \quad . \quad . \quad . \quad (1)$$

To measure the force $(P - P')$, an apparatus called a *Dynamometer of Transmission* may be placed between the main shaft and the machine, and the belt made to pass through it in such a way as to measure the tensions P and P', or principally their difference, without meeting any resistance in so doing; that is, the power is *transmitted*, not absorbed, by the apparatus. One invention for this purpose (mentioned in the *Journal of the Franklin Institute* some years ago) is shown (*in principle*) in Fig. 162. A vertical plate carrying four pulleys and a scale-pan is first balanced on the pivot C. The belt being then adjusted, as shown, and the power turned on, a sufficient weight G is placed in the scale-pan to balance the plate again, for whose equilibrium we must have $Gb = Pa - P'a$, since the P and P' on the right *have action-lines passing through C*. The velocity of belt, v, is obtained by a simple counting device. Hence $(P - P')$ and v become known, and $\therefore$ L from (1).



Fig. 162.

Many other forms of transmission-dynamometers are in use, some applicable whether the machine is driven by belting or gearing from the main shaft. Emerson's *Hydrodynamics* describes his own invention* on p. 283, and gives results of measurements with it; e.g., at Lowell, Mass., the power required to drive 112 looms, weaving 36-inch sheetings, No. 20 yarn, 60 threads to the inch, speed 130 picks to the minute, was found to be 16 H.P., i.e., $\frac{1}{7}$ H.P., to each loom (p. 335).

* Prof. Flather's "*Dynamometers*" is a standard book (1907).

Example.—The endless belt connecting the pulley (running at $n=180$ revs./min., with a radius of $r=2$ ft.) of an engine shaft with that of a planing machine is led over the idle pulleys of the apparatus in Fig. 162, as there shown (engine pulley on left, and that of machine on right; but neither shown in figure). To balance the plate in position shown (with $a=2$ ft. and $b=4$ ft.) is found to require a weight $G=210$ lbs. We have, therefore, from $(P-P')\,a=Gb$, $P-P'=210\times4\div2=420$ lbs. as the net working force operating the machine; while the velocity of the belt is v, $=n\,2\pi r$, $=(180\div60)\,2\pi2=18.85$ ft./sec. Hence the power transmitted through the dynamometer of transmission is L, $=(P-P')v$, $=420\times18.85=79{,}170$ ft.-lbs. per sec., or 14.4 H.P

151. Dynamometers of Absorption.—These are so named since they furnish in themselves the resistance (friction or a weight) in the overcoming (or raising) of which the power is expended or absorbed. Of these the *Prony Friction Brake* is the most common, and is used for measuring the power developed by a given motor (e.g., a steam-engine or turbine) not absorbed in the friction of the motor itself. Fig. 163



FIG. 163.

shows one fitted to a vertical pulley driven by the motor. By tightening the bolt B, the velocity v of pulley-rim may be made constant at any desired value (within certain limits) by the consequent friction. v is measured by a counting apparatus, while the friction (or *tangential* components of action between pulley and brake), $=F$, becomes known by noting the weight G which must be placed in the scale pan to balance the arm between the checks; then with $G'=$weight of brake and $b'=$the horizontal distance of its center of gravity from the center of pulley, we have, for the equilibrium of the brake (moments about pulley center),

$$Fa=Gb+G'b'; \quad \ldots\ldots \quad (1)$$

and the work done on F per unit of time, or *power*, is

$$L=Fv, \text{ ft.-lbs. per sec.} \quad \ldots\ldots \quad (2)$$

(In case the pulley is horizontal, a bell-crank must be interposed between the arm and the scale-pan.)

ward through the small space (the "slip") $= s_1$ (average). Hence by eq. (XVI.), § 142,

$$2Ps_2 - 2Ps_3 - Rs_3 - 2P_1s_1 = \tfrac{1}{2}M(v_n^2 - v_0^2);$$

i.e., $2P(s_2 - s_3) = 2P \times \overline{AE} = 2Ps = Rs_3 + 2P_1s_1 + \tfrac{1}{2}M(v_n^2 - v_0^2)$;

or, in words, the product of the oar-handle pressures into the distance described by them *measured on the boat*, i.e., the work done by these pressures *relatively to the boat*, is entirely accounted for in the work of slip and of liquid-resistance, and in-



Fig. 166.

creasing the kinetic energy of the mass. (The useless work due to slip is inevitable in all paddle or screw propulsion, as well as a certain amount lost in machine-friction, not considered in the present problem.) During the "recover" the velocity decreases again to v_0. (See example on p. 97, *Notes*, etc.)

155. Examples.—1. What work is done* on a level track, in bringing up the velocity of a train weighing 200 tons, from zero to 30 miles per hour, if the total frictional resistance (at any velocity, say) is 10 lbs. per ton, and if the change of speed is accomplished in a length of 3000 feet?

(*Foot-ton-second system.*) 30 miles per hour = 44 ft. per sec. The mass

$$= 200 \div 32.2 = 6.2;$$

∴ the change in kinetic energy,

$$(= \tfrac{1}{2}Mv^2 - \tfrac{1}{2}M \times 0^2),$$
$$= \tfrac{1}{2}(6.2) \times 44^2 = 6001.6 \text{ ft.-tons.}$$

* That is, what work is done by the pull, or tension, P, in the draw-bar between the locomotive and the "tender."

The work done in overcoming friction $= Fs$, i.e.,

$= 200 \times 10 \times 3000 = 6{,}000{,}000$ ft.-lbs. $= 3000$ ft.-tons;

$\therefore$ total work $= 6001.6 + 3000 = 9001.6$ ft.-tons.

(If the track were an up-grade, 1 in 100 say, the item of $200 \times 30 = 6000$ ft.-tons would be added.)

Example 2.—Required the rate of work, or power, in Example 1. The power is variable, depending on the velocity of the train at any instant. Assume the motion to be uniformly accelerated, then the working force is constant; call it P. The acceleration (§ 56) will be $p = v^2 \div 2s = 1936 \div 6000 = 0.322$ ft. per sq. sec.; and since $P - F = Mp$, we have

$$P = 1 \text{ ton} + (200 \div 32.2) \times 0.322 = 3 \text{ tons},$$

which is $6000 \div 200 = 30$ lbs. per ton of train, of which 20 is due to its inertia, since when the speed becomes uniform the work of the engine is expended on friction alone.

Hence when the velocity is 44 ft. per sec., the engine is working at the rate of $Pv = 264{,}000$ ft.-lbs. per sec., i.e., at the rate of 480 H. P.;

At $\frac{1}{4}$ of 3000 ft. from the start, at the rate of 240 H. P., half as much;

At a uniform speed of 30 miles an hour the power would be simply $1 \times 44 = 44$ ft.-tons per sec. $= 160$ H. P.

Example 3.—The resistance offered by still water to the passage of a certain steamer at 10 knots an hour is 15,000 lbs. What power must be developed by its engines, at this uniform speed, considering no loss in "slip" nor in friction of machinery? *Ans.* 461 H. P.

Example 4.—Same as 3, except that the speed is to be 15 knots (i.e., nautical miles; each $= 6086$ feet) an hour, assuming that the resistances are as the square of the speed (approximately true). *Ans.* 1556 H. P.

Example 5.—Same as 3, except that 12% of the power is absorbed in the "slip" (i.e., in pushing aside and backwards the water acted on by the screw or paddle), and 8% in friction of machinery. *Ans.* 576 H. P.

Example 6.—In Example 3, if the crank-shaft makes 60

revolutions per minute, the crank-pin describing a circle of 18 inches radius, required the average* value of the tangential component of the thrust (or pull) of the connecting-rod against the crank-pin. *Ans.* 26890 lbs.

Example 7.—A solid sphere of cast-iron is *rolling* up an incline of 30°, and at a certain instant its centre has a velocity of 36 inches per second. Neglecting friction of all kinds, how much further will the ball mount the incline (see § 143)?

Ans. 0.390 ft.

Example 8.—In Fig. 163, with $b = 4$ ft. and $a = 16$ inches, it is found in one experiment that the friction which keeps the speed of the pulley at 120 revolutions per minute is balanced by a weight $G = 160$ lbs. Required the power thus measured.

Ans. 14.6 H. P.

Although in Examples 1 to 6 the steam cylinder is itself in motion, the work per stroke is still = mean effective steam-pressure on piston × length of stroke, for this is the final form to which the separate amounts of work done by, or upon, the two cylinder heads and the two sides of the piston will reduce, when added algebraically. See § 154.

* By "average value" is meant such a value, T_m, as multiplied into the length of path described by the crank-pin per unit of time shall give the power exerted.

CHAPTER VII.

FRICTION.

156. Sliding Friction.—When the surfaces of contact of two bodies are perfectly smooth, the direction of the pressure or pair of forces between them is normal to these surfaces, i.e., to their tangent-plane; but when they are rough, and moving one on the other, the forces or actions between them incline away from the normal, each on the side opposite to the direction of the (relative) motion of the body on which it acts. Thus, Fig. 167, a block whose weight is G, is drawn on a rough horizontal table by a horizontal cord, the tension in which is P. On account of the roughness of one or both bodies the action of the table upon the block is a force P_1, inclined to the normal (which is vertical in this case) at an angle $= \varphi$ *away* from the direction of the relative velocity v. This angle φ is called the *angle of friction*, while the tangential component of P_1 is called the *friction* $= F$. The normal component N, which in this case is equal and opposite to G the weight of the body, is called the *normal pressure*.



FIG. 167.

Obviously $F = N \tan \varphi$, and denoting $\tan \varphi$ by f, we have

$$F = fN. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

f is called the *coefficient of friction*, and may also be defined as the ratio of the friction F to the normal pressure N which produces it.

In Fig. 167, if the motion is accelerated (acc. $= p$), we have (eq. (IV.), § 55) $P - F = Mp$; if uniform, $P - F = 0$; from which equations (see also (1)) f may be computed. In the latter case f may be found to be different with different velocities (the surfaces retaining the same character of course), and then a uniformly accelerated motion is impossible unless $P - F$ were constant.

As for the lower block or table, forces the equals and opposites of N and F (or a single force equal and opposite to P_1) are comprised in the system of forces acting upon it.

As to whether F is a *working force* or a *resistance*, when

either of the two bodies is considered free, depends on the circumstances of its motion. For example, in friction-gearing the tangential action between the two pulleys is a resistance for one, a working force for the other.

If the force P, Fig. 167, is just sufficient to start the body, or is just on the point of starting it (this will be called *impending motion*), F is called the *friction of rest.* If the body is at rest and P is not sufficient to start it, the tangential component will then be $<$ the friction of rest, viz., just $= P$. As P increases, this component continually equals it in value, and P_1 acquires a direction more and more inclined from the normal, until the instant of impending motion, when the tangential component $= fN =$ the *friction of rest.* When motion is once in progress, the friction, called then the *friction of motion*, $= fN$, in which f is not necessarily the same as in the friction of rest.

157. Variation of Friction and of the Coefficient of Friction, f.—Careful distinction must be made between the friction of *dry surfaces* and of those that are *lubricated;* though in the latter case as the supply of lubricant (oil, soap, graphite, etc.) is reduced from the extreme state of "flooding," the friction approximates in variation and magnitude to that of dry surfaces. Also, if the pressure is very great, the lubricant may be pressed out and the phenomena reduced to those of dry surfaces, which under great pressures "*seize,*" i.e., abrade, one another.

With **dry surfaces** the amount of friction, F (lbs.), depends on the nature of the materials and their initial roughness, being somewhat reduced as they become more polished, when a sliding motion has been long continued. With the surfaces in a given condition it is found (unless the pressure is very low) that increase of velocity diminishes the friction, as is unfortunately the case with railroad brakes, the friction between a brake-shoe and the rim of the car-wheel being least at the first application of the brakes, when the velocity of rubbing is greatest (see p. 168). The friction increases with the normal pressure N (the coefficient f, itself, increasing with N when N is large) and is somewhat smaller after motion begins than when motion is "impending" (friction of rest).

With **well lubricated surfaces,** however, the following may be said: The nature of the materials of the two bodies has but slight influence on the amount of friction, F, and when motion has begun, the friction is very much less than that of "impending motion." The friction is practically independent of the pressure when the lubrication is very copious (bearings "flooded") (resembling, therefore, "fluid friction;" see p. 695), the coefficient f being as small as 0.001 or under (Tower); but with more scanty lubrication conditions may approach those of dry surfaces. As to the effect of velocity (Goodman), the frictional resistance

varies directly as the speed for low pressures. For high pressures, however, it is relatively great at low velocities, a minimum at about 100 ft./min., and afterwards increases approximately as the *square root* of the speed. A rise of temperature has a very important influence in diminishing the viscosity of the oil and enlarging the diameter of the bearing of a shaft more than that of the shaft itself.

In the problems of this chapter the coefficient f will be considered as constant; so that where it really varies (as when the velocity changes) an average value will be understood.

158. Experiments on Sliding Friction.—These may be made with simple apparatus. If a block of weight $= G$, Fig. 168, be placed on an inclined plane of uniformly rough surface, and the latter be gradually more and more inclined from the horizontal until the block *begins* to move, the value of β at



Fig. 168.



Fig. 169.

this instant $= \varphi$, and $\tan \varphi = f =$ coefficient of friction of rest. For from $\Sigma X = 0$ we have F, i.e., fN, $= G \sin \beta$; from $\Sigma Y = 0$, $N = G \cos \beta$; whence $\tan \beta = f$, $\therefore \beta$ must $= \varphi$.

Suppose β so great that the motion is accelerated, the body starting from rest at o, Fig. 169. If it is found that the distance x varies as the square of the time, then (§ 56) the motion is uniformly accelerated (along the axis X). (Notice in the figure that G is no longer equal and opposite to P_1, the resultant of N and F, as in Fig. 168.) We have, then

$$\Sigma Y = 0, \quad \text{which gives } N - G \cos \beta = 0;$$

$$\Sigma X = Mp_1, \text{ which gives } G \sin \beta - fN = (G \div g)p_1;$$

while (from § 56) $$p_1 = 2x \div t^2.$$

Hence, by elimination, x and the corresponding time t having been observed, we have for the coefficient of friction of motion

$$f = \tan \beta - \frac{2x}{gt^2 \cos \beta}$$

as an average (since the acceleration may not be uniform).

In view of (3), § 157, it is evident that if a value β_m has been found experimentally for β such that the block, *once started by hand*, preserves a uniform motion down the plane, then, since $\tan \beta_m = f$ for friction of motion, β_m may be less than the β in Fig. 168, for friction of rest.

159. Another apparatus consists of a horizontal plane, a pulley, cord, and two weights, as shown in Fig. 59. The masses of the cord and pulley being small and hence neglected, the analysis of the problem when G is so large as to cause an accelerated motion is the same as in that example [(2) in § 57], except in Fig. 60, where the frictional resistance fN should be put in pointing toward the left. N still $= G_1$, and $\therefore$

$$S - fG_1 = (G_1 \div g)p; \quad . \quad . \quad . \quad . \quad . \quad (1)$$

while for the other free body in Fig. 61 we have, as before,

$$G - S = (G \div g)p. \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

From (1) and (2), S the cord-tension can be eliminated, and solving for p, writing it equal to $2s \div t^2$, s and t being the observed distance described (from rest) and corresponding time, we have finally for friction of motion (as an average)

$$f = \frac{G}{G_1} - \frac{G + G_1}{G_1} \cdot \frac{2s}{gt^2}. \quad . \quad . \quad . \quad . \quad . \quad (3)$$

If G, Fig. 59, is made just sufficient to start the block, or sledge, G_1, we have for the friction of rest

$$f = \frac{G}{G_1}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

160. Results of Experiments on Sliding Friction.—For accounts of recent experiments (and others) and deductions therefrom, the reader may consult the Engineer's "Pocket-books" of Kent and Trautwine; also Thurston's "*Friction* and *Lost Work*," Barr and Kimball's "*Machine Design*," and "*Lubrication and Lubricants*," by Archbutt and Deely. The following table gives a few values for the coefficient of friction, f, for slow motion, taken from the results obtained by Morin and others. Small changes in the condition of the surfaces may produce considerable variation in the value of f. Our knowledge is still quite incomplete in this respect.

TABLE FOR FRICTION OF SLOW MOTION.

No.	Surfaces.	Unguent.	Angle ϕ.	$f = \tan \phi$.
1	Wood on wood.	None.	14° to 26½°	0.25 to 0.50
2	Wood on wood.	Soap.	2° to 11½°	0.04 to 0.20
3	Metal on wood.	None.	26½° to 31½°	0.50 to 0.60
4	Metal on wood.	Water.	15° to 20°	0.25 to 0.35
5	Metal on wood.	Soap.	11½°	0.20
6	Leather on metal.	None.	29½°	0.56
7	Leather on metal.	Greased.	13°	0.23
8	Leather on metal.	Water.	20°	0.36
9	Leather on metal.	Oil.	8½°	0.15
10	Metal on metal	None	8½° to 18°	0.15 to 0.30
11	Metal on metal	Water	18° (average)	0.30
12	Metal on metal	Oil		0.001 to 0.080

For the coefficient of *friction of rest*, the above values might be increased from 20 to 40 per cent., roughly speaking.

As showing the effect of velocity in diminishing the friction of dry surfaces, we may note that in the Galton-Westinghouse experiments with railroad brakes (cast-iron brake-shoes on steel-tired car-wheels), values for f were found as follows: When the velocity of rubbing was 10 miles per hour, $f=0.24$; for 20 miles per hour, $f=0.19$; for 30, 40, 50, and 60 miles per hour f was found to be 0.164, 0.14, 0.116, and 0.074, respectively. The foregoing values of f were obtained immediately on the application of the brake, but when the brake-shoe and wheel had been in contact some five seconds at a constant velocity, f was reduced some 20 or 30 per cent.; while for a contact of 15 seconds still further reduction ensued. The value of f for a "skidding" car-wheel (i.e., held fast by the brake pressure) sliding or "skidding" on the rail, was reduced from 0.25 for impending skidding, to 0.09 at a velocity of 7 miles per hour; and to 0.03 for 60 miles per hour. (See p. 190.)

That increasing the velocity of lubricated surfaces diminishes the coefficient of friction is well shown in the results obtained by Mr. Wellington, in 1884, with journals revolving at different speeds, viz.,

For velocity =	0.00	2.16	4.86	21.42	53.01	106 ft./min.
Coeff. f =	0.118	0.094	0.069	0.047	0.035	0.026

For a sledge on dry ground Morin found $f=0.66$. For stone on stone, see p. 555 of this book.

161. Cone of Friction.—Fig. 170. Let A and B be two rough blocks, of which B is immovable, and P the resultant of all the forces acting on A, except the pressure from B. B can furnish any required normal pressure N to balance $P \cos \beta$, but the limit of its tangential resistance is fN. So long then as β is $< \varphi$ the angle of friction, or in other words, so long as the line of action of P is *within the "cone of friction"*



FIG. 170.

generated by revolving OC about ON, the block A will not slip on B, and the tangential resistance of B is simply $P \sin \beta$; but if β is $> \varphi$, this tangential resistance being only fN and $< P \sin \beta$, A will begin to slip, with an acceleration.

162. Problems in Sliding Friction.—In the following problems f is supposed known at points where rubbing occurs, or is impending. As to the pressure N to which the friction is due, it is generally to be considered unknown until determined by the conditions of the problem. Sometimes it may be an advantage to deal with the single unknown force P_1 (resultant of N and fN) acting in a line making the known angle φ with the normal (on the side *away* from the motion).

Problem 1.—Required the value of the weight P, Fig. 171, the slightest addition to which will cause motion of the horizontal rod OB, resting on rough planes at 45°. The weight G of the rod may be applied at the middle. Consider the rod free; at each point of contact there is an unknown N and a friction due to it fN; the tension in the cord will be $= P$, since there is no acceleration and no friction at pulley. Notice the direction of the frictions, both opposing the impending motion. Take axes OX and OY as shown, and note the intersections, A and C, of the line of G with axes OX and OY. The student should not rush to the conclusion that, if G were transferred to A and there resolved into components along AO and AB, the value of N (and N_1) would be equal to that of one of these components, viz., mG (where m denotes sin 45°). Few problems in mechanics are so simple as to admit of an immediate mental solution, and guess-work should be carefully avoided.



Fig. 171.

It will be found of advantage to take C as a center of moments. The line of P at O is considered as passing through point C, as also the lines of fN and fN_1. For equilibrium (impending slipping) we have, therefore,

$$\Sigma X = 0; \text{ i.e., } fN_1 + mG - N - P = 0; \quad . \quad . \quad . \quad (1)$$

$$\Sigma Y = 0; \text{ i.e., } N_1 + fN - mG = 0; \quad . \quad . \quad . \quad . \quad (2)$$

$$\Sigma(\text{moms.})_C = 0; \text{ i.e., } Na - N_1 a = 0. \quad . \quad . \quad . \quad (3)$$

The three unknowns P, N, and N_1, can now be found. From (3) we have $N = N_1$, which in (2) gives $N = \frac{mG}{1+f}$. Also from (1) we now find $P = 2fN$; and hence finally

$$P = \frac{2mfG}{1+f} = \frac{f\sqrt{2}}{1+f} \cdot G.$$

Problem 2.—Fig. 172. A rod, centre of gravity at middle, leans against a rough wall, and rests on an equally rough floor; how small may the angle α become before it slips? Let a = the half-length. The figure shows the rod free, and following the suggestion of §162, a single unknown force P_1 making a known angle φ (whose tan $= f$) with the normal DE, is put in at D, leaning away from the direction of the impending motion, instead of an N and fN; similarly P_2 acts at C. The present system consisting of but three forces, the most direct method of finding α, without introducing the other two unknowns P_1 and P_2 at all, is to use the principle that if three forces balance, their lines of action must intersect in a point. That is, P_2 must intersect the vertical containing G, the weight, in the same point as P_1, viz., A.



Fig. 172.

Now, since CF is ⌝ to FD and the two angles ϕ are equal, CA is ⌝ to DA and therefore DAC is a right triangle. We also note that if CA be prolonged to meet DF in some point K, A must be the mid-point of CK, since B is the mid-point of CF; and therefore it follows that in triangle DCK not only does DA bisect the side KC but is ⌝ to it. In other words, KDC is an isosceles triangle, with DK and DC as the two equal sides, and therefore the line DA bisects the angle KDC. Hence the angle $KDC = 2\phi$. That is to say, the angle α, which was to be determined, is the *complement of double the friction-angle*, or

$$\alpha = 90° - 2\phi.$$

PROBLEM 3.—Fig. 173. Given the resistance Q, acting parallel to the fixed guide C, the angle α, and the (equal) coefficients of friction at the rubbing surfaces, required the



FIG. 173.



FIG. 174.

amount of the horizontal force P, at the head of the block A (or *wedge*), to overcome Q and the frictions. D is fixed, and ab is perpendicular to cd. Here we have four unknowns, viz., P, and the three pressures N, N_1, and N_2, between the blocks. Consider A and B as free bodies, separately (see Fig. 174), remembering Newton's law of action and reaction. The full values (e.g., fN) of the frictions are put in, since we suppose a slow uniform motion taking place.

For A, $\Sigma X = 0$ and $\Sigma Y = 0$ give

$$N_1 - N\cos\alpha + fN\sin\alpha - P\sin\alpha = 0\,; \quad . \quad . \quad (1)$$

$$fN_1 + N\sin\alpha + fN\cos\alpha - P\cos\alpha = 0. \quad . \quad . \quad (2)$$

For B, ΣX and ΣY give

$$Q - N_1 + fN_2 = 0\,; \ldots . \ (3) \quad \text{and} \quad N_2 - fN_1 = 0. \ldots (4)$$

Solve (4) for N_2 and substitute in (3), whence

$$N_1(1 - f^2) = Q. \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

Solve (2) for N, substitute the result in (1), as also the value of N_1 from (5), and the resulting equation contains but one unknown, P. Solving for P, putting for brevity

$$f\cos\alpha + \sin\alpha = m \quad \text{and} \quad \cos\alpha - f\sin\alpha = n,$$

we have $$P = \frac{(m + fn)Q}{(n\,.\cos\alpha + m\,.\sin\alpha)(1 - f^2)}. \quad . \quad . \quad . \quad (6)$$

or $$P = Q(m + fn) \div (1 - f^2). \quad . \quad . \quad . \quad . \quad (7)$$

Numerical Example of Problem 3.—If $Q = 120$ lbs., $f = 0.20$ (*an abstract number, and* $\therefore$ *the same in any system of units*), while $\alpha = 14°$, whose sine $= 0.240$ and cosine $= .970$, then

$$m = 0.2 \times .97 + 0.24 = 0.43 \quad \text{and} \quad n = .97 - .2 \times .24 = 0.92,$$

whence $$P = 0.64Q = 76.8 \text{ lbs.}$$

While the wedge moves 2 inches P does the work (or exerts an energy) of $2 \times 76.80 = 153.6$ in.-lbs. $= 12.8$ ft.-lbs.

For a distance of 2 inches described by the wedge horizontally, the block B (and $\therefore$ the resistance Q) has been moved through a distance $= 2 \times \sin 14° = 0.48$ in. along the guide C, and hence the work of $120 \times 0.48 = 57.6$ in.-lbs. has been done upon Q. Therefore for the supposed portion of the motion $153.6 - 57.6 = 96.0$ in.-lbs. of work has been lost in friction (converted into heat).

For the "mechanical efficiency" of this machine (see § 153) we have $57.6 \div 153.6 = 0.375$. Also note that for $f = 1.00$ $P = \infty$; and for $\alpha = 90°$, $P = Q$.

Problem 4. *Numerical.*—With what minimum pressure P should the pulley A be held against B, which it drives by "frictional gearing," to transmit 2 H.P.; if $\alpha = 45°$, f for impending (relative) motion, i.e., for impending slipping $=$ 0.40, and the velocity of the pulley-rim is 9 ft. per second?



Fig. 175.

The limit-value of the tangential "grip"

$$T = 2fN = 2 \times 0.40 \times P \sin 45°,$$
$$2 \text{ H. P.} = 2 \times 550 = 1100 \text{ ft.-lbs. per second.}$$

Putting $T \times 9$ ft. $= 1100$, we have*

$$2 \times 0.40 \times \sqrt{\tfrac{1}{2}} \times P \times 9 = 1100 ; \therefore P = 215 \text{ lbs.}$$

Problem 6.—A block of weight G lies on a rough plane, inclined an angle β from the horizontal; find the pull P, making an angle α with the first plane, which will maintain a uniform motion *up* the plane.

* In this problem the student should note that, in general, when α is not 45°, we have $N = \frac{1}{2}P \div \cos \alpha$ (since in such a case the parallelogram of forces is not a square).

PROBLEM 7.—Same as 6, except that the pull P is to permit a uniform motion *down* the plane.

PROBLEM 8.—The thrust of a screw-propeller is 15 tons. The ring against which it is exerted has a mean radius of 8 inches, the shaft makes one revolution per second, and $f = 0.06$. Required the H. P. lost in friction from this cause.

Ans. 13.7 H. P.

163. The Bent-Lever with Friction. Worn Bearing.—Fig. 176. Neglect the weight of the lever, and suppose the plumber-block so worn that there is contact along one element only of the shaft. Given the amount and line of action of the resistance R, and the line of action of P, required the amount of the latter for impending slipping in the direction of the dotted arrow. As P gradually increases, the shaft of the lever (or gear-wheel) rolls on its bearing until the line of contact has reached some position A, when rolling ceases and slipping begins. To find A, and the value of P, note that the total action of the bearing upon the lever is some force P_1, applied at A and making a known angle φ ($f = \tan \varphi$) with the normal AC. P_1 must be equal and opposite to the resultant of the known R and the unknown P, and hence graphically (a graphic is much simpler here than an analytical solution) if we describe about C a circle of radius $= r \sin \varphi$, r being the radius of shaft (or gudgeon), and draw a tangent to it from D, we determine DA as the line of action of P_1. If DG is made $= R$, to scale, and GF drawn parallel to $D \ldots P$, P is determined, being $= DE$, while $P_1 = DF$.



FIG. 176.

If the known force R is capable of acting as a working force, by drawing the other tangent DB from D to the "friction-circle," we have $P = DH$, and $P_1 = DK$, for impending rotation in an opposite direction.

If R and P are the tooth-pressures upon two spur-wheels, keyed upon the same shaft and nearly in the same plane, the

same constructions hold good, and for a continuous uniform motion, since the friction $= P_1 \sin \varphi$,

$$\left.\begin{matrix}\text{the work lost in friction} \\ \text{per revolution,}\end{matrix}\right\} = [P_1 \sin \varphi] 2\pi r.$$

It is to be remarked, that without friction P_1 would pass through C, and that the moments of R and P would balance about C (for rest or uniform rotation); whereas with friction they balance about the proper tangent-point of the friction-circle.

Another way of stating this is as follows: So long as the resultant of P and R falls within the "dead-angle" BDA, motion is impossible in either direction.

If the weight of the lever is considered, the resultant of it and the force R can be substituted for the latter in the foregoing.

164. Bent-Lever with Friction. Triangular Bearing.—Like the preceding, the gudgeon is much exaggerated in the figure (177). For impending rotation in direction of the force P, the total actions at A_1 and A_2 must lie in known directions, making angles $= \varphi$ with the respective normals, and inclined away from the slipping. Join the intersections D and L. Since the resultant of P and R at D must act along DL to balance that of P_1 and P_2, having given one force, say R, we easily find $P = DE$, while P_1 and $P_2 = LM$ and LN respectively, LO having been made $= DF$, and the parallelogram completed.



FIG. 177.

(If the direction of impending rotation is reversed, the change in the construction is obvious.) If $P_2 = 0$, the case reduces to that in Fig. 176; if the construction gives P_2 negative, the supposed contact at A_2 is not realized, and the angle A_2CA_1 should be increased, or shifted, until P_2 is positive.

As before, P and R may be the tooth-pressures on two

spur-wheels nearly in the same plane and on the same shaft; if so, then, for a uniform rotation.

Work lost in fric. per revol. $= [P_1 \sin \varphi + P_2 \sin \varphi] 2\pi r$.

165. Axle-Friction.—The two foregoing articles are introductory to the subject of axle-friction. When the bearing is new, or nearly so, the elements of the axle which are in contact with the bearing are infinite in number, thus giving an infinite number of unknown forces similar to P_1 and P_2 of the last paragraph, each making an angle φ with its normal. Refined theories as to the law of distribution of these pressures are of little use, considering the uncertainties as to the value of $f (= \tan \varphi)$; hence for practical purposes axle-friction may be written

$$F' = f' R,$$

in which f' is a *coefficient of axle-friction* derivable from experiments with axles, and R the resultant pressure on the bearing. In some cases R may be partly due to the tightness of the bolts with which the cap of the bearing is fastened.

As before, the work lost in overcoming axle-friction *per revolution* is $= f' R 2\pi r$, in which r is the radius of the axle. f', like f, is an abstract number. As in Fig. 176, a "friction-circle," of radius $= f' r$, may be considered as subtending the "dead-angle."

166. Experiments with Axle-Friction.—Prominent among recent experiments have been those of Professor Thurston (1872–73), who invented a special instrument for that purpose, shown (in principle only) in Fig. 178. By means of an internal spring, the amount of whose compression is read on a scale, a weighted bar or pendulum is caused to exert pressure on a projecting axle from which it is suspended. The axle is made to rotate at any desired velocity by some source of power, the axle-friction causing



Fig. 178.

the pendulum to remain at rest at some angle of deviation from the vertical. The figure shows the pendulum free, the action of gravity upon it being G, that of the axle consisting of the two pressures,* each $= R$, and of the two frictions (each being $F = f'R$), due to them. Taking moments about C, we have for equilibrium

$$2f'Rr = Gb,$$

in which all the quantities except f' are known or observed. The temperature of the bearing is also noted, with reference to its effect on the lubricant employed. Thus the instrument covers a wide range of relations.

General Morin's experiments as interpreted by Weisbach give the following practical results: (See also p. 192).

For iron axles, in iron or brass bearings $\Big\}$ $f' = \begin{cases} 0.054 \text{ for well-sustained lubrication;} \\ 0.07 \text{ to } .08 \text{ for ordinary lubrication.} \end{cases}$

By "pressure per square inch on the bearing" is commonly meant the quotient of the total *pressure in lbs.* by the area in *square inches* obtained by multiplying the width of the axle by the length of bearing (this length is quite commonly four times the diameter); call it p, and the velocity of rubbing in *feet per minute*, v. Then, according to Rankine, to prevent overheating, we should have

$$p(v + 20) < 44800 \ldots \text{(not homog.)}.$$

Still, in marine-engine bearings pv alone often reaches 60,000, as also in some locomotives (Cotterill). Good practice keeps p within the limit of 800 (lbs. per sq. in.) for other metals than steel (Thurston), for which 1200 is sometimes allowed.

With $v = 200$ (feet per min.) Professor Thurston found that for ordinary lubricants p should not exceed values ranging from 30 to 75 (lbs. per sq. in.).

The product pv is obviously proportional to the power expended in wearing the rubbing surfaces, per unit of area.

* The weight G being small compared with the compressive force R in the spring, each pressure is practically equal to R.

167. Friction-Wheels—(Or, rather, *anti-friction* wheels). In Fig. 179, M and M (and two more behind) are the "friction-wheels," with axles C_1 and C_1 in fixed bearings.

G is the weight of a heavy wheel, P_1 is a known vertical resistance (tooth-pressure), and P an unknown vertical working force, whose value is to be determined to maintain a uniform rotation. The utility of the friction-wheels is also to be shown. The resultant of P_1, G, and P is a vertical force R, passing nearly through the centre C of the main axle which rolls on the four friction-wheels. R, resolved along CA and CB, produces (nearly) equal pressures, each being $N = R \div 2 \cos \alpha$, at the two axles of the friction-wheels, which rub against their fixed plumber-blocks. $R = P + P_1 + G_1$, and $\therefore$ contains the unknown P, but approximately $= G + 2P_1$, i.e., is nearly the same (in this case) whether friction-wheels are employed or not.



Fig. 179.

When G makes one revolution, the friction $f'N$ at each axle C_1 is overcome through a distance $= (r_1 : a_1)\, 2\pi r$, and

$$\left.\begin{array}{c}\text{Work lost per revol.}\\ \text{with}\\ \text{friction-wheels,}\end{array}\right\} = 2 f' N \frac{r_1}{a_1} 2\pi r = \frac{r_1}{a_1} \frac{1}{\cos \alpha} f' R 2\pi r.$$

Whereas, if C revolved in a fixed bearing,

$$\left.\begin{array}{c}\text{Work lost per revol.}\\ \text{without}\\ \text{friction-wheels,}\end{array}\right\} = f' R 2\pi r.$$

Apparently, then, there is a saving of work in the ratio $r_1 : a_1 \cos \alpha$, but strictly the R is not quite the same in the two cases; for with friction-wheels the force P is less than without, and R depends on P as well as on the known G and P_1. By diminishing the ratio $r_1 : a_1$, and the angle α, the saving is increased. If α were so large that $\cos \alpha < r_1 : a_1$, there would be no saving, but the reverse.

As to the value of P to maintain uniform rotation, we have

for equilibrium of moments about C, with friction-wheels (considering the large wheel and axle *free*),

$$Pb = P_1 b_1 + 2Tr, \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

in which T is the tangential action, or "grip," between one pair of friction-wheels and the axle C which rolls upon them. T would not equal fN unless slipping took place or were impending at E, but is known by considering a pair of friction-wheels free, when $\Sigma(Pa)$ about C_1 gives

$$Ta_1 = f'Nr_1 = f'\frac{R}{2} \cdot \frac{r_1}{\cos \alpha},$$

which in (1) gives finally

$$P = \frac{b_1}{b} P_1 + \frac{r_1}{a_1 \cos \alpha} f' R \frac{r}{b}. \quad . \quad . \quad . \quad . \quad (2)$$

Without friction-wheels, we would have

$$P = \frac{b_1}{b} P_1 + f' R \frac{r}{b}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

The last term in (2) is seen to be less than that in (3) (unless α is too large), in the same ratio as already found for the saving of work, supposing the R's equal.

If P_1 were on the same side of C as P, it would be of an opposite direction, and the pressure R would be diminished. Again, if P were horizontal, R would not be vertical, and the friction-wheel axles would not bear equal pressures. Since P depends on P_1, G, and *the frictions*, while the friction depends on R, and R on P_1, G, and P, an exact analysis is quite complex, and is not warranted by its practical utility.

Example.—If an empty vertical water-wheel weighs 25,000 lbs., required the force P to be applied at its circumference to maintain a uniform motion, with $a = 15$ ft., and $r = 5$ inches. Here $P_1 = 0$, and $R = G$ (nearly; neglecting the influence of P on R), i.e., $R = 25{,}000$ lbs.

First, without friction-wheels (adopting the foot-pound-second system of units), with $f' = .07$ (abstract number). From eq. (3) we have

$$P = 0 + 0.07 \times 25{,}000 \times (\tfrac{5}{12} \div 15) = 48.6 \text{ lbs.}$$

The work lost in friction per revolution is

$$f R 2\pi r = 0.07 \times 25{,}000 \times 2 \times 3.14 \times \tfrac{5}{12} = 4580 \text{ ft.-lbs.}$$

Secondly, with friction-wheels, in which $r_1 : a_1 = \frac{1}{5}$ and $\cos \alpha = 0.80$ (i.e., $\alpha = 36°$). From eq. (2)

$$P = 0 + \tfrac{1}{5} \cdot \tfrac{10}{8} \times 48.6 = \text{only } 12.15 \text{ lbs.},$$

while the work lost per revolution

$$= \tfrac{1}{5} \cdot \tfrac{10}{8} \times 4580 = 1145 \text{ ft.-lbs.}$$

Of course with friction-wheels the wheel is not so steady as without.

In this example the force P has been simply enough to overcome friction. In case the wheel is in actual use, P is the weight of water actually in the buckets at any instant, and does the work of overcoming P_1, the resistance of the mill machinery, and also the friction. By placing P_1 pointing upward on the same side of C as P, and making b_1 nearly $= b$, R will $= G$ nearly, just as when the wheel is running empty; and the foregoing numerical results will still hold good for practical purposes.

168. Friction of Pivots.—In the case of a vertical shaft or axle, and sometimes in other cases, the extremity requires support against a thrust along the axis of the axle or pivot. If the end of the pivot is *flat* and also the surface against which it rubs, we may consider the pressure, and therefore the friction, as uniform over the surface. With a flat circular pivot, then, Fig. 180, the frictions on a small sector of the circle form a system of parallel forces whose resultant is equal to their sum, and is applied a distance of $\frac{2}{3}r$ from the centre. Hence the sum of the moments of all the frictions about the centre $= fR\frac{2}{3}r$, in which R is the axial pressure. Therefore a force P necessary to overcome the friction with uniform rotation must have a moment



FIG. 180.

$$Pa = fR\tfrac{2}{3}r,$$

and the work lost in friction per revolution is

$$= fR2\pi \cdot \tfrac{2}{3}r = \tfrac{4}{3}\pi fRr. \quad . \quad . \quad . \quad . \quad (1)$$

As the pivot and step become worn, the resultant frictions in the small sectors probably approach the centre; for the greatest wear occurs first near the outer edge, since there the product pv is greatest (see § 166). Hence for $\frac{2}{3}r$ we may more reasonably put $\frac{1}{2}r$.

Example.—A vertical flat-ended pivot presses its step with a force of 12 tons, is 6 inches in diameter, and makes 40 revolutions per minute. Required the H. P. absorbed by the friction. Supposing the pivot and step new, and f for good lubrication $= 0.07$, we have, from eq. (1) (*foot-lb.-second*),

Work lost per revolution

$$= .07 \times 24{,}000 \times 6.28 \times \tfrac{2}{3} \cdot \tfrac{1}{4} = 1758.4 \text{ ft.-lbs.},$$

and ∴ work per second

$$= 1758.4 \times \tfrac{40}{60} \qquad = 1172.2 \text{ ft.-lbs.},$$

which ÷ 550 gives 2.13 H. P. absorbed in friction. If ordinary axle-friction also occurs its effect must be added.

If the flat-ended pivot is *hollow*, with radii r_1 and r_2, we may put $\frac{1}{2}(r_1 + r_2)$ instead of the $\frac{2}{3}r$ of the preceding.

It is obvious that the smaller the lever-arm given to the resultant friction in each sector of the rubbing surface the smaller the power lost in friction. Hence pivots should be made as small as possible, consistently with strength.

For a *conical pivot* and step, Fig. 181, the resultant friction in each sector of the conical bearing surface has a lever-arm $= \frac{2}{3}r_1$ about the axis A, and a value $>$ than for a flat-ended pivot; for, on account of the wedge-like action of the bodies, the pressure causing friction is greater. The sum of the moments of these resultant frictions about A is the same as if only two elements of the cone received pressure (each $= N = \frac{1}{2}R \div \sin \alpha$). Hence the



FIG. 181.

moment of friction of the pivot, i.e., the moment of the force necessary to maintain uniform rotation, is

$$Pa = f2N\frac{2}{3}r_1 = f\frac{R}{\sin\alpha}\frac{2}{3}r_1,$$

and work lost per revolution $= \frac{4}{3}\pi f\frac{R}{\sin\alpha}r_1$.

By making r_1 small enough, these values may be made less than those for a flat-ended pivot of the same diameter = 2r.

In Schiele's "anti-friction" pivots the outline is designed according to the following theory for securing uniform vertical wear. Let p = the pressure per *horizontal* unit of area (i.e., = $R \div$ horizontal projection of the *actual rubbing surface*); this is assumed constant. Let the unit of area be small, for algebraic simplicity. The friction on the rubbing surface, whose horizontal projection = unity, is $= fN = f(p \div \sin\alpha)$ (see Fig. 182; the horizontal component of p is annulled by a corresponding one opposite). The work per revolution in producing wear on this area $= fN2\pi y$. But the *vertical depth* of wear per revolution is to be the same at all parts of the surface; and this implies that the same volume of material is worn away under each horizontal unit of area. Hence $fN2\pi y$, i.e., $f\frac{p}{\sin\alpha}2\pi y$, is to be constant for all values of y; and since fp and 2π are constant, we must have, as the law of the curve,



FIG. 182.

$$\frac{y}{\sin\alpha}, \text{ i.e., } \textit{the tangent } BC = \textit{the same at all points.}$$

This curve is called the "*tractrix*." Schiele's pivots give a very uniform wear at high speeds. The smoothness of wear prevents leakage in the case of cocks and faucets.

169. Normal Pressure of Belting.—When a perfectly flexible cord, or belt, is stretched over a smooth cylinder, both at rest,

the action between them is normal at every point. As to its amount, p, per linear unit of arc, the following will determine. Consider a semicircle of the cord free, neglecting its weight. Fig. 183. The forces holding it in equilibrium are the tensions at the two ends (these are equal, manifestly, the cylinder being smooth; for they are the only two forces having moments about C, and each has the *same lever-arm*), and the normal pressures, which are infinite in number, but have an intensity, p, per linear unit, which must be constant along the curve since S is the same at all points. The normal pressure on a single element, ds, of the cord is $= pds$, and its X component $= pds \cos\theta = prd\theta \cos\theta$. Hence $\Sigma X = 0$ gives



Fig. 183.

$$rp\int_{-\frac{1}{2}\pi}^{+\frac{1}{2}\pi} \cos\theta d\theta - 2S = 0, \text{ i.e., } rp\Big[_{-\frac{1}{2}\pi}^{+\frac{1}{2}\pi} \sin\theta = 2S;$$

$$\therefore rp[1-(-1)] = 2S \quad \text{or} \quad p = \frac{S}{r}. \quad . \quad . \quad . \quad . \quad (1)$$

170. Belt on Rough Cylinder. Impending Slipping.—If friction is possible between the two bodies, the tension may vary along the arc of contact, so that p also varies, and consequently



Fig. 184.



Fig. 185.

the friction on an element ds being $= fpds = f(S \div r)ds$, also varies. If *slipping is impending*, the law of variation of the tension S may be found, as follows: Fig. 184, in which the

impending slipping is toward the left, shows the cord free. For any element, ds, of the cord, we have, putting Σ (moms. about O) $= 0$ (Fig. 185),

$$(S + dS)r = Sr + dFr\,;\ \text{i.e.,}\ dF = dS,$$

or (see above) $dS = f(S \div r)ds$.

But $ds = rd\theta$; hence, after transforming,

$$fd\theta = \frac{dS}{S}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

In (1) the two variables θ and S are separated; (1) is therefore ready for integration.

$$\therefore f\int_0^{\alpha} d\theta = \int_{S_0}^{S_n} \frac{dS}{S}\,;\ \text{i.e.,}$$

$$f\alpha = \log_e S_n - \log_e S_0 = \log_e\left[\frac{S_n}{S_0}\right]. \quad (2)$$

Or, by inversion, $$S_0 e^{f\alpha} = S_n, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

e, denoting the Naperian base, $= 2.71828 +$; α of course is in π-measure.

Since S_n evidently increases very rapidly as α becomes larger, S_0 remaining the same, we have the explanation of the well-known fact that a comparatively small tension, S_0, exerted by a man, is able to prevent the slipping of a rope around a pile-head, when the further end is under the great tension S_n due to the stopping of a moving steamer. For example, with $f = \frac{1}{3}$, we have (Weisbach)

$$\begin{aligned}
\text{for } \alpha &= \tfrac{1}{4} \text{ turn, or } \alpha = \tfrac{1}{2}\pi,\ S_n = 1.69S_0\,;\\
&= \tfrac{1}{2} \text{ turn, or } \alpha = \pi,\ S_n = 2.85S_0\,;\\
&= 1 \text{ turn, or } \alpha = 2\pi,\ S_n = 8.12S_0\,;\\
&= 2 \text{ turns, or } \alpha = 4\pi,\ S_n = 65.94S_0\,;\\
&= 4 \text{ turns, or } \alpha = 8\pi,\ S_n = 4348.56S_0.
\end{aligned}$$

If slipping actually occurs, we must use a value of f for friction of motion.

Example.—A leather belt drives an iron pulley, covering one half the circumference. What is the limiting value of the

ratio of S_n (tension on driving-side) to S_0 (tension on following side) if the belt is not to slip, taking the low value of $f = 0.25$ for leather on iron?

We have given $f\alpha = 0.25 \times \pi = .7854$, which by eq. (2) is the Naperian log. of $(S_n : S_0)$ when slipping occurs. Hence the common log. of $(S_n : S_0) = 0.7854 \times 0.43429 = 0.34109$; i.e., if

$$(S_n : S_0) = 2.193, \text{ say } 2.2,$$

the belt will (barely) slip (for $f = 0.25$).

(0.43429 is the modulus of the common system of logarithms, and $= 1 : 2.30258$. See example in § 48.)

At very high speeds the relation $p = S \div r$ (in § 169) is not strictly true, since the tensions at the two ends of an element ds are partly employed in furnishing the necessary deviating force to keep the element of the cord in its circular path, the remainder producing normal pressure.

171. Transmission of Power by Belting or Wire Rope.—In the simple design in Fig. 186, it is required to find the *motive weight* G, necessary to overcome the given resistance R at a



FIG. 186.

uniform velocity $= v_1$; also the proper stationary *tension weight* G_0 to prevent slipping of the belt on its pulleys, and the amount of power, L, transmitted.

In other words,

Given: { R, a, r, a_1, r_1; $\alpha = \pi$ for both pulleys, v_1; and f for both pulleys; }

Required: { L; G, to furnish L; G_0 for no slip; v the velocity of G; v' that of belt; and the tensions in belt.

Neglecting axle-friction and the rigidity of the belting, the power transmitted is that required to overcome R through a distance $= v_1$ every second, i.e.,

$$L = Rv_1. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

Since (if the belts do not slip)

$$a : r :: v' : v, \quad \text{and} \quad a_1 : r_1 :: v' : v_1,$$

we have $$v' = \frac{a_1}{r_1} v_1, \quad \text{and} \quad v = \frac{r}{a}\frac{a_1}{r_1} v_1. \quad . \quad . \quad . \quad . \quad (2)$$

Neglecting the mass of the belt, and assuming that each pulley revolves on a gravity-axis, we obtain the following, by considering the free bodies in Fig. 187:



FIG. 187.

$$\Sigma(\text{moms.}) = 0 \text{ in } A \textit{ free} \text{ gives } Rr_1 = (S_n - S_0)a_1; \quad . \quad (3)$$

$$\Sigma(\text{moms.}) = 0 \text{ in } B \text{ free gives } Gr = (S_n - S_0)a; \quad . \quad (4)$$

whence we readily find $$G = \frac{a}{r} \cdot \frac{r_1}{a_1} R.$$

Evidently R and G are inversely proportional to their velocities v_1 and v; see (2). This ought to be true, since in Fig. 186 G is the only working-force, R the only resistance, and the motions are uniform; hence (from eq. (XVI.), § 142)

$$Gv - Rv_1 = 0.$$

$\Sigma X = 0$, for B and truck free, gives

$$G_0 = S_n + S_0, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

while, for impending slip,

$$S_n = S_0 e^{f\pi}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (6)$$

By elimination between (4), (5), and (6), we obtain

$$G_0 = G\frac{r}{a} \cdot \frac{e^{f\pi}+1}{e^{f\pi}-1} = \frac{L}{v'} \cdot \frac{e^{f\pi}+1}{e^{f\pi}-1}, \quad . \quad . \quad . \quad (7)$$

and

$$S_n = \frac{L}{v'} \cdot \frac{e^{f\pi}}{e^{f\pi}-1}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (8)$$

Hence G_0 and S_n vary directly as the power transmitted and inversely as the velocity of the belt. For safety G_0 should be made $>$ the above value in (7); corresponding values of the two tensions may then be found from (5), and from the relation (see § 150)

$$(S_n - S_0)v' = L. \quad . \quad . \quad . \quad . \quad . \quad . \quad (6a)$$

These *new* values of the tensions will be found to satisfy the condition of no slip, viz.,

$$(S_n : S_0) < e^{f\pi} (\S\ 170).$$

For leather on iron, $e^{f\pi} = 2.2$ (see example in § 170), as a low value. The belt should be made strong enough to withstand S_n safely.

As the belt is more tightly stretched, and hence elongated, on the driving than on the following side, it "*creeps*" backward on the driving and forward on the driven pulley, so that the former moves slightly faster than the latter. The loss of work due to this cause does not exceed 2 per cent with ordinary belting (Cotterill).

In the foregoing it is evident that the sum of the tensions in the two sides $= G_0$, i.e., is the same, whether the power is being transmitted or not; and this is found to be true, both in theory and by experiment, when a tension-weight is not used, viz., when an initial tension S is produced in the whole belt before transmitting the power, then after turning on the latter the sum of the two tensions (driving and following) always $= 2S$, since one side elongates as much as the other contracts; it being understood that the pulley-axles preserve a constant distance apart.

172. Rolling Friction.—The few experiments which have been made to determine the resistance offered by a level road-

way to the uniform motion of a roller or wheel rolling upon it corroborate approximately the following theory. The word friction is hardly appropriate in this connection (except when the roadway is perfectly elastic, as will be seen), but is sanctioned by usage.

First, let the roadway or track be compressible, but *inelastic*, G the weight of the roller and its load, and P the horizontal force necessary to preserve a uniform motion (both of translation and rotation). The track (or roller itself) being compressed just in front, and not reacting symmetrically from behind, its resultant pressure against the roller is not at O vertically under the centre, but some small distance, $OD = b$, in front. (The successive crushing of small projecting particles has the same effect.) Since for this case of motion the forces have the same relations as if balanced (see § 124), we may put Σ moms. about $D = 0$,



Fig. 188.

$$\therefore Pr = Gb; \quad \text{or,} \quad P = \frac{b}{r}G. \quad . \quad . \quad . \quad . \quad (1)$$

According to Professor Goodman we have the following values of b, approximately:

	Inches.
Iron or steel wheels on iron or steel rails..	$b = 0.007$ to 0.015
" " " " " wood.....	0.06 " 0.10
" " " " " macadam.....	0.05 " 0.20
" " " " " soft ground.....	3.0 " 5.0
Pneumatic tires on good road, or asphalt..	0.02 " 0.022
" " " heavy mud	0.04 " 0.06
Solid rubber tires on good road, or asphalt	0.04
" " " " heavy mud.....	0.09 " 0.11

According to the foregoing theory, P, the "rolling friction" (see eq. (1)), is directly proportional to G, and inversely to the radius, if b is constant. The experiments of General Morin and others confirm this, while those of Dupuit, Poirée, and Sauvage indicate it to be proportional directly to G, and inversely to the square root of the radius.

Although b is a *distance* to be expressed in linear units, and not an abstract number like the f and f' for sliding and axle-friction, it is sometimes called a "coefficient of rolling friction." In eq. (1), b and r should be expressed in the same unit.

Of course if P is applied at the top of the roller its lever-arm about D is $2r$ instead of r, with a corresponding change in eq. (1).

With ordinary railroad cars the resistance due to axle and rolling frictions combined is about 8 lbs. per ton of weight on a level track. For wagons on macadamized roads $b = \frac{1}{2}$ inch, but on soft ground from 2 to 3 inches.

Secondly, when the roadway is *perfectly elastic*. This is chiefly of theoretic interest, since at first sight no force would be considered necessary to maintain a uniform rolling motion. But, as the material of the roadway is compressed under the roller its surface is first elongated and then recovers its former state; hence some rubbing and consequent sliding friction must



FIG. 189.

occur. Fig. 189 gives an exaggerated view of the circumstances, P being the horizontal force applied at the centre necessary to maintain a uniform motion. The roadway (rubber for instance) is heaped up both in front and behind the roller, O being the point of greatest pressure and elongation of the surface. The forces acting are G, P, the normal pressures, and the frictions due to them, and must form a balanced system. Hence, since G and P, and also the normal pressures, pass through C, the resultant of the frictions must also pass through C; therefore the frictions, or tangential actions, on the roller must be some forward and some backward (and not all in one direction, as seems to be asserted on p. 260 of Cotterill's Applied Mechanics, where Professor Reynolds'

explanation is cited). The resultant action of the roadway upon the roller acts, then, through some point D, a distance $OD = b$ ahead of O, and in the direction DC, and we have as before, with D as a centre of moments,

$$Pr = Gb, \quad \text{or} \quad P = \frac{b}{r}G.$$

If rolling friction is encountered *above as well as below* the rollers, Fig. 190, the student may easily prove, by considering three separate free bodies, that for uniform motion



FIG. 190.

$$P = \frac{b + b_1}{2r}G, \quad \ldots\ldots \quad (2)$$

where b and b_1 are the respective "coefficients of rolling friction" for the upper and lower contacts. (See Kent's "*Pocket-Book for Mechanical Engineers*" for "friction-rollers," "ball-bearings," and "roller-bearings."

Example 1.—If it is found that a train of cars will move *uniformly* down an incline of 1 in 200, gravity being the only working force, and friction (both rolling and axle) the only resistance, required the coefficient, f', of axle-friction, the diameter of all the wheels being $2r = 30$ inches, that of the journals $2a = 3$ inches, taking $b = 0.02$ inch for the rolling friction. Let us use equation (XVI.) (§ 142), noting that while the train moves a distance s measured on the incline, its weight G does the work $G\frac{1}{200}s$, the rolling friction $\frac{b}{r}G$ (at* the axles) has been overcome through the distance s, and the axle-friction (total) through the (relative) distance $\frac{a}{r}s$ in the journal boxes; whence, the change in kinetic energy being zero,

$$\frac{1}{200}Gs - \frac{b}{r}Gs - \frac{a}{r}f'Gs = 0.$$

Gs cancels out, the ratios $b : r$ and $a : r$ are $= \frac{2}{1000}$ and $\frac{1}{10}$, respectively (being ratios or abstract numbers they have the

* That is, the ideal resistance, at centre of axles and ‖ to the incline, equivalent to actual rolling resistance.

same numerical values, whether the inch or foot is used), and solving, we have

$$f' = 0.05 - 0.0133 = 0.036.$$

Example 2.—How many pounds of tractive effort per ton of load would the train in Example 1 require for uniform motion on a level track? *Ans.* 10 lbs.

173. Railroad Brakes.*—During the uniform motion of a railroad car the tangential action between the track and each wheel is small. Thus, in Example 1, just cited, if ten cars of eight wheels each make up the train, each car weighing 20 tons, the backward tangential action of the rails upon each wheel is only 25 lbs. When the brakes are applied to stop the train this action is much increased, and is the only agency by which the rails can retard the train, directly or indirectly: *directly*, when the pressure of the brakes is so great as to prevent the wheels from turning, thereby causing them to "skid" (i.e., slide) on the rails; *indirectly*, when the brake-pressure is of such a value as still to permit perfect rolling of the wheel, in which case the rubbing (and heating) occurs between the brake and wheel, and the tangential action of the rail has a value equal to or less than the friction of rest. In the first case, then (skidding), the retarding influence of the rails is the *friction of motion* between rail and wheel; in the second, a force which may be made as great as the *friction of rest* between rail and wheel. Hence, aside from the fact that skidding produces objectionable flat places on the wheel-tread, the brakes are more effective if so applied that skidding is *impending*, but not actually produced; for the friction of rest is usually greater than that of actual slipping (§ 160). This has been proved experimentally in England. The retarding effect of axle and rolling friction has been neglected in the above theory.

Example 1.—A twenty-ton car with an initial velocity of 80 feet per second (nearly a mile a minute) is to be stopped on a level within 1000 feet; required the necessary friction on each of the eight wheels.

Supposing the wheels not to skid, the friction will occur

* See statement on p. 168, as to diminution of the coefficient f with speed.

between the brakes and wheels, and is overcome through the (relative) distance 1000 feet. Eq. (XVI.), § 142, gives (foot-lb.-second system)

$$0 - 8F \times 1000 = 0 - \frac{1}{2}\frac{40000}{32.2}(80)^2,$$

from which F (= friction at circumference of each wheel) = 496 lbs.

Note.—This result of 496 lbs. must be looked upon as only an average value. For a given pressure, N, of brake-shoe on wheel-rim on account of the variation of the coefficient f' with changing speed (see p. 168) the friction will be small at first and gradually increase. This same remark applies to Examples 3 and 4, also.

Example 2.—Suppose skidding to be impending in the foregoing, and the coefficient of friction of rest (i.e., impending slipping) between rail and wheel to be $f = 0.20$. In what distance will the car be stopped? *Ans.* 496 ft.

Example 3.—Suppose the car in Example 1 to be on an upgrade of 60 feet to the mile. (In applying eq. (XVI.) here, the weight 20 tons will enter as a resistance.) *Ans.* 439 lbs.

Example 4.—In Example 3, consider all four resistances, viz., gravity, rolling friction, and brake and axle frictions, the distance being 1000 ft., and F the unknown quantity.

(Take the wheel dimensions of p. 189.) *Ans.* 414 lbs.

174. Friction of Car-journals in Brass Bearings.—(Prof. J. E. Denton, in Vol. xii Transac. Am. Soc. Mech. Engs., p. 405; also Kent's Pocket-Book.) A new brass dressed with an emery wheel, loaded with 5000 lbs., may have an actual bearing surface on the journal, as shown by the polish of a portion of the surface, of only one sq. inch. With this pressure of 5000 lbs./sq.in. the coefficient of friction may be 0.060 and the brass may be overheated, scarred, and cut; or, on the contrary, it may wear down evenly to a smooth bearing, giving a highly polished area of contact of 3 sq. in., or more, inside of two hours of running, gradually decreasing the pressure per sq. in. of contact, and showing a coefficient of friction of less than 0.005. A reciprocating motion in the direction of the axis is of importance in reducing the friction. With such polished surfaces any oil will lubricate and the

coefficient of friction then depends on the viscosity of the oil. With a pressure of 1000 lbs. per sq. in., revolutions from 170 to 320 per min., and temperature of 75° to 113° Fahr., with both sperm and parraffine oils, a coefficient as low as 0.0011 has been obtained, the oil being fed continuously by a pad.

175. Well Lubricated Journals. Laws of Friction.—In the Proc. Inst. Civ. Engs. for 1886 (see also *Engineering News* for Mar. 31, April 7 and 14, 1888) Prof. Goodman presents the conclusions arrived at by him as to the laws of friction of well lubricated journals as based on the experiments made by Thurston, Beauchamp Tower, and Stroudley. They are as follows:

1. The coefficient friction with the surfaces efficiently lubricated is from $\frac{1}{6}$ to $\frac{1}{10}$ that for dry or scantily lubricated surfaces.

2. The coefficient of friction for moderate pressures and speeds varies approximately inversely as the normal pressure; the frictional resistance varies as the area in contact, the normal pressure remaining constant.

3. At very low journal speeds the coefficient of friction is abnormally high, but as the speed of sliding increases from about 10 to 100 ft. per min. the friction diminishes; and again rises when that speed is exceeded, varying approximately as the square root of the speed.

4. The coefficient of friction varies approximately inversely as the temperature, within certain limits, viz., just before abrasion takes place.

In one of Mr. Tower's experiments it was found that when the lubrication was made by a pad under the journal (which received pressure on its upper surface) the coefficient was some seven times as large as when an "oil bath," or copious supply of oil, was provided; (0.0090 as against 0.0014).

176. Rigidity of Ropes.—If a rope or wire cable passes over a pulley or sheave, a force P is required on one side greater than the resistance Q on the other for uniform motion, aside from axle-friction. Since in a given time both P and Q describe the same space s, if P is $> Q$, then Ps is $> Qs$, i.e., the work done by P is $>$ than that expended upon Q. This is because some of the work Ps has been expended in bending the stiff rope or cable, and in overcoming friction between the strands, both where the rope passes upon and where it leaves

the pulley. With hemp ropes, Fig. 191, the material being nearly inelastic, the energy spent in bending it on at D is nearly all lost, and energy must also be spent in straightening



Fig. 191.

it at E; but with a wire rope or cable some of this energy is restored by the elasticity of the material. The energy spent in friction or rubbing of strands, however, is lost in both cases.

The figure shows geometrically why P must be $> Q$ for a uniform motion, for the lever-arm, a, of P is evidently $< b$ that of Q. If axle-friction is also considered, we must have

$$Pa = Qb + f'(P + Q)r,$$

r being the radius of the journal.

Experiments with cordage have been made by Prony, Coulomb, Eytelwein, and Weisbach, with considerable variation in the results and formulæ proposed. (See Coxe's translation of vol. i., Weisbach's Mechanics.)

With pulleys of large diameter the effect of rigidity is very slight. For instance, Weisbach gives an example of a pulley five feet in diameter, with which, Q being $= 1200$ lbs., $P = 1219$. A wire rope $\frac{3}{8}$ in. in diameter was used. Of this difference, 19 lbs., only 5 lbs. was due to rigidity, the remainder, 14 lbs., being caused by axle-friction. When a hemp-rope 1.6 inches in diameter was substituted for the wire one, $P - Q = 27$ lbs., of which 12 lbs. was due to the rigidity. Hence in one case the loss of work was less than $\frac{1}{2}$ of 1%, in the other about 1%, caused by the rigidity. For very small sheaves and thick ropes the loss is probably much greater.

177. **Miscellaneous Examples.**—*Example* 1. The end of a shaft 12 inches in diameter and making 50 revolutions per minute exerts against its bearing an axial pressure of 10 tons and a lateral pressure of 40 tons. With $f = f' = 0.05$, required the H. P. lost in friction. *Ans.* 22.2 H. P.

Example 2.—A leather belt passes over a vertical pulley, covering half its circumference. One end is held by a spring balance, which reads 10 lbs. while the other end sustains a weight of 20 lbs., the pulley making 100 revolutions per minute. Required the coefficient of friction, and the H. P. spent in overcoming the friction. Also suppose the pulley turned in the other direction, the weight remaining the same. The diameter of the pulley is 18 inches. *Ans.* $\begin{cases} f = 0.22\,; \\ 0.142 \text{ and } .284 \text{ H. P.} \end{cases}$

Example 3.—A grindstone with a radius of gyration = 12 inches has been revolving at 120 revolutions per minute, and at a given instant is left to the influence of gravity and axle friction. The axles are $1\frac{1}{2}$ inches in diameter, and the wheel makes 160 revolutions in coming to rest. Required the coefficient of axle-friction. (Average.) *Ans.* $f = 0.039$.

Example 4.—A board A, weight 2 lbs., rests horizontally on another B; coefficient of friction of rest between them being $f = 0.30$. B is now moved horizontally with a uniformly accelerated motion, the acceleration being = 15 feet per "square second;" will A keep company with it, or not? *Ans.* "No."

PART III.

STRENGTH OF MATERIALS.

[Or Mechanics of Materials].

CHAPTER I.

ELEMENTARY STRESSES AND STRAINS.

178. Deformation of Solid Bodies.—In the preceding portions of this work, what was called technically a "rigid body," was supposed incapable of changing its form, i.e., the positions of its particles relatively to each other, under the action of any forces to be brought upon it. This supposition was made because the change of form which must actually occur does not appreciably alter the distances, angles, etc., measured in any one body, among most of the pieces of a properly designed structure or machine. To show how the individual pieces of such constructions should be designed to avoid undesirable deformation or injury is the object of this division of Mechanics of Engineering, viz., the Strength of Materials.



Fig. 192. § 178.

As perhaps the simplest instance of the deformation or distortion of a solid, let us consider the case of a prismatic rod in a state of tension, Fig. 192 (eye-bar of a bridge

truss, e.g.). The pull at each end is P, and the body is said to be under a tension of P (lbs., tons, or other unit), not $2P$. Let $ABCD$ be the end view of an elementary parallelopiped, originally of square section and with faces at 45° with the axis of the prism. It is now deformed, the four faces perpendicular to the paper being longer* than before, while the angles BAD and BCD, originally right angles, are now smaller by a certain amount δ, ABC and ADC larger by an equal amount δ. The element is said to be in a state of **strain**, viz.: the elongation of its edges (parallel to paper) is called a **tensile strain**, while the alteration in the angles between its faces is called a *shearing strain*, or angular distortion (sometimes also called a sliding, or tangential, strain, since BC has been made to slide, relatively to AD, and thereby caused the change of angle). [This use of the word strain, to signify change of form and not the force producing it, is of recent adoption among many, though not all, technical writers.]

179. Strains. Two Kinds Only.—Just as a curved line may be considered to be made up of small straight-line elements, so the substance of any solid body may be considered to be made up of small contiguous parallelopipeds, whose angles are each 90° before the body is subjected to the action of forces, but which are not necessarily cubes. A line of such elements forming an elementary prism is sometimes called a *fibre*, but this does not necessarily imply a fibrous nature in the material in question. The system of imaginary cutting surfaces by which the body is thus subdivided need not consist entirely of planes ; in the subject of Torsion, for instance, the parallelopipedical elements considered lie in concentric cylindrical shells, cut both by transverse and radial planes.

Since these elements are taken so small that the only possible changes of form in any one of them, as induced by a system of external forces acting on the body, are

* When α is nearly 0° (or 90°) BC and AD (or AB and DC) are shorter than before, on account of lateral contraction; see § 193.

elongations or contractions of its edges, and alteration of its angles, there are but two kinds of strain, **elongation** (contraction, if negative) and **shearing**.

180. **Distributed Forces or Stresses.**—In the matter preceding this chapter it has sufficed for practical purposes to consider a force as applied at a *point* of a body, but in reality it must be distributed over a definite area; for otherwise the material would be subjected to an infinite force per unit of area. (Forces like gravity, magnetic attraction, etc., we have already treated as distributed over the mass of a body, but reference is now had particularly to the pressure of one body against another, or the action of one portion of the body on the remainder.) For instance, sufficient surface must be provided between the end of a loaded beam and the pier on which it rests to avoid injury to either. Again, too small a wire must not be used to sustain a given load, or the tension per unit of area of its cross section becomes sufficient to rupture it.

Stress is distributed force, and its intensity at any point of the area is

$$p=\frac{dP}{dF} \quad . \quad . \quad . \quad (1)$$

where dF is a small area containing the point and dP the force coming upon that area. If equal dP's (all parallel) act on equal dF's of a plane surface, the stress is said to be of uniform intensity, which is then

$$p=\frac{P}{F} \quad . \quad . \quad . \quad . \quad (2)$$

where P = total force and F the total area over which it acts. The steam pressure on a piston is an example of stress of uniform intensity.

For example, if a force $P=28800$ lbs, is uniformly distributed over a plane area of $F=72$ sq. inches, or ½ of a sq. foot, the intensity of the stress is

$$p=\frac{28800}{72}=400 \text{ lbs. per sq. inch,}$$

(or $p=28800\div ½=57600$ lbs. per sq. foot, or $p=14.400\div ½=28.8$ tons per sq. ft., etc.

181. Stresses on an Element: of Two Kinds Only.—When a solid body of any material is in equilibrium under a system of forces which do not rupture it, not only is its shape altered (i.e. its elements are *strained*), and stresses produced on those planes on which the forces act, but other stresses also are induced on some or all internal surfaces which separate element from element, over and above the forces with which the elements may have acted on each other before the application of the external stresses or "applied forces"). So long as the whole solid is the "*free body*" under consideration, these internal stresses, being the forces with which the portion on one side of an imaginary cutting plane acts on the portion on the other side, do not appear in any equation of equilibrium (for if introduced they would cancel out); but if we consider free a portion only, some or all of whose bounding surfaces are cutting planes of the original body, the stresses existing on these planes are brought into the equations of equilibrium.

Similarly, if a single element of the body is treated by itself, the stresses on all six of its faces, together with its weight, form a balanced system of forces, the body being supposed at rest.

FIG. 198.

As an example of internal stress, consider again the case of a bar in tension; Fig. 193 shows the whole bar (or eye-bar) free, the forces P being the pressures of the pins in the eyes, and causing external stress (compression here) on the surfaces of contact. Conceive a right section made through RS, far enough from the eye, C, that we may consider the internal stress to be uniform * in this section, and consider the portion RSC as a free body, in Fig. 194. The stresses on RS, now one of the bounding surfaces of the free body, must be parallel to P, i.e., normal to RS; (otherwise they would have components perpendicular to P, which is precluded by the necessity of ΣY being $= 0$, and the supposition of uniformity.) Let F = the sec-



FIG. 194.



FIG. 195.

tional area RS, and p = the stress per unit of area; then

$$\Sigma X = 0 \text{ gives } P = Fp, \text{ i.e., } p = \frac{P}{F} \qquad . \qquad .(2)$$

The state of internal stress, then, is such that on planes perpendicular to the axis of the bar the stress is *tensile* and *normal* (to those planes). Since if a section were made oblique to the axis of the bar, the stress would still be parallel to the axis for reasons as above, it is evident that on an oblique section, the stress has components both *normal* and *tangential* to the section, the normal component being a tension.

* As will be shown later (§ 295) the line of the two P's in Fig. 193 must pass through the centre of gravity of the cross-section RS (plane figure) of the bar, for the stress to be uniform over the section.

The presence of the *tangential* or *shearing* stress in oblique sections is rendered evident by considering that if an oblique dove-tail joint were cut in the rod, Fig. 195, the shearing stress on its surfaces may be sufficient to overcome friction and cause sliding along the oblique plane.

If a short prismatic block is under the compressive action of two forces, each $= P$ and applied centrally in one base, we may show that the state of internal stress is the same as that of the rod under tension, except that the normal stresses are of contrary sign, i.e., compressive instead of tensile, and that the shearing stresses (or tendency to slide) on oblique planes are opposite in direction to those in the rod.

Since the resultant stress on a given internal plane of a body is fully represented by its normal and tangential components, we are therefore justified in considering but two kinds of internal stress, *normal* or *direct*, and *tangential* or *shearing*.

182. Stress on Oblique Section of Rod in Tension.—Consider free a small cubic element whose edge $= a$ in length; it has two faces parallel to the paper, being taken near the middle of the rod in Fig. 192. Let the angle which the face AB, Fig. 196, makes with the axis of the rod be $= \alpha$. This angle, for our present purpose, is considered to remain the same while the two forces P are acting, as before their action. The resultant stress on the face AB having an intensity $p = P \div F$, (see eq. 2) per unit of *transverse section* of rod, is $= p\,(a \sin \alpha)\,a$. Hence its component normal to AB is $pa^2 \sin^2 \alpha$; and the tangential or shearing component along $AB = pa^2 \sin \alpha \cos \alpha$. Dividing by the area, a^2, we have the following:



FIG. 196.



FIG. 197.

For a rod in simple tension we have, on a plane making an angle, α, with the axis:

a **Normal Stress** $= p \sin^2 \alpha$ per unit of area . . (1)
and a **Shearing Stress** $= p \sin \alpha \cos \alpha$ per unit of area . (2)

"Unit of area" here refers to the oblique plane in question, while p denotes the normal stress per unit of area of a transverse section, i.e., when $\alpha = 90°$, Fig. 194.

The stresses on CD are the same in value as on AB, while for BC and AD we substitute $90° - \alpha$ for α. Fig. 197 shows these normal and shearing stresses, and also, much exaggerated, the strains or change of form of the element (see Fig. 192).

182a. Relation between Stress and Strain.—Experiment shows that so long as the stresses are of such moderate value that the piece recovers its original form completely when the external forces which induce the stresses are removed, the following is true and is known as *Hooke's Law* (stress proportional to strain). As the forces P in Fig. 193 (rod in tension) are gradually increased, the elongation, or additional length, of RK increases in the same ratio as the normal stress, p, on the sections RS and KN, per unit of area [§ 191].

As for the distorting effect of shearing stresses, consider in Fig. 197 that since

$$p \sin \alpha \cos \alpha = p \cos (90° - \alpha) \sin (90° - \alpha)$$

the shearing stress per unit of area is of *equal value on all four of the faces* (perpendicular to paper) in the elementary block, and is evidently accountable for the shearing strain, i.e., for the angular distortion, or difference, δ, between 90° and the present value of each of the four angles. According to Hooke's Law then, as P increases within the limit mentioned above, δ varies proportionally to

$$p \sin \alpha \cos \alpha, \text{ i.e. to the stress.}$$

182b. Example.—Supposing the rod in question were of a kind of wood in which a shearing stress of 200 lbs. per sq. inch along the grain, or a normal stress of 400 lbs. per sq. inch, perpendicular to a fibre-plane will produce rupture, required the value of α the angle which the grain must make with the axis that, as P increases, the danger of rupture from each source may be the same. This re-

quires that $200:400::p \sin \alpha \cos \alpha : p \sin^2 \alpha$, i.e. tan. α must $= 2.000 \therefore \alpha = 63\frac{1}{2}°$. If the cross section of the rod is 2 sq. inches, the force P at each end necessary to produce rupture of either kind, when $\alpha = 63\frac{1}{2}°$, is found by putting $p \sin \alpha \cos \alpha = 200 \therefore p = 500.0$ lbs. per sq. inch. Whence, since $p = P \div F$, $P = 1000$ lbs. (Units, inch and pound.)

183. Elasticity is the name given to the property which most materials have, to a certain extent, of regaining their original form when the external forces are removed. If the state of stress exceeds a certain stage, called the **Elastic Limit**, the recovery of original form on the part of the elements is only partial, the permanent deformation being called the **Set.**

Although theoretically the elastic limit is a perfectly definite stage of stress, experimentally it is somewhat indefinite, and is generally considered to be reached when the permanent set becomes well marked as the stresses are increased and the test piece is given ample time for recovery in the intervals of rest.

The **Safe Limit** of stress, taken well within the elastic limit, determines the *working strength* or safe load of the piece under consideration. E.g., the tables of safe loads of the structural steel beams for floors, made by the Cambria Steel Co., at Johnstown, Pa., are computed on the basis that the greatest normal stress (tension or compression) occurring on any internal plane shall not exceed 16,000 lbs. per sq. inch; and, again, by the building laws of Philadelphia, the greatest shearing stress to be permitted in "web plates" of "mild steel" is 8750 lbs./in.^{2}

The Ultimate Limit is reached when rupture occurs.

184. The Modulus of Elasticity (sometimes called co-efficient of elasticity) is the number obtained by dividing the stress per unit of area by the corresponding relative strain.

Thus, a rod of wrought iron ½ sq. inch sectional area being subjected to a tension of 2½ tons = 5,000 lbs., it is

found that a length which was six feet before tension is = 6.002 ft. during tension. The relative longitudinal strain or elongation is then = (0.002) ÷ 6 = 1 : 3,000 and the corresponding stress (being the normal stress on a transverse plane) has an intensity of

$$p_t = P \div F = 5{,}000 \div \tfrac{1}{2} = 10{,}000 \text{ lbs., per sq. inch.}$$

Hence by definition the modulus of elasticity is (for tension), if we denote the relative elongation by ϵ,

$$E_t = p_t \div \epsilon = 10{,}000 \div \tfrac{1}{3{,}000} = 30{,}000{,}000 \text{ lbs. per sq. inch, (the}$$

sub-script "t" refers to tension).

It will be noticed that since ϵ is an abstract number, E_t is of the same quality as p_t, i.e., lbs. per sq. inch, or one dimension of force divided by two dimensions of length. (In the subject of strength of materials the inch is the most convenient English linear unit, when the pound is the unit of force; sometimes the foot and ton are used together.)

The foregoing would be called *the modulus of elasticity of wrought iron in tension* in the direction of the fibre, as given by the experiment quoted. But by Hooke's Law p and ϵ vary together, for a given direction in a given material, hence *within the elastic limit E is constant* for a given direction in a given material. Experiment confirms this approximately.

Similarly, the modulus of elasticity for *compression* E_c in a given direction in a given material may be determined by experiments on short blocks, or on rods confined laterally to prevent flexure.

As to the modulus of elasticity for shearing, E_s, we divide the shearing stress per unit of area in the given direction by δ (in radians) the corresponding angular strain or distortion; e.g., for an angular distortion of 0.10° or $\delta = .00174$, and a shearing stress of 15,660 lbs. per sq. inch, we have $E = \frac{15.660}{.00174} = 9{,}000{,}000$ lbs. per sq. inch.

184a. Young's Modulus is a name frequently given to E_t and E_c, it being understood that in the experiments to determine these moduli the elastic limit is not passed, and also that the rod or prism tested *is not subjected to any stress on the sides.* See p. 507.

185. Isotropes.—This name is given to materials which are homogenous as regards their elastic properties. In such a material the moduli of elasticity are individually the same for all directions. E.g., a rod of rubber cut out of a large mass will exhibit the same elastic behavior when subjected to tension, whatever its original position in the mass. Fibrous materials like wood and wrought iron are not isotropic; the direction of grain in the former must always be considered. The "piling" and welding of numerous small pieces of iron prevent the resultant forging from being isotropic.

186. Resilience refers to the potential energy stored in a body held under external forces in a state of stress which does not pass the elastic limit. On its release from constraint, by virtue of its elasticity it can perform a certain amount of work called the resilience, depending in amount upon the circumstances of each case and the nature of the material. See § 148.

187. General Properties of Materials.—In view of some definitions already made we may say that a material is *ductile* when the ultimate limit is far removed from the elastic limit; that it is *brittle* like glass and cast iron, when those limits are near together. A small modulus of elasticity means that a comparatively small force is necessary to produce a given change of form, and vice versâ, but implies little or nothing concerning the stress or strain at the elastic limit; thus Weisbach gives E_c, lbs. per sq. inch for wrought iron $= 28{,}000{,}000 =$ double the E_c for cast iron while the compressive stresses at the elastic limit are the same for both materials (nearly).

188. Element with Normal Stress on Sides as well as on End-Faces. Ellipse of Stress.—In Fig. 193, p. 198, the parallelopiped $RKNS$ is subjected to stress on the two end-faces only. Let us now consider a small square-cornered element of material subjected to a normal stress p_1 (tension) on the two vertical end-faces, while on the horizontal side faces there acts a normal (also tensile) stress of p_2 lbs./in.^{2}; (but no stress on the vertical side faces). In Fig. 197*a* is shown, as a free body in equilibrium, a triangular prism ABC, which is the upper right-hand half of such an element; obtained by passing the cutting plane AC along a diagonal of the side plane (plane of paper) on which there is no stress, and ⊥ to it. The angle θ *may have any value* and it is desired to determine the unit stress q_0 induced on the oblique plane AC by the normal stresses p_1 and p_2 acting respectively on the end face BC and on the side face AB. The unit stress q_0 on the face AC is not ⊥ to that face but makes with it some angle μ. Let $\overline{AB}=b$ inches, $\overline{BC}=n$ in., and $\overline{AC}=c$ in.; each of the rectangular areas having a common dimension, $=d$ in., ⊥ to the paper. Then the total (oblique) stress on face AC is q_0cd lbs., that on AB is p_2bd, and that on BC is p_1nd lbs. Since the total stress on AC is the anti-resultant of the other two, and these are ⊥ to each other, we have



FIG. 197*a*.

$$(q_0cd)^2=(p_1nd)^2+(p_2bd)^2;\quad \text{i.e., } q_0^2=\left(p_1\frac{n}{c}\right)^2+\left(p_2\frac{b}{c}\right)^2.$$

But, since $n\div c=\sin\theta$, and $b\div c=\cos\theta$, this may be written

$$q_0^2=(p_1\sin\theta)^2+(p_2\cos\theta)^2 \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

Eq. (1) gives the magnitude of q_0 for any value of angle θ; but both position and magnitude are best shown by a geometrical construction. O being any point on AC, draw a circle with center at O and radius, OH_1, equal by scale to the unit stress p_1. Similarly, with radius OH_2, equal (on same scale) to the unit stress p_2, draw the circle H_2E_2. Through O draw E_1ON normal to the face AC on which the stress q_0 is to be determined, and note the intersections E_1 and E_2 (both on left of O) with the two circles respectively. A vertical line through E_1 and a horizontal through E_2 intersect at some point m. Om is the magnitude and position of the stress q_0; since $\overline{mD_2}=\overline{E_1D_1}=p_1\sin\theta$, and $OD_2=p_2\cos\theta$; hence from eq. (1) $Om=q_0$.

The point m is a point in an *ellipse* whose semi-principal axes are $\overline{OH_1}$ and $\overline{OH_2}$, i.e., p_1 and p_2. This ellipse is called the **Ellipse of Stress**; Om being a semi-diameter, determined in the way indicated. (Similarly, if the elementary right parallelopiped is subjected to the action of three normal stresses, p_1, p_2, and p_3, on all *three* pairs of faces, respectively, the unit stress on any oblique plane is a semi-diameter of an *Ellipsoid of Stress*).

The unit shearing stress on the oblique face AC is $q_s = q_0 \cos \mu$; and the unit normal stress is $q = q_0 \sin \mu$.

In case the normal stress p_2 on the face AB were *compressive*, p_1 being tensile, a horizontal would be drawn through E'_2 on the circle of radius OH_2, instead of through E_2, to meet the vertical through E_1, and would thus determine Om', instead of Om, as the stress on AC. If, in such a case, p_2 were numerically equal to p_1, and θ were 45°, q_0 would $= p_1 = p_2$, and would lie *in the surface AC* (*pure shear*; compare with Exam. 5, p. 242). With $p_1 = p_2$, and both tensile, or both compressive, q_0 would be equal to p_1, $= p_2$, *for all values of* θ.

189. Classification of Cases.—Although in almost any case whatever of the deformation of a solid body by a balanced system of forces acting on it, normal and shearing stresses are both developed in every element which is affected at all (according to the plane section considered,) still, cases where the body is prismatic, and the external system consists of two equal and opposite forces, one at each end of the piece and directed away from each other, are commonly called cases of **Tension**; (Fig. 192); if the piece is a short prism with the same two terminal forces directed *toward* each other, the case is said to be one of **Compression**; a case similar to the last, but where the prism is quite long ("long column"), is a case of **Flexure** or bending, as are also most cases where the "applied forces" (i.e., the external forces), are not directed along the axis of the piece. Riveted joints and "pin-connections" present cases of **Shearing**; a twisted shaft one of **Torsion**. When the gravity forces due to the weights of the elements are also considered, a combination of two or more of the foregoing general cases may occur.

In each case, as treated, the principal objects aimed at are, so to design the piece or its loading that the greatest stress,* in whatever element it may occur, shall not exceed a safe value; and sometimes, furthermore, to prevent too great deformation on the part of the piece. The first object is to provide sufficient **strength**; the second sufficient **stiffness**.

* See § 405*b* for mention of the "elongation theory" of safety. This is based on considerations of *strain*, or deformation, instead of stress.

TENSION.

191. Hooke's Law by Experiment.—As a typical experiment in the tension of a long rod of ductile metal such as wrought iron and the mild steels, the following table is quoted from Prof. Cotterill's "Applied Mechanics." The experiment is old, made by Hodgkinson for an English Railway Commission, but well adapted to the purpose. From the great length of the rod, which was of wrought iron and 0.517 in. in diameter, the portion whose elongation was observed being 49 ft. 2 in. long, the small increase in length below the elastic limit was readily measured. The successive loads were of such a value that the tensile stress $p = P \div F$, or normal stress per sq. in. in the transverse section, was made to increase by equal increments of 2657.5 lbs. per sq. in., its initial value. After each application of load the elongation was measured, and after the removal of the load, the permanent set, if any.

TABLE OF ELONGATIONS OF A WROUGHT IRON ROD, OF A LENGTH = 49 FT. 2 IN.

p	λ	$\Delta\lambda$	$\varepsilon = \lambda \div l$	λ'
Load (lbs. per square inch.)	Elongation. (inches.)	Increment of Elongation.	ε, the relative elongation, (abstract number.)	Permanent Set. (inches.)
1×2667.5	.0485	.0485	0.000082	
2× "	.1095	.061	.000186	
3× "	.1675	.058	.000283	0.0015
4× "	.224	.0565	.000379	.002
5× "	.2805	.0565	.000475	.0027
6× "	.337	.0565	.000570	.003
7× "	.393	.056		.004
8× "	.452	.059	.000766	.0075
9× "	.5155	.0635		.0195
10× "	.598	.0825		.049
11× "	.760	.162		.1545
12× "	1.310	.550		.667
etc.				

Referring now to Fig. 198, the notation is evident. P is the total load in any experiment, F the cross section of the rod; hence the normal stress on the transverse section is $p = P \div F$. When the loads are increased by equal increments, the corresponding increments of the elongation λ should also be equal if Hooke's law is true. It will be noticed in the table that this is very nearly true up to the 8th loading, i.e., that $\Delta\lambda$, the difference between two consecutive values of λ, is nearly constant. In other words the proposition holds good:

$$P : P_1 :: \lambda : \lambda_1$$

if P and P_1 are any two loads below the 8th, and λ and λ_1 the corresponding elongations.

The permanent set is just perceptible at the 3d load, and increases rapidly after the 8th, as also the increment of elongation. Hence at the 8th load, which produces a tensile stress on the cross section of $p = 8 \times 2667.5 = 21340.0$ lbs. per sq. inch, the *elastic limit* is reached.

As to the state of stress of the individual elements, if we conceive such sub-division of the rod that four edges of each element are parallel to the axis of the rod, we find that it is in equilibrium between two normal stresses on its end faces (Fig. 199) of a value $= pdF = (P \div F)dF$ where dF is the horizontal section of the element. If dx was the original length, and $d\lambda$ the elongation produced by pdF, we shall have, since all the dx's of the length are equally elongated at the same time,



Fig. 198



Fig. 199.

$$\frac{d\lambda}{dx} = \frac{\lambda}{l}$$

where l = total (original) length. But $d\lambda \div dx$ is the relative elongation ε, and by definition (§ 184) the *Modulus of Elasticity for Tension*, $E_t = p \div \varepsilon$, (*Young's Modulus*, § 184*a*).

$$\therefore E_t = \frac{p}{\frac{d\lambda}{dx}}; \text{ or } E_t = \frac{Pl}{F\lambda} \quad . \quad . \quad . \quad . \quad (1)$$

Eq. (1) enables us to solve problems involving the elongation of a prism under tension, so long as the elastic limit is not surpassed.

The values of E_t computed from experiments like those just cited should be the same for any load under the elastic limit, if Hooke's law were accurately obeyed, but in reality they differ somewhat, especially if the material lacks homogeneity. In the present instance (see Table) we have from the

2d Exper. $E = p \div \varepsilon = 28{,}680{,}000$ lbs. per sq. in.
5th " $E_t =$ " $= 28{,}009{,}000$ " "
8th " $E_t =$ " $= 27{,}848{,}000$ " "

192. Stress-Strain Diagrams.—If the relative elongations or "strains" (ε) corresponding to a series of values of the tensile unit-stresses (p) (lbs./in.^{2}) to which a rod of metal has been subjected in a testing machine, are plotted as abscissæ, and the unit-stresses themselves (p) as ordinates, we have in the curve joining these points a useful graphic representation of the results of experiment.

Fig. 200 shows some of these curves, giving average results for the principal "ferrous" metals. On the left, in (I), the scale adopted (horizontal) for the "strain" (ε) or "unit-elongation" is one hundred times as great as that used in the right-hand diagram, (II); while the vertical scale for stress (p) in (I) is only twice as great as that in (II). The change of form within the elastic limit is so small compared with that beyond, that this difference in scale is quite necessary in order that diagram (I) may show what occurs within the elastic limit and a little beyond. Diagram (II) shows the remainder of the curves of wrought iron and soft steel, up to the point of rupture.

We have here the means of comparing the properties of the four typical metals represented, as to elasticity and tenacity. Up to the respective elastic limits, B, B', B'', and B''', stress is fairly proportional to strain, and a straight line is the result;

the "true elastic limit" being regarded as the point where such proportionality ceases. In the case of wrought iron and soft steel there is a point Y, called the "*yield point*," a little above the true elastic limit, and sometimes called the "apparent elastic limit," or "commercial elastic limit," immediately beyond which further slight increments of stress produce relatively great increments of strain, permanent set becoming very marked; i.e., the part YD of the curve is almost horizontal. Beyond D the curve rises again, more steeply, but just before rupture [see (II)] may descend somewhat; since,



FIG. 200.

on account of the lateral contraction mentioned in the next paragraph, here plotted, the stress being computed by dividing the total pull by the *original* sectional area, is less toward rupture than at stages closely preceding.

If at any point beyond the elastic limit, as at C (see curve for wrought iron) in (I), the stress be gradually removed, the relations of stress and strain during this gradual diminution of stress, are shown by the straight line CC'. The position of the point C' indicates that there is in the rod (now under no stress) a *permanent set*, or relative elongation, of $\varepsilon = 0.0015$, or 15 parts in 10,000, an elastic recovery having occurred from 0.0028 to 0.0015 (see horizontal scale).

Since by definition the modulus of elasticity $E = p \div \varepsilon$, the values of the respective moduli for the metals in diagram (I) are propor-

tional to the tangent of the angle which the corresponding straight portions OB, OB', etc., make with the horizontal axis. From the various ordinates and abscissæ for the points B, B', etc., we find E for cast iron to be 14,000,000 lbs./in.^{2} and for the other three metals 28,000,000, 30,000,000, and 40,000,000, respectively. The curve for the "harder steel" is not shown in (II), being beyond the limits of the diagram, as to stress; and the complete curve for cast iron is contained within the limits of diagram (I), since the elongation at rupture is very small in the case of this metal, only about 3/10 of one per cent, or 3 parts in 1000; whereas that for wrought iron or soft steel is 300 parts in 1000 (or 30 per cent). In the case of cast iron the elastic limit is very ill-defined and the proportion of carbon and the mode of manufacture have much influence on its behavior under test.

"Soft steel" is another name for "structural steel," used in construction on a large scale, as in buildings and bridge trusses; "medium steel" being a somewhat harder grade of the same. Many grades of steel are made which are much stronger and harder than these, such as tool steel, nickel steel, and piano wire (whose rupturing stress may be as high as 300,000 lbs./in.^{2}). Wrought iron in the form of wire is much stronger than in bars.

Note.—Such a line as CC', showing the relation of stress and strain as the stress is gradually removed, will be called an "elasticity line" on p. 241. In § 206 some mention will be made of the phenomena of "overstraining" a test-piece of iron or steel, showing that on re-applying stress after a certain period of rest the plotted results of stress and strain relations show that the line $C'C$ is retraced to C and continues in the same straight line prolonged, to a *new elastic limit higher than C*, before curving off to the right.

193. Lateral Contraction.—In the stretching of prisms of nearly all kinds of material, accompanying the elongation of length is found also a diminution of width whose relative amount in the case of the three metals just treated is about $\frac{1}{3}$ or $\frac{1}{4}$ of the relative elongation (within elastic limit). Thus, in the third experiment in the table of § 191, this relative lateral contraction or decrease of diameter $= \frac{1}{3}$ to $\frac{1}{4}$ of ϵ, i.e., about 0.00008. In the case of cast iron and hard steels contraction is not noticeable ex-

cept by very delicate measurements, both within and without the elastic limit; but the more ductile metals, as wrought iron and the soft steels, when stretched beyond the elastic limit show this feature of their deformation in a very marked degree. Fig. 201 shows by dotted lines the original contour of a wrought iron rod, while the continuous lines indicate that at rupture. At the cross section of rupture, whose position is determined by some local weakness, the drawing out is peculiarly pronounced.



FIG. 201.

The contraction of area thus produced is sometimes as great as 50 or 60% at the fracture.

194. **"Flow of Solids."**—When the change in relative position of the elements of a solid is extreme, as occurs in the making of lead pipe, drawing of wire, the stretching of a rod of ductile metal as in the preceding article, we have instances of what is called the *Flow of Solids*, interesting experiments on which have been made by Tresca.

195. **Moduli of Tenacity.**—The tensile stress per square inch (of original sectional area) required to rupture a prism of a given material will be denoted by T and called the *modulus of ultimate tenacity;* similarly, the *modulus of safe tenacity*, or greatest safe tensile stress on an element, by T'; while the tensile stress at elastic limit may be called T''. The ratio of T' to T'' is not fixed in practice but depends upon circumstances (from $\frac{1}{3}$ to $\frac{2}{3}$).

Hence, if a prism of any material sustains a total pull or load P, and has a sectional area $=F$, we have

$$\left.\begin{array}{l} P = FT \text{ for the ultimate or breaking load.} \\ P' = FT' \text{ " " safe load.} \\ P'' = FT'' \text{ " " load at elastic limit.} \end{array}\right\} \quad . \quad . \quad (2)$$

Of course T' should always be less than T''. (The handbook of the Cambria Steel Co., in quoting from the building laws of various cities of the U. S., gives allowable unit-stresses for ordinary materials, both in tension and compression.)

196. Resilience of a Stretched Prism.—Fig. 202. In the gradual stretching of a prism, *fixed at one extremity*, the value of the tensile force P at the other necessarily depends on the elongation λ at each stage of the lengthening, according to the relation [eq. (1) of § 191.]

$$\lambda = \frac{Pl}{FE_t} \quad . \quad . \quad . \quad . \quad . \quad (3)$$

within the elastic limit. (If we place a weight G on the flanges of the unstretched prism and then leave it to the action of gravity and the elastic action of the prism, the weight begins to sink, meeting an increasing pressure P, proportional to λ, from the flanges). Suppose the stretching to continue until P reaches some value P'' (at elastic limit say), and λ a value λ''. Then the work done so far is (see p. 155)

Fig. 202.

$$U = \text{mean force} \times \text{space} = \tfrac{1}{2} P'' \lambda'' \quad . \quad . \quad (4)$$

But from (2) $P'' = FT''$, and (see §§ 184 and 191)

$$\lambda'' = \varepsilon'' l$$

$$\therefore \text{(4) becomes } U = \tfrac{1}{2} T'' \varepsilon''. Fl = \tfrac{1}{2} T'' \varepsilon'' V \quad . \quad . \quad (5)$$

where V is the volume of the prism. The quantity $\frac{1}{2} T'' \varepsilon''$, or work done in stretching to the elastic limit a cubic inch (or other unit of volume) of the given material, may be called the *Modulus of Resilience for tension*. From (5) it appears that the amounts of work done in stretching to the elastic limit prisms of the same material but of different dimensions are proportional to *their volumes* simply.

The quantity $\frac{1}{2} T'' \varepsilon''$ is graphically represented by the area of one of the triangles such as $OA'B$, $OA''B''$ in Fig. 200; for (in the curve for wrought iron for instance) the modulus of tenacity at elastic limit is represented by $A'B$, and ε'' (i.e., ε for elastic limit) by OA'. The remainder of

the area OBC included between the curve and the horizontal axis, i.e., from B to C, represents the work done in stretching a cubic unit from the elastic limit to the point of rupture, for each vertical strip having an altitude $=p$ and a width $=d\varepsilon$, has an area $=pd\varepsilon$, i.e., the work done by the stress p on one face of a cubic unit through the distance $d\varepsilon$, or increment of elongation.

If a weight or load $= G$ be "suddenly "applied to stretch the prism, i.e., placed on the flanges, barely touching them, and then allowed to fall, when it comes to rest again it has fallen through a height λ_1, and experiences at this instant some pressure P_1 from the flanges; $P_1 = ?$. Applying to this body the "Work and Energy" method (p. 138), noting that its initial and final kinetic energy are each zero and that the force G is constant, while the upward force P (from the flanges) is variable, with an average value of $\frac{1}{2}P_1$, we have

$$G\lambda_1 = \tfrac{1}{2}P_1\lambda_1 + 0 - 0\,;\ \text{whence } P_1 = 2G.$$

Since $P_1 = 2G$, i.e., is $> G$, the body does not remain in this position but is pulled upward by the elasticity of the prism. In fact, the motion is *harmonic* (see §§ 59 and 138). Theoretically, the elastic limit not being passed, the oscillations should continue indefinitely.

Hence a load G "suddenly applied" occasions *double the tension* it would if compelled to sink gradually by a support underneath, which is not removed until the tension is just $= G$, oscillation being thus prevented.

If the weight G sinks through a height $=h$ before striking the flanges, Fig. 202, we shall have similarly, within elastic limit, if $\lambda_1 =$ greatest elongation, (the mass of rod being small compared with that of G).

$$G(h+\lambda_1) = \tfrac{1}{2}P_1\lambda_1 \quad . \quad . \quad . \quad . \quad (6)$$

If the elastic limit is to be just reached we have from eqs. (5) and (6), neglecting λ_1 compared with h,

$$Gh = \tfrac{1}{2}T''\varepsilon''V \quad . \quad . \quad . \quad (7)$$

an equation of condition that the prism shall not be injured.

Example.—If a steel prism have a sectional area of ¼ sq. inch and a length l=10 ft. =120 inches, what is the greatest allowable height of fall of a weight of 200 lbs., that the final tensile stress induced may not exceed T''= 30,000 lbs. per sq. inch, if ϵ'' =.002 ? From (7), using the inch and pound, we have

$$h=\frac{T''\epsilon''V}{2G}=\frac{30{,}000\times.002\times\frac{1}{4}\times120}{2\times200}=4.5 \text{ inches.}$$

197. Stretching of a Prism by Its Own Weight.—In the case of a very long prism such as a mining-pump rod, its weight must be taken into account as well as that of the terminal load P, see Fig. 203. At (a.) the prism is shown in its unstrained condition; at (b) strained by the load P_1 and its own weight. Let the cross section be $=F$, the heaviness of the prism $=\gamma$. Then the relative extension of any element at a distance



Fig. 203.

x from o is *

$$\epsilon=\frac{d\lambda}{dx}=\frac{(P_1+\gamma Fx)}{FE_t} \quad . \quad . \quad . \quad (1)$$

(See eq. (1) § 191); since $P_1+F\gamma x$ is the load hanging upon the cross section at that locality. Equal dx's, therefore, are unequally elongated, x varying from 0 to l. The total elongation is

$$\lambda=\int_0^l d\lambda=\frac{1}{FE_t}\int_0^l [P_1dx+\gamma Fxdx]=\frac{P_1l}{FE_t}+\frac{\frac{1}{2}Gl}{FE_t}$$

I.e., λ= the amount due to P_1, plus an extension which half the weight of the prism would produce, hung at the lower extremity.

* In $\lambda=\frac{Pl}{FE_t}$ put $d\lambda$ for λ, dx for l, and $(P_1+\gamma Fx)$ for P.

The foregoing relates to the deformation of the piece, and is therefore a problem of *stiffness*. As to the *strength* of the prism, the relative elongation $\varepsilon = d\lambda \div dx$ [see eq. (1)], which is variable, must nowhere exceed a safe value $\varepsilon' = T' \div E_t$ (from eq. (1) § 191, putting $P = FT'$, and $\lambda = \lambda'$). Now the greatest value of the ratio $d\lambda : dx$, by inspecting eq. (1), is seen to be at the upper end where $x = l$. The proper cross section F, for a given load P_1, is thus found.

$$\text{Putting } \frac{P_1 + \gamma F l}{F E_t} = \frac{T'}{E_t}, \text{ we have } F = \frac{P_1}{T' - \gamma l} \quad . \quad (2)$$

198. Solid of Uniform Strength in Tension, or *hanging body of minimum material supporting its own weight and a terminal load* P_1. Let it be a solid of revolution. If every cross-section F at a distance $= x$ from the lower extremity, bears its safe load FT', every element of the body is doing full duty, and its form is the most economical of material.



FIG. 204.

The lowest section must have an area $F_0 = P_1 \div T'$, since P_1 is its safe load. Fig. 204. Consider any horizontal lamina; its weight is $\gamma F dx$, (γ = heaviness of the material, supposed homogenous), and its lower base F must have $P_1 + G$ for its safe load, i.e.

$$G + P_1 = FT' \quad . \quad . \quad . \quad (1)$$

in which G denotes the weight of the portion of the solid below F. Similarly for the upper base $F + dF$, we have

$$G + P_1 + \gamma F dx = (F + dF)T' \quad . \quad . \quad (2)$$

By subtraction we obtain

$$\gamma F dx = T' dF; \quad \text{i.e. } \frac{\gamma}{T'} dx = \frac{dF}{F}$$

in which the two variables x and F are separated. By integration we now have

$$\frac{\gamma}{T'}\int_0^x dx = \int_{F_0}^{F}\frac{dF}{F}\ ;\ \text{or}\ \frac{\gamma x}{T'} = \log_e\frac{F}{F_0} \quad . \quad . \quad (3)$$

$$\text{i.e.,}\ F = F_0 e^{\frac{\gamma x}{T'}} = \frac{P_1}{T'}\ e^{\frac{\gamma x}{T'}} \quad . \quad . \quad . \quad . \quad . \quad (4)$$

from which F may be computed for any value of x.

The *weight* of the portion below any F is found from (1) and (4); i.e.

$$G = P_1\left(e^{\frac{\gamma x}{T'}} - 1\right); \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

while the total extension λ will be

$$\lambda = \varepsilon''\frac{T'}{T''}l \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (6)$$

the relative elongation $d\lambda \div dx$ being the same for every dx and bearing the same ratio to ε'' (at elastic limit), as T' does to T''.

199. Tensile Stresses Induced by Temperature.—If the two ends of a prism are immovably fixed, when under no strain and at a temperature t, and the temperature is then lowered to a value t', the body suffers a tension proportional to the fall in temperature (within elastic limit). If for a rise or fall of 1° Fahr. (or Cent.) a unit of length of the material would change in length by an amount η (called the co-efficient of expansion) a length $=l$ would be contracted an amount $\lambda = \eta l(t - t')$ during the given fall of temperature if one end were free. Hence, if this contraction is prevented by fixing both ends, the rod must be under a tension P, equal in value to the force which would be

necessary to produce the elongation λ, just stated, under ordinary circumstances at the lower temperature.

From eq. (1) §191, therefore, we have for this tension due to fall of temperature

$$P = \frac{E_t F}{l} \eta l(t - t') = E_t F(t - t')\eta$$

For 1° Cent. we may write

For Cast iron $\eta = .0000111$;
" Wrought iron $= .0000120$;
" Steel $= .0000108$ to $.0000114$;
" Copper $\eta = .0000172$;
" Zinc $\eta = .0000300$.

COMPRESSION OF SHORT BLOCKS.

200. Short and Long Columns.—In a prism in tension, its own weight being neglected, all the elements between the localities of application of the pair of external forces producing the stretching are in the same state of stress, if the external forces act axially (excepting the few elements in the immediate neighborhood of the forces; these suffering local stresses dependent on the manner of application of the external forces), and the prism may be of any length without vitiating this statement. But if the two external forces are directed *toward* each other the intervening elements will not all be in the same state of compressive stress unless the prism is comparatively short (or unless numerous points of lateral support are provided). A long prism will buckle out sideways, thus even inducing tensile stress, in some cases, in the elements on the convex side.

Hence the distinction between *short blocks* and *long columns*. Under compression the former yield by crushing or splitting, while the latter give way by flexure (i.e. bending). *Long columns*, then will be treated separately

in a subsequent chapter. In the present section the blocks treated being about three or four times as long as wide, all the elements will be considered as being under equal compressive stresses at the same time.

201. Notation for Compression.—By using a subscript c, we may write

E_c= Modulus of Elasticity;* i.e. the quotient of the compressive stress per unit of area divided by the relative shortening. (*Young's Modulus;* no stress on sides);

C= Modulus of crushing; i.e. the force per unit of sectional area necessary to rupture the block by crushing;

C'= Modulus of safe compression, a safe compressive stress per unit of area; and

C''= Modulus of compression at elastic limit.

For the absolute and relative shortening in length we may still use λ and ε, respectively, and within the elastic limit may write equations similar to those for tension, F being the sectional area of the block and P one of the terminal forces, while p = compressive stress per unit of area of F, viz.:

$$E_c = \frac{p}{\varepsilon} = \frac{P \div F}{d\lambda \div dx} = \frac{P \div F}{\lambda \div l} = \frac{Pl}{F\lambda} \quad . \quad . \quad . \quad . \quad (1)$$

within the elastic limit.

Also for a short block

$$\left.\begin{array}{l} \text{Crushing force} = FC \\ \text{Compressive force at elastic limit} = FC'' \\ \text{Safe compressive force} = FC' \end{array}\right\} \quad . \quad (2)$$

202. Remarks on Crushing.—As in § 182 for a tensile stress, so for a compressive stress we may prove that a

---

*[NOTE.—It must be remembered that the modulus of elasticity, whether for normal or shearing stresses, is a number indicative of *stiffness*, not of strength, and has no relation to the elastic limit (except that experiments to determine it must not pass that limit).]

shearing stress $= p . \sin \alpha \cos \alpha$ is produced on planes at an angle α with the axis of the short block, p being the compressive stress per unit of area of transverse section. Experiment shows, however, that, although the above value for the shearing stress is a maximum for $\alpha = 45°$, in the crushing of short blocks or rather brittle materials like cast iron and stone, the surface along which separation takes place makes an angle smaller than 45° with the axis (35° for cast iron, according to Hodgkinson's experiments); but the block must be two or three times as long as wide to enable this phenomenon to take place. This seems to show that the presence of the compressive stress on the 45° plane is sufficient to strengthen the material against rupture by shearing on that plane, causing the separation to occur along a plane on which the compressive stress is considerably less. Crushing by splitting into pieces parallel to the axis sometimes occurs.

Blocks of *ductile* material, however, yield by swelling out, or bulging, laterally, resembling plastic bodies somewhat in this respect.

The elastic limit is more difficult to locate than in tension, but seems to have a position corresponding to that in tension, in the case of wrought iron and steel. With cast iron, however, the relative compression at elastic limit is about double the relative extension (at elastic limit in tension), but the force producing it is also double. For all three metals it is found that $E_c = E_t$ quite nearly, so that the single symbol E may be used for both.

EXAMPLES IN TENSION AND COMPRESSION.

203. Tables for Tension and Compression.—The round numbers in the following tables are to be taken as rude averages only; the scope and design of the present work admitting of nothing more. For abundant details of the more important experiments and researches of recent years, the reader is referred to Professor J. B. Johnson's "Materials of Construction" and the works of Professors Thurston, Burr, and Lanza; also to "Testing of Materials" by Unwin, and Martens' work of similar title. Another column might have been added giving the Modulus of Resilience, viz.: $\frac{1}{2}\epsilon'' T''$, $(= \frac{1}{2} T''^2 \div 2E$; see § 196). ϵ is an abstract num-

ber, and $=\lambda \div l$, while E_t, T'', and T are given in pounds per square inch:

TABLE OF THE MODULI, ETC., OF MATERIALS IN TENSION.

Material.	ϵ'' (Elastic limit.)	ϵ At Rupture.	E_t Mod. of Elast.	T'' Elastic limit.	T Rupture.
	abst. number.	abst. number.	lbs. per sq. in.	lbs. per sq. in.	lbs. per sq. in.
Soft Steel,	.00120	.3000	30,000,000	35,000	60,000
Hard Steel,	.00200	.0500	40,000,000	60,000	120,000
Cast Iron,	.00066	.0020	14,000,000	9,000	18,000
Wro't Iron,	.00080	.3000	28,000,000	22,000	45 000 to 60,000
Brass,	.00100		10,000,000	7,000 to 19,000	16,000 to 50,000
Glass,			9,000,000		3,500
Wood, with the fibres,	.00200 to .01100	.0070 to .0150	200,000 to 2,000,000	3,000 to 19,000	6,000 to 28,000
Hemp rope,					7,000

[N.B.—Expressed in *kilograms per square centim.*, E_t, T and T'' would be numerically about $^1/_{14}$ as large as above, while ϵ and ϵ'' would be unchanged.]

TABLE OF MODULI, ETC.; COMPRESSION OF SHORT BLOCKS.

Material.	ϵ'' Elastic limit.	ϵ At Rupture.	E_c Mod. of Elast.	C'' Elastic limit.	C Rupture.
	abst. number.	abst. number.	lbs. per sq. in.	lbs. per sq. in.	lbs. per sq. in.
Soft Steel,	0.00100		30,000,000	30,000	
Hard Steel,	0.00120	0.3000	40,000,000	50,000	200,000
Cast Iron,	0.00150		14,000,000	20,000	90,000
Wro't Iron,	0.00080	0.3000	28,000,000	24,000	40,000
Glass,					20,000
Granite,			See § 213a		10,000
Sandstone,					5,000
Brick,					3,000
Wood, with the fibres,		0.0100 to 0.0400	350,000 to 2,000,000		2,000 to 10,000
Portland Cement,			(§ 213a)		4,000

204. **Examples.** No. 1.—A bar of tool steel, of sectional area $=0.097$ sq. inches, is ruptured by a tensile force of 14,000 lbs. A portion of its length, originally ½ a foot, is now found to have a length of 0.532 ft. Required T, and ε at rupture. Using the inch and pound as units (as in the foregoing tables) we have $T=\frac{14.000}{.097}=144326$ lbs. per sq. in.; (eq. (2) § 195); while

$$\varepsilon=(0.532-0.5)\times 12\div(0.50\times 12)=0.064.$$

Example 2.—Tensile test of a bar of "Hay Steel" for the Glasgow Bridge, Missouri. The portion measured was originally 3.21 ft. long and 2.09 in. × 1.10 in. in section. At the elastic limit P was 124,200 lbs., and the elongation was 0.064 ins. Required E_t, T'', and ε'' (for elastic limit).

$$\varepsilon''=\frac{\lambda}{l}=\frac{0.064}{3.21\times 12}=.00166 \text{ at elastic limit.}$$

$$T''=124{,}200\div(2.09\times 1.10)=54{,}000 \text{ lbs. per sq. in.}$$

$$E_t=\frac{p}{\varepsilon}=\frac{P}{F\varepsilon}=\frac{124{,}200}{2.30\times .00166}=32{,}520{,}000 \text{ lbs. per sq. in.}$$

Nearly the same result for E_t would probably have been obtained for values of p and ε below the elastic limit.

The *Modulus of Resilience* of the above steel (see § 196) would be $\frac{1}{2}\,\varepsilon''\,T''=44.82$ inch-pounds of work per cubic inch of metal, so that the whole work expended in stretching to the elastic limit the portion above cited is

$$U=\tfrac{1}{2}\,\varepsilon''\,T''\,V=3968. \text{ inch-lbs.}$$

An equal amount of work will be done by the rod in recovering its original length.

Example 3.—A hard steel rod of ½ sq. in. section and 20 ft. long is under no stress at a temperature of 130°

Cent., and is provided with flanges so that the slightest contraction of length will tend to bring two walls nearer together. If the resistance to this motion is 10 tons how low must the temperature fall to cause any motion? η being $=.0000110$ (Cent. scale). From § 199 we have, expressing P in lbs. and F in sq. inches, since $E_t = 40{,}000{,}000$ *lbs. per sq. inch*,

$$10 \times 2{,}000 = 40{,}000{,}000 \times \tfrac{1}{2} \times (130 - t') \times 0.000011;$$ whence $t' = 39.0°$ Centigrade.

EXAMPLE 4.—If the ends of an iron beam bearing 5 tons at its middle rest upon stone piers, required the necessary bearing surface at each pier, putting C' for stone $= 200$ lbs. per sq. inch. 25 sq. in., Ans.

EXAMPLE 5.—How long must a wrought iron wire* be, supported vertically at its upper end, to break with its own weight? 216,000 inches, Ans.

EXAMPLE 6.—One voussoir (or block) of an arch-ring presses its neighbor with a force of 50 tons, the joint having a surface of 5 sq. feet; required the compression per sq. inch. 138.8 lbs. per sq. in., Ans.

205. Factor of Safety.—When, as in the case of stone, the value of the stress at the elastic limit is of very uncertain determination by experiment, it is customary to refer the value of the safe stress to that of the ultimate by making it the n'th portion of the latter. n is called a *factor of safety*, and should be taken large enough to make the safe stress come within the elastic limit. For stone, n should not be less than 10, i.e. $C' = C \div n$; (see Ex. 6, just given).

---

206. Practical Notes.—It was discovered independently by Commander Beardslee and Prof. Thurston, in 1873, that if wrought iron rods were strained considerably beyond the elastic limit and allowed to remain free from stress

* Take $T = 60{,}000$ lbs. per square inch.

for at least one day thereafter, a second test would show *higher limits* both elastic and ultimate.

In 1899 Mr. James Muir discovered that this recovery of elasticity and raising of both the yield-point and ultimate strength, in the case of iron and steel after "overstraining," may be brought about by simply heating the metal *for a few minutes* in a bath of boiling water. In one experiment a bar of a kind of mild steel which under ordinary tests broke at 39 tons/in.^{2} with 20% elongation on 8 in., was stretched just to its yield-point, then relieved and heated for a few minutes to 100° Cent., then stretched just to its new yield-point, then relieved and heated as before; and so on, for three times more. The first yield-point was at 27, the others at 33, 38, 43¼, and 47 tons/in.^{2} The bar was then broken at 49 tons/in.^{2} with total extension of 12%. The diminished ultimate extension shows the hardening effect of the treatment. (See Prof. Ewing's "*Strength of Materials*," pp. 38 and 40.)

By *fatigue of metals* we understand the fact, recently discovered by Wöhler in experiments made for the Prussian Government, that rupture may be produced by causing the stress on the elements to vary repeatedly between two limiting values, the highest of which may be considerably below T (or C), the number of repetitions necessary to produce rupture being dependent both on the range of variation and the higher value.

For example, in the case of Phœnix iron in tension, rupture was produced by causing the stress to vary from 0 to 52,800 lbs. per sq. inch, 800 times; also, from 0 to 44,000 lbs. per sq. inch 240,853 times; while 4,000,000 variations between 26,400 and 48,400 per sq. inch did not cause rupture. Many other experiments were made and the following conclusions drawn (among others):

Unlimited repetitions of variations of stress (lbs. per sq. in.) between the limits given below will not injure the metal (Prof. Burr's Materials of Engineering).

Wrought iron.	From	17,600 Comp.	to 17,600	Tension.
	"	0	to 33,000	"
Axle Cast Steel.	From	30,800 Comp.	to 30,800	Tension.
	"	0	to 52,800	"
	"	38500 Tens.	to 88,000	"

(See p. 232 for an *addendum* to this paragraph.)

SHEARING.

207. Rivets.—The angular distortion called shearing strain in the elements of a body, is specially to be provided for in the case of *rivets* joining two or more plates. This distortion is shown, in Figs. 205 and 206, in the elements near the plane of contact of the plates, much exaggerated.



FIG. 205.



FIG. 206.

In Fig. 205 (a lap-joint) the rivet is said to be in *single shear*; in Fig. 206 in *double shear*. If P is just great enough to shear off the rivet, the *modulus of ultimate shearing*, which may be called S, (being the shearing force per unit of section when rupture occurs) is

$$S = \frac{P}{F} = \frac{P}{\frac{1}{4}\pi d^2} \quad \ldots\ldots\ldots \quad (1)$$

in which F = the cross section of the rivet, its diameter being $= d$. For safety a value $S' = \frac{1}{4}$ to $\frac{1}{6}$ of S should be taken for metal, in order to be within the elastic limit.

As the width of the plate is diminished by the rivet hole the remaining sectional area of the plate should be ample to sustain the tension P, or $2P$, (according to the plate considered, see Fig. 206), P being the safe shearing force for the rivet. Also the thickness t of the plate should be such that the side of the hole shall be secure against crushing; P must not be $> C'td$, Fig. 205.

Again, the distance a, Fig. 205, should be such as to prevent the tearing or shearing out of the part of the plate between the rivet and edge of the plate.

For economy of material the seam or joint should be no more liable to rupture by one than by another, of the



FIG. 207.

four modes just mentioned. The relations which must then subsist will be illustrated in the case of the "butt-joint" with two cover-plates, Fig. 207. Let the dimensions be denoted as in the figure and the total tensile force on the joint be $= Q$. Each rivet (see also Fig. 206) is exposed in each of two of its sections to a shear of $\frac{1}{12}\ Q$, hence for safety against shearing of rivets we put

$$\tfrac{1}{12}\,Q = \tfrac{1}{4}\,\pi d^2 S' \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

Along one row of rivets in the main plate the sectional area for resisting tension is reduced to $(b-3d)t_1$, hence for safety against rupture of that plate by the tension Q, we put

$$Q = (b-3d)t_1 T' \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

Equations (1) and (2) suffice to determine d for the rivets and t_1 for the main plates, Q and b being given; but the values thus obtained should also be examined with reference to the compression in the side of the rivet hole, i.e., $\frac{1}{6}\,Q$ must not be $> C't_1 d$. [The distance a, Fig. 205, to the edge of the plate is recommended by different authorities to be from d to $3d$.]

Similarly, for the cover-plate we must have

$$\tfrac{1}{2}\,Q \begin{matrix} = \\ \text{or} \\ < \end{matrix} (b-3d)tT' \quad . \quad . \quad . \quad . \quad (3)$$

and $\frac{1}{12}Q$ not $> C'td$.

If the rivets do not fit their holes closely, a large margin should be allowed in practice. Again, in boiler work, the *pitch*, or distance between centers of two consecutive rivets may need to be smaller, to make the joint steam-tight, than would be required for strength alone.

208. **Shearing Distortion.**—The change of form in an element due to shearing is an angular deformation and will be measured in π-measure. This angular change or difference between the value of the corner angle during strain and $\frac{1}{2}\pi$, its value before strain, will be called δ, and is proportional (within elastic limit) to the shearing stress per unit of area, p_s, existing on all the four faces whose angles with each other have been changed.

Fig. 208. (See § 181). By § 184 the **Modulus of Shearing Elasticity** is the quotient obtained by dividing p_s by δ; i.e. (*elastic limit not passed*),

$$E_s = \frac{p_s}{\delta} \quad . \quad . \quad . \quad . \quad (1)$$

or inversely,

$$\delta = p_s \div E_s. \quad . \quad . \quad . \quad . \quad (1)'$$

The value of E_s for different substances is most easily determined by experiments on torsion in which shearing is the most prominent stress.* (This prominence depends on the position of the bounding planes of the element considered; e.g., in Fig. 208, if another element were considered within the one there shown and with its planes at 45° with those of the first, we should find tension alone on one pair of opposite faces, compression alone on the other pair.) It will be noticed that shearing stress cannot be present on two opposite faces only, but exists also on another pair of faces (those perpendicular to the stress on the first), forming a couple of equal and opposite moment to the first, this being necessary for the equilibrium of the element, even when



Fig. 208.

* For instance, see numerical example on p. 237, giving a value of E_s as resulting from a torsion test made by students in the Civil Engineering Laboratory at Cornell University, April, 1904.

tensile or compressive stresses are also present on the faces considered.

209. Shearing Stress is Always of the Same Intensity on the Four Faces of an Element.—(By *intensity* is meant *per unit of area;* and the four faces referred to are those perpendicular to the paper in Fig. 208, the shearing stress being parallel to the paper.)

Let dx and dz be the width and height of the element in Fig. 208, while dy is its thickness perpendicular to the paper. Let the *intensity* of the shear on the right hand face be $=q_s$, that on the top face $=p_s$. Then for the element as a free body, taking moments about the axis O perpendicular to paper, we have

$$q_s\,dz\,dy \times dx - p_s\,dx\,dy \times dz = 0 \therefore q_s = p_s$$

(dx and dz being the respective lever arms of the forces $q_s\,dz\,dy$ and $p_s\,dx\,dy$.)

Even if there were also tensions (or compressions) on one or both pairs of faces their moments about O would balance (or fail to do so by a differential of a higher order) independently of the shears, and the above result would still hold.

210. Table of Moduli for Shearing.

Material.	δ'' i.e. δ at elastic limit.	E_s Mod. of Elasticity for Shearing.	S'' (Elastic limit.)	S (Rupture.)
	arc in radians.	lbs. per sq. in.	lbs. per sq. in	lbs. per sq. in.
Soft Steel,		9,000,000	30,000	70,000
Hard Steel,	0.0032	14,000,000	45,000	90,000
Cast Iron,	0.0021	7,000,000	15,000	30,000
Wrought Iron,	0.0022	9,000,000	20,000	50,000
Brass,		5,000,000		
Glass,				
Wood, across fibre,				1,500 to 8,000
Wood, along fibre,				500 to 1,200

As in the tables for tension and compression, the above values are averages. The true values may differ from these as much as 30 per cent. in particular cases, according to the quality of the specimen.

211. Punching rivet holes in plates of metal requires the overcoming of the shearing resistance along the convex surface of the cylinder punched out. Hence if d = diameter of hole, and t = the thickness of the plate, the necessary force for the punching, the surface sheared being $F = t\pi d$, is

$$P = St\pi d \quad . \quad . \quad . \quad . \quad (2)$$

Another example of shearing action is the "stripping" of the threads of a screw, when the nut is forced off longitudinally without turning, and resembles punching in its nature.

212. **E and E_s; Theoretical Relation.**—In case a rod is in tension within the elastic limit, the relative (linear) lateral contraction (let this $= m$) is so connected with E_t and E_s that if two of the three are known the third can be deduced theoretically. This relation is proved as follows, by Prof. Burr. Taking an elemental cube with four of its faces at 45° with the axis of the piece, Fig. 209, the axial half-diagonal AD becomes of a length $AD' = AD + \varepsilon . \overline{AD}$ under stress, while the transverse half diagonal contracts to a length $B'D' = AD - m.AD$. The angular distortion δ



Fig. 209. § 212.



Fig. 210.

is supposed very small compared with 90° and is due to the shear p_s per unit of area on the face BC (or BA). From the figure we have

$$\tan(45°-\frac{\delta}{2}) = \frac{B'D'}{AD'} = \frac{1-m}{1+\varepsilon} = 1-m-\varepsilon, \text{ approx.}$$

[But, Fig. 210, $\tan(45°-x) = 1-2x$ nearly, where x is a small angle, for, taking $\overline{CA}$ = unity = AE, tan $AD = AF = AE-EF$. Now approximately $\overline{EF} = \overline{EG}.\sqrt{2}$ and $\overline{EG} = \overline{BD}\sqrt{2} = x\sqrt{2}$. $\therefore AF = 1-2x$ nearly.] Hence

$$1-\delta = 1-m-\varepsilon; \text{ or } \delta = m+\varepsilon \quad . \quad . \quad (2)$$

Eq. (2) holds good whatever the stresses producing the deformation, but in the present case of a rod in tension, if it is an isotrope, and if p = tension per unit of area on its transverse section, (see § 182, putting $\alpha = 45°$), we have $E_t = p \div \varepsilon$ and $E_s = (p_s \text{ on } BC) \div \delta = \frac{1}{2}p \div \delta$. Putting also $(m : \varepsilon) = k$, whence $m = k\varepsilon$, eq. (2) may finally be written*

$$\frac{1}{2E_s} = (k+1)\frac{1}{E_t}; \text{ i.e., } E_s = \frac{E_t}{2(1+k)} \quad . \quad . \quad (3)$$

Prof. Bauschinger, experimenting with cast iron rods, found that in tension the ratio $m : \varepsilon$ was $= \frac{23}{100}$, as an average, which in eq. (3) gives

$$E_s = \frac{100}{246}E_t = \frac{2}{5}E_t \text{ nearly.} \quad . \quad . \quad . \quad (4)$$

His experiments on the torsion of cast iron rods gave E_s = 6,000,000 to 7,000,000 lbs. per sq. inch. By (4), then, E_t should be 15,000,000 to 17,500,000 which is approximately true (§ 203).

Corresponding results may be obtained for short blocks in compression, the lateral change being a dilatation instead of a contraction.

* This ratio, $m \div \varepsilon$, denoted by k, is called *Poisson's Ratio*. For metals its value lies approximately between 0.20 and 0.35. See also p. 507.

213. Examples in Shearing.—EXAMPLE 1.—Required the proper length, a, Fig. 211, to guard against the shearing off, along the grain, of the portion ab, of a wooden tie-rod, the force P being = 2 tons, and the width of the tie = 4 inches. Using a value of $S' = 100$ lbs. per sq. in., we put $baS' = 4{,}000 \cos 45°$; i.e. $a = (4{,}000 \times 0.707) \div (4 \times 100) = 7.07$ inches.



FIG. 211.

EXAMPLE 2.—A ⅞ in. rivet of wrought iron, in *single shear* (see Fig. 205) has an ultimate shearing strength $P = FS = \frac{1}{4}\pi d^2 S = \frac{1}{4}\pi(\frac{7}{8})^2 \times 50{,}000 = 30{,}050$ lbs. For safety, putting $S' = 8{,}000$ instead of S, $P' = 4{,}800$ lbs. is its safe shearing strength in single shear.

The wrought iron plate, to be secure against the side-crushing in the hole, should have a thickness t, computed thus:

$$P' = tdC'; \text{ or } 4{,}800 = t.\tfrac{7}{8} \times 12{,}000 \therefore t = 0.46 \text{ in.}$$

If the plate were only 0.23 in. thick the safe value of P would be only ½ of 4,800.

EXAMPLE 3.—Conversely, given a lap-joint, Fig. 205, in which the plates are ¼ in. thick and the tensile force on the joint = 600 lbs. per linear inch of seam, how closely must ¾ inch rivets be spaced in one row, putting $S' = 8{,}000$ and $C' = 12{,}000$ lbs. per sq. in.? Let the distance between centres of rivets be $= x$ (in inches), then the force upon each rivet $= 600x$, while its section $F = 0.44$ sq. in. Having regard to the shearing strength of the rivet we put $600x = 0.44 \times 8{,}000$ and obtain $x = 5.86$ in.; but considering that the safe crushing resistance of the hole is $= \frac{1}{4} \cdot \frac{3}{4} \cdot 12{,}000 = 2{,}250$ lbs., $600x = 2{,}250$ gives $x = 3.75$ inches, which is the pitch to be adopted. What is the tensile strength of the reduced sectional area of the plate, with this pitch?

EXAMPLE 4.—Double butt-joint; (see Fig. 207); $\frac{3}{8}$ inch plate; $\frac{3}{4}$ in. rivets; $T'=C'=12{,}000$; $S'=8{,}333$; width of plates=14 inches. Will one row of rivets be sufficient at each side of joint, if $Q=30{,}000$ lbs.? The number of rivets $=$? Here each rivet is in double shear and has therefore a double strength as regards shear. In double shear the safe strength of each rivet $=2FS'=7{,}333$ lbs. Now $30{,}000 \div 7{,}333=4.0$ (say). With the four rivets in one row the reduced sectional area of the main plate is $=[14-4\times\frac{3}{4}]\times\frac{3}{8}=4.12$ sq. in., whose safe tensile strength is $=FT'=4.12\times 12{,}000=49{,}440$ lbs.; which is $>30{,}000$ lbs. $\therefore$ main plate is safe in this respect. But as to side-crushing in holes in main plate we find that $C't_1d$ (i.e. $12{,}000\times\frac{3}{8}\times\frac{3}{4}=3{,}375$ lbs.) is $<\frac{1}{4}Q$ i.e. $<7{,}500$ lbs., the actual force on side of hole. Hence four rivets in one row are too few unless thickness of main plate be doubled. Will eight in one row be safe?

213a. (Addendum to § 206.) **Elasticity of Stone and Cements.**—Experiments by Gen. Gillmore with the large Watertown testing-machine in 1883 resulted as follows (see p. 221 for notation):

With cubes of Haverstraw Freestone (a homogeneous brownstone) from 1 in. to 12 in. on the edge, E_c was found to be from 900,000 to 1,000,000 lbs. per sq. in. approximately; and C about 4,000 or 5,000 lbs. per sq. in. Cubes of the same range of sizes of Dyckerman's Portland cement gave E_c from 1,350,000 to 1,630,000, and C from 4,000 to 7,000, lbs. per sq. in. Cubes of concrete of the above sizes, made with the Newark Co.'s Rosendale cement, gave E_c about 538,000, while cubes of cement-mortar, and some of concrete, both made with National Portland cement, showed E_c from 800,000 to 2,000,000 lbs. per sq. in.

The compressibility of *brick piers* 12 in. square in section and 16 in. high was also tested. They were made of common North River brick with mortar joints $\frac{1}{8}$ in. thick, and showed a value for E_c of about 300,000 or 400,000, while at elastic limit C'' was on the average 1,000, lbs. per sq. in.

CHAPTER II.

TORSION.

214. Angle of Torsion and of Helix. When a cylindrical beam or shaft is subjected to a twisting or torsional action, *i.e.* when it is the means of holding in equilibrium two couples in parallel planes and of equal and opposite moments, the longitudinal axis of symmetry remains straight and the elements along it experience no stress (whence it may be called the "line of no twist"), while the lines originally parallel to it assume the form of helices, each element of which is distorted in its angles (originally right angles), the amount of distortion being assumed proportional to the radius of the helix. The directions of the



FIG. 212.



FIG. 213.

faces of any element were originally as follows: two radial, two in consecutive transverse sections, and the other two tangent to two consecutive circular cylinders whose common axis is that of the shaft. E.g. in Fig. 212 we have an unstrained shaft, while in Fig. 213 it holds the two

couples (of equal moment $P a = Q b$) in equilibrium. These couples act in parallel planes perpendicular to the axis of the prism and a distance, l, apart. Assuming that the transverse sections *remain plane and parallel* during torsion, any surface element, m, which in Fig. 212 was entirely right-angled, is now distorted. Two of its angles have been increased, two diminished, by an amount δ, the angle between the helix and a line parallel to the axis. Supposing m to be the most distant of any element from the axis, this distance being e, any other element at a distance z from the axis experiences an angular distortion $= \frac{z}{e}\delta$.

If now we draw $O\,B'$ parallel to $O'A$ the angle $B\,O\,B'$, $= \alpha$, is called the **Angle of Torsion**, while δ may be called the *helix angle*; the former lies in a transverse plane, the latter in a plane tangent to the cylinder. Now

$\tan \delta =$ (linear arc $B\,B'$) $\div l$; but lin. arc $B\,B' = e\alpha$; hence, putting δ for $\tan \delta$, (δ being small)

$$\delta = \frac{e\alpha}{l} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

(δ and α both in radians).

215. Shearing Stress on the Elements. The angular distortion, or shearing strain, δ, of any element (bounded as already described) is due to the shearing stresses exerted on it by its neighbors on the four faces perpendicular to the tangent plane of the cylindrical shell in which the element is situated. Consider these neighboring elements of an *outside element* removed, and the stresses put in; the latter are accountable for the distortion of the element and



Fig. 214.

hold it in equilibrium. Fig. 214 shows this element "free." Within the elastic limit δ is known to be proportional to p_s, the shearing stress per unit of area on the faces whose relative angular positions have been changed. That is, from eq. (1), § 208, $\delta = p_s \div E_s$; whence, see (1) of § 214,

$$p_s = \frac{e\,a\,E_s}{l} \quad \cdots\cdots\cdots \quad (2)$$

In (2) p_s and e both refer to a surface element, e being the radius of the cylinder, and p_s the greatest intensity of shearing stress existing in the shaft. Elements lying nearer the axis suffer shearing stresses of less intensity in proportion to their radial distances, i.e., to their helix-angles. That is, the shearing stress on that face of the element which forms a part of a transverse section and whose distance from the axis is z, is p, $= \frac{z}{e}\ p_s$, per unit of area, and the total shear on the face is pdF, dF being the area of the face.

216. **Torsional Strength.**—We are now ready to expose the full transverse section of a shaft under torsion, to deduce formulæ of practical utility. Making a right section of the shaft of Fig. 213 anywhere between the two couples and considering the left hand portion as a free body, the forces holding it in equilibrium are the two forces P of the left-hand couple and an infinite number of shearing forces, each tangent to its circle of radius z, on the cross section exposed by the removal of the right-hand portion. The cross section is assumed to remain plane during torsion, and is composed of an infinite number of dF's, each being the area of an exposed face of an element; see Fig. 215.



FIG. 215.

Each elementary shearing force $= \frac{z}{e} p_s dF$, and z is its lever arm about the axis Oo. For equilibrium, Σ (mom.) about the axis Oo must $=0$; i.e. in detail

$$-P\tfrac{1}{2}a-P\tfrac{1}{2}a+\int\left(\frac{z}{e}\,p_s dF\right)z=0$$

or, reducing,

$$\frac{p_s}{e}\int z^2 dF=Pa\text{; or, }\frac{p_s I_p}{e}=Pa \quad . \quad . \quad (3)$$

Eq. (3) relates to *torsional strength*, since it contains p_s, the greatest shearing stress induced by the torsional couple, whose moment Pa is called the **Moment of Torsion**, the stresses in the cross section forming a couple of equal and opposite moment. Pa is also called the "*torque*."

I_p is recognized as the **Polar Moment of Inertia** of the cross section, discussed in § 94; e is the radial distance of the outermost element, and = the radius for a circular shaft.

217. **Torsional Stiffness.**—In problems involving the angle of torsion, or deformation of the shaft, we need an equation connecting Pa and α, which is obtained by substituting in eq. (3) the value of p_s in eq. (2), whence

$$\frac{\alpha I_p E_s}{l}=Pa. \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

From this is appears that the angle of torsion, α, is proportional to the moment of torsion, or "torque," Pa inch-lbs., within the elastic limit; α must be expressed in *radians*.

Example.—A portion 3.4 ft. long, of a solid cylindrical shaft of soft steel, of diam.$=1.5$ in., is found by the use of "Torsion Clinometers" (see frontispiece) to be held at an angle of torsion of $\alpha=5.41°$, $=0.0944$ radians, just before the elastic limit is reached, by a "*torque*," $=Pa$, of 10,200 in.-lbs. Compute the Modulus of Elasticity for Shearing.

Substituting in eq. (4), with $I_p=\pi r^4/2$, (§ 94), $=\pi(0.75)^4\div 2$, $=0.497$ in.^{4}, and $l=3.4\times 12=40.8$ in., we have

$$E_s=\frac{10{,}200\times 40.8}{0.0944\times 0.497}=8{,}870{,}000 \text{ lbs. per sq. in.}$$

218. Torsional Resilience is the work done in twisting a shaft from an unstrained state until the elastic limit is reached in the outermost elements. If in Fig. 213 we imagine the right-hand extremity to be fixed, while the other end is gradually twisted through an angle each force P of the couple must be made to increase gradually from a zero value up to the value P_1, corresponding to α_1. In this motion each end of the arm a describes a space $=\frac{1}{2}a\alpha_1$, and the mean value of the force $=\frac{1}{2}P_1$ (compare § 196). Hence the work done in twisting is

$$U_1=\tfrac{1}{2}P_1\times\tfrac{1}{2}a\alpha_1\times 2=\tfrac{1}{2}P_1a\alpha_1 \quad . \quad . \quad (5)$$

By the aid of preceding equations, (5) can be written

$$U_1=\frac{a_1^2E_sI_p}{2l}, \text{ or } =\frac{P_1^2a^2l}{2I_pE_s}, \text{ or } =\frac{p_s^2I_pl}{2E_se^2} \quad . \quad . \quad (6)$$

If for p_s we write S' (Modulus of safe shearing) we have for the *safe resilience* of the shaft

$$U'=\frac{S'^2I_pl}{2E_se^2} \quad . \quad . \quad . \quad . \quad (7)$$

If the torsional elasticity of an originally unstrained shaft is to be the means of arresting the motion of a moving mass whose weight is G, (large compared with the parts intervening) and velocity $=v$, we write (§ 133)

$$U'=\frac{G}{g}\cdot\frac{v^2}{2};$$

as the condition that the shaft shall not be injured.

219. Polar Moment of Inertia.—For a shaft of circular cross section (see § 94) $I_p = \frac{1}{2}\pi r^4$; for a hollow cylinder $I_p = \frac{1}{2}\pi(r_1^4 - r_2^4)$; while for a square shaft $I_p = \frac{1}{6}b^4$, b being the side of the square; for a rectangular cross-section sides b and h, $I_p = \frac{1}{12}bh(b^2+h^2)$. For a cylinder $e = r$; if hollow, $e = r$, the greater radius. For a square, $e = \frac{1}{2}b\sqrt{2}$.

220. Non-Circular Shafts.—If the cross-section is not circular it becomes warped, in torsion, instead of remaining plane. Hence the foregoing theory does not strictly apply. The celebrated investigations of St. Venant, however, cover many of these cases. (See § 708 of Thompson and Tait's Natural Philosophy; also, Prof. Burr's Elasticity and Strength of the Materials of Engineering). His results give for a square shaft (instead of the

$$\frac{ab^4E_s}{6l} = Pa \text{ of eq. (4) of § 217),}$$

$$Pa = 0.841\,\frac{ab^4E_s}{6l} \quad . \quad . \quad . \quad . \quad (1)$$

and $Pa = \frac{1}{5}b^3p_s$, instead of eq. (3) of § 216, p_s being the greatest shearing stress.

The elements under greatest shearing strain are found at the middles of the sides, instead of at the corners, when the prism is of square or rectangular cross-section. The warping of the cross-section in such a case is easily verified by the student by twisting a bar of india-rubber in his fingers.

221. Transmission of Power.—Fig. 216. Suppose the cog-wheel B to cause A, on the same shaft, to revolve uniformly and overcome a resistance Q, the pressure of the teeth of another cog-wheel, B being driven by still another wheel. The shaft AB is under torsion, the moment of torsion being $= Pa = Qb$. (P_1 and Q_1 the bearing reactions have no moment about the axis of the shaft). If the shaft makes u revolutions per unit-time, the work transmitted (*transmitted*; not *expend-*



FIG. 216.

ed in twisting the shaft whose angle of torsion remains constant, corresponding to Pa) per unit-time, i.e. the **Power**, is

$$L = P.2\pi a.u = 2\pi uPa \quad . \quad . \quad . \quad (8)$$

To reduce L to Horse Power (§ 132), we divide by N, the number of units of work per unit-time constituting one H. P. in the system of units employed, i.e.,

$$\text{Horse Power} = \text{H. P.} = \frac{2\pi uPa}{N}$$

For example N=33,000 ft.-lbs. per minute, or =396,000 inch-lbs. per minute; or =550 ft.-lbs. per second. Usually the rate of rotation of a shaft is given in revolutions per minute.

But eq. (8) happens to contain Pa the moment of torsion acting to maintain the constant value of the angle of torsion, and since for safety (see eq. (3) § 216) $Pa = S'I_p \div e$, with $I_p = \frac{1}{2}\pi r^4$ and $e = r$ for a solid circular shaft, we have for such a shaft

$$\text{(Safe), H. P.} = \frac{\pi^2 S' u r^3}{N} \quad . \quad . \quad . \quad (9)$$

which is the safe H. P., which the given shaft can transmit at the given speed. S' may be made 7,000 lbs. per sq. inch for wrought iron; 10,000 for steel, and 5,000 for cast-iron. If the value of Pa fluctuates periodically, as when a shaft is driven by a connecting rod and crank, for (H. P.) we put $m \times$(H. P.), m being the ratio of the maximum to the mean torsional moment; m = about $1\frac{1}{2}$ under ordinary circumstances (Cotterill).

With a **hollow cylindrical shaft**, of outer radius $= r_1$, and inner $= r_2$ the r^3 of eq. (9) must be replaced by $(r_1^4 - r_2^4) \div r_1$. If, furthermore, the *thickness of metal is small*, we may proceed thus, taking numerical data: Let the radius to the middle of the thickness be $r_0 = 10$ in., the thickness $t = \frac{1}{4}$ in., and the (steel) shaft make $u = 120$ revs./min.; with $S' = 5000$ lbs./in.^{2}; then the total safe shearing stress in the cross-section is $R' = 2\pi r_0 t S' = 2\pi 10 \times \frac{1}{4} \times 5000 = 78{,}540$ lbs., while the velocity of the mid-thickness is $v' = 2\pi r_0 u = 2\pi\ 10 \times 2 = 125.6$ in./sec. $= 10.47$ ft./sec. Hence the (safe) power that may be transmitted at given speed is $L = R'v' = 78{,}540 \times 10.47 = 822{,}100$ ft.-lbs. per sec.; or, ($\div 550$), $= 1495$ H.P.

222. Autographic Testing Machine.—The principle of Prof. Thurston's invention bearing this name is shown in Fig.



FIG. 217.

217. The test-piece is of a standard shape and size, its central cylinder being subjected to torsion. A jaw, carrying a handle (or gear-wheel turned by a worm) and a drum on which paper is wrapped, takes a firm hold of one end of the test-piece, whose further end lies in another jaw rigidly connected with a heavy pendulum carrying a pencil free to move axially. By a continuous slow motion of the handle the pendulum is gradually deviated more and more from the vertical, through the intervention of the test-piece, which is thus subjected to an increasing torsional moment. The axis of the test-piece lies in the axis of motion. This motion of the pendulum by means of a properly curved guide, *WR*, causes an axial (i.e., parallel to axis of test-piece) motion of the pencil *A*, as well as an angular deviation β equal to that of the pendulum, and this axial distance $CF, = sT$, of the pencil from its initial position measures the moment of torsion $= I'a = Pc \sin \beta$. As the piece twists, the drum and paper move relatively to the pencil through an angle sUo equal to the angle of torsion a so far attained. The abscissa so and ordinate sT of the curve thus marked on the paper, measure, when the paper is unrolled, the values of a and Pa through

all the stages of the torsion. Fig. 218 shows typical



FIG. 218.

curves thus obtained. Many valuable indications are given by these strain diagrams as to homogeneousness of composition, ductility, etc., etc. On relaxing the strain at any stage within the elastic limit, the pencil retraces its path; but if beyond that limit, a new path is taken called an "elasticity-line," in general parallel to the first part of the line, and showing the amount of angular recovery, BC, and the permanent angular set, OB.

222a. Torsion Clinometers.—When the test-piece used in the Thurston testing machine is short, the indicated angles of torsion below the elastic limit are far in excess of the actual values, on account of the initial yielding of the wedges in the jaws. By the use of "*torsion clinometers*," however (see frontispiece) the angle of torsion can be measured accurately within one minute of arc.

223. Examples in Torsion.—The modulus of safe shearing strength, S', as given in § 221, is expressed in pounds per square inch; hence these two units should be adopted throughout in any numerical examples where one of the above values for S' is used. The same statement applies to the modulus of shearing elasticity, E_s, in the table of § 210.

EXAMPLE 1.—Fig. 216. With $P = 1$ ton, $a = 3$ ft., $l = 10$ ft., and the radius of the cylindrical shaft $r = 2.5$ inches, required the max. shearing stress per sq. inch, p_s, the shaft being of wrought iron. From eq. (3) § 216

$$p_s = \frac{Pae}{I_p} = \frac{2{,}000 \times 36 \times 2.5}{\frac{1}{2}\pi \times (2.5)^4} = 2{,}930 \text{ lbs. per sq. inch,}$$

which is a safe value for any ferrous metal.

EXAMPLE 2.—What H. P. is the shaft in Ex. 1 transmitting, if it makes 50 revolutions per minute? Let u = number of revolutions per unit of time, and N = the number of units of work per unit of time constituting one horse-power. Then H. P. $= Pu2\pi a \div N$, which for the foot-pound-minute system of units gives

$$\text{H. P.} = 2{,}000 \times 50 \times 2\pi \times 3 \div 33{,}000 = 57\tfrac{1}{4} \text{ H. P.}$$

EXAMPLE 3.—What different radius should be given to the shaft in Ex. 1, if two radii at its extremities, originally parallel, are to make an angle of 2° when the given moment of torsion is acting, the strains in the shaft remaining constant. From eq. (4) § 217, and the table 210, with $a = \frac{2^\circ}{180^\circ}\pi =$ 0.035 *radians* (i.e. π-measure), and $I_p = \frac{1}{2}\pi r^4$, we have

$$r^4 = \frac{2{,}000 \times 36 \times 120}{\frac{1}{2}\pi 0.035 \times 9{,}000{,}000} = 17.45 \therefore r = 2.04 \text{ inches.}$$

(This would bring about a different p_s, but still safe.) The foregoing is an example in *stiffness*.

EXAMPLE 4.—A working shaft of steel (solid) is to transmit 4,000 H. P. and make 60 rev. per minute, the maximum twisting moment being 1½ times the average; required its diameter. $d = 14.74$ inches. Ans.

EXAMPLE 5.—In example 1, $p_s = 2{,}930$ lbs. per square inch; what tensile stress does this imply on a plane at 45° with the pair of planes on which p_s acts? Fig. 219 shows



FIG. 219



FIG. 220.

a small cube, of edge $=dx$, (taken from the outer helix of Fig. 215,) free and in equilibrium, the plane of the paper being tangent to the cylinder; while 220 shows the portion BDC, also free, with the unknown total tensile stress $pdx^2\sqrt{2}$ acting on the newly exposed rectangle of area $=dx\times dx\sqrt{2}$, p being the unknown stress per unit of area. From symmetry the stress on this diagonal plane has no shearing component. Putting Σ [components normal to BD]$=0$, we have

$$pdx^2\sqrt{2}=2dx^2p_s\cos 45°=dx^2p_s\sqrt{2}\therefore p=p_s \quad . \quad (1)$$

That is, a normal tensile stress exists in the diagonal plane BD of the cubical element equal in intensity to the shearing stress on one of the faces, i.e., =2,930 lbs. per sq. in. in this case.

Similarly in the plane AC will be found a compressive stress of 2,930 lbs. per sq. in. If a plane surface had been exposed making any other angle than 45° with the face of the cube in Fig. 219, we should have found shearing and normal stresses each less than p_s per sq. inch. Hence the interior dotted cube in 219, if shown "free" is in tension in one direction, in compression in the other, and with no shear, these normal stresses having equal intensities. Since S' is usually less than T' or C', if p_s is made $= S'$ the tensile and compressive actions are not injurious. It follows therefore that when a cylinder is in torsion any helix at an angle of 45° with the axis is a line of tensile, or of compressive stress, according as it is a right or left handed helix, or vice versâ.

Example 6.—A solid and a hollow cylindrical shaft, of equal length, contain the same amount of the same kind of metal, the solid one fitting the hollow of the other.

Compare their torsional strengths, used separately. The solid shaft has only $\frac{471}{1,000}$ the strength of the hollow one. Ans.

Example 7.—Compare the shafts of Example 6 as to torsional *stiffness* (i.e., the angles of torsion due to equal moments). The solid shaft is only one-third as stiff as the other; an equal moment produces three times the angle. Ans.

CHAPTER III.

FLEXURE OF HOMOGENEOUS PRISMS UNDER PERPENDICULAR FORCES IN ONE PLANE.

224. Assumptions of the Common Theory of Flexure.—When a prism is bent, under the action of external forces perpendicular to it and in the same plane with each other, it may be assumed that the longitudinal fibres are in tension on the convex side, in compression on the concave side, and that the relative stretching or contraction of the elements is proportional to their distances from a plane intermediate between, with the understanding that the flexure is slight and that the elastic limit is not passed in any element.

This "common theory" is sufficiently exact for ordinary engineering purposes if the constants employed are properly determined by a wide range of experiments, and involves certain assumptions of as simple a nature as possible, consistently with practical facts. These assumptions are as follows, (for prisms, and for solids with variable cross sections, when the cross sections are similarly situated as regards a central straight axis) and are approximately borne out by experiment:

(1.) The external or "applied" forces are all perpendicular to the axis of the piece and lie in one plane, which may be called the force-plane; the force-plane contains the axis of the piece and cuts each cross-section symmetrically;

(2.) The cross-sections remain plane surfaces during flexure;

(3.) There is a surface (or, rather, sheet of elements) which is parallel to the axis and perpendicular to the force-plane, and along which the elements of the solid ex-

perience no tension nor compression in an axial direction, this being called the **Neutral Surface**;

(4.) The projection of the neutral surface upon the force plane (or a ∥ plane) being called the **Neutral Line** or **Elastic Curve**, the bending or flexure of the piece is so slight that an elementary division, ds, of the neutral line may be put $=dx$, its projection on a line parallel to the direction of the axis before flexure;

(5.) The elements of the body contained between any two consecutive cross-sections, whose intersections with the neutral surface are the respective **Neutral Axes** of the sections, experience elongations (or contractions, according as they are situated on one side or the other of the neutral surface), in an axial direction, whose amounts are proportional to their distances from the neutral axis, and indicate corresponding tensile or compressive stresses;

(6.) $E_t = E_c$;

(7.) The dimensions of the cross-section are small compared with the length of the piece;

(8.) There is no shear perpendicular to the force plane on internal surfaces perpendicular to that plane.

In the locality where any one of the external forces is applied, local stresses are of course induced which demand separate treatment. These are not considered at present.

225. Illustration.—Consider the case of flexure shown in **Fig. 221.** The external forces are three (neglecting the



FIG. 221.

weight of the beam), viz.: P_1, P_2, and P_3. P_1 and P_3 are loads, P_2 the reaction of the support.

The force plane is vertical. N_1L is the neutral line or elastic curve. NA is the neutral axis of the cross-section at m; this cross-section, originally perpendicular to the sides of the prism, is during flexure ⌝ to their tangent planes drawn at the intersection lines; in other words, the side view QNB, of any cross-section is perpendicular to the neutral line. In considering the whole prism free we have the system P_1, P_2, and P_3 in equilibrium, whence from $\Sigma Y=0$ we have $P_2=P_1+P_3$, and from Σ(mom. about O) $=0$, $P_3l_3=P_1l_1$. Hence given P_1 we may determine the other two external forces. A reaction such as P_2 is sometimes called a supporting force. The elements above the neutral surface N_1OLS are in tension; those below in compression (in an axial direction).

226. The Elastic Forces.—Conceive the beam in Fig. 221 separated into two parts by any transverse section such as QA, and the portion N_1ON, considered as a free body in Fig. 222. Of this free body the surface QAB is one of



FIG. 222

the bounding surfaces, but was originally an internal surface of the beam in Fig. 221. Hence in Fig. 222 we must put in the stresses acting on all the dF's or elements of area of QAB. These stresses represent the actions of the body taken away upon the body which is left, and according to assumptions (5), (6) and (8) consist of normal stresses (tension or compression) proportional per unit of area, to the distance, z, of the dF's from the neutral axis, and of shearing stresses parallel to the force-plane (which in most cases will be vertical).

The intensity of this shearing stress on any dF varies with the position of the dF with respect to the neutral axis, but the law of its variation will be investigated later (§§ 253 and 254). These stresses, called the **Elastic Forces** of the cross-section exposed, and the external forces P_1 and P_2, form a system in equilibrium. We may therefore apply any of the conditions of equilibrium proved in § 38.

227. The Neutral Axis Contains the Centre of Gravity of the Cross-Section.—Fig. 222. Let e= the distance of the *outermost* element of the cross-section from the neutral axis, and the normal stress per unit of area upon it be $=p$, whether tension or compression. Then by assumptions (5) and (6), § 224, the intensity of normal stress on any dF is $= \frac{z}{e} p$ and the actual

$$\text{normal stress on any } dF \text{ is} = \frac{z}{e} \, pdF \quad . \quad (1)$$

This equation is true for dF's having negative z's, i.e. on the other side of the neutral axis, the negative value of the force indicating normal stress of the opposite character; for if the relative elongation (or contraction) of two axial fibres is the same for equal z's, one above, the other below, the neutral surface, the stresses producing the changes in length are also the same, provided $E_t = E_c$; see §§ 184 and 201.

For this free body in equilibrium put $\Sigma X = 0$ (X is a horizontal axis). Put the normal stresses equal to their X components, the flexure being so slight, and the X com-

ponent of the shears = 0 for the same reason. This gives (see eq. (1))

$$\int \frac{z}{e} p dF = 0 \text{ ; i.e. } \frac{p}{e} \int dFz = 0 \text{ ; or, } \frac{p}{e} F\bar{z} = 0 \qquad (2)$$

In which $\bar{z}$ = distance of the centre of gravity of the cross-section from the neutral axis, from which, though unknown in position, the z's have been measured (see eq. (4) § 23).

In eq. (2) neither $p \div e$ nor F can be zero $\therefore \bar{z}$ must $= 0$; i.e. the neutral axis contains the centre of gravity. Q. E. D. [If the external forces were not all perpendicular to the beam this result would not be obtained, necessarily.]

228. The Shear.—The "total shear," or simply the "shear," in the cross-section is the sum of the vertical shearing stresses on the respective dF's. Call this sum J, and we shall have from the free body in Fig. 222, by putting $\Sigma Y = 0$ (Y being vertical)

$$P_2 - P_1 - J = 0 . \therefore J = P_2 - P_1 \quad . \quad . \qquad (3)$$

That is, the shear equals the algebraic sum of the external forces acting on one side (only) of the section considered. This result implies nothing concerning its mode of distribution over the section.

229. The Moment.—By the "Moment of Flexure" or simply the *Moment*, at any cross-section is meant the sum of the moments of the elastic forces of the section, taking the neutral axis as an axis of moments. In this summation the normal stresses appear alone, the shear taking no part, having no lever arm about the axis NA. Hence, Fig. 222, the *moment of flexure* (or "moment of resistance")

$$= \int \left(\frac{z}{e} p dF \right) z = \frac{p}{e} \int dFz^2 = \frac{pI}{e} . \quad . \quad . \quad . \quad . \qquad (4)$$

This function, $\int dFz^2$, of the cross-section or plane figure

is the quantity called **Moment of Inertia** of a plane figure, § 85. For the free body in Fig. 222, by putting Σ(mom.s about the neutral axis NA)=0, we have then

$$\frac{pI}{e} - P_1x_1 + P_2x_2 = 0, \text{ or } \textit{in general}, \quad \frac{pI}{e} = M \quad . \quad (5)$$

in which M signifies the sum of moments,* *about the neutral axis of the section*, of all the forces acting on the free body considered, exclusive of the elastic forces of the exposed section itself. M is also called the "**Bending Moment.**"

Example.—In Fig. 222 let $P_1=3$ and $P_2=4$ tons, $x_1=1$ ft. 8 in. and $x_2=5$ in.; the section of the beam being a rectangle, with $NA=b=3$ in. and $QB=h=6$ in. Then I about axis NA is, (p. 94), $bh^3 \div 12 = 54$ in.^{4}; and $e=3$ in. Hence the "*bending moment*," M, $=3\times 20 - 4\times 5 = 40$ in.-tons. Equating M to the "*moment of resistance*" [or moment of the "stress couple" (see § 230)] we obtain, from eq. (5), $p = Me \div I = 40\times 3 \div 54 = 2.22$ tons/in.^{2}, for the unit normal stress in the outer fibre at Q, or B. We find also, for the shear at section QB, $J=4-3=1$ ton.

230. Strength in Flexure.—Eq. (5) is available for solving problems involving the **Strength** of beams and girders, since it contains p, the greatest normal stress per unit of area to be found in the section.

In the cases of the present chapter, where all the external forces are perpendicular to the prism or beam, and have therefore no components parallel to the beam, i.e. to the axis X, it is evident that the normal stresses in any section, as QB Fig. 222, are equivalent to a couple; for the condition $\Sigma X=0$ falls entirely upon them and cannot be true unless the resultant of the tensions is equal, parallel, and opposite to that of the compressions. These two equal and parallel resultants, not being in the same line, form a couple (§ 28), which we may call the *stress-couple*. The moment of this couple is the "moment of flexure" $\frac{pI}{e}$, and it is further evident that the remaining forces in Fig. 222, viz.: the shear J and the external forces P_1 and P_2, are equivalent to a couple of equal and opposite moment to the one formed by the normal stresses.

* It is evident, therefore, that M (ft.-lbs., or in.-lbs.) is numerically equal to the "moment of flexure," or moment of the "stress couple"; so that occasionally it may be convenient to use "M" to denote the value of the latter moment also.

231. Flexural Stiffness.—The neutral line, or **elastic curve,** containing the centres of gravity of all the sections, was originally straight; its radius of curvature at any point, as N, Fig. 222, during flexure may be introduced as follows. QB and $U'V'$ are two consecutive cross-sections, originally parallel, but now inclined so that the intersection C, found by prolonging them sufficiently, is the centre of curvature of the ds (put $=dx$) which separates them at N, and $CG=\rho=$ the radius of curvature of the elastic curve at N. From the similar triangles $U'UG$ and GNC we have $d\lambda : dx :: e : \rho$, in which $d\lambda$ is the elongation, $U'U$, of a portion, originally $=dx$, of the outer fibre. But the relative elongation $\varepsilon=\dfrac{d\lambda}{dx}$ of the latter is, by §184, within the elastic limit, $=\dfrac{p}{E}\therefore \dfrac{p}{E}=\dfrac{e}{\rho}$ and eq. (5) becomes

$$\frac{EI}{\rho}=M \quad . \quad . \quad . \quad . \quad (6)$$

From (6) the radius of curvature can be computed. $E=$ the value of $E_t=E_c$, as ascertained from experiments in bending.

To obtain a differential equation of the elastic curve, (6) may be transformed thus, Fig. 223. The curve being very flat, consider two consecutive ds's with equal dx's; they may be put = their dx's. Produce the first to intersect the dy of the second, thus cutting off the d^2y, i.e. the difference between two consecutive dy's. Drawing a perpendicular to each ds at its left extremity, the centre of curvature C is determined by their intersection, and thus the radius of curvature ρ. The two shaded triangles have their small angles equal, and d^2y is nearly perpendicular to the prolonged ds; hence, considering them similar, we have



FIG. 223.

$$\left.\begin{array}{l}\rho : dx :: dx : d^2y\end{array}\right\} \therefore \frac{1}{\rho}=\frac{d^2y}{dx^2},$$

and hence from eq. (6) we may write } (*approx.*) $\pm EI\frac{d^2y}{dx^2}=M$. (7)

as a differential equation of the elastic curve. From this the equation of the elastic curve may be found, the deflections at different points computed, and an idea thus formed of the stiffness. All beams in the present chapter being *prismatic* and *homogeneous* both E and I are the same (i.e. constant) at all points of the elastic curve. In using (7) the axis X must be taken parallel to the length of the beam before flexure, which must be slight ; the minus sign in (7) provides for the case when $d^2y \div dx^2$ is essentially negative.

232. Resilience of Flexure.—If the external forces are made to increase gradually from zero up to certain maximum values, some of them may do work, by reason of their points of application moving through certain distances due to the yielding, or flexure, of the body. If at the beginning and also at the end of this operation the body is at rest, this work has been expended on the elastic resistance of the body, and an equal amount, called the work of resilience (or springing-back), will be restored by the elasticity of the body, if released from the external forces, provided the elastic limit has not been passed. The energy thus temporarily stored is of the potential kind; see §§ 148, 180, 196 and 218.

232a. Distinction Between Simple, and Continuous, Beams (or "Girders").—The external forces acting on a beam consist generally of the loads and the "reactions" of the supports. If the beam is horizontal and rests on two supports only, the reactions of those supports are easily found by elementary statics [§ 36] alone, without calling into account the theory of flexure, and the beam is said to be a **Simple Beam**, or girder; whereas if it is in contact with more than two supports, being "continuous," therefore, over some of them, it is a **Continuous Girder** (§ 271). The remainder of this chapter will deal only with simple beams.

ELASTIC CURVES.

233. Case I. Horizontal Prismatic Beam, Supported at Both Ends, With a Central Load, Weight of Beam Neglected.—Fig. 224. First considering the whole beam free, we find each



Fig. 224. § 233.

reaction to be $=\frac{1}{2}P$. AOB is the neutral line; required the equation of the portion OB referred to O as an origin, and to the tangent line through O as the axis of X. To do this consider as free the portion mB between any section m on the right of O and the near support, in Fig. 225 The forces holding this free body in equilibrium



Fig. 225.



Fig. 226.

are the one external force $\frac{1}{2}P$, and the elastic forces acting on the exposed surface. The latter consist of J, the shear, and the tensions and compressions represented in the figure by their equivalent "stress-couple." Selecting N, the neutral axis of m, as an axis of moments (that J may not appear in the moment equation) and putting $\Sigma\,(\text{mom}) = 0$ we have

$$\frac{P}{2}\left(\frac{l}{2} - x\right) - EI\frac{d^2y}{dx^2} = 0 \therefore EI\frac{d^2y}{dx^2} = \frac{P}{2}\left(\frac{l}{2} - x\right) \quad . \quad (1)$$

Fig. 226 shows the elastic curve OB in its purely geometrical aspect, much exaggerated. For axes and origin as in figure $d^2y \div dx^2$ is positive.

Eq. (1) gives the second x-derivative of y equal to a function of x. Hence the first x-derivative of y will be equal to the x-anti-derivative of that function, plus a constant, C. (By anti-derivative is meant the converse of derivative, sometimes called integral though not in the sense of summation). Hence from (1) we have (EI being a constant factor remaining undisturbed)

$$EI\frac{dy}{dx}=\frac{P}{2}\left(\frac{l}{2}x-\frac{x^2}{2}\right)+C \quad . \quad . \quad (2)'$$

(2)′ is an equation between two variables $dy \div dx$ and x, and holds good for any point between O and B; $dy \div dx$ denoting the tang. of α, the *slope*, or angle between the tangent line and X. At O the slope is zero, and x also zero; hence at O (2)′ becomes

$$EI\times 0=0-0+C$$

which enables us to determine the constant C, whose value must be the same at O as for all points of the curve. Hence $C=0$ and (2)′ becomes

$$EI\frac{dy}{dx}=\frac{P}{2}\left(\frac{l}{2}x-\frac{x^2}{2}\right) \quad . \quad . \quad . \quad (2)$$

from which the slope, tan. α, (or simply α, in π-measure; since the angle is small) may be found at any point. Thus at B we have $x=\frac{1}{2}l$ and $dy \div dx=\alpha_1$, and

$$\therefore \alpha_1=\frac{1}{16}\cdot\frac{Pl^2}{EI}$$

Again, taking the x-anti-derivative of both members of eq. (2) we have

$$EIy=\frac{P}{2}\left(\frac{lx^2}{4}-\frac{x^3}{6}\right)+C' \quad . \quad . \quad . \quad (3)'$$

and since at O both x and y are zero, C' is zero. Hence the equation of the elastic curve OB is

$$EIy = \frac{P}{2}\left(\frac{lx^2}{4} - \frac{x^3}{6}\right) \quad . \quad . \quad . \quad (3)$$

To compute the deflection of O from the right line joining A and B in Fig. 224, i.e. $BK, = d$, we put $x = \frac{1}{2}l$ in (3), y being then $= d$, and obtain

$$BK = d = \frac{1}{48} \cdot \frac{Pl^3}{EI} \quad . \quad . \quad . \quad (4)$$

Eq. (3) does not admit of negative values for x; for if the free body of Fig. 225 extended to the left of O, the external forces acting would be P, downward, at O; and $\frac{1}{2}P$, upward, at B, instead of the latter alone; thus altering the form of eq. (1). From symmetry, however, we know that the curve AO, Fig. 224, is symmetrical with OB about the vertical through O.

Numerical Illustration.—Let the beam shown in Fig. 224, resting on two unyielding supports at the same level, be of white oak timber and bear a load of $P = 200$ lbs. at the middle, its length being $l = 12$ ft. and cross-section rectangular with a width (horizontal) of $b = 2$ in. and height $h = 6$ in. The modulus of elasticity E will be taken as 1,600,000 lbs./in.^{2} Required the radius of curvature, ρ, or the elastic curve at a point 4 ft. from the right-hand pier (or left).

From the free body in Fig. 225 we have, using the form $EI \div \rho$ for the moment of the stress-couple in the section, and putting $\Sigma(\text{moms.})_N = 0$, with $x = 2$ ft., $EI \div \rho = 100 \times 48$, the inch and pound being selected as units. Now $I = bh^3 \div 12$ (p. 94) which $= 36$ in.^{4}; whence, solving, $\rho = 1{,}600{,}000 \times 36 \div 4800 = 4000$ in. The curve is evidently very flat. The smallest radius of curvature is found at the middle of the beam and is 2666 in.; at either extremity, A or B, it is *infinite*, since at each of these points the moment of the stress-couple is zero.

At the same point (4 ft. from B) the "slope" of the elastic curve, viz., $dy \div dx$, is found by putting $x = 2$ ft. $= 24$ in., in eq. (2) from which is derived $\tan \alpha = dy/dx = 0.0025$, corresponding to an angle of 0° 8′ 36″. At the extremity B we find, from $\alpha_1 = Pl^2 \div 16EI$, the slope of the tangent line to be $\alpha_1 = 0.0045$; which is the tangent of 0° 15′ 29″.

The deflection of the middle point is known from eq. (4), viz., $d = Pl^3 \div 48EI$; i.e., $d = (200 \times 144 \times 144 \times 144) \div (48 \times 1{,}600{,}000 \times 36) = 0.216$ in.

It now remains to ascertain if the elastic limit is passed in any fibre of the beam. If we put the form $pI \div e$ (for moment of stress-couple) in place of the present left-hand member of eq. (1), and solve for the unit (normal) stress in outer fibre, we find $p = \frac{1}{2}Pe(\frac{1}{2}l - x) \div I$, which shows that p is greatest in the outer fibre of the section for which $\frac{1}{2}l - x$ is greatest, within the limits of the half-length; and this occurs at the middle of the beam, where $x = 0$. With this substitution we obtain $p(\text{max.}) = p_m = Ple \div (4I)$; or $p_m = (200 \times 12 \times 12 \times 3) \div (4 \times 36) = 600$ lbs./in.^{2}, which is well within the elastic limit, for tension or compression, in white oak.

233a. Load Suddenly Applied.—Eq. (4) gives the deflection d corresponding to the force or pressure P applied at the middle of the beam, and is seen to be proportional to it. If a load G hangs at rest from the middle of the beam, $P=G$; but if the load G, being initially placed at rest upon the unbent beam, is suddenly released from the external constraint necessary to hold it there, it sinks and deflects the beam, the pressure P actually felt by the beam varying with the deflection as the load sinks. What is the maximum deflection d_m? and what the pressure P_m between the load and the beam at the instant of maximum deflection? In this motion of the body, or "load," it is acted on by two forces, the constant downward force G (its weight) and the variable upward force P, whose average value is $\frac{1}{2}P_m$; while its initial and final kinetic energy are each zero. G does the work Gd_m, while the work done upon P is $\frac{1}{2}P_m d_m$; hence, by the theorem of "*Work and Energy*" (p. 138), we have

$$Gd_m=\tfrac{1}{2}P_m d_m+0-0. \quad . \quad . \quad . \quad . \quad . \quad (5)$$

That is, $P_m=2G$. Since at this instant the load is subjected to an upward force of $2G$ and to a downward force of only G (gravity) it immediately begins an upward motion, reaching the point whence the motion began, and thus the oscillation continues. We here suppose the elasticity of the beam unimpaired. This is called the "sudden" application of a load, and produces, as shown above, double the pressure on the beam which it does when gradually applied, and a double deflection. The work done by the beam in raising the weight again is called its resilience.

Similarly, if the weight G is allowed to fall on the middle of the beam from a height h, we shall have

$$G\times(h+d_m), \text{ or approx., } Gh,=\tfrac{1}{2}P_m d_m;$$

and hence, since (4) gives d_m in terms of P_m,

$$Gh=\frac{1}{96}\cdot\frac{P_m^2 l^3}{EI}; \text{ or } Gh=\frac{24EId_m^2}{l^3} \quad . \quad (6)$$

This theory supposes the mass of the beam small compared with the falling weight.

234. Case II. Horizontal Prismatic Beam, Supported at Both Ends. Bearing a Single Eccentric Load. Weight of Beam Neglected.—Fig. 227. The reactions of the points of support, P_0 and P_1, are easily found by considering the whole beam free, and putting first $\Sigma(\text{mom.})_0=0$, whence $P_1=Pl\div l_1$, and then $\Sigma(\text{mom.})_B=0$, whence $P_0=P(l_1-l)\div l_1$. P_0 and P_1 will now be treated as known quantities.



FIG 227.

The elastic curves OC and CB, though having a common tangent line at C (and hence the same slope α_c), and a common ordinate at C, have separate equations and are both referred to the same origin and axes, as shown in the figure. The slope at O, α_0, and that at B, α_1, are unknown constants, to be determined in the progress of the work.

Equation of OC.—Considering as free a portion of the beam extending from B to a section made anywhere on OC, x and y being the co-ordinates of the neutral axis of that section, we conceive the elastic forces put in on the exposed surface, as in the preceding problem, and put $\Sigma(\text{mom. about neutral axis of the section})=0$ which gives (remembering that here $d^2y\div dx^2$ is negative.)

$$EI\frac{d^2y}{dx^2}=P(l-x)-P_1(l_1-x); \quad . \quad . \quad (1)$$

whence, by taking the x anti-derivatives of both members

$$EI\frac{dy}{dx}=P(lx-\frac{x^2}{2})-P_1(l_1x-\frac{x^2}{2})+C$$

To find C, write out this equation for the point O, where $dy\div dx=\alpha_0$ and $x=0$, and we have $C=EI\alpha_0$; hence the equation for slope is

$$EI\frac{dy}{dx}=P(lx-\frac{x^2}{2})-P_1(l_1x-\frac{x^2}{2})+EIa_0 \quad . \quad (2)$$

Again taking the x anti-derivatives, we have from (2)

$$EIy=P\left(\frac{lx^2}{2}-\frac{x^3}{6}\right)-P_1\left(\frac{l_1x^2}{2}-\frac{x^3}{6}\right)+EIa_0x+(C'=0) \quad (3)$$

(at O both x and y are $=0$ $\therefore$ $C'=0$). In equations (1), (2), and (3) no value of x is to be used <0 or $>l$, since for points in CB different relations apply, thus

Equation of CB.—Fig. 227. Let the free body extend from B to a section made anywhere on CB. Σ(moms.), as before, $=0$, gives (see foot-note on p. 322)

$$EI\frac{d^2y}{dx^2}=-P_1(l_1-x) \quad . \quad . \quad . \quad (4)$$

(*N.B.* In (4), as in (1), $EId^2y\div dx^2$ is written equal to a negative quantity because itself essentially negative; for the curve is concave to the axis X in the first quadrant of the co-ordinate axes.)

From (4) we have in the ordinary way (x-anti-deriv.)

$$EI\frac{dy}{dx}=-P_1(l_1x-\frac{x^2}{2})+C'' \quad . \quad . \quad (5)'$$

To determine C'', consider that the curves CB and OC have the same slope ($dy\div dx$) at C where $x=l$; hence put $x=l$ in the right-hand members of (2) and of (5)' and equate the results. This gives $C''=\frac{1}{2}Pl^2+EIa_0$ and $\therefore$

$$EI\frac{dy}{dx}=\frac{Pl^2}{2}+EIa_0-P_1[l_1x-\frac{x^2}{2}] \quad . \quad (5)$$

$$\text{and } \therefore EIy=\frac{Pl^2}{2}x+EIa_0x-P_1[l_1\frac{x^2}{2}-\frac{x^3}{6}]+C''' \quad . \quad (6)'$$

At C, where $x=l$, both curves have the same ordinate; hence, by putting $x=l$ in the right members of (3) and (6)′ and equating results, we obtain $C'''=-\frac{1}{6}Pl^3$. ∴ (6)′ becomes

$$EIy=\tfrac{1}{2}Pl^2x+EIa_0x-P_1\left[\frac{l_1x^2}{2}-\frac{x^3}{6}\right]-\frac{Pl^3}{6} \quad . \quad (6)$$

as the **Equation of CB**, Fig. 227. But a_0 is still an unknown constant, to find which write out (6) for the point B where $x=l_1$, and $y=0$, whence we obtain

$$a_0=\frac{1}{6EIl_1}[Pl^3-3Pl^2l_1+2P_1l_1^3] \quad . \quad . \quad (7)$$

$a_1=$ a similar form, putting P_0 for P_1, and (l_1-l) for l.

235. Maximum Deflection in Case II.—Fig. 227. The ordinate y_m of the lowest point is thus found. Assuming $l>\frac{1}{2}l_1$, it will occur in the curve OC. Hence put the $dy\div dx$ of that curve, as expressed in equation (2), $=0$. Also for a_0 write its value from (7), having put $P_1=Pl\div l_1$, and we have

$$P(lx-\frac{x^2}{2})-P\frac{l}{l_1}(l_1x-\frac{x^2}{2})+\tfrac{1}{6}\frac{Pl}{l_1}(l^2-3ll_1+2l_1^2)=0$$

$$\text{whence } [x \text{ for max. } y]=\sqrt{\tfrac{1}{3}l(2l_1-l)}$$

Now substitute this value of x in (3), also a_0 from (7), and put $P_1=Pl\div l_1$, whence

$$\text{Max. Deflec.}=y\max=\tfrac{1}{9}\cdot\frac{P}{EIl_1}[l^3-3l^2l_1+2ll_1^2]\sqrt{\tfrac{1}{3}l(2l_1-l)}.$$

236. Case III. Horizontal Prismatic Beam Supported at Both Ends and Bearing a Uniformly Distributed Load along its Whole Length.—(The weight of the beam itself, if considered,

constitutes a load of this nature.) Let l= the length of the beam and w= the weight, per unit of length, of the loading; then the load coming upon any length x will be $=wx$, and the whole load $=wl$. By hypothesis w is constant. Fig. 228. From symmetry we know that the



FIG. 228.

reactions at A and B are each $=\frac{1}{2}wl$, that the middle O of the neutral line is its lowest point, and the tangent line at O is horizontal. Conceiving a section made at any point m of the neutral line at a distance x from O, consider as free the portion of beam on the right of m. The forces holding this portion in equilibrium are $\frac{1}{2}wl$, the reaction at B; the elastic forces of the exposed surface at m, viz.: the tensions and compressions, forming a couple, and J the total shear; and a portion of the load, $w(\frac{1}{2}l-x)$. The sum of the moments of these latter forces about the neutral axis of m, is the same as that of their resultant; (i.e., their sum, since they are parallel), and this resultant acts in the middle of the length $\frac{1}{2}l-x$. Hence the sum of these moments $=w(\frac{1}{2}l-x)\frac{1}{2}(\frac{1}{2}l-x)$. Now putting Σ (mom. about neutral axis of m)$=0$ for this free body, we have

$$EI\frac{d^2y}{dx^2}=\tfrac{1}{2}wl(\tfrac{1}{2}l-x)-\tfrac{1}{2}w(\tfrac{1}{2}l-x)^2;$$

$$\text{i.e., } EI\frac{d^2y}{dx^2}=\tfrac{1}{2}w(\tfrac{1}{4}l^2-x^2) \quad . \quad . \quad (1)$$

Taking the x-anti-derivative of both sides of (1),

$$EI\frac{dy}{dx} = \tfrac{1}{2}w(\tfrac{1}{4}l^2x - \tfrac{1}{3}x^3) + (C=0) \qquad (2)$$

as the equation of slope. (The constant is $=0$ since at O both $dy \div dx$ and x are $=0$.) From (2),

$$EIy = \frac{w}{2}(\tfrac{1}{8}l^2x^2 - \tfrac{1}{12}x^4) + [C'=0] \quad . \quad . \quad (3)$$

which is the equation of the elastic curve; throughout, i.e., it admits any value of x from $x=+\frac{1}{2}l$ to $x=-\frac{1}{2}l$. This is an equation of the fourth degree, one degree higher than those for the Curves of Cases I and II, where there were no distributed loads. If w were not constant, but proportional to the ordinates of an inclined right line, eq. (3) would be of the fifth degree; if w were proportional to the vertical ordinates of a parabola with axis vertical, (3) would be of the sixth degree; and so on.

By putting $x=\frac{1}{2}l$ in (3) we have the deflection of O below the horizontal through A and B, viz.: (with $W=$ total load $=wl$)

$$d = \frac{5}{384} \cdot \frac{wl^4}{EI} = \frac{5}{384} \cdot \frac{Wl^3}{EI} \quad . \quad . \quad (4)$$

237. Case IV. Cantilevers.—A horizontal beam whose only support consists in one end being built in a wall, as in Fig. 229(a), or supported as in Fig. 229(b) is sometimes called a cantilever. Let the student prove that in Fig. 229(a) with a single end load P, the deflection of B below the tangent at O is $d=\frac{1}{3}Pl^3 \div EI$; the same statement applies to Fig. 229(b), but the tangent at O is not horizontal if the beam was originally so. It can also be proved that the slope at B, Fig. 229(a) (from the tangent at O) is



Fig. 229.

$$a_1 = \frac{Pl^2}{2EI}.$$

The greatest deflection of the elastic curve from the right line joining AB, in Fig. 229(b), is evidently given by the equation for y max. in § 235, by writing, instead of P of that equation, the reaction at O in Fig. 229(b). This assumes that the max. deflection occurs between A and O. If it occurs between O and B put $(l_1 - l)$ for l.

If in Fig. 229(a) the loading is uniformly distributed along the beam at the rate of w pounds per linear unit, the student may also prove that the deflection of B below the tangent at O is

$$d = \tfrac{1}{8} wl^4 \div EI = \tfrac{1}{8} \frac{Wl^3}{EI}$$

238. Case V. Horizontal Prismatic Beam Bearing Equal Terminal Loads and Supported Symmetrically at Two Points.— Fig. 231. Weight of beam neglected. In the preceding cases we have made use of the approximate form $EId^2y \div dx^2$ in determining the forms of elastic curves. In the present



Fig. 231.



Fig. 232.

case the elastic curve from O to C is more directly dealt with by employing the more exact expression $EI \div \rho$ (see § 231) for the moment of the stress-couple in any section. The reactions at O and C are each $= P$, from symmetry. Considering free a portion of the beam extending from A to any section m between O and C (Fig. 232) we have, by putting Σ (mom. about neutral axis of m) $= 0$,

$$P(l+x) - \frac{EI}{\rho} - Px = 0 \therefore \rho = \frac{EI}{Pl}$$

That is, the radius of curvature is the same at all points of OC; in other words OC is the *arc of a circle* with the above radius. The upward deflection of F from the right line joining O and C can easily be computed from a knowledge of this fact. This is left to the student as also the value of the slope of the tangent line at O (and C). The deflection of D from the tangent at $C = {}^1/_3 Pl^3 \div EI$, as in Fig. 229(a).

SAFE LOADS IN FLEXURE.

239. Maximum Moment.—As we examine the different sections of a given beam under a given loading we find different values of p, the normal stress per unit of area in the outer element, as obtained from eq. (5) § 229, viz.:

$$\frac{pI}{e} = M. \qquad . \quad . \quad . \quad . \quad (1)$$

in which I is the "Moment of Inertia" (§ 85) of the plane figure formed by the section, about its neutral axis, e the distance of the most distant (or outer) fibre from the neutral axis, and M the sum of the moments, about this neutral axis, of all the forces acting on the free body of which the section in question is one end, exclusive of the stresses on the exposed surface of that section. In other words M is the sum of the moments of the forces which balance the stresses of the section, these moments being taken about the neutral axis of the section under examination.

For the prismatic beams of this chapter e and I are the same at all sections, hence p varies with M and becomes a maximum when M is a maximum. In any given case the location of the "*dangerous section*," or section of maximum M, and the amount of that maximum value may be determined by inspection and trial, this being the only method (except by graphics) if the external forces are detached.

If, however, the loading is continuous according to a definite algebraic law the calculus may often be applied, taking care to treat separately each portion of the beam between two consecutive reactions of supports, or detached loads.

As a graphical representation of the values of M along the beam in any given case, these values may be conceived laid off as vertical ordinates (according to some definite scale, e.g. so many inch-lbs. of moment to the linear inch of paper) from a horizontal axis just below the beam. If the upper fibres are in compression in any portion of the beam, so that that portion is convex downwards, these ordinates will be laid off below the axis, and vice versâ; for it is evident that at a section where $M=0$, p also $=0$, i.e., the character of the normal stress in the outermost fibre changes (from tension to compression, or vice versâ) when M changes sign. It is also evident from eq. (6) § 231 that the radius of curvature changes sign, and consequently the curvature is reversed, when M changes sign. These moment ordinates form a **Moment Diagram**, and the extremities a **Moment Curve.**

The maximum moment, M_m, being found, in terms of the loads and reactions, we must make the p of the "dangerous section," where $M=M_m$, equal to a safe value R', and thus may write

$$\frac{R'I}{e}=M_m \quad . \quad . \quad . \quad . \quad (2)$$

Eq. (2) is available for finding any one unknown quantity, whether it be a load, span, or some one dimension of the beam, and is concerned only with the **Strength**, and not with the stiffness of the beam. If it is satisfied in any given case, the normal stress on all elements in all sections is known to be $=$ or $<R'$, and the design is therefore safe in that one respect.

As to danger arising from the shearing stresses in any

section, the consideration of the latter will be taken up in a subsequent chapter and will be found to be necessary only in beams composed of a thin web uniting two flanges. The *total shear*, however, denoted by J, bears to the moment M, an important relation of great service in determining M_m. This relation, therefore, is presented in the next article.

240. The Shear is the First x-Derivative of the Moment.—Fig. 233. (x is the distance of any section, *measured parallel to the beam* from an arbitrary origin). Consider as free a vertical slice of the beam included between any two consecutive vertical sections whose distance apart is dx. The forces acting are the elastic forces of the two internal surfaces now laid bare, and, possibly, a portion, wdx, of the loading, which at this part of the beam has some intensity $=w$ lbs. per running linear unit. Putting Σ(mom. about axis N')$=0$ we have (noting that since the tensions and compressions of section N form a couple, the sum of their moments about N' is just the same as about N,)



Fig. 233.

$$\frac{pI}{e}-\frac{p'I}{e}+Jdx+wdx.\frac{dx}{2}=0$$

But $\frac{pI}{e}=M$, the Moment of the left hand section, $\frac{p'I}{e}=M'$, that of the right; whence we may write, after dividing through by dx and transposing,

$$\frac{M'-M}{dx}=J+w\frac{dx}{2} \quad \text{i.e.,} \frac{dM}{dx}=J; \tag{3}$$

for $w\frac{dx}{2}$ vanishes when added to the finite J, and $M'-M=dM=$ increment of the moment corresponding to the increment, dx, of x. This proves the theorem.

Now the value of x which renders M a maximum or minimum would be obtained by putting the derivative $dM \div dx =$ zero; hence we may state as a

Corollary.—*At sections where the moment is a maximum or minimum the shear passes through the value zero.*

The shear J at any section is easily determined by considering free the portion of beam from the section to either end of the beam and putting Σ(vertical components)$=0$.

In this article the words maximum and minimum are used in the same sense as in calculus; i.e., graphically, they are the ordinates of the moment curve at points where the *tangent line is horizontal.* If the moment curve be reduced to a straight line, or a series of straight lines, it has no maximum or minimum in the strict sense just stated; nevertheless the relation is still practically borne out by the fact that at the sections of greatest and least ordinates in the moment diagram the shear changes sign suddenly. This is best shown by drawing a *shear diagram*, whose ordinates are laid off vertically from a horizontal axis and under the respective sections of the beam. They will be laid off upward or downward according as J is found to be upward or downward, when the free body considered extends from the section toward the right.

In these diagrams the moment ordinates are set off on an arbitrary scale of so many inch-pounds, or foot-pounds, to the linear inch of paper; the shears being simply pounds, or some other unit of *force*, on a scale of so many pounds to the inch of paper. The scale on which the beam is drawn is so many feet, or inches, to the inch of paper.

241. Safe Load at the Middle of a Prismatic Beam Supported at the Ends.—Fig. 234. The reaction at each support is $\frac{1}{2}P$. Make a section n at any distance $x < \frac{l}{2}$ from B. Consider the portion nB free, putting in the proper elastic and external forces. The weight of beam is neglected. From Σ(mom. about n)$=0$ we have

$$\frac{pI}{e}=\frac{P}{2}x\text{; i.e., } M=\tfrac{1}{2}Px$$

Evidently M is proportional to x, and the ordinates representing it will therefore be limited by the straight line



FIG. 234.

$B'R$, forming a triangle $B'RA'$. From symmetry, another triangle $O'RA'$ forms the other half of the moment diagram. From inspection, the maximum M is seen to be in the middle where $x=\frac{1}{2}l$, and hence

$$(M \text{ max.})=M_m=\tfrac{1}{4}Pl \quad . \quad . \quad . \quad (1)$$

Again by putting Σ(vert. compons.)$=0$, for the free body nB we have

$$J=\frac{P}{2}$$

and must point downward since $\frac{P}{2}$ points upward. Hence the shear is constant and $=\frac{1}{2}P$ at any section in the right hand half. If n be taken in the left half we would have, nB being free, from Σ(vert. com.)$=0$,

$$J=P-\tfrac{1}{2}P=\tfrac{1}{2}P$$

the same numerical value as before; but J must point upward, since $\frac{P}{2}$ at B and J at n must balance the downward P at A. At A, then, the shear changes sign suddenly, that is, passes through *the value zero;* also at A, M *is a maximum*, thus illustrating the statement in § 240. Notice the shear diagram in Fig. 234.

To find the safe load in this case we write the maximum value of the normal stress, $p, = R'$, a safe value, (see table in a subsequent article) and solve the equation for P. But the maximum value of p is in the outer fibre at A, since M for that section is a maximum. Hence

$$\frac{R'I}{e} = \tfrac{1}{4}Pl \qquad (2)$$

is the equation for safe loading in this case, so far as the normal stresses in any section are concerned.

Example.—If the beam is of wood and has a rectangular section with width $b = 2$ in., height $h = 4$ in., while its length $l = 10$ ft., required the safe load, if the greatest normal stress is limited to 1,000 lbs. per sq. in. Use the pound and inch. From § 90 $I = \frac{1}{12}bh^3 = \frac{1}{12} \times 2 \times 64 = 10.66$ biquad. inches, while $e = \frac{h}{2} = 2$ in.

$$\therefore P = \frac{4R'I}{le} = \frac{4 \times 1{,}000 \times 10.66}{120 \times 2} = 177.7 \text{ lbs.}$$

242. Safe Load Uniformly Distributed along a Prismatic Beam Supported at the Ends.—Let the load per lineal unit of the length of beam be $= w$ (this can be made to include the weight of the beam itself). Fig. 235. From symmetry, each reaction $= \frac{1}{2}wl$. For the free body nO we have, putting $\Sigma(\text{mom. about } n) = 0$,

$$\frac{pI}{e} = \frac{wl}{2}x - (wx)\frac{x}{2} \therefore M = \frac{w}{2}(lx - x^2)$$

which gives M for any section by making x vary from 0 to l. Notice that in this case the law of loading is continuous along the whole length, and that hence the moment curve is continuous for the whole length.



FIG. 235.

To find the shear J, at n, we may either put Σ(vert. components)$=0$ for the free body, whence $J=\frac{1}{2}wl-wx$, and must therefore be downward for a small value of x; or, employing § 240, we may write out $dM \div dx$, which gives

$$J=\frac{dM}{dx}=\frac{w}{2}(l-2x) \qquad (1)$$

the same as before. To find the max. M, or M_m, put $J=0$, which gives $x=\frac{1}{2}l$. This indicates a maximum, for when substituted in $d^2M \div dx^2$, i.e., in $-w$, a negative result is obtained. Hence M_m occurs at the middle of the beam and its value is

$$M_m=\frac{1}{8}wl^2\,;\ \therefore \frac{R'I}{e}=\frac{1}{8}wl^2=\frac{1}{8}Wl \qquad (2)$$

the equation of safe loading. $W=$ total load $=wl$.

It can easily be shown that the moment curve is a por-

tion of a parabola, whose vertex is at A'' under the middle of the beam, and axis vertical. The shear diagram consists of ordinates to a single straight line inclined to its axis and crossing it, i.e., giving a zero shear, under the middle of the beam, where we find the max. M.

If a frictionless dove-tail joint with vertical faces were introduced at any locality in the beam and thus divided the beam into two parts, the presence of J would be made manifest by the downward slipping of the left hand part on the right hand part if the joint were on the right of the middle, and vice versâ if it were on the left of the middle. This shows why the ordinates in the two halves of the shear diagram have opposite signs. The greatest shear is close to either support and is $J_m = \frac{1}{2}wl$.

243. Prismatic Beam Supported at its Extremities and Loaded in any Manner. Equation for Safe Loading.—Fig. 236. Given the loads P_1, P_2, and P_3, whose distances from the right support are l_1, l_2, and l_3; ,required the equation for safe loading; i.e., find M_m and write it $= R'I \div e$.



FIG. 236.

If the moment curve were continuous, i.e., if M were a continuous function of x from end to end of the beam, we could easily find M_m by making $dM \div dx = 0$, i.e., $J = 0$, and substitute the resulting value of x in the expression for M. But in the present case of detached loads, J is not zero, necessarily, at any section of the beam. Still there is some one section where it changes sign, i.e., passes suddenly through the value zero, and this will be the section of greatest moment (though not a maximum in the strict sense used in calculus). By considering any portion nO as free, J is found equal to the Reaction at O Diminished by the Loads Occurring Between n and O. The reaction at B is

$$P_B=(P_1l_1+P_2l_2+P_3l_3)\div l$$

obtained by treating the whole beam as free (in which case no elastic forces come into play) and putting Σ(mom. about O)$=0$; while that at O, $=P_0=P_1+P_2+P_3-P_B$

If n is taken anywhere between O and E, $J=P_0$

" " " " E " F, $J=P_0-P_1$

" " " " F " H, $J=P_0-P_1-P_2$

" " " " H " B, $J=P_0-P_1-P_2-P_3$

This last value of J also = the reaction at the other support, B. Accordingly, the shear diagram is seen to consist of a number of horizontal steps. The relation $J=dM\div dx$ is such that the *slope* of the moment curve is proportional to the *ordinate* of the shear diagram, and that for a sudden change in the *slope* of the moment curve there is a sudden change in the shear *ordinate*. Hence in the present instance, J being constant between any two consecutive loads, the moment curve reduces to a straight line between the same loads, this line having a different inclination under each of the portions into which the beam is divided by the loads. Under each load the *slope* of the moment curve and the *ordinate* of the shear diagram change suddenly. In Fig. 236 the shear passes through the value zero, i.e., changes sign, at F; or algebraically we are supposed to find that P_0-P_1 is + while $P_0-P_1-P_2$ is −, in the present case. Considering FO, then, as free, we find M_m to be

$M_m=P_0l_2-P_1(l_2-l_1)$ and the equation for safe loading is

$$\frac{R'I}{e}=P_0l_2-P_1(l_2-l_1) \qquad (1)$$

(i.e., if the max. M is at F). It is also evident that the greatest shear is equal to the reaction at one or the other support, whichever is the greater, and that the moment at either support is zero.

The student should not confuse the moment curve, which

is entirely imaginary, with the neutral line (or elastic curve) of the beam itself. The greatest moment is not necessarily at the section of maximum deflection of the neutral line (or elastic curve).

For the case in Fig. 236 we may therefore state that the max. moment, and consequently the greatest tension or compression in the outer fibre, will be found in the section under that load for which the sum of the loads (including this load itself) between it and either support first equals or exceeds the reaction of that support. The amount of this moment is then obtained by treating as free either of the two portions of the beam into which this section divides the beam.

244. Numerical Example of the Preceding Article.—Fig. 237. Given P_1, P_2, P_3, equal to ½ ton, 1 ton, and 4 tons, re-



Fig. 237.

spectively; l_1=5 feet, l_2=7 feet, and l_3=10 feet; while the total length is 15 feet. The beam is of timber, of rectangular cross-section, the horizontal width being b=10 inches, and the value of R' (greatest safe normal stress), = ½ ton per sq. inch, or 1,000 lbs. per sq inch.

Required the proper depth h for the beam, for safe loading.

Solution.—Adopting a definite system of units, viz., the *inch-ton-second* system, we must reduce all distances such as l, etc., to inches, express all forces in tons, write $R' = \frac{1}{2}$ (tons per sq. inch), and *interpret all results by the same system.* Moments will be in inch-tons, and shears in tons. [N. B. In problems involving the strength of materials the inch is more convenient as a linear unit than the foot, since any stress expressed in lbs., or tons, per sq. inch, is numerically 144 times as small as if referred to the square foot.]

Making the whole beam free, we have from moms. about O, $P_B = \frac{1}{180}[\frac{1}{2} \times 60 + 1 \times 84 + 4 \times 120] = 3.3$ tons $\therefore$ $P_0 = 5.5 - 3.3 = 2.2$ tons.

The shear anywhere between O and E is $J = P_0 = 2.2$ tons.

" " " " E and F is $J = 2.2 - \frac{1}{2} = 1.7$ tons.

The shear anywhere between F and H is $J = 2.2 - \frac{1}{2} - 1 = 0.7$ tons.

The shear anywhere between H and B is $J = 2.2 - \frac{1}{2} - 1 - 4 = -3.3$ tons.

Since the shear changes sign on passing H, $\therefore$ the max. moment is at H; whence making HO free, we have

M at $H = M_m = 2.2 \times 120 - \frac{1}{2} \times 60 - 1 \times 36 = 198$ inch-tons.

For safety M_m must $= \frac{R'I}{e}$, in which $R' = \frac{1}{2}$ ton per sq. inch, $e = \frac{1}{2}h = \frac{1}{2}$ of unknown depth of beam, and I, §90, $= \frac{1}{12} bh^3$, with $b = 10$ inches

$\therefore \frac{1}{12} \cdot \frac{1}{2} \cdot \frac{2}{h} \times 10h^3 = 198$; or $h^2 = 237.6$ $\therefore$ $h = 15.4$ inches.

245. **Comparative Strength of Rectangular Beams.**—For such a beam, under a given loading, the equation for safe loading is

$$\frac{R'I}{e} = M_m \text{ i. e. } \frac{1}{6} R' bh^2 = M_m \ldots . (1)$$

whence the following is evident, (since for the same length, mode of support, and distribution of load, M_m is proportional to the safe loading.)

For rectangular prismatic beams of the same length, same material, same mode of support and same arrangement of load:

(1) The safe load is proportional to the width of beams having the same depth (h).

(2) The safe load is proportional to the square of the depth of beams having the same width (b).

(3) The safe load is proportional to the depth of beams having the *same volume* (i. e. the same bh).

(It is understood that the sides of the section are horizontal and vertical respectively and that the material is homogeneous.)

246. Comparative Stiffness of Rectangular Beams.—Taking the deflection under the same loading as an inverse measure of the stiffness, and noting that in §§ 233, 235, and 236, this deflection is inversely proportional to $I=\frac{1}{12}bh^3=$ the "moment of inertia" of the section about its neutral axis, we may state that:

For rectangular prismatic beams of the same length, same material, same mode of support, and *same loading*:

(1) The stiffness is proportional to the width for beams of the same depth.

(2) The stiffness is proportional to the cube of the height for beams of the same width (b).

(3) The stiffness is proportional to the square of the depth for beams of equal volume (bhl).

(4) If the length alone vary, the stiffness is inversely proportional to the cube of the length.

247. Table of Moments of Inertia.—These are here recapitulated for the simpler cases, and also the values of e, the distance of the outermost fibre from the axis.

Since the stiffness varies as I (other things being equal).

while the strength varies* as $I \div e$, it is evident that a square beam has the same stiffness in any position (§89), while its strength is greatest with one side horizontal, for then e is smallest, being $= \frac{1}{2}b$.

Since for any cross-section $I = \int dF\, z^2$, in which z = the distance of any element, dF, of area from the neutral axis, a beam is made both stiffer and stronger by throwing most of its material into two flanges united by a vertical web, thus forming a so-called "I-beam" of an I shape. But not without limit, for the web must be thick enough to cause the flanges to act together as a solid of continuous substance, and, if too high, is liable to buckle sideways, thus requiring lateral stiffening. These points will be treated later.



FIG. 238.

SECTION.	I	e
Rectangle, width $= b$, depth $= h$ (vertical)	$\frac{1}{12}\, bh^3$	$\frac{1}{2}\, h$
Hollow Rectangle, symmet. about neutral axis. See Fig. 238 (*a*)	$\frac{1}{12}\,[b_1 h_1^3 - b_2 h_2^3]$	$\frac{1}{2}\, h_1$
Triangle, width $= b$, height $= h$, neutral axis parallel to base (horizontal)	$\frac{1}{36}\, bh^3$	$\frac{2}{3}\, h$
Circle of radius r	$\frac{1}{4}\pi r^4$	r
Ring of concentric circles. Fig. 238 (*b*)	$\frac{1}{4}\pi(r^4_1 - r^4_2)$	r_1
Rhombus; Fig. 238 (*c*) h = diagonal which is vertical.	$\frac{1}{48}\, bh^3$	$\frac{1}{2}h$
Square with side b vertical.	$\frac{1}{12}\, b^4$	$\frac{1}{2}\, b$
" " " b at 45° with horiz.	$\frac{1}{12}\, b^4$	$\frac{1}{2}b\sqrt{2}$

248. Moment of Inertia of I-beams, Box-girders, Etc.—In common with other large companies, the Cambria Steel

* This function, $I \div e$, of the plane figure formed by the cross-section of a beam is evidently of three dimensions of length (cubic inches, for example), and is tabulated in the handbooks of the steel companies for different shapes of section; it is called the "*section-modulus.*" See next page.

Co. of Johnstown, Pa., manufactures prismatic rolled beams and other "shapes," of structural steel, which are variously called I-beams, deck-beams (or "bulb-beams"), rails, angles, T-bars, channels, Z-bars, etc., according to the form of their sections. See Fig. 239 for some of these forms. The company



FIG. 239.

publishes a pocket-book giving tables of quantities relating to the strength and stiffness of beams, such as the safe loads for various spans, moments of inertia of their sections in various positions, etc., etc. The moments of inertia of *I*-beams and deck-beams are computed according to §§ 92 and 93, with the inch as linear unit. The *I*-beams range from 4 in. to 24 inches deep, the deck-beams being about 7 and 8 in. deep. (See foot-note, p. 274.)

For beams of still greater stiffness and strength combinations of plates, channels, angles, etc., are riveted together, forming "built-beams," or "plate girders." The proper design for the riveting of such beams will be examined later. For the present the parts are assumed to act together as a continuous mass. For example, Fig. 240 shows a "box-girder," formed of two "channels" and two plates riveted together. If the axis of symmetry, *N*, is to be horizontal it becomes the neutral axis. Let C = the moment of inertia of one channel (as given in the pocket-book mentioned) about the axis *N* perpendicular to the web of the channel. Then the total *moment of inertia of the combination* is (nearly)



FIG. 240.

$$I_N = 2C + 2btd^2 - 4d't'(d - \tfrac{1}{2}t)^2 \quad . \quad . \quad (1)$$

In (1), b, t, and d are the distances given in Fig. 240 (d extends to the middle of plate) while d' and t' are the length and width of a rivet, the former from head to head (i.e., d' and t' are the dimensions of a rivet-hole).

For example, a box-girder of structural steel is formed of two 15-in. channels (35 lbs. per foot) and two plates 10 in. wide and 1 in. thick; the rivet-holes $\frac{3}{4}$ in. wide and $1\frac{3}{4}$ in. long. That is, $b=10$; $t=1$; $d=8$; $t'=\frac{3}{4}$; and $d'=1\frac{3}{4}$ in. Also from the hand-book we find that for the channel in question $C=320$ in.^{4} (i.e., biquad. in.). Hence, eq. (1),

$$I_N=640+2\times10\times1\times64-4\times\tfrac{7}{4}.\tfrac{3}{4}(8-\tfrac{1}{2})^2=1625 \text{ in.}^4$$

In this instance $e=8\frac{1}{2}$ in.; and if 15,000 lbs./in.^{2} (=7.5 tons/in.^{2}) be taken as the value of R' (greatest safe normal stress in the extreme fibre of any section) as used by the Cambria Steel Co. for box-girders in buildings, we have

$$\frac{R'I}{e}=\frac{15000\times1625}{8.5}=2{,}867{,}500 \text{ inch-lbs.}$$

That is, the max. safe "*moment of resistance*" of the box-girder is $M_m=2{,}867{,}000$ inch-lbs. $=1433.7$ inch-tons; this quantity having to do with normal stresses in the section. The greatest "*bending-moment*" due to the amount, and mode, of loading on the beam, must not exceed this. Proper provision for the shearing stresses in the section, and in the rivets, will be considered later.)

249. Strength of Cantilevers.—In Fig. 241 with a single concentrated load P at the projecting extremity, we easily find the moment at n to be $M=Px$, and the max. moment to occur at the section next the wall, its value being $M_m=Pl$.



Fig. 241.



Fig. 242.

The shear, J, is constant, and $=P$ at all sections. The moment and shear diagrams are drawn in accordance with these results.

If the load $W = wl$ is uniformly distributed on the cantilever, as in fig. 242, by making nO free we have, putting Σ(mom. about n) = 0,

$$\frac{pI}{e} = wx \cdot \frac{x}{2} \therefore M = \tfrac{1}{2}wx^2 \therefore M_m = \tfrac{1}{2}wl^2 = \tfrac{1}{2}Wl.$$

Hence the moment curve is a parabola, whose vertex is at O' and axis vertical. Putting Σ (vert. compons.) = 0 we obtain $J = wx$. Hence the shear diagram is a triangle, and the max. $J = wl = W$.

250. **Résumé of the Four Simple Cases.**—The following table shows the values of the deflections under an arbitrary load P, or W, (within elastic limit), and of the safe load;

	Cantilevers.		Beams with two end supports.	
	With one end load P Fig. 241	With unif. load $W = wl$ Fig. 242	Load P in middle Fig. 234	Unif. load $W = wl$ Fig. 235
Deflection	$\frac{1}{3} \cdot \frac{Pl^3}{EI}$	$\frac{1}{8} \cdot \frac{Wl^3}{EI}$	$\frac{1}{48} \cdot \frac{Pl^3}{EI}$	$\frac{5}{384} \cdot \frac{Wl^3}{EI}$
Safe load (from $\frac{R'I}{e}$ = M_m)	$\frac{R'I}{le}$	$2\frac{R'I}{le}$	$4\frac{R'I}{le}$	$8\frac{R'I}{le}$
Relative strength	1	2	4	8
Relative stiffness under same load	1	$\frac{8}{3}$	16	$\frac{128}{5}$
Relative stiffness under safe load	1	$\frac{4}{3}$	4	$\frac{16}{5}$
Max. shear = J_m, (and location,	P, (at wall)	W, (at wall)	$\frac{1}{2}P$, (at supp).	$\frac{1}{2}$ W, (at supp)

also the relative strength, the relative stiffness (under the same load), and the relative stiffness under the safe load, *for the same beam.*

The max. shear will be used to determine the proper web-thickness for I-beams and "built-girders." The student should carefully study the foregoing table, noting especially the relative strength, stiffness, and stiffness under safe load, of the same beam.

Thus, a beam with two end supports will bear a double

load, if uniformly distributed instead of concentrated in the middle, but will deflect ¼ more; whereas with a given load uniformly distributed the deflection would be only ⅝ of that caused by the same load in the middle, provided the elastic limit is not surpassed in either case.

251. R′, etc. For Various Materials.—The formula $\frac{p_m I}{e} = M_m$, from which in any given case of flexure we can compute the value of p_m, the greatest normal stress in any outer element, provided all the other quantities are known, holds good theoretically within the elastic limit only. Still, some experimenters have used this formula for the rupture of beams by flexure, calling the value of p_m thus obtained the *Modulus of Rupture*, R. R may be found to differ considerably from both the T or C of § 203 with some materials and forms, being frequently much larger. This might be expected, since even supposing the relative extension or compression (i.e., strain) of the fibres to be proportional to their distances from the neutral axis as the load increases toward rupture, the corresponding stresses, not being proportional to these strains beyond the elastic limit, no longer vary directly as the distances from the neutral axis; and the neutral axis does not pass through the centre of gravity of the section, necessarily.

The following table gives average values for R, R', R'', and E for the ordinary materials of construction.* E, the modulus of elasticity for use in the formulæ for deflection, is given as computed from experiments in flexure, and is nearly the same as E_t and E_c.

In any example involving R', e is usually written equal to the distance of the outer fibre from the neutral axis, whether that fibre is to be in tension or compression; since in most materials not only is the tensile equal to the compressive stress for a given strain (relative extension or contraction) but the elastic limit is reached at about the *same strain* both in tension and compression.

* Wet, or unseasoned, timber is very considerably weaker than that (such as ordinary "dry" timber) containing only 12 per cent. of moisture. Large pieces of timber take a much longer time to season than small ones. (Johnson.)

TABLE FOR USE IN EXAMPLES IN FLEXURE.

	Timber.	Cast Iron.	Wro't Iron.	Structural Steel.
Max. safe stress in outer fibre $=R'$(lbs. per sq. inch).	600 to 1,200	6,000 in tens. 12,000 in comp.	12,000	15,000
Stress in outer fibre at Elas. limit $=R''$(lbs. per sq. in.)			17,000* to 35,000	30,000 and upward.
"Modul. of Rupture" $=R=$lbs. per sq. inch.	4,000 to 10,000	40,000	50,000	60,000
E=Mod. of Elasticity, =lbs. per sq. inch.	1,000,000 to 2,000,000	17,000,000	25,000,000	29,000,000

In the case of cast iron, however, (see § 203) the elastic limit is reached in tension with a stress =9,000 lbs. per sq. inch and a relative extension of $\frac{66}{1000}$ of one per cent., while in compression the stress must be about double to reach the elastic limit, the relative change of form (strain) being also double. Hence with cast iron beams, once extensively used but now largely replaced by rolled beams of structural steel, an economy of material was effected by making the outer fibre on the compressed side twice as far from the neutral axis as that on the stretched side. Thus, Fig. 243, cross-sections with unequal flanges were used, so proportioned that the centre of gravity was twice as near to the outer fibre in tension as to that in compression, i.e., $e_2=2e_1$; in other words more material is placed in tension than in compression. The fibre A being in tension (within elastic limit), that at B, since it is twice as far from the neutral axis and on the other side, is contracted twice as much as A is extended; i.e., is under a compressive strain double the tensile strain at A, but in accordance with the above figures its state of stress is proportionally as much within the elastic limit as that of A.



FIG. 243.

* In the tests by U. S. Gov. in 1879 with I-beams, R'' ranged from 25,000 to 38,000, and the elastic limit was reached with less stress in the large than in the smaller beams. Also, for the same beam, R'' decreased with larger spans.

The great range of values of R for timber is due not only to the fact that the various kinds of wood differ widely in strength, while the behavior of specimens of any one kind depends somewhat on age, seasoning, etc., but also to the circumstance that the size of the beam under experiment has much to do with the result. The experiments of Prof. Lanza at the Mass. Institute of Technology in 1881 were made on full size lumber (spruce), of dimensions such as are usually taken for floor beams in buildings, and gave much smaller values of R (from 3,200 to 8,700 lbs. per sq. inch) than had previously been obtained. The loading employed was in most cases a concentrated load midway between the two supports.

These low values are probably due to the fact that in large specimens of ordinary lumber the continuity of its substance is more or less broken by cracks, knots, etc., the higher values of most other experimenters having been obtained with small, straight-grained, selected pieces, from one foot to six feet in length. See footnote p. 278.

Valuable information and tables relating to timber beams may be found in the hand-book of the Cambria Steel Co.

The value $R'_{\cdot}=16{,}000$ lbs. per sq. inch is employed by the Cambria Steel Co. in computing the safe loads for their rolled I-beams of structural steel; but with the stipulation that the beams (which are high and of narrow width) must be secure against yielding sideways. If such is not the case the ratio of the actual safe load to that computed with $R'=16{,}000$ is taken less and less as the span increases. The lateral security referred to may be furnished by the brick arch-filling of a fire-proof floor, or by light lateral bracing with the other beams.

252. Numerical Examples.—EXAMPLE 1.—A square bar of wrought iron, 1½ in. in thickness is bent into a circular‡ arc whose radius is 200 ft., the plane of bending being parallel to the side of the square. Required the greatest normal stress p_m in any outer fibre.

Solution. From §§ 230 and 231 we may write

$$\frac{Ey}{\rho}=\frac{pI}{e} \quad \therefore p=eE\div\rho, \text{ i.e., is constant.}$$

For the units *inch* and *pound* (viz. those of the table in § 251) we have $e=\frac{3}{4}$ in., $\rho=2{,}400$ in., and $E=25{,}000{,}000$ lbs. per sq. inch, and $\therefore$

$$p=p_m=\tfrac{3}{4}\times 25{,}000{,}000\div 2{,}400=7{,}812 \text{ lbs. per sq. in.,}$$

which is quite safe. At a distance of $\frac{1}{2}$ inch from the neutral axis, the normal stress is $=[\frac{1}{2}\div\frac{3}{4}]p_m=\frac{2}{3}p_m=$ 5,208 lbs. per sq. in. (If the force-plane (i.e., plane of bending) were parallel to the *diagonal* of the square, e would $=\frac{1}{2}\times 1.5\sqrt{2}$ inches, giving $p_m=[7{,}812\times\sqrt{2}\,]$ lbs. per sq. in.) § 238 shows an instance where a portion, OC, Fig. 231, is bent in a circular arc.

EXAMPLE 2.—A hollow cylindrical cast-iron pipe of radii $3\frac{1}{2}$ and 4 inches* is supported at its ends and loaded in middle (see Fig. 234). Required the safe load, neglecting the weight of the pipe. From the table in § 250 we have for safety

$$P=4\,\frac{R'I}{le}$$

From § 251 we put $R'=6{,}000$ lbs. per sq. in.; and from § 247 $I=\frac{\pi}{4}(r_1^4-r_2^4)$; and with these values, r_2 being $=\frac{7}{2}$, $r_1=4$, $e=r_1=4$, $\pi=\frac{22}{7}$ and $l=144$ inches (the inch must be the unit of length since $R'=6{,}000$ lbs. per sq. inch) we have

$$P=4\times 6{,}000\times\tfrac{1}{4}\cdot\tfrac{22}{7}(256-150)\div[144\times 4]\ \therefore\ P=3{,}470 \text{ lbs.}$$

The weight of the beam itself is $G=V\gamma$, (§ 7), i.e.,

$$G=\pi(r_1^2-r_2^2)l\gamma=\tfrac{22}{7}(16-12\tfrac{1}{4})144\times\tfrac{450}{1{,}728}=443 \text{ lbs.}$$

(Notice that γ, here, must be lbs., per *cubic inch*). This weight being a uniformly distributed load is equivalent to half as much, 221 lbs., applied in the middle, as far as the *strength* of the beam is concerned (see § 250), $\therefore$ P must be taken $=3{,}249$ lbs. when the weight of the beam is considered.

* And length of 12 feet, should be added.

EXAMPLE 3.—A Cambria I-beam, of structural steel, is to be placed horizontally on two supports at its extremities and is to be loaded uniformly (Fig. 235), the span being $l=20$ ft. Its cross-section, Fig. 244, has a depth parallel to the web, of 15 in. In the handbook of the Cambria Steel Co. it is designated as B 53, 15 in. in depth, and weighing 42 lbs. per foot of length; its section having a moment of inertia $I_1=442$ in.^{4} about a gravity axis perpendicular to the web (for use when the web is vertical; the strongest position) and $I_2=14.6$ in.^{4} about a gravity axis parallel to the web (i.e., when the web is placed horizontally).



FIG. 244.

First, placing the web vertically, we have from § 250,

W_1 = safe load, distributed, $=8\dfrac{R'I_1}{le_1}$. With $R'=16{,}000$,

$I_1=442$, $l=240$ *inches*, and $e_1=7\frac{1}{2}$ inches, this gives *

$W_1=(8\times16{,}000\times442)\div(240\times7.5)=31{,}430$ lbs.

But this includes the weight of the beam, $=20\times42=840$ lbs.; hence a distributed load of 30,600 lbs., or 15.3 tons, may be placed on the beam (secured against lateral yielding). The handbook of the Cambria Steel Co. referred to gives 15.7 tons as the safe load.)

With the web placed *horizontally*, we find as safe load

$$W_2=8\frac{R'I_2}{le_2}=(8\times16{,}000\times14.6)\div\left(240\times\frac{5.5}{2}\right)=2830 \text{ lbs.};$$

or less than 1/10 of W_1. Hence in this position the beam could carry safely only 1990 lbs. above its own weight.

EXAMPLE 4.—Required the deflection at the middle in the first case of Ex. 3. From § 250 this deflection is

$$d_1=\frac{5}{384}\cdot\frac{W_1l^3}{EI_1}=\frac{5}{384}\cdot\frac{8R'I_1}{le_1}\cdot\frac{l^3}{EI_1}=\frac{5}{48}\cdot\frac{R'}{E}\cdot\frac{l^2}{e_1}.$$

* The handbook of the Cambria Steel Co. also gives in a separate column the quantity $I_1\div e_1$, called the "*section-modulus*," S, (cub. in. or in.^{3}); so that the formula for the safe load would be $W_1=8R'S\div l$, S having the value 58.9 in.^{3} in the present instance.

i.e., $d_1=\frac{5}{48}\cdot\frac{16{,}000}{29{,}000{,}000}\cdot\frac{(240)^2}{\frac{15}{2}}$; (inch and pound)

$\therefore d_1=0.441$ in.

EXAMPLE 5.—A rectangular beam of yellow pine, of width $b=4$ inches, is 20 ft. long, rests on two end supports, and is to carry a load of 1,200 lbs. at the middle; required the proper depth h. From § 250

$$P=4\frac{R'I}{le}=4\frac{R'}{l}\cdot\frac{bh^3}{12}\cdot\frac{1}{\frac{1}{2}h}$$

$\therefore h^2=6Pl\div 4R'b$. For variety, use the *inch* and *ton*. For this system of units $P=0.60$ tons, $R'=0.50$ tons per sq. in., $l=240$ inches and $b=4$ inches.

$\therefore h^2=(6\times 0.6\times 240)\div(4\times 0.5\times 4)=108$ sq. in. $\therefore h=10.4$ in.

EXAMPLE 6.—Suppose the depth in Ex. 5 to be determined by the condition that the deflection shall be $=\frac{1}{500}$ of the span or length. We should then have from § 250

$$d=\frac{1}{500}\ l=\frac{1}{48}\cdot\frac{Pl^3}{EI}$$

Using the inch and ton, with $E=1{,}200{,}000$ lbs. per sq. in., which $=600$ tons per sq. inch, and $I=\frac{1}{12}bh^3$, we have

$$h^3=\frac{500\times 0.60\times 240\times 240\times 12}{48\times 600\times 4}=1{,}800\ \therefore h=12.2\text{ in.}$$

As this is >10.4 the load would be safe, as well.

EXAMPLE 7.—Required the length of a wro't iron pipe supported at its extremities, its internal radius being $2\frac{1}{4}$ in., the external 2.50 in., that the deflection *under its own weight* may equal $\frac{1}{100}$ of the length. 579.6 in. Ans.

EXAMPLE 8.—Fig. 245. The wall is 6 feet high and one foot thick, of common brick work (see § 7) and is to be borne by an *I*-beam in whose outer fibres no greater normal stress than 8,000 lbs. per sq. inch is allowable. If a number of I-beams is available,



FIG. 245.

ranging in height from 6 in. to 15 in. (by whole inches), which one shall be chosen in the present instance, if their cross-sections are Similar Figures, the moment of inertia of the 15-inch beam being 800 biquad. inches?

The 12-inch beam. **Ans.**

SHEARING STRESSES IN FLEXURE.

253. Shearing Stresses in Surfaces Parallel to the Neutral Surface.—If a pile of boards (see Fig. 246) is used to support a load, the boards being free to slip on each other, it is noticeable that the ends overlap, although the boards



FIG. 246.

FIG. 247.

are of equal length (now see Fig. 247); i.e., slipping has occurred along the surfaces of contact, the combination being no stronger than the same boards side by side. If, however, they are glued together, piled as in the former figure, the slipping is prevented and the deflection is much less under the same load P. That is, the compound beam is both stronger and stiffer than the pile of loose boards, but the *tendency* to slip still exists and is known as the "shearing stress in surfaces parallel to the neutral surface." Its intensity per unit of area will now be determined by the usual "free-body" method. In Fig. 248 let AN' be a portion, considered free, on the left of any

FIG. 248.

section N', of a prismatic beam slightly bent under forces in one plane and perpendicular to the beam. The moment equation, about the neutral axis at N', gives

$$\frac{p'I}{e} = M' \text{; whence } p' = \frac{M'e}{I} \quad . \quad . \quad (1)$$

Similarly, with AN as a free body, NN' being $= dx$,

$$\frac{pI}{e} = M \text{; whence } p = \frac{Me}{I} \quad . \quad . \quad . \quad (2)$$

p and p' are the respective normal stresses in the outer fibre in the transverse sections N and N' respectively.

Now separate the block NN', lying between these two consecutive sections, as a free body (in Fig. 249). And



Fig. 249.



Fig. 250.

furthermore remove a portion of the top of the latter block, the portion lying above a plane passed parallel to the neutral surface and at *any* distance z'' from that surface. This latter free body is shown in Fig. 250, with the system of forces representing the actions upon it of the portions taken away. The under surface, just laid bare, is a portion of a surface (parallel to the neutral surface) in which the above mentioned slipping, or shearing, tendency exists. The lower portion (of the block NN') which is now removed exerted this

rubbing, or sliding, force on the remainder along the under surface of the latter. Let the unknown intensity of this shearing force be X (per unit of area); then the shearing force on this under surface is $= Xy''dx$, ($y'' = oa$ in figure, being the horizontal width of the beam at this distance z'' from the neutral axis of N') and takes its place with the other forces of the system, which are the normal stresses between $\begin{bmatrix} z=e \\ z=z'' \end{bmatrix}$, and portions of J and J', the respective total vertical shears. (The manner of distribution of J over the vertical section is as yet unknown; see next article.)

Putting Σ (horiz. compons.) $= 0$ in Fig. 250, we have

$$\int_{z''}^{e} \frac{z}{e} p'dF - \int_{z''}^{e} \frac{z}{e} pdF - Xy''dx = 0$$

$$\therefore Xy''dx = \frac{p'-p}{e} \int_{z''}^{e} zdF$$

But from eqs. (1) and (2), $p'-p = (M'-M)\frac{e}{I} = \frac{e}{I} dM$, while from § 240 $dM = Jdx$;

$$\therefore Xy''dx = \frac{Jdx}{I} \int_{z''}^{e} zdF. \therefore X = \frac{J}{Iy''} \int_{z''}^{e} zdF \quad . \quad . \quad . \quad . \quad (3)$$

as the required intensity *per unit of area* of the shearing force in a surface parallel to the neutral surface and at a distance z'' from it. It is seen to depend on the "shear" J and the moment of inertia I of the *whole* vertical section; upon the horizontal thickness* y'' of the beam at the surface in question; and upon the integral $\int_{z''}^{e} zdF$, which (from § 23) is the *product of the area of that part of the vertical section extending from the surface in question to the outer fibre, by the distance of the centre of gravity of that part from the neutral surface.*

* Thickness of *actual substance.*

It now follows, from § 209, that the intensity (per unit area) of the shear on an elementary area of the *vertical cross section* of a bent beam, and this intensity we may call Z, is equal to that X, just found, in the horizontal section which is at the same distance (z'') from the neutral axis.

254. Mode of Distribution of J, the Total Shear, over the Vertical Cross Section.—The intensity of this shear, Z (lbs. per sq. inch, for instance) has just been proved to be

$$Z=X=\frac{J}{Iy''}\int_{z''}^{e} zdF \qquad (4)$$

To illustrate this, required the value of Z two inches above the neutral axis, in a cross section close to the abutment, in Ex. 5, § 252. Fig. 251 shows this section. From it we have for the *shaded portion*, lying above the locality in question, y'' = 4 inches, and $\int_{z''=2}^{e=5.2} zdF$ = (area of shaded portion) × (distance of its centre of gravity from NA) = (12.8 sq. in.) × (3.6 in.) = 46.08 cubic inches.



Fig. 251.

The total shear J = the abutment reaction = 600 lbs., while $I=\frac{1}{12}bh^3=\frac{1}{12}\times 4\times(10.4)^3$ = 375 biquad. inches. Both J and I refer to the *whole section.*

$$\therefore Z=\frac{600\times 46.08}{375\times 4}=18.42 \text{ lbs. per sq. in.,}$$

quite insignificant. In the neighborhood of the neutral axis, where $z''=0$, we have $y''=4$ and

$$\int_{z''=0}^{e} zdF=\int_{0}^{e} zdF=20.8\times 2.6=54.8,$$

where J and I of course are the same as before. Hence for $z''=0$

$$Z = Z_0 = 21.62 \text{ lbs. per sq. in.}$$

At the outer fibre since $\int_e^e z dF = 0$, z'' being $= e$, Z is $= 0$

for a beam of any shape.

For a solid rectangular section like the above, Z and z'' bear the same relation to each other as the co-ordinates of the parabola in Fig. 252 (axis horizontal).



FIG. 252

Since in equation (4) the horizontal thickness, y'', from side to side ef the section of the locality where Z is desired, occurs in the denominator, and since $\int_{z''}^{e} z dF$ increases as z'' grows *numerically* smaller, the following may be stated, as to the distribution of J, the shear, in any vertical section, viz.:

The intensity (lbs. per sq. in.) of the shear is zero at the outer elements of the section, and for beams of ordinary shapes is greatest where the section crosses the neutral surface. For forms of cross section having thin webs its value may be so great as to require special investigation for safe design.

Denoting by Z_0 the value of Z at the neutral axis, (which $= X_0$ in the neutral surface where it crosses the vertica section in question) and putting the thickness of the substance of the beam $= b_0$ at the neutral axis, we have,

$$Z_0 = X_0 = \frac{J}{Ib_0} \times \left\{ \begin{matrix} \text{area above} \\ \text{neutral axis} \\ \text{(or below)} \end{matrix} \right\} \times \left\{ \begin{matrix} \text{the dist. of its cent.} \\ \text{grav. from that axis} \end{matrix} \right\} \quad (5)$$

255. Values of Z_0 for Special Forms of Cross Section.—From the last equation it is plain that for a prismatic beam the value of Z_0 is proportional to J, the total shear, and hence to the ordinate of the shear diagram for any particular case of loading. The utility of such a diagram, as obtain-

ed in Figs. 234–237 inclusive, is therefore evident, for by locating the greatest shearing stress in the beam it enables us to provide proper relations between the loading and the form and material of the beam to secure safety against rupture by shearing.

The table in § 210 gives safe values which the maximum Z_0 in any case should not exceed. It is only in the case of beams with thin webs (see Figs. 238 and 240) however, that Z_0 is likely to need attention.

Fig. 253.

For a **Rectangle** we have, Fig. 253, (see eq. 5, § 254) $b_0=b$, $I=\frac{1}{12}bh^3$, and $\int_0^e zdF=\frac{1}{2}bh \cdot \frac{1}{4}h=\frac{1}{8}bh^2$

$$\therefore Z_0=X_0=\tfrac{3}{2}\,\tfrac{J}{bh}\ \text{i.e.,}\ =\tfrac{3}{2}\ (\text{total shear})\div(\text{whole area})$$

Hence the greatest intensity of shear in the cross-section is $\frac{3}{2}$ as great per unit of area as if the total shear were uniformly distributed over the section.


Fig. 254.

Fig. 255.



Fig. 256.



Fig. 257.

For a **Solid Circular** section Fig. 254

$$Z_0=\frac{J}{Ib_0}\int_0^e zdF=\frac{J}{\frac{1}{4}\pi r^4 \cdot 2r}\cdot\frac{\pi r^2}{2}\cdot\frac{4r}{3\pi}=\frac{4}{3}\cdot\frac{J}{\pi r^2}$$

[See § 26 Prob. 3].

For a **Hollow Circular** section (concentric circles) Fig. 255, we have similarly,

$$Z_0 = \frac{J}{\frac{1}{4}\pi(r_1^4 - r_2^4)2(r_1 - r_2)}\left[\frac{\pi r_1^2}{2}\cdot\frac{4r_1}{3\pi} - \frac{\pi r_2^2}{2}\cdot\frac{4r_2}{3\pi}\right]$$

$$= \frac{4}{3}\cdot\frac{J(r_1^3 - r_2^3)}{\pi(r_1^4 - r_2^4)(r_1 - r_2)}$$

Applying this formula to Example 2 § 252, we first have as the max. shear $J_m = \frac{1}{2}P = 1{,}735$ lbs., this being the abutment reaction, and hence (putting $\pi = (22 \div 7)$)

$$Z_0 \text{ max.} = \frac{4\times 7\times 1735[64-42.8]}{3\times 22[256-150](4-3.5)} = 294 \text{ lbs. per sq. in.}$$

which cast iron is abundantly able to withstand in shearing.

For a **Hollow Rectangular Beam**, symmetrical about its neutral surface, Fig. 256 (box girder)

$$Z_0 = \frac{J\,\frac{1}{8}(b_1h_1^2 - b_2h_2^2)}{\frac{1}{12}(b_1h_1^3 - b_2h_2^3)(b_1 - b_2)} = \frac{3}{2}\cdot\frac{J[b_1h_1^2 - b_2h_2^2]}{[b_1h_1^3 - b_2h_2^3][b_1 - b_2]}$$

The same equation holds good for Fig. 257 (I-beam with square corners) but then b_2 denotes the sum of the widths of the hollow spaces.

256. Shearing Stress in the Web of an I-Beam.—It is usual to consider that, with I-beams (and box-beams) with the web vertical the shear J, in any vertical section, is borne exclusively by the web and is uniformly distributed over its section. That this is nearly true may be proved as follows, the flange area being comparatively large. Fig. 258. Let F_1 be the area of one flange, and F_0 that of the half web. Then since



FIG. 258.

$$I = \tfrac{1}{12}b_0h_0^3 + 2F_1\left(\frac{h_0}{2}\right)^2,$$

(the last term approximate, ½ h_0 being taken for the radius of gyration of F_1,) while

$$\int_0^e z dF = F_1 \frac{h_0}{2} + F_0 \frac{h_0}{4}, \text{ (the first term approx.) we have}$$

$$Z_0 = \frac{J \int_0^e z dF}{I b_0} = \frac{J \frac{1}{4} h_0 (2F_1 + F_0)}{\frac{1}{12} h_0^3 b_0 (6F_1 + 2F_0)}, \text{ which} = \frac{J}{b_0 h_0},$$

if we write $(2F_1+F_0) \div (6F_1+2F_0) = \frac{1}{3}$. But $b_0 h_0$ is the area of the whole web, ∴ the shear per unit area at the neutral axis is nearly the same as if J were uniformly distributed over the web. E. g., with $F_1 = 2$ sq. in., and $F_0 = 1$ sq. in. we obtain $Z_0 = 1.07$ $(J \div b_0 h_0)$.

Similarly, the shearing stress per unit area at n, the upper edge of the web, is also nearly equal to $J \div b_0 h_0$ (see eq., 4 (§254) for then $\left[\int_{z''=\frac{1}{2}h_0}^{e} (z dF)\right] = F_1 . \frac{1}{2} h_0$ nearly,

while I remains as before.

The shear per unit area, then, in an ordinary I-beam is obtained by dividing the total shear J by the area of the web section.*

Example.—It is required to determine the proper thickness to be given to the web of the 15-inch structural steel rolled I-beam of Example 3 of p. 282, the height of web being 13 in., and the maximum safe shearing stress being taken as 8750 lbs./in.^{2} (as prescribed by the Philadelphia building laws for mild steel). The web is vertical.

The greatest total shear, J_m, which occurs at either support, is equal to half the load, i.e., to 15,715 lbs.; and hence, with b_0 denoting the thickness of web, we have

$$Z_0 \text{ max.} = \frac{J_m}{b_0 h_0}; \text{ i.e., } 8750 = \frac{15{,}715}{b_0 \times 13}; \therefore b_0 = 0.138 \text{ in.}$$

* That is, for the vertical, or horizontal, section of web. The shear on some oblique plane may be somewhat larger than this. See §§ 270*a* and 314.

(Units, inch and pound). The 15-inch I-beam in question of the Cambria Steel Co.), weighing 42 lbs. to the linear foot, has a web 0.41 in. thick, which provides a very ample resistance to shearing stress.

In the middle of the span, $Z_0 = 0$, since $J = 0$.

257. Designing of Riveting for Built Beams.—The latter are generally of the I-beam and box forms, made by riveting together a number of continuous shapes, most of the material being thrown into the flange members. *E. g.*, in fig. 259, an I-beam* is formed by riveting together, in the manner shown in the figure, a "vertical stem plate" or web, four "angle-bars," and two "flange-plates," each of



Fig. 259.



Fig. 260.

these seven pieces being continuous through the whole length of the beam. Fig 260 shows a box-girder. If the riveting is well done, the combination forms a single rigid beam whose safe load for a given span may be found by foregoing rules; in computing the moment of inertia, however, the portion of cross section cut out by the rivet holes must not be included. (This will be illustrated in a subsequent paragraph.) The safe load having been computed from a consideration of normal stresses only, and the web being made thick enough to take up the max. total shear, J_n, with safety, it still remains to design the riveting, through whose agency the web and flanges are caused to act together as a single continuous rigid mass. It will be on the side of safety to consider that at a given

* Such a built I-beam is usually designated a "*plate-girder.*" See handbook of the Cambria Steel Co.

locality in the beam the shear carried by the rivets connecting the angles and flanges, per unit of length of beam, is the same as that carried by those connecting the angles and the web ("vertical stem-plate"). The amount of this shear may be computed from the fact that it is equal to that occurring in the surface (parallel to the neutral surface) in which the web joins the flange, in case the web and flange were of continuous substance, as in a solid I-beam. But this shear must be of the same amount per horizontal unit of length as it is per vertical linear unit in the web itself, where it joins the flange; (for from § 254 $Z = X$.) But the shear in the vertical section of the web, being uniformly distributed, is the same per vertical linear unit at the junction with the flange as at any other part of the web section (§ 256,) and the whole shear on the vertical section of web $= J$, the "total shear" of that section of the beam.

Hence we may state the following:

The riveting connecting the angles with the flanges, (or the web with the angles) in any locality of a built beam, must safely sustain *a shear equal to J on a horizontal length equal to the height of web.*

The strength of the riveting may be limited by the resistance of the rivet to being sheared (and this brings into account its cross section) or upon the crushing resistance of the side of the rivet hole in the plate (and this involves both the diameter of the rivet and the thickness of the metal in the web, flange, or angle. In its hand-book, the Cambria Steel Co. gives tables for the safe strength of rivets, and compressive resistance of plates; based on unit shearing stresses from 6,000 to 10,000 lbs./sq. in. for shearing stress in the rivets, and 12,000 to 20,000 lbs./sq. in. compressive resistance in the side of the rivet hole, the axial plane section of the hole being the area of reference.

In fig. 259 the rivets connecting the web with the angles are in *double shear*, which should be taken into account in considering their shearing strength, which is then double; those connecting the angles and the flange plates are in

single shear. In fig. 260 (box-beam) where the beam is built of two webs, four angles, and two flange plates, all the rivets are in single shear. If the web plate is very high compared with its thickness, vertical stiffeners in the form of "angles" may need to be riveted upon them laterally [see § 314].

EXAMPLE.—A built I-beam of structural steel (fig. 259) is to support a uniformly distributed load of 40 tons, its extremities resting on supports 20 feet apart, and the height and thickness of web being 20 ins. and $\frac{1}{2}$ in. respectively. How shall the rivets, which are $\frac{7}{8}$ in. in diameter, be spaced between the web and the angles which are also $\frac{1}{2}$ in. in thickness? Let the unit stresses taken be 7500 for shearing, and 12,500 for side compression (lbs./in.^{2}). Referring to fig. 235 we find that $J = \frac{1}{2}\ W = 20$ tons at each support and diminishes regularly to zero at the middle, where no riveting will therefore be required. Each rivet, having a sectional area of $\frac{1}{4}\pi(\frac{7}{8})^2 = 0.60$ sq. inches, can bear a safe shear of $0.60 \times 7500 = 4500$ lbs. in single shear, and hence of 9000 lbs. in double shear, which is the present case. But the safe compressive resistance of the side of the rivet hole in either the web or the angle is only $\frac{7}{8}$ in. $\times \frac{1}{2}$ in. $\times 12500 = 5470$ lbs., and thus determines the spacing of the rivets as follows:

Near a support the riveting must sustain a shear equal to 40,000 lbs. on a horizontal length equal to the height of web, i.e., to 20 ins., and the safe compression for each rivet is 5470 lbs. Hence $4000 \div 5470$, or 7.2, rivets will be needed for the 20-inch length. In other words, they must be spaced $20 \div 7.2 = 2.7$ in. apart, center to center, near the supports; 5.4 in. apart at $\frac{1}{4}$ the span from a support; none at all in the middle. By the Cambria handbook, this distance apart should never be less than 3 diameters of the rivet; and, in connecting plates in compression, should not exceed 16 times the thickness of the plate.

As for the rivets connecting the angles and flange plates, being in two rows and opposite (in pairs) the safe shear-

ing resistance of a pair (each in single shear) is 9,000 lbs., while the safe compressive resistance of the sides of the two rivet holes in the angle bars (the flange plate being much thicker) is =10,940 lbs. Hence the former figure (9,000) divided into 40,000, gives 4.44 as the number of pairs of rivets for 20 in. of length of the beam; i.e., the rivets in one row should be $20 \div 4.44 = 4.5$ in. apart, centre to centre, near a support; the interval to be increased in inverse ratio to the distance from the middle of span, (bearing in mind the practical limitation just given).

If the load is concentrated in the middle of the span, instead of uniformly distributed, J is constant along each half-span, (see fig. 234) and the rivet spacing must accordingly be made the same at all localities of the beam.

SPECIAL PROBLEMS IN FLEXURE.

258. Designing Cross Sections of Built Beams.—The last paragraph dealt with the riveting of the various plates; we now consider the design of the plates themselves. Take for instance a plate-girder, fig. 261; one vertical stem-



Fig. 261.

plate, four angle bars, (each of sectional area = A, remaining after the holes are punched, with a gravity axis parallel to, and at a distance = a from its base), and two flange plates of width = b, and thickness = t. Let the whole depth of girder = h, and the diameter of a rivet hole = t'. To safely resist the tensile and compressive forces induced in this section by M_m inch-lbs. (M_m being the greatest moment in the beam which is prismatic) we have from § 239,

$$M_m = \frac{R'I}{e} \qquad (1)$$

R' for mild steel = 15,000 lbs. per sq. inch, e is = ½ h while I, the moment of inertia of the compound section, is obtained as follows, taking into account the fact that the rivet holes cut out part of the material. In dealing with the sections of the angles and flanges, we consider them concentrated at their centres of gravity (an approximation, of course,) and treat their moments of inertia about N as single terms in the series $\int dF\, z^2$ (see § 85). The subtractive moments of inertia for the rivet holes in the web are similarly expressed; let b_0 = thickness of web.

$$\therefore \begin{cases} I_N \text{ for web} = \frac{1}{12} b_0\, (h-2t)^3 - 2b_0 t' \left[\frac{h}{2} - t - a'\right]^2 \\ I_N \text{ for four angles} = 4A \left[\frac{h}{2} - t - a\right]^2 \\ I_N \text{ for two flanges} = 2(b-2t')\, t \left(\frac{h-t}{2}\right)^2 \end{cases}$$

the sum of which makes the I_N of the girder. Eq. (1) may now be written

$$\frac{M_m h}{2R'} = I_N \qquad (2)$$

which is available for computing any one unknown quantity. The quantities concerned in I_N are so numerous and they are combined in so complex a manner that in any numerical example it is best to adjust the dimensions of the section to each other by successive assumptions and

trials. (The hand-book of the Cambria Steel Co. gives tables of safe loads of beam box-girders and plate-girders for a large variety of sizes and distances between supports; but attention is called to the fact that the loads given in the tables are based on the assumption that the girder is *supported laterally*, and that otherwise a proper reduction in the allowable safe load must be made, as explained elsewhere in the hand-book. The value of 15,000 lbs./sq. in. for R' has been used in computing these tables.)

Example.—(Units, inch and pound). A plate-girder with end supports, of span = 20 ft. = 240 inches, is to support a uniformly distributed load of 45 tons = 90,000 lbs. If $\frac{3}{4}$ inch rivets are used, angle bars $3'' \times 3'' \times \frac{1}{2}''$, vertical web $\frac{1}{2}''$ in thickness, and plates 1 inch thick for flanges, how wide (b = ?) must these flange-plates be ? taking $h = 22$ inches = total height of girder.

Solution.—From the table in § 250 we find that the max. M for this case is $\frac{1}{8}\ Wl$, where W = the total distributed load (including the weight of the girder) and l = span. Hence the left hand member of eq. (2) reduces to

$$\frac{Wl}{16} \cdot \frac{h}{R'} = \frac{90000 \times 240 \times 22}{16 \times 15000} = 1980.$$

That is, the total moment of inertia of the section must be = 1,980 biquad. inches, of which the web and angles supply a known amount, since $b_0 = \frac{1}{2}''$, $t = 1''$, $t' = \frac{3}{4}''$, $a' = 1\frac{3}{4}''$, $A = 2.0$ sq. in., $a = 0.9''$, and $h = 22''$, are known, while the remainder must be furnished by the flanges, thus determining their width b, the unknown quantity.

The *effective* area, A, of an angle bar is found thus: The full sectional area for the size given, $= 3 \times \frac{1}{2} + 2\frac{1}{2} \times \frac{1}{2} = 2.75$ sq. inches, from which deducting for two rivet holes we have

$$A = 2.75 - 2 \times \tfrac{3}{4} \times \tfrac{1}{2} = 2.0 \text{ sq. in.}$$

The value $a = 0.90''$ is found by cutting out the shape

of two angles from sheet iron, thus: and balancing it on a knife edge.* (The gaps left by the rivet holes may be ignored, without great error, in finding a). Hence, substituting we have

Fig. 261 a.

$$I_N \text{ for web } = \tfrac{1}{12} \cdot \tfrac{1}{2} \times 20^3 - 2 \times \tfrac{1}{2} \cdot \tfrac{3}{4} [8\tfrac{1}{4}]^2 = 282.3$$
$$I_N \text{ for four angles } = 4 \times 2 \times [9.10]^2 = 662.5$$
$$I_N \text{ for two flanges} = 2(b - \tfrac{6}{4}) \times 1 \times (10\tfrac{1}{2})^2 = 220.4\,(b - 1.5)$$
$$\therefore 1980 = 282.3 + 662.5 + (b - 1.5)220.4$$

whence $b = 4.6 + 1.5 = 6.1$ inches

the required total width of each of the 1 in. flange plates. This might be increased to 6.5 in. so as to equal the united width of the two angles and web.

The rivet spacing can now be designed by § 257, and the assumed thickness of web, ½ in., tested for the max. total shear by § 256. The latter test results as follows: The max. shear J_m occurs near either support and $= \frac{1}{2} W = 45{,}000$ lbs. $\therefore$, calling b'_0 the least allowable thickness of web in order to keep the shearing stress as low as 8,000 lbs. per sq. inch,

$$b'_0 \times 20'' \times 8000 = 45000 \quad \therefore \; b'_0 = 0.28 \text{ in.}$$

showing that the assumed width of ½ in. is safe.

This girder will need vertical stiffeners near the ends, as explained subsequently, and is understood to be supported laterally.† Built beams of double web, or box-form, (see Fig. 260) do not need this lateral support.

259. Set of Moving Loads.—When a locomotive passes over a number of parallel prismatic girders, each one of which experiences certain detached pressures corresponding to the different wheels, by selecting any definite position of the wheels on the span, we may easily compute the reactions of the supports, then form the shear diagram, and finally as in § 243 obtain the max. moment, M_m, and the

* The Cambria hand-book gives values of I and a for sections of angle-bars.

† See § 314.

max. shear J_m, for this particular position of the wheels. But the values of M_m and J_m for some other position may be greater than those just found. We therefore inquire which will be the greatest moment among the infinite number of (M_m)'s (one for each possible position of the wheels on the span). It is evident from Fig. 236 from the nature of the moment diagram, that when the pressures or loads are detached, the M_m for any position of the loads, which of course are in this case at fixed distances apart, must occur under one of the loads (i.e. under a wheel). We begin ∴ by asking: What is the position of the set of moving loads when the moment under a given wheel is greater than will occur under that wheel in any other position? For example, in Fig. 262, in what position of the



Fig 262.

loads P_1, P_2, etc. on the span will the moment M_2, i.e., under P_2, be a maximum as compared with its value under P_2 in any other position on the span. Let R be the resultant of the *loads which are now on the span*, its *variable* distance from O be $= \bar{x}$, and its *fixed* distance from $P_2 = a'$; while a, b, c, etc., are the fixed distances between the loads (wheels). For any values of $\bar{x}$, as the loading moves through the range of motion within which no wheel of the set under consideration goes off the span, and no new wheel comes on it, we have $R_1 = \frac{\bar{x}}{l} R$, and the moment under P_2

$$= M_2 = R_1[l-(\bar{x}-a')] - P_3 b - P_4(b+c)$$

$$\text{i.e. } M_2 = \frac{R}{l}(l\bar{x} - \bar{x}^2 + a'\bar{x}) - P_3 b - P_4(b+c) \quad \ldots\ldots\ldots \quad (1)$$

In (1) we have M_2 as a function of $\bar{x}$, all the other quantities in the right hand member remaining constant as the loading moves; $\bar{x}$ may vary from $\bar{x}=a+a'$ to $\bar{x}=l-(c+b-a')$. For a max. M_2, we put $dM_2 \div d\bar{x}=0$, *i. e.*

$$\frac{R}{l}(l-2\bar{x}+a')=0 \quad \therefore \bar{x}\,(\text{for Max } M_2)=\tfrac{1}{2}l+\tfrac{1}{2}a'$$

(For this, or any other value of $\bar{x}$, $d^2M_2 \div d\bar{x}^2$ is negative, hence a maximum is indicated). For a max. M_2, then, R must be as as far ($\frac{1}{2}a'$) on one side of the middle of the span as P_2 is on the other; *i.e.*, as the loading moves, the moment under a given wheel becomes a max. when that wheel and the centre of gravity of all the loads (*then on the span*) are *equi-distant from the middle of the span.*

In this way in any particular case we may find the respective max. moments occurring under each of the wheels during the passage, and the greatest of these is the M_m to be used in the equation $M_m=R'I \div e$ for safe loading.*

As to the shear J, for a given position of the wheels this will be the greatest at one or the other support, and equals the reaction at that support. When the load moves toward either support the shear at that end of the beam evidently increases so long as no wheel rolls completely over and beyond it. To find J max., then, dealing with each support in turn, we compute the successive reactions at the support when the loading is successively so placed that consecutive wheels, in turn, are on the point of rolling off the girder at that end; the greatest of these is the max. shear, J_m. As the max. moment is apt to come under the heaviest load it may not be necessary to deal with more than one or two wheels in finding M_m.

EXAMPLE.—Given the following wheel pressures,

$A< \ldots 8' \ldots >B< \ldots 5' \ldots >C< \ldots 4 \ldots <D$

4 tons. 6 tons. 6 tons. 5 tons.

on one rail which is continuous over a girder of 20 ft. span, under a locomotive.

* Since this may be regarded as a case of "sudden application" of a load, it is customary to make R' much smaller than for a dead load; from one-third to one-half smaller.

1. Required the position of the resultant of A, B, and C;
2. " " " " A, B, C, and D;
3. " " " " B, C, and D.

4. In what position of the wheels on the span will the moment under B be a max.? Ditto for wheel C? Required the value of these moments and which is M_m?

5. Required the value of J_m, (max. shear), its location and the position of loads.

Results.—(1.) 7.8′ to right of A. (2.) 10′ to right of A. (3.) 4.4′ to right of B. (4.) Max. $M_B = 1{,}273{,}000$ inch lbs. with all the wheels on; Max. $M_C = 1{,}440{,}000$ inch-lbs. with wheels B, C, and D on. (5.) $J_m = 13.6$ tons at right support with wheel D close to this support.

260. Single Eccentric Load.—In the following special cases of prismatic beams, peculiar in the distribution of the loads, or mode of support, or both, the main objects sought are the values of the max. moment M_m, for use in the equation

$$M_m = \frac{R'I}{e} \text{ (see §239)};$$

and of the max. shear J_m, from which to design the web riveting in the case of an I or box-girder. The modes of support will be such that the reactions are independent of the form and material of the beam (the weight of beam being neglected). As before, the flexure is to be slight, and the forces are all perpendicular to the beam.



FIG. 263.

The present problem is that in fig. 263, the beam being prismatic, supported at the ends, with a single eccentric load, P. We shall first disregard the weight of the beam itself. Let the span $= l_1 + l_2$. First considering the whole beam free we have the reactions $R_1 = Pl_2 \div l$ and $R_2 = Pl_1 \div l$.

Making a section at m and having Om free, x being $< l_2$, Σ (vert. compons.) $= 0$ gives

$$R_2 - J = 0, \text{ i.e., } J = R_2;$$

while from $\Sigma\,(\text{mom.})_m = 0$ we have

$$\frac{pI}{e} - R_2 x = 0 \therefore M = R_2 x = \frac{Pl_1}{l} x$$

These values of J and M hold good between O and C, J being constant, while M is proportional to x. Hence for OC the shear diagram is a rectangle and the moment diagram a triangle. By inspection the greatest M for OC is for $x = l_2$, and $= Pl_1 l_2 \div l$. This is the max. M for the beam, since between C and B, M is proportional to the distance of the section from B.

$$\therefore M_m = \frac{Pl_1 l_2}{l} \text{ and } \frac{R'I}{e} = \frac{Pl_1 l_2}{l} \quad . \quad . \quad . \qquad (1)$$

is the equation for safe loading.

$J = R_1$ in any section along CB, and is opposite in sign to what it is on OC; i.e., practically, if a dove-tail joint existed anywhere on OC the portion of the beam on the right of such section would slide downward relatively to the left hand portion; but vice versâ on CB.

Evidently the max. shear $J_m = R_1$ or R_2, as l_2 or l_1 is the greater segment.

It is also evident that for a given span and given beam the safe load P', as computed from eq. (1) above, becomes very large as its point of application approaches a support; this would naturally be expected but not without limit, as the shear for sections between the load and the support is equal to the reaction at the near support and may thus soon reach a limiting value, when the safety of the web or the spacing of the rivets, if any, is considered.

Secondly, considering the *weight of the beam*, or *any uniformly distributed loading*, weighing w lbs. per unit of length of beam, in addition to P, Fig. 264, we have the reactions

$$R_1 = \frac{Pl_2}{l} + \frac{W}{2}; \text{ and } R_2 = \frac{Pl_1}{l} + \frac{W}{2}$$

Let l_2 be $> l_1$; then for a portion Om of length $x < l_2$, moments about m give

$$\frac{pI}{e} - R_2 x + wx.\frac{x}{2} = 0$$

i.e., *on* OC, $M = R_2 x - \frac{1}{2} wx^2$ . . . . . (2)

Evidently for $x = 0$ (i.e. at O) $M = 0$, while for $x = l_2$ (i.e. at C) we have, putting $w = W \div l$

$$M_C = R_2 l_2 - \tfrac{1}{2} w l_2^2 = \frac{P l_1 l_2}{l} + \frac{W l_2}{2} - \tfrac{1}{2}\frac{W l_2^2}{l} \quad . \quad (3)$$

It remains to be seen whether a value of M may not exist in some section between O and C, (i.e., for a value of $x < l_2$ in eq. (2)), still greater than M_C. Since (2) gives M as a continuous function of x between O and C, we put $dM \div dx = 0$, and obtain, substituting the value of the constants R_2 and w,

$$R_2 - wx = 0 \therefore x_n \left\{ \text{for } M \begin{matrix} \text{max.} \\ \text{or} \\ \text{min.} \end{matrix} \right\} = \frac{P l_1}{W} + \tfrac{1}{2} l. \quad (4)$$

This must be for M max., since $d^2M \div dx^2$ is negative when this value of x is substituted. If the particular value of x given by (4) is $< l_2$, the corresponding value of M (call it M_n) from eq. (2) will occur on OC and will be greater than M_C (Diagrams II. in fig. 264 show this case); but if x_n is $> l_2$, we are not concerned with the corresponding value of M, and the greatest M on OC would be M_C.



FIG. 264.

For the short portion BC, which has moment and shear diagrams of its own not continuous with those for OC, it may easily be shown that M_C is the greatest moment of any section. Hence the M

max., or M_m, of the whole beam is either M_c or M_n, according as x_n is $>$ or $< l_2$. This latter criterion may be expressed thus, [with $l_2 - \frac{1}{2} l$ denoted by l_3, the distance of P from the middle of the span] :

From (eq. 4) $\left[\left(\frac{Pl_1}{W}+\frac{1}{2}l\right) \gtrless l_2\right]$ is equivalent to $\left[\left(\frac{P}{W}\right) \gtrless \left(\frac{l_3}{l_1}\right)\right]$

and since from (4) and (2)

$$M_n=\left[\frac{Pl_1}{l}+\frac{1}{2}W\right]\left[\frac{Pl_1}{W}+\frac{1}{2}\ l\right]-\frac{1}{2}\frac{W}{l}\left[\frac{Pl_1}{W}+\frac{1}{2}l\right]^2 \quad (5)$$

The equation for safe loading is

$$\left.\begin{aligned} &\frac{R'I}{e}=M_c, \text{ when } \frac{P}{W} \text{ is } > \frac{l_3}{l_1} \\ \text{and} \quad &\frac{R'I}{e}=M_n, \text{ when } \frac{P}{W} \text{ is } < \frac{l_3}{l_1} \end{aligned}\right\} \quad (6)$$

See eqs. (3) and (5) for M_c and M_n

If either P, W, l_3, or l_1 is the unknown quantity sought, the criterion of (6) cannot be applied, and we $\therefore$ use both equations in (6) and then discriminate between the two results.

The greatest shear is $J_m = R_1$, in Fig. 264, where l_2 is $> l_1$.

261. Two Equal Terminal Loads, Two Symmetrical Supports Fig. 265. [Same case as in Fig. 231, § 238]. Neglect weight of beam. The reaction at each support being $= P$, (from symmetry), we have for a free body Om with $x < l_1$

$$Px - \frac{pI}{e} = 0 \ \therefore M = Px \quad (1)$$

while where $x > l_1$ and $< l_1 + l_2$

$$Px - P(x - l_1) - \frac{pI}{e} = 0 \ \therefore M = Pl_1 \quad (2)$$

That is, see (1), M varies directly with x between O and C, while between C and D it is constant. Hence for safe loading

$$\frac{R'I}{e} = M_m \quad i.e., \frac{R'I}{e} = Pl_1 \quad (3)$$



FIG. 265

The construction of the moment diagram is evident from equations (1) and (2).

As for J, the shear, the same free bodies give, from Σ (vert. forces)$=0$.

On OC . $J=P$ . . . (4)
On CD . $J=P-P=zero$ (5)

(4) and (5) might also be obtained from (1) and (2) by writing $J=d\,M \div dx$, but the former method is to be preferred in most cases, since the latter requires M to be expressed as a function of x while the former is applicable for examining separate sections without making use of a variable.

If the beam is an I-beam, the fact that J is zero anywhere on $C\,D$ would indicate that we may dispense with a web along $C\,D$ to unite the two flanges; but the lower flange being in compression and forming a "long column" would tend to buckle out of a straight line if not stayed by a web connection with the other, or some equivalent bracing.

262. Uniform Load over Part of the Span. Two End Supports. Fig. 266. Let the load $= W$, extending from one support over a portion $= c$, of the span, (on the left, say,) so that $W=wc$, w being the load per unit of length. Neglect weight of beam. For a free body Om of any length $x < \overline{O\,B}$ (*i.e.* $< c$), $\Sigma\, moms_m=0$ gives

$$\frac{pI}{e}+\frac{wx^2}{2}-R_1x=0 \therefore M=R_1x-\frac{wx^2}{2} \quad . \quad . \quad . \quad (1)$$

which holds good for any section on $O\,B$. As for sections on $B\,C$ it is more simple to deal with the free body $m'C$. of length

$x' < C\,B$ from which we have $M=R_2\,x'$. (2)



FIG. 266.

which shows the moment curve for $B\,C$ to be a straight line DC, tangent at D to the parabola $O'\,D$ representing eq. (1.) (If there were a concentrated load at B, $C\,D$ would meet the tangent at D at an angle instead of coinciding with it; let the student show why, from the shear diagram).

The shear for any value of x on $O\,B$ is:

$$\text{On } O\,B \;.\;.\;.\; J = R_1 - wx \;.\;.\;.\; (3)$$
$$\text{while on } B\,C \;.\;.\;.\; J = R_2 = \text{constant} \;.\; (4)$$

The shear diagram is constructed accordingly.

To find the position of the max. ordinate of the parabola, (and this from previous statements concerning the tangent at the point D must occur on $O\;B$, as will be seen and will $\therefore$ be the M_m for the whole beam) we put $J = 0$ in eq (3) whence

$$x \text{ (for } M_m) = \frac{R_1}{w} = \frac{W}{w}\frac{[l - \frac{c}{2}]}{l} = c - \frac{c^2}{2l} \;.\;.\;. \quad (5)$$

and is less than c, as expected. [The value of $R_1 = \frac{W}{l}(l - \frac{c}{2})$, $= (wc \div l)(l - \frac{c}{2})$, (the whole beam free) has been substituted]. This value of x substituted in eq. (1) gives

$$M_m = (1 - \tfrac{1}{2}\tfrac{c}{l})^2 \cdot \tfrac{1}{2} \cdot Wc \therefore \frac{R'I}{e} = \tfrac{1}{2}[1 - \tfrac{1}{2} \cdot \frac{c}{l}]^2 Wc \;.\;.\;.\; (6)$$

is the equation for safe loading.

The max. shear J_m is found at O and is $= R_1$, which is evidently $> R_2$, at C.

263. Uniform Load Over Whole Length With Two Symmetrical Supports. Fig. 267.—With the notation expressed in the figure, the following results may be obtained, after having divided the length of the beam into three parts for separate treatment as necessitated by the external forces, which are the distributed load W, and and the two reactions, each $= \frac{1}{2} W$. The moment curve is made up of parts of three distinct parabolas, each with its axis vertical. The central parabola may sink below the horizontal axis of reference if the supports are far enough apart, in which case (see Fig.) the elastic curve of the beam itself becomes concave upward between the points E and F of "contrary flexure." At each of these points the moment must be zero, since the radius of curvature is ∞ and $M = EI \div \rho$ (see § 231) at any section; that is, at these points the moment curve crosses its horizontal axis.



FIG. 267.

As to the location and amount of the max. moment M_m, inspecting the diagram we see that it will be either at H, the middle, or at both of the supports B and C (which from symmetry have equal moments), i.e., (with l = total length,)

$$M_m \left[\text{and } \therefore \frac{R'I}{e}\right] = \begin{cases} \text{either } \dfrac{W}{2l}\left[\tfrac{1}{4}l_2^2 - l_1^2\right] \text{ . . . . . at } H \\ \text{or } \quad \dfrac{W}{2l} l_1^2 \text{ . . . . . at } B \text{ and } C \end{cases}$$

according to which is the greater in any given case; i.e. according as l_2 is $>$ or $< l_1 \sqrt{8}$.

The shear close on the left of $B = wl_1$, while close to the right of B it $= \frac{1}{2} W - wl_1$. (It will be noticed that in this case since the beam *overhangs*, beyond the support, the shear near the support is not equal to the reaction there, as it was in some preceding cases.)

$$\text{Hence } J_m = \left\{ \begin{matrix} wl_1 \\ \frac{1}{2} W - wl_1 \end{matrix} \right\} \text{ according as } l_1 \gtrless \tfrac{1}{4} l$$

264. Hydrostatic Pressure Against a Vertical Plank.—From elementary hydrostatics we know that the pressure, per unit area, of quiescent water against the vertical side of a tank, varies directly with the depth, x, below the surface, and equals the weight of a prism of water whose altitude $= x$, and whose sectional area is unity. See Fig. 268.



FIG. 268.

The plank is of rectangular cross section, its constant breadth, $= b$, being $\perp$ to the paper, and receives no support except at its two extremities, O and B, *O being level with the water surface.* The loading, or pressure, *per unit of length of the beam*, is here *variable* and, by above definition, is $= w = \gamma x b$, where γ = weight of a cubic unit (i.e. the *heaviness*, see § 7) of water, and $x = Om$ = depth of any section m below the surface. The hydrostatic pressure on $dx = wdx$. These pressures for equal dx's, vary as the ordinates of a triangle OR_1B.

Consider Om free. Besides the elastic forces of the exposed section m, the forces acting are the reaction R_0, and the triangle of pressure OEm. The total of the latter is

$$W_x = \int_0^x wdx = \gamma b \int_0^x xdx = \gamma b \frac{x^2}{2} \ldots\ldots \qquad (1)$$

and the sum of the moments of these pressures about m is equal to that of their resultant (= their sum, since they are parallel) about m, and $\therefore = \gamma b \frac{x^2}{2} \cdot \frac{x}{3}$

[From (1) when $x = l$, we have for the total water pressure on the beam $W_1 = \gamma b \frac{l^2}{2}$ and since one-third of this will be borne at O we have $R_0 = \frac{1}{6} \gamma b l^2$.]

Now putting Σ(moms. about the neutral axis of m)$=0$, for Om free, we have

$$R_0 x - W_x \cdot \frac{x}{3} - \frac{pI}{e} = 0 \therefore M = \tfrac{1}{6}\gamma b (l^2 x - x^3) \quad \ldots\ldots\ldots \quad (2)$$

(which holds good from $x = 0$ to $x = l$). From Σ (horiz. forces) $= 0$ we have also the shear

$$J = R_0 - W_x = \tfrac{1}{6} \gamma b (l^2 - 3x^2) \quad \ldots\ldots \quad (3)$$

as might also have been obtained by differentiating (2), since $J = dM \div dx$. By putting $J = 0$ (§ 240, corollary) we have for a max. M, $x = l \div \sqrt{3}$, which is less than l and hence is applicable to the problem. Substitute this in eq. 2, and reduce, and we have

$$\frac{R'I}{e} = M_m, \text{ i.e. } \frac{R'I}{e} = \frac{1}{9} \cdot \frac{1}{\sqrt{3}} \cdot \gamma b l^3 \quad \ldots\ldots \quad (4)$$

as the equation for safe loading.

265. Example.—If the thickness of the plank is h, required $h = ?$, if R' is taken $= 1{,}000$ lbs. per sq. in. for timber (§ 251), and $l = 6$ feet. For the *inch-pound-second* system of units, we must substitute $R' = 1{,}000$; $l = 72$ *inches*; $\gamma = 0.036$ lbs. per cubic inch (heaviness of water in this system of units); while $I = bh^3 \div 12$, (§ 247), and $e = \frac{1}{2} h$. Hence from (4) we have

$$\frac{1000\, bh^3}{12 \times \frac{1}{2} h} = \frac{0.036 b \times 72^3}{9\sqrt{3}}, \therefore h^2 = 5.16 \therefore h = 2.27 \text{ in.}$$

It will be noticed that since x for $M_m = l \div \sqrt{3}$, and not $\frac{2}{3} l$, M_m does not occur in the section opposite the resultant of the water pressure; see Fig. 268. The shear curve is a parabola here; eq. (3).

266. Flat Circular Plate, Homogeneous and of Uniform Thickness, Supported all Round its Edge and Subjected to Uniform Fluid Pressure of w lbs. per sq. in. A strict treatment of this case being very complicated, an approximate method, due to Prof. C. Bach, will be presented.* Fig. 269 shows a top view of the circular plate, in a horizontal position and covering a circular opening, its edge being supported continuously on the edge of the opening (but not clamped to it). Let the radius of the plate be r and its thickness h. Under the plate is the atmosphere, while on its upper surface, acting uniformly over the whole of that surface, is a fluid pressure whose *excess* over that of the atmosphere is w lbs./sq. in. The particles near the upper surface are under compressive stress, which is obviously greater near the center of the circle; those near the lower surface are in tension.



Fig. 269.



Fig. 269a.

Let now the half-plate, *CODB*, (cutting along the diameter *CD*) be considered as a "free body" in Fig. 269*a*; the tensile and compressive stresses in the section *COD* being assumed to form a stress-couple, as in previous case of flexure, the unit-stress varying as the distance from the middle of the thickness, with the stress in the outermost fiber denoted by p. Then the moment of this couple will be written $pI \div e$, as before, where $e = \frac{1}{2}h$ and $I = 2rh^3 \div 12$. On the upper surface of the free body we find a total pressure of $\frac{1}{2}w\pi r^2$ lbs., covering a semicircular *surface;* so that (p. 22) the distance of the resultant from O is $4r \div 3\pi$. The upward reaction from the supporting *edge* is also $\frac{1}{2}w\pi r^2$ lbs., but its resultant acts $2r/\pi$ in. from O (center of gravity of a semicircular "wire," p. 20). Taking moments, then, about O we have

$$\frac{w\pi r^2}{2}\left[\frac{2r}{\pi} - \frac{4r}{3\pi}\right] = \frac{prh^2}{3}; \text{ or, } w = \frac{h^2}{r^2}p \quad . \quad . \quad . \quad . \quad (0)$$

* Elasticitaet und Festigkeit, by C. Bach; Berlin, 1898.

Notwithstanding the imperfections of this analysis, the experimental work of Prof. Bach shows that a modification of eq. (0), viz. :—

$$w = \frac{5}{6} \cdot \frac{h^2}{r^2} \cdot R', \quad \ldots \ldots \quad (1)$$

may be used with safety for the design of a plate under these circumstances; R', a safe unit working stress for the material, having been substituted for p.

For example, let the plate (e.g., cylinder-head of a locomotive) be of mild steel with $h = 1$ in. and $r = 8$ in. Putting $R' = 16{,}000$ lbs. / sq. in., we have from eq. (1) a safe $w = \frac{5}{6}\ (16000) \times (1 \div 8)^2 = 208$ lbs. per sq. in.

[N.B. If the plate is *clamped* all round the edge, we may write $\frac{5}{4}$ instead of the $\frac{5}{6}$. (Bach.)]

266a. Homogeneous Circular Plate of Uniform Thickness, h, Supported all Round the Edge, with Concentrated Load (P lbs.) in Center. By the same method as before we may here derive $P = \frac{1}{3}\pi h^2 p$; but from his experiments in this case Prof. Bach concludes that the formula for safe design should be written

$$P = \frac{1}{5}\pi h^2 R'. \quad \ldots \ldots \quad (2)$$

It is seen from eq. (2) that the value of P is *independent of the radius of the plate;* depending only on the material and the thickness, h.

266b. Homogeneous Elliptical and Rectangular Plates of Constant Thickness, h, Supported all Round the Periphery. According to Prof. Bach's approximate analysis, as supplemented by his experimental researches, we may use the following formulæ for



FIG. 269*b*.

safe design of elliptical and rectangular plates, supported (not clamped) around the whole periphery. See Fig. 269*b* for notation of dimensions; h being the uniform thickness in each

case, and a being $> b$. R' = max. safe unit stress for the material.

For the **elliptical plate** under **uniformly distributed pressure** (over whole area) of w lbs. / sq. in., denoting the ratio $b \div a$ by m, we have

$$w = \tfrac{5}{3}\,(1 + m^2) \cdot \frac{h^2}{b^2} \cdot R'; \quad \ldots\ldots (3)$$

and under a *central concentrated load* of P lbs.,

$$P = \frac{3\pi}{8m} \cdot \frac{3 + 2m^2 + 3m^4}{8 + 4m^2 + 3m^4} \cdot h^2 R'. \quad \ldots\ldots (4)$$

(N.B. If the edge is clamped down all round we may use values of w and P about 50 per cent. greater than the above.)

With **rectangular plates** under a **uniformly distributed pressure,** denoting the ratio $b \div a$ by m, we have

$$w = \frac{9}{5}(1 + m^2) \frac{h^2}{b^2} \cdot R' \quad \ldots\ldots (5)$$

and for a concentrated central load P, with n denoting the ratio $a \div b$,

$$P = \frac{1}{3n}(1 + n^2) \cdot h^2 R' \quad \ldots\ldots (6)$$

In the particular case of the **square plate**, the side of the square being a, eqs. (5) and (6) reduce to

(uniform pressure) $$w = 3.6 \frac{h^2}{a^2} \cdot R'; \quad \ldots\ldots (7)$$

(central load) $$P = \frac{2}{3} h^2 R' \quad \ldots\ldots (8)$$

266c. Homogeneous Flat Circular Plate, of Uniform Thickness, used as Piston of an Engine. In such a case we have fluid pressures on both sides of the plate or disc, neither of which is necessarily one atmosphere; while at the center we have acting the concentrated pull or thrust, P lbs., of the piston rod. (Frictional forces around the edge may be disregarded.) If w denote the greatest difference between the (uniform) fluid pressures (per sq. in.) on the two sides, we may write (according to Grashof's analysis, as quoted by Unwin), for safe design in this case: —

$$w = \frac{6}{5} \cdot \frac{h^2}{r^2} \cdot R'. \quad \ldots\ldots (9)$$

(R', h, and r, have the same meaning as before.)

267. Resilience of Beam With End Supports.—Fig. 270. If a mass whose weight is G (G large compared with that of beam) be allowed to fall freely through a height $= h$ upon the centre of a beam supported at its extremities, the pressure P felt by the beam increases from zero at the first instant of contact up to a maximum P_m, as already stated in §233*a*, in which the equation was derived, d_m being small compared with h,



Fig. 270.

$$Gh = \frac{1}{96} \cdot \frac{P_m^2 l^3}{EI} \quad . \quad . \quad . \quad (a)$$

The elastic limit is supposed not passed. In order that the maximum normal stress in any outer fibre shall at most be $= R'$, a safe value, (see table §251) we must put $\frac{R'I}{e} = \frac{P_m l}{4}$ [according to eq. (2) §241,] i.e. in equation (*a*) above, substitute $P_m = [4\,R'I] \div le$, which gives

$$Gh = \tfrac{1}{6} \cdot \frac{R'^2 Il}{Ee^2} = \tfrac{1}{6} \cdot \frac{R'^2}{E} \cdot \frac{k^2}{e^2} \cdot Fl = \tfrac{1}{6} \cdot \frac{R'^2}{E} \cdot \frac{k^2}{e^2} V \quad (b)$$

having put $I = Fk^2$ (k being the radius of gyration §85) and $Fl = V$ the volume of the (prismatic) beam. From equation (*b*) we have the *energy*, Gh, (in ft.-lbs., or inch-lbs.) of the vertical blow at the middle which the beam of Fig. 270 will safely bear, and any one unknown quantity can be computed from it, (but the mass of G should not be small compared with that of the beam.)

The energy of this safe impact, for two beams of the same material and similar cross-sections (similarly placed), is seen to be proportional to their *volumes;* while if furthermore their cross-sections are the *same* and similarly placed, the safe Gh is proportional to their *lengths.* (These same relations hold good, approximately, beyond the elastic limit.)

It will be noticed that the last statement is just the re-

verse of what was found in §245 for static loads, (the pressure at the centre of the beam being then equal to the weight of the safe load); for there the longer the beam (and ∴ the span) the less the safe load, in inverse ratio. As appropriate in this connection, a quotation will be given from p. 186 of "The Strength of Materials and Structures," by Sir John Anderson, London, 1884, viz.:

"It appears from the published experiments and statements of the Railway Commissioners, that a beam 12 feet long will only support ½ of the load that a beam 6 feet long of the same breadth and depth will support, but that it will bear double the weight suddenly applied, as in the case of a weight falling upon it," (from the *same height*, should be added); "or if the same weights are used, the longer beam will not break by the weight falling upon it unless it falls through twice the distance required to fracture the shorter beam."

268. Combined Flexure and Torsion. Crank Shafts. Fig. 271. Let O_1B be the crank, and NO_1 the portion *projecting* beyond the nearest bearing N. P is the pressure of the connecting-rod against the crank-pin at a definite instant, the rotary motion being uniform. Let a= the perpendicular dropped from the axis OO_1 of the shaft upon P, and l= the distance of P, along the axis OO_1 from the cross-section NmN' of the shaft, close to the bearing. Let NN' be a diameter of this section, and parallel to a. In considering the portion NO_1B free, and thus exposing the circular section NmN', we may assume that the stresses to be put in on the elements of this surface are the tensions (above NN') and the compressions (below NN') and shears ⊓ to NN', due to the bending action of P; and the shearing stress tan-



FIG. 271.

gent to the circles which have O as a common centre, and pass through the respective dF's or elementary areas, these latter stresses being due to the twisting action of P.

In the former set of elastic forces let $p =$ the tensile stress per unit of area in the small parallelopipedical element m of the helix which is furthest from NN' (the neutral axis) and $I =$ the moment of inertia of the circle about NN'; then taking moments about NN' for the free body, (disregarding the motion) we have as in cases of flexure (see §239)

$$\frac{pI}{r} = Pl \text{; i.e., } p = \frac{Plr}{I} \quad . \quad . \quad (a)$$

[None of the shears has a moment about NN'.] Next taking moments about OO_1, (the flexure elastic forces, both normal and shearing, having no moments about OO_1) we have as in torsion (§216)

$$\frac{p_s I_p}{r} = Pa \text{; i.e., } p_s = \frac{Par}{I_p} \quad . \quad . \quad (b)$$

in which p_s is the shearing stress per unit of area, in the torsional elastic forces, on any outermost dF, as at m; and I_p the polar moment of inertia of the circle about its centre O.

Next consider free, in Fig. 272, a small parallelopiped taken from the helix at m (of Fig. 271.) The stresses [see §209] acting on the four faces ⌐ to the paper in Fig. 272 are there represented, the dimensions (infinitesimal) being n ‖ to NN', b ‖ to OO_1, and d ⌐ to the paper in Fig. 272.



Fig. 272.



Fig. 273.

By altering the ratio of b to n we may make the angle θ what we please. It is now proposed to consider free the triangular prism, GHT, to find the intensity of normal stress q, per unit of area, on the diagonal plane GH, (of length $=c$,) which is a bounding face of that triangular prism. See Fig. 273. By writing Σ (compons. in direction of normal to GH)$=0$, we shall have, transposing,

$$qcd = pnd \sin\theta + p_s bd \sin\theta + p_s nd \cos\theta\,;$$ and solving for q

$$q = p\frac{n}{c}\sin\theta + p_s\left[\frac{b}{c}\sin\theta + \frac{n}{c}\cdot\cos\theta\right]; \quad . \quad (1)$$

but $n : c = \sin\theta$ and $b : c = \cos\theta$ $\therefore$

$$q = p\sin^2\theta + p_s 2\sin\theta\cos\theta \quad . \quad . \quad (2)$$

This may be written (see eqs. 63 and 60, O. W. J. Trigonometry)

$$q = \tfrac{1}{2}p(1-\cos 2\theta) + p_s \sin 2\theta \quad . \quad . \quad (3)$$

As the diagonal plane GH is taken in different positions (i.e., as θ varies), this tensile stress q (lbs. per sq. in. for instance) also varies, being a function of θ, and its max. value may be $> p$. To find θ for q max. we put

$$\frac{dq}{d\theta}, = p\sin 2\theta + 2p_s\cos 2\theta, \quad . \quad . \quad (4)$$

$=0$, and obtain: $\tan[2(\theta \text{ for } q \text{ max})] = -\dfrac{2p_s}{p}$ . . . (5)

Call this value of θ, θ'. Since $\tan 2\theta'$ is negative, $2\theta'$ lies either in the second or fourth quadrant, and hence

$$\sin 2\theta' = \pm\frac{2p_s}{\sqrt{p^2+4p_s^2}} \quad \text{and} \quad \cos 2\theta' = \mp\frac{p}{\sqrt{p^2+4p_s^2}} \quad (6)$$

[See equations 28 and 29 Trigonometry, O. W. J.] The

upper signs refer to the second quadrant, the lower to the fourth. If we now differentiate (4), obtaining

$$\frac{d^2q}{d\theta^2} = -2p\cos 2\theta - 4p_s \sin 2\theta \quad . \quad . \quad . \quad (7)$$

we note that if the sine and cosine of the $[2\theta']$ of the 2nd quadrant [upper signs in (6)] are substituted in (7) the result is *negative*, indicating a maximum; that is, q is a maximum for $\theta =$ the θ' of eq. (6) *when the upper signs are taken* (2nd quadrant). To find q max., then, put θ' for θ in (3) substituting from (6) (upper signs). We thus find*

$$q \text{ max} = \tfrac{1}{2}[p + \sqrt{p^2 + 4p_s^2}] \quad . \quad . \quad (8)$$

A similar process, taking components *parallel* to *GH*, Fig. 273, will yield q_s max., i.e., the max. shear per unit of area, which for a given p and p_s exists on the diagonal plane *GH* in any of its possible positions, as θ varies. This max. shearing stress is

$$q_s \text{ max} = \tfrac{1}{2}\sqrt{p^2 + 4p_s^2} \quad . \quad . \quad (9)$$

In the element diametrically opposite to m in Fig. 271, p is compression instead of tension; q maximum will also be compression but is numerically the same as the q max. of eq. 8.

269. Example.—In Fig. 271 suppose $P=2$ tons $= 4{,}000$ lbs., $a=6$ in., $l=5$ in., and that the shaft is of wrought iron. Required its radius that the max. tension or compression may not exceed $R'=12{,}000$ lbs. per sq. in.; nor the max. shear exceed $S'=7{,}000$ lbs. per sq. in. That is, we put $q=12{,}000$ in eq. (8) and solve for r: also $q_s=7{,}000$ in (9) and solve for r. The greater value of r should be taken. From equations (*a*) and (*b*) we have (see §§ 219 and 247 for I_p and I)

* According to the conceptions of § 405*b*, safe design would require that we put the max. "*strain*" in this case equal to a safe value, as determined by simple tensile or compressive tests. Here the max. strain (tensile) is $\varepsilon = [\frac{5}{8}p + \frac{5}{8}\sqrt{p^2 + 4p_s^2}] \div E$. (Grashof's method.)

$$p=\frac{4Pl}{\pi r^3} \text{ and } p_s=\frac{2Pa}{\pi r^3}$$

which in (8) and (9) give

$$\text{max. } q=\tfrac{1}{2}\frac{P}{\pi r^3}\left[4l+\sqrt{(4l)^2+4(2a)^2}\right] \quad . \quad . \quad (8a)$$

and $$\text{max. } q_s=\tfrac{1}{2}\frac{P}{\pi r^3}\sqrt{(4l)^2+4(2a)^2} \quad . \quad . \quad . \quad (9a)$$

With max. q=12,000, and the values of P, a, and l, already given, (units, inch and pound) we have from (8a), r^3=2.72 cubic inches $\therefore$ r=1.39 inches.

Next, with max. q_s=7,000; P, a, and l as before; from (9a), r^3=2.84 cubic inches $\therefore$ r=1.41 inches.

The latter value of r, 1.41 inches, should be adopted. It is here supposed that the crank-pin is in such a position (when P=4,000 lbs., and a=6 in.) that q max. (and q_s max.) are greater than for any other position; a number of trials may be necessary to decide this, since P and a are different with each new position of the connecting rod. If the shaft and its connections are exposed to shocks, R' and S' should be taken much smaller.

270. **Another Example** of combined torsion and flexure is shown in Fig. 274. The work of the working force P_1(vertical cog-pressure) is expended in overcoming the resistance (another vertical cog-pressure) Q_1.



FIG. 274.

That is, the rigid body consisting of the two wheels and shaft is employed to transmit power, at a uniform angular velocity, and since it is symmetrical about its axis of rotation the forces acting on it, considered free, form a balanced system. (See § 114). Hence given P_1 and the various geometrical quan-

tities a_1, b_1, etc., we may obtain Q_1, and the reactions P_0 and P_B, in terms of P_1. The greatest moment of flexure in the shaft will be either $P_0 l_1$, at C; or $P_B l_3$, at D. The portion CD is under torsion, of a moment of torsion $= P_1 a_1 = Q_1 b_1$. Hence we proceed as in the example of § 269, simply putting $P_0 l_1$ (or $P_B l_3$, whichever is the greater) in place of Pl, and $P_1 a_1$ in place of Pa. We have here neglected the weight of the shaft and wheels. If Q_1 were an *upward* vertical force and hence on the same side of the shaft as P_1, the reactions P_0 and P_B would be less than before, and one or both of them might be reversed in direction.

270a. Web of I-Beam. Maximum Stresses on an Oblique Plane.—The analysis of pp. 315, 316, etc., also covers the case of an element of the web of a horizontal I-beam under stress, when this element is taken near the point of junction with the flange. Supposing that the thickness of web has already been designed such that the shearing stress on the vertical (and therefore also on the horizontal) edges of such an element is at rate of 8000 lbs. per sq. inch; and that the horizontal tension at each end of this element (since it is not far from the outer fibre of the whole section) is at rate of 10,000 lbs. per sq. in.; we note that Fig. 272 gives us a side view of this element, with $p_s = 8000$, and $p = 14.000$, lbs. per sq. inch. GT is the lower edge of the upper flange, corresponding (in an end view) to the point n in Fig. 258 on p. 290. (We here suppose the upper flange to be in tension; of course, an illustration taken from the compression side would do as well.)

Substitution in equations (8) and (9) of p. 317 results in giving as maximum stresses on internal oblique planes:

q max. = 17,630 lbs. per sq. in. tension;

and q_s max. = 10,630 " " " " shearing.

These two values are seen to be considerably in excess of the respective safe values for shearing and tensile stresses in the case of structural steel, and the necessity is therefore emphasized of adopting values for shearing stress in webs somewhat lower than the 8000 lbs./in.^{2} used above; to avoid the occurrence of excessive stress on internal oblique planes. See p. 291.

CHAPTER IV.

FLEXURE, CONTINUED.

CONTINUOUS GIRDERS.

271. Definition.—A continuous girder, for present purposes, may be defined to be a loaded straight beam supported in *more than two points*, in which case we can no longer, as heretofore, determine the reactions at the supports from simple Statics alone, but must have recourse to the equations of the several elastic curves formed by its neutral line, which equations involve directly or indirectly the reactions sought; the latter may then be found as if they were constants of integration. Practically this amounts to saying that the reactions depend on the manner in which the beam bends; whereas in previous cases, with only two supports, the reactions were independent of the forms of the elastic curves (the flexure being slight, however).

As an **Illustration**, if the straight beam of Fig. 275 is placed on three supports O, B, and C, at the same level, the reactions of these supports seem at first sight indeterminate; for on considering the whole beam free, we have three unknown quantities and only two equations, viz: Σ (vert. compons.) $= 0$ and Σ (moms. about some point) $= 0$. If now O be gradually lowered, it receives less and less pres-



FIG. 275.

sure, until it finally reaches a position where the beam barely touches it; and then O's reaction is zero, and B and C support the beam as if O were not there. As to how low O must sink to obtain this position, depends on the stiffness and load of the beam. Again, if O be raised above the level of B and C it receives greater and greater pressure, until the beam fails to touch one of the other supports. Still another consideration is that if the beam were tapering in form, being stiffest at O, and pointed at B and C, the three reactions would be different from their values for a prismatic beam. It is therefore evident that for more than two supports the values of the reactions depend on the relative heights of the supports and upon the form and elasticity of the beam, as well as upon the load. The circumstance that the beam is made *continuous* over the support O, instead of being cut apart at O into two independent beams, each covering its own span and having its own two supports, shows the significance of the term "continuous girder."

All the cases here considered will be comparatively simple, from the symmetry of their conditions. The beams will all be prismatic, and all external forces (i.e. loads and reactions) perpendicular to the beam and in the same plane. All supports at the same level.

272. Two Equal Spans; Two Concentrated Loads, One in the Middle of Each Span. Prismatic Beam.—Fig. 275. Let each half-span $= \frac{1}{2}\ l$. Neglect the weight of the beam. Required the reactions of the three supports. Call them P_B, P_O and P_C. From symmetry $P_B = P_C$, and the tangent to the elastic curve at O is horizontal; and since the supports are *on a level* the deflection of C (and B) below O's tangent is zero. The *separate* elastic curves OD and DC have a common slope and a common ordinate at D.

For the equation of OD, make a section n anywhere between O and D, considering nC a free body. Fig. 276 (*a*)



FIG. 276.

with origin and axes as there indicated.* From Σ (moms about neutral axis of n) $= 0$ we have (see § 231)

$$EI\frac{d^2y}{dx^2} = P(\tfrac{1}{2}l - x) - P_c(l - x) \quad . \quad . \quad . \quad (1$$

$$\therefore \quad EI\frac{dy}{dx} = P\left(\tfrac{1}{2}lx - \frac{x^2}{2}\right) - P_c\left(l\,x - \frac{x^2}{2}\right) + (C=0) \quad . \quad (2)$$

The constant $= 0$, for at O both x, and $dy \div dx$, $= 0$.

Taking the x-anti-derivative of (2) we have

$$EIy = P\left(\frac{lx^2}{4} - \frac{x^3}{6}\right) - P_c\left[\frac{lx^2}{2} - \frac{x^3}{6}\right] \quad . \quad . \quad (3)$$

Here again the constant is zero since at O, x and y both $=0$. (3) is the equation of OD, and allows no value of $x < 0$ or $> \frac{l}{2}$. It contains the unknown force P_c.

For the equation of DC, let the variable section n be made anywhere between D and C, and we have (Fig. 276 (*b*); x may now range between $\frac{1}{2}l$ and l)

$$EI\frac{d^2y}{dx^2} = -P_c(l - x) \quad . \quad . \quad . \quad . \quad . \quad (4)$$

$$\therefore \quad EI\frac{dy}{dx} = -P_c\left(lx - \frac{x^2}{2}\right) + C' \quad (5)'$$

To determine C', put $x = \frac{1}{2}l$ both in (5)′ and (2), and equate the results (for the two curves have a common tangent line at D) whence $C' = \frac{1}{8}\,Pl^2$

$$\therefore \quad EI\frac{dy}{dx} = \tfrac{1}{8}\,Pl^2 - P_c\left(lx - \frac{x^2}{2}\right) \quad . \quad . \quad . \quad (5)$$

* These are such that XOY is our "first quadrant"; in which, for points in a part of a curve convex toward the axis of X, d^2y/dx^2 is essentially positive; and *vice versa*. It will be seen that both eqs. (1) and (4) are on this basis. They must be on the *same basis*; otherwise, later comparisons of equations would result in error.

Hence $EIy = \frac{1}{8} Pl^2x - P_c\left[\frac{lx^2}{2} - \frac{x^3}{6}\right] + C'' \quad . \quad . \quad (6)'$

At D the curves have the same y, hence put $x = \frac{l}{2}$ in the right hand member both of (3) and (6)′, equating results, and we derive $C'' = -\frac{1}{48} Pl^3$

$$\therefore \quad EIy = \frac{1}{8} Pl^2x - P_c\left[\frac{lx^2}{2} - \frac{x^3}{6}\right] - \frac{1}{48} Pl^3 \quad . \quad . \quad (6)$$

which is the equation of DC, but contains the unknown reaction P_c. To determine P_c we employ the fact that O's tangent passes through C, (supports on *same level*) and hence when $x = l$ in (6), y is known to be zero. Making these substitutions in (6) we have

$$0 = \frac{1}{8} Pl^3 - \frac{1}{3} P_c l^3 - \frac{1}{48} Pl^3 \therefore P_c = \frac{5}{16} P$$

From symmetry P_B also $= \frac{5}{16} P$, while P_0 must $= \frac{22}{16} P$, since $P_B + P_O + P_C = 2\,P$ (whole beam free). [NOTE.—If the supports were not on a level, but if, (for instance) the middle support O were a small distance $= h_0$ below the level line joining the others, we should put $x = l$ and $y = -h_0$ in eq. (6), and thus obtain $P_B = P_C = \frac{5}{16}\ P + 3EI\frac{h_0}{l^3}$, which depends on the material and form of the prismatic beam and upon the length of one span, (whereas with supports *all on a level*, $P_B = P_C = \frac{5}{16}\ P$ is independent of the material and form of the beam so long as it is homogeneous and prismatic.) If P_0, which would then $= \frac{22}{16}\ P - 6\ EI\ (h_0 \div l^3)$, is found to be *negative*, it shows that O requires a support from above, instead of below, to cause it to occupy a position h_0 below the other supports, i.e. the beam must be "latched down" at O.]

The *moment diagram* of this case can now be easily constructed; Fig. 277. For any free body nC, n lying in DC, we have



Fig. 277.

$$M=\tfrac{5}{16}Px,$$

i.e., varies directly as x, until x passes D when, for any point on DO,

$$M=\tfrac{5}{16}Px-P(x-\tfrac{l}{2})$$

which is $=0$, (point of inflection of elastic curve) for $x=\tfrac{8}{11}l$ (note that x is measured from C in this figure) and at O, where $x=l$, becomes $-\tfrac{6}{32}Pl$

$$\therefore M_O=-\tfrac{6}{32}Pl;\ M_G=0;\ M_D=\tfrac{5}{32}Pl;\text{ and } M_C=0$$

Hence, since M max. $=\tfrac{6}{32}Pl$, the equation for safe loading is

$$\frac{R'I}{e}=\frac{6}{32}Pl \quad . \quad . \quad . \quad . \quad (7)$$

The shear at C and anywhere on $CD=\tfrac{5}{16}P$, while on DO it $=\tfrac{11}{16}P$ in the opposite direction

$$\therefore J_m=\tfrac{11}{16}P \quad . \quad . \quad . \quad . \quad (8)$$

The moment and shear diagrams are easily constructed, as shown in Fig. 277, the former being symmetrical about a vertical line through O, the latter about the *point* O'' Both are bounded by right lines.

273. Two Equal Spans. Uniformly Distributed Load Over Whole Length. Prismatic Beam. —Fig. 278. *Supports B, O, C, on a level.* Total load $=2W=2wl$ and may include that of the beam; w is constant. As before, from symmetry $P_B=P_C$, the unknown reactions at the extremities.



Fig. 278.

Let $On=x$; then with nC free, Σ moms. about $n=0$ gives

$$EI\frac{d^2y}{dx^2}=w(l-x)(\frac{l-x}{2})-P_c(l-x)=\frac{w}{2}[l^2-2lx+x^2]-P_c(l-x) \quad (1)$$

$$\therefore EI\frac{dy}{dx}=\frac{w}{2}\left[l^2x-lx^2+\frac{x^3}{3}\right]-P_c\left[lx-\frac{x^2}{2}\right]+[\text{Const}=0] \quad (2)$$

[Const.=0 for at O both $dy \div dx$ the slope, and x, are =0]

$$\therefore EIy=\frac{w}{2}[\tfrac{1}{2}l^2x^2-\tfrac{1}{3}lx^3+\tfrac{1}{12}x^4]-P_c[\tfrac{1}{2}lx^2-\tfrac{1}{6}x^3]+(C=0) \quad (3)$$

[Const. =0 for at O both x and y are =0]. Equations (1), (2), and (3) admit of any value of x from 0 to l, i.e., hold good for any point of the elastic curve OC, the loading on which follows a continuous law (viz.: w= constant). But when $x=l$, i.e., at C, y is known to be equal to zero, since O, B and C are on the axis of X, (tangent at O). With these values of x and y in eq. (3) we have

$$0=\frac{w}{2}\cdot\frac{l^4}{4}-\tfrac{1}{3}P_cl^3 \therefore P_c=\tfrac{3}{8}wl=\tfrac{3}{8}W$$

$$\therefore P_B=\tfrac{3}{8}W \text{ and } P_0=2W-2P_c=\tfrac{10}{8}W$$

The Moment and Shear Diagrams can now be formed since all the external forces are known. In Fig. 279 measure x from C. Then in any section n the moment of the "stress-couple" is



Fig. 279.

$$M=\tfrac{3}{8}Wx-\frac{wx^2}{2} \quad . \quad (1)$$

which holds good for any value of x on CO, i.e., from $x=0$ up to $x=l$. By inspection it is seen that for $x=0$, $M=0$; and also for $x=\frac{3}{4}l$, $M=0$, at the *inflection point* G, beyond which, toward O, the upper fibres are in tension

the lower in compression, whereas between C and G they are vice versâ. As to the greatest moment to be found on CG, put $dM \div dx = 0$ and solve for x. This gives

$$\tfrac{3}{8}W - wx = 0 \therefore [x \text{ for } M \text{ max.}] = \tfrac{3}{8}l \quad . \quad (2)$$

which in eq. (1) gives

$$M_N \text{ (at } N \text{, see figure)} = +\tfrac{9}{128}Wl \quad . \quad . \quad (2)$$

But this is numerically less than $M_o (= -\tfrac{1}{8}Wl)$ hence the stress in the outer fibre at O being

$$p_o = \tfrac{1}{8}\frac{Wle}{I}, \quad . \quad . \quad . \quad (3)$$

the equation for safe loading is

$$\frac{R'I}{e} = \tfrac{1}{8}Wl \quad . \quad . \quad . \quad . \quad (4)$$

the same as if the beam were cut through at O, each half, of length l, retaining the same load as before [see § 242 eq. (2)]. Hence making the girder continuous over the middle support does not make it any stronger under a uniformly distributed load; but it does make it considerably *stiffer*.

As for the shear, J, we obtain it for any section by taking the x-derivative of M in eq. (1), or by putting Σ(vertical forces) $=0$ for the free body nC, and thus have for any section on CO

$$J = \tfrac{3}{8}W - wx \quad . \quad . \quad . \quad (5)$$

J is zero for $x = \tfrac{3}{8}l$ (where M reaches its calculus maximum M_N; see above) and for $x = l$ it $= -\tfrac{5}{8}W$ which is numerically greater than $\tfrac{3}{8}W$, its value at C. Hence

$$J_m = \tfrac{5}{8}W \quad . \quad . \quad . \quad . \quad (6)$$

The moment curve is a parabola (a separate one for each span), the shear curve a straight line, inclined to the horizontal, for each span.

Problem.—How would the reactions in Fig. 278 be changed if the support O were lowered a (small) distance h_0 below the level of the other two?

274. Prismatic Beam Fixed Horizontally at Both Ends (at Same Level). Single Load at Middle.—Fig. 280. [As usual the beam is understood to be homogeneous so that E is the same at all sections]. The building in, or fixing, of the two ends is supposed to be of such a nature as to cause *no horizontal constraint;* i.e., the beam does not act as a cord or chain, in any manner, and hence the sum of the horizontal components of the stresses in any section is zero, as in all preceding cases of flexure. In other words the neutral axis still contains the centre of gravity of the section and the tensions and compressions are equivalent to a couple (the stress-couple) whose moment is the "moment of flexure."



FIG. 280.

If the beam is conceived cut through close to both wall faces, and this portion of length$=l$, considered free, the forces holding it in equilibrium consist of the downward force P (the load); two upward shears J_o and J_c (one at each section); and two "stress-couples" one in each section, whose moments are M_o and M_c. From symmetry we know that $J_o = J_c$, and that $M_o = M_c$. From $\Sigma Y = 0$ for the free body just mentioned, (but not shown in the figure), and from symmetry, we have $J_o = \frac{1}{2} P$ and $J_c = \frac{1}{2} P$; but to determine M_o and M_c, the form of the elastic curves $O B$ and $B C$ must be taken into account as follows:

Equation of OB, Fig. 280. Σ [mom. about neutral axis of *any* section n on $O B$] $= 0$ (for the free body nC which

has a section exposed at each end, n being the variable section) will give

$$EI\frac{d^2y}{dx^2} = P(\tfrac{1}{2}\,l - x) + M_c - \tfrac{1}{2}\,P\,(l - x) \quad . \quad . \quad (1)$$

[**Note.** In forming this moment equation, notice that M_c is the sum of the moments of the tensions and compressions at C about the neutral axis at n, just as much as about the neutral axis of C; for those tensions and compressions are equivalent to a couple, and hence the sum of their moments is the same taken about any axis whatever ⊥ to the plane of the couple (§32).]

Taking the x-anti-derivative of each member of (1),

$$EI\frac{dy}{dx} = P(\tfrac{1}{2}\,l\,x - \tfrac{1}{2}\,x^2) + M_c\,x - \tfrac{1}{2}\,P(l\,x - \tfrac{1}{2}\,x^2) \quad . \quad (2)$$

(The constant is not expressed, as it is zero). Now from symmetry we know that the tangent-line to the curve $O\,B$ at B is horizontal, *i.e.*, for $x = \tfrac{1}{2}l$, $dy \div dx = 0$, and these values in eq. (2) give us

$$0 = \tfrac{1}{8}\,Pl^2 + \tfrac{1}{2}M_c l - \tfrac{3}{16}Pl^2; \text{ whence } M_c = M_0 = \tfrac{1}{8}\,Pl \quad . \quad (3)$$

Safe Loading. Fig. 281. Having now all the forces which *act as external forces* in straining the beam OC, we are ready to draw the moment diagram and find M_m. For convenience measure x from C. For the free body nC, we have [see eq. (3)]

$$\tfrac{1}{2}\,Px - M_c + \frac{pI}{e} = 0 \therefore M = \tfrac{1}{8}\,Pl - \tfrac{1}{2}Px \quad . \quad . \quad . \quad (4)$$



Fig. 281.

Eq. (4) holds good for any section on CB. By putting $x = 0$ we have $M = M_c = \tfrac{1}{8}\,Pl$; lay off $HC' = M_c$ to scale (so many inch-pounds moment to the inch of paper). At B, for $x = \tfrac{1}{2}\,l$, $M_B = -\tfrac{1}{8}\,Pl$; hence lay off $B'D = \tfrac{1}{8}\,Pl$ on the opposite side of the axis $O'C'$

from HC', and join DH. DK, symmetrical with DH about $B'D$, completes the moment curves, viz.: two right lines. The max. M is evidently $=\frac{1}{8}\,Pl$ and the equation of safe loading

$$\frac{R'I}{e}=\frac{1}{8}\,Pl \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

Hence the beam is twice as strong as if simply supported at the ends, under this load; it may also be proved to be four times as stiff.

The points of inflection of the elastic curve are in the middles of the half-spans, while the max. shear is

$$J_m=\frac{1}{2}P \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (6)$$

275. Prismatic Beam Fixed Horizontally at Both Ends [at Same Level]. Uniformly Distributed Load Over the Whole Length. Fig. 282. As in the preceding problem, we know from symmetry that $J_0=J_c=\frac{1}{2}\,W=\frac{1}{2}\,wl$, and that $M_0=M_c$, and determine the latter quantities by the equation of the curve OC, there being but one curve in the present instance, instead of two, as there is no change in the law of loading between O and C. With nO free, $\Sigma\,(\text{mom}_n)=0$ gives

$$EI\frac{d^2y}{dx^2}=-\frac{1}{2}\,Wx+M_0+\frac{wx^2}{2} \quad . \quad . \quad . \quad . \quad (1)$$

and $\therefore$ $$EI\frac{dy}{dx}=-\frac{1}{2}\,W\frac{x^2}{2}+M_0x+\frac{wx^3}{6}+[C=0] \quad . \quad . \quad (2)$$



Fig. 282.

The tangent line at O being horizontal we have for $x=0, \frac{dy}{dx}=0$, $\therefore C=0$. But since the tangent line at C is also horizontal, we may for $x=l$ put $dy \div dx=0$, and obtain

$$0=-\tfrac{1}{4}Wl^2+M_0l+\tfrac{1}{6}wl^2; \text{ whence } M_0=\tfrac{1}{12}Wl \quad . \quad (3)$$

as the moment of the stress-couple close to the wall at O and at C.

Hence, Fig. 283, the equation of the moment curve (a single continuous curve in this case) is found by putting $\Sigma'(\text{mom}_n)=0$ for the free body nO, of length x, thus obtaining



FIG. 283.

$$\frac{pI}{e}+\tfrac{1}{2}Wx-M_0-\frac{wx^2}{2}=0$$

i.e., $$M=\tfrac{1}{12}Wl+\frac{wx^2}{2}-\tfrac{1}{2}Wx \quad . \quad . \quad . \quad . \quad . \quad (4)$$

an equation of the second degree, indicating a conic. At O, $M=M_0$ of course, $=\frac{1}{12}Wl$; at B by putting $x=\frac{1}{2}l$ in (4), we have $M_B=-\frac{1}{24}Wl$, which is less than M_0, although M_B is the calculus max. (negative) for M, as may be shown by writing the expression for the shear ($J=\frac{1}{2}W-wx$) equal to zero, etc.

Hence $M_m = \frac{1}{12} Wl$, and the equation for *safe loading* is

$$\frac{R'I}{e} = \frac{1}{12} Wl \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

Since (with this form of loading) if the beam were not built in but simply rested on two end supports, the equation for safe loading would be $[R'I \div e] = \frac{1}{8} Wl$, (see §242), it is evident that with the present mode of support it is 50 per cent. stronger as compared with the other; i.e., as regards normal stresses in the outer elements. As regards shearing stresses in the web if it has one, it is no stronger, since $J_m = \frac{1}{2} W$ in both cases.

As to *stiffness* under the uniform load, the max. deflection in the present case may be shown to be only $\frac{1}{5}$ of that in the case of the simple end supports.

It is noteworthy that the shear diagram in Fig. 283 is identical with that for simple end supports §242, under uniform load; while the moment diagrams differ as follows: The parabola $KB'A$, Fig. 283, is identical with that in Fig. 235, but the horizontal axis from which the ordinates of the former are measured, instead of joining the extremities of the curve, cuts it in such a way as to have equal areas between it and the curve, on opposite sides

$$\text{i.e., areas } [KC'H' + AG'O'] = \text{area } H'G'B'$$

In other words, the effect of fixing the ends horizontally is to shift the moment parabola upward a distance $= M_c$ (to scale), $= \frac{1}{12} Wl$, with regard to the axis of reference, $O'B'$, in Fig. 235.

276. Remarks.—The foregoing very simple cases of continuous girders illustrate the means employed for determining the reactions of supports and eventually the max. moment and the equations for safe loading and for deflections When there are more than three supports, with spans of unequal length, and loading of any description, the analysis leading to the above results is much more complicated and tedious, but is considerably simplified

and systematized by the use of the remarkable **theorem of three moments**, the discovery of Clapeyron, in 1857. By this theorem, given the spans, the loading, and the vertical heights of the supports, we are enabled to write out a relation between the moments of each three consecutive supports, and thus obtain a sufficient number of equations to determine the moments at all the supports [p. 641 Rankine's Applied Mechanics.] From these moments the shears close to each side of each support are found, then the reactions, and from these and the given loads the moment at any section can be determined; and hence finally the max. moment M_m, and the max. shear J_m.

The treatment of the general case of continuous girders by *algebraic methods founded on the properties of familiar geometrical figures*, however, is comparatively simple; and will be developed and applied in another part of this book. (See Chap. XII, pp. 485, etc.)

THE DANGEROUS SECTION OF NON-PRISMATIC BEAMS.

277. **Remarks.** By "*dangerous section*" is meant that section (in a given beam under given loading with given mode of support) where p, the normal stress in the outer fibre, at distance e from its neutral axis, is greater than in the outer fibre of any other section. Hence the elasticity of the material will be first impaired in the outer fibre of this section, if the load is gradually increased in amount (but not altered in distribution).

In all preceding problems, the beam being prismatic, I, the moment of inertia, and e were the same in all sections, hence when the equation $\frac{pI}{e} = M$ [§239] was solved for p, giving

$$p = \frac{Me}{I} \quad . \quad . \quad . \quad . \quad (1)$$

we found that p was a max., $= p_m$, for that section whose M was a maximum, since p varied as M, or the moment

of the stress-couple, as successive sections along the beam were examined.

But for a non-prismatic beam I and e change, from section to section, as well as M, and the ordinate of the moment diagram no longer shows the variation of p, nor is p a max. where M is a max. To find the dangerous section, then, for a non-prismatic beam, we express the M, the I, and the e of any section in terms of x, thus obtaining p=func. (x), then writing $dp \div dx = 0$, and solving for x.

278. Dangerous Section in a Double Truncated Wedge. Two End Supports. Single Load in Middle.—The form is shown in Fig. 284. Neglect weight of beam; measure x from one support O. The reaction at each support is $\frac{1}{2} P$. The width of the beam $= b$ at all sections, while its height, v, varies, being $= h$ at O. To express the $e = \frac{1}{2} v$, and the $I = \frac{1}{12} bv^3$ (§247) of any section on OC, in terms of x, conceive the sloping faces of the truncated wedge to be prolonged to their intersection A, at a known distance $= c$ from the face at O. We then have from similar triangles



Fig. 284.

$$v : x + c :: h : c, \therefore v = \frac{h}{c}(x + c) \quad . \quad . \quad (1)$$

$$\text{and } \therefore e = \tfrac{1}{2} \frac{h}{c}(x+c) \text{ and } I = \tfrac{1}{12} b \frac{h^3}{c^3}[x+c]^3 \quad . \quad (2)$$

For the free body nO, $\Sigma(\text{moms.}_n) = 0$ gives

$$\tfrac{1}{2} Px - \frac{pI}{e} = 0 \therefore p = \frac{Pxe}{2I} \quad . \quad . \quad . \quad (3)$$

[That is, the $M = \frac{1}{2} Px$.] But from (2), (3) becomes

$$p = 3P \frac{c^2}{bh^2} \cdot \frac{x}{(x+c)^2}; \text{ and } \frac{dp}{dx} = 3P \frac{c^2}{bh^2} \cdot \frac{(x+c)^2 - 2x(x+c)}{(x+c)^4} \quad (4)$$

By putting $dp \div dx = 0$ we find $x = +c$; showing a

maximum for p (since it will be found to give a negative result on substitution in $d^2p \div dx^2$).

Hence the dangerous section is as far from the support O, as the imaginary edge, A, of the completed wedge, but of course on the opposite side. This supposes that the half-span, $\frac{1}{2}l$, is $> c$; if not, the dangerous section will be at the middle of the beam, as if the beam were prismatic.

Hence, with $\frac{1}{2}l < c$ } the equation for safe loading is: (h' = height at middle) { $\frac{R'bh'^2}{6} = \frac{1}{4}Pl$ (5)

while with $\frac{1}{2}l > c$ } the equation for safe loading is: (put $x=c$ and $p=R'$ in [3]) { $\frac{R'b\,[2h]^2}{6} = \frac{1}{2}Pc$ (6)

(see §239.)

279. Double Truncated Pyramid and Cone. Fig. 285. For



FIG. 285.

the truncated pyramid both width $= u$, and height $= v$, are variable, and if b and h are the dimensions at O, and $c = \overline{OA}$ = distance from O to the imaginary vertex A, we shall have from similar triangles $u = \frac{b}{c}(x+c)$ and $v = \frac{h}{c}(x+c)$. Hence, substituting $e = \frac{1}{2}v$ and $I = \frac{1}{12}uv^3$, in the moment equation

$$\frac{pI}{e} - \frac{Px}{2} = 0, \text{ we have } p = 3P\frac{c^3}{bh^2}\cdot\frac{x}{(x+c)^3} \quad . \quad . \quad (7)$$

$$\therefore \frac{dp}{dx} = 3P\frac{c^3}{bh^2}\cdot\frac{(x+c)^3 - 3x\,(x+c)^2}{(x+c)^6} \quad . \quad . \quad (8)$$

Putting the derivative $=0$, for a maximum p, we have $x = + \frac{1}{2} c$, hence the dangerous section is at a distance $x = \frac{1}{2} c$ from O, and the equation for safe loading is

$$\text{either } \frac{R'b'h'^2}{6} = \frac{1}{4} Pl \ldots \text{ if } \frac{1}{2} l \text{ is } < \frac{1}{2} c \quad \ldots \quad (9)$$

(in which b' and h' are the dimensions at mid-span)

$$\text{or } \frac{R\,(\frac{1}{2} b)\,(\frac{3}{2} h)^2}{6} = \frac{1}{4} Pc \text{ if } \frac{1}{2} l \text{ is } > \frac{1}{2} c \quad \ldots \quad (10)$$

For the **truncated cone** (see Fig. 285 also, on right) where $e =$ the variable radius r, and $I = \frac{1}{4} \pi r^4$, we also have

$$p = [\text{Const.}] \cdot \frac{x}{(x+c)^3} \quad \ldots \quad (11)$$

and hence p is a max. for $x = \frac{1}{2} c$, and the equation for safe loading

$$\text{either } \frac{\pi R' r'^3}{4} = \frac{1}{4} Pl, \text{ for } \frac{1}{2} l < \frac{1}{2} c \quad \ldots \quad (12)$$

(where $r' =$ radius of mid-span section);

$$\text{or } \frac{\pi R' (\frac{3}{2} r_0)^3}{4} = \frac{1}{4} Pc, \text{ for } \frac{1}{2} l > \frac{1}{2} c \quad \ldots \quad (13)$$

(where $r_0 =$ radius of extremity.)

NON-PRISMATIC BEAMS OF "UNIFORM STRENGTH."

280. Remarks. A beam is said to be of "*uniform strength*" when its form, its mode of support, and the distribution of loading, are such that the normal stress p has the same value in all the outer fibres, and thus one element of economy is secured, viz.: that all the outer fibres may be made to do full duty, since under the safe loading, p will be $=$ to R' in all of them. [Of course, in all cases of flexure, the elements between the neutral surface and

the outer fibres being under tensions and compressions less than R' per sq. inch, are not doing full duty, as regards economy of material, unless perhaps with respect to shearing stresses.] In Fig. 265, §261, we have already had an instance of a body of uniform strength in flexure, viz.: the middle segment, CD, of that figure; for the moment is the same for all sections of CD [eq. (2) of that §], and hence the normal stress p in the outer fibres (the beam being prismatic in that instance).

In the following problems the weight of the beam itself is neglected. The general method pursued will be to find an expression for the outer-fibre-stress p, at a *definite* section of the beam, where the dimensions of the section are known or assumed, then an expression for p in the variable section, and equate the two. For clearness the figures are exaggerated, vertically.

281. Parabolic Working Beam. Unsymmetrical. Fig. 286



FIG. 286.

CBO is a working beam or lever, B being the fixed fulcrum or bearing. The force P_o being given we may compute P_c from the mom. equation $P_o l_o = P_c l_1$, while the fulcrum reaction is $P_B = P_o + P_c$. All the forces are ⊓ to the beam. The beam is to have the same width b at all points, and is to be *rectangular* in section.

Required **first**, the proper height h_1, at B, for safety. From the free body BO, of length $= l_o$, we have Σ (moms$_B$) $= 0$; i.e.,

$$\frac{p_B I}{e} = P_o l_o; \text{ or } p_B = \frac{6 P_o l_o}{b h_1^2} \quad . \quad . \quad . \quad (1)$$

Hence, putting $p_B = R'$, h_1 becomes known from (1).

Required, secondly, the relation between the variable height v (at any section n) and the distance x of n from O. For the free body nO, we have (Σ moms$_n$ $= 0$)

$$\frac{p_n I}{e} = P_o x\,; \text{ or } \frac{p_n \frac{1}{12} bv^3}{\frac{1}{2}v} = P_o x \text{ and } \therefore p_n = \frac{6P_o x}{bv^2} \qquad (2)$$

But for "uniform strength" p_n must $= p_B$; hence equate their values from (1) and (2) and we have

$$\frac{x}{v^2} = \frac{l_o}{h_1^2}, \text{ which may be written } (\tfrac{1}{2}v)^2 = \frac{(\frac{1}{2}h_1)^2}{l_o}\, x \qquad (3)$$

so as to make the relation between the abscissa x and the ordinate $\frac{1}{2}v$ more marked; it is the equation of a parabola, whose vertex is at O.

The parabolic outline for the portion BC is found similarly. The local stresses at C, B, and O must be properly provided for by evident means. The shear $J = P_0$, at O, also requires special attention.

This shape of beam is often adopted in practice for the working beams of engines, etc.

The parabolic outlines just found may be replaced by trapezoidal forms, Fig. 287, without using much more material, and by making the sloping plane faces tangent to the parabolic outline at points T_0 and T_1, *half-way* between O and B, and C and B, respectively. It can be proved that they contain *minimum volumes*, among all trapezoidal forms capable of circumscribing the given parabolic bodies. The dangerous sections of these trapezoidal bodies are at the tangent points T_0 and T_1. This is as it should be, (see § 278), remembering that the subtangent of a parabola is bisected by the vertex.



Fig. 287.

283. Rectang. Section. Height Constant. Two Supports (at Extremities). Single Eccentric Load.—Fig. 289. b and h are the dimensions of the section at B. With BO free we have

$$\frac{p_B I_B}{e_B} - P_0 l_0 = 0 \therefore p_B = \frac{6 P_0 l_0}{b h^2} \quad (1)$$



FIG. 289.

At any other section on BO, as n, where the width is u, the variable whose relation to x is required, we have for nO free

$$\frac{p_n I_n}{e_n} = P_0 x; \text{ or } \frac{p_n {}^1/_{12} u h^3}{{}^1/_2 h} = P_0 x \therefore p_n = \frac{6 P_0 x}{u h^2} \quad . \quad . \quad . \quad (2)$$

Equating p_B and p_n we have $u : b :: x : l_0$ . . (3)

That is, BO must be wedge-shaped; edge at O, vertical.



FIG. 289 *a*.



FIG. 289 *b*.

283a. Sections Rectangular and Similar. Otherwise as Before.—Fig. 289a. The dimensions at B are b and h; at any other section n, on BO, the height v, and width u, are the variables whose relation to x is desired, and by hypothesis are connected by the relation $u : v :: b : h$ (since the section at n is a rectangle *similar* to that at B). By the same method as before, putting $p_B = p_n$, we obtain $l_0 \div bh^2 = x \div uv^2$; in which placing $u = bv \div h$, we have finally

$$v^3 = (h^3 \div l_0)x; \quad \text{and similarly,} \quad u^3 = (b^3 \div l_0)x; \quad . \quad . \quad . \quad (4)$$

i.e., the width u, and height v, of the different sections are each proportional to the *cube* root of the distance x from the support. (The same relation would hold for the radii, in case all sections were circular.)

283b. Beam of Uniform Strength under Uniform Load. Two End Supports. Sections Rectangular with Constant Width.—Fig. 289*b*. Weight of beam neglected. How should the height v vary, (the height and width at middle being h and b)? As before, we equate p_B and p_n; whence finally

$$({}^1/_2 v)^2 = [h^2 \div l^2](lx - x^2). \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

This relation between the half-height $\frac{1}{2}v$ (as ordinate) and the abscissa x is seen to be the equation to an **ellipse** with origin at vertex.

CHAPTER V.

FLEXURE OF REINFORCED CONCRETE BEAMS.

284. Concrete and "Concrete-Steel" Beams. Concrete is an artificial stone composed of broken stone or gravel (sometimes cinders), cement and sand, properly mixed and wet beforehand and then rammed into moulds or "forms" and left to harden or "set." This material, after thorough hardening or "setting," though fairly strong in resisting compressive stress is comparatively weak in tension. When it is used in the form of beams to bear transverse loads (i. e., under "transverse stress") the side of the beam subjected to tensile stress is frequently "reinforced" by the imbedding of steel rods on that side. In this way a composite beam may be formed which is cheaper than a beam of equal strength composed entirely of concrete or one composed entirely of steel.

Of course the steel rods are placed in the mixture when wet, and previous to the ramming and compacting, and their aggregate sectional area may not need to be more than about one per cent. of that of the concrete.

No reliance being placed on the tensile resistance of the concrete (on the tension side of the beam) it is extremely important that there should be a good adhesion, and consequent resistance to shearing, between the sides of the steel rods and the adjacent concrete, for without this adhesion the rods and the concrete would not act together as a beam of continuous substance.*

In some specifications, for instance, it is required that the shearing stress, or tendency to slide, between the steel rods and the concrete shall not exceed 64 lbs. per sq. in. Sometimes the steel rods are provided with projecting shoulders, or ridges, or corrugations, along their sides, to secure greater resistance to sliding.

* For an account of tests of this adhesion see *Engineering News*, Aug. 15, 1907, p. 169, and also p. 120 of the *Engineering Record* for Aug. 3, 1907.

Fig. 290 gives a perspective view of a concrete-steel beam of rectangular section, placed in a horizontal position on two



FIG. 290.

supports at its extremities, and thus fitted to sustain vertical loads or weights; while Fig. 291 shows a concrete-steel beam



FIG. 291.

of T-section, in which the flange is intended to resist compression, while the steel rods in the lower part of the "stem" are to take care of the tension. These two shapes of beam will be the only ones to be considered here, in a theoretical treatment.

The ratio of the Modulus of Elasticity of steel (viz. — about 30,000,000 lbs. per sq. in.) to that of concrete (say, from 1,000,000 to 4,000,000 lbs. per sq. in., according to the proportions of ingredients used) is of great importance in the theory, since in general the stresses induced in two materials for a given percentage change of length are directly proportional to the modulus of elasticity (for same sectional area).

Generally the diameter of a steel rod is so small compared with the full height of the beam that the stress in the rod is taken as uniform over the whole of its section.

285. Concrete-Steel Beam of Rectangular Section. Flexure Stresses. — As in the common theory of flexure of homogeneous beams, it will be assumed that cross-sections plane before flexure are still plane when the beam is slightly bent, so that changes of length occurring in the various fibers are propor-

tional to the distances of those fibers from a certain *neutral axis* of the cross-section, and upon the amount of any such change of length (relative elongation) can be based an expression for the accompanying stress. Now in the case of concrete it is not strictly true that stresses are proportional to changes of length ("strains" or deformations); in other words its modulus of elasticity, E, is not constant for different degrees of shortening under compressive stress. Nevertheless, since this modulus does not vary much, within the limits of stress to which the concrete is subjected in safe design, it will be considered constant, the resulting equations being sufficiently accurate for practical purposes.

Let us now take as a "free body" any portion, ON, of the beam in Fig. 290, extending from the left-hand support to any section, at any distance x from that support. In the plane section terminating this body on the right, DNS (see now Fig. 292, in which we have also, at the right-hand, an end-view of



FIG. 292.

the body), we note that the fibers of concrete from D down to a neutral axis N are in a state of compression, while below N the steel rod alone is considered as under stress, viz., a total tensile stress of $F'p'$, where F' is the aggregate sectional area of all the steel rods, these rods being at a common distance a' above the lower edge of the section, and p' is the unit (tensile) stress in the steel rods.

The distance DN, or "e," of the neutral axis N below the "outer fiber" D, is to be determined. Let p denote the unit compressive stress in the fiber at D (outer fiber) of the concrete; then the unit stress in any fiber of the concrete at distance z from N will be $\frac{z}{e}p$, lbs. per sq. in., and the total stress on any

such fiber is $\frac{z}{e}\ pdF$, lbs. (where dF is the sectional area of the fiber). All the (horizontal) fibers between the two consecutive cross sections DS and $D'S'$ were originally dx inches long, but now (during stress), we find that the fiber at D has been shortened an amount $d\lambda$ and the steel rod "fibers" elongated an amount $d\lambda'$, so that we have the proportion $d\lambda : d\lambda' :: e : a - e$;

or,
$$\frac{d\lambda}{d\lambda'} = \frac{e}{a-e} \quad . \ . \ . \ . \ . \ . \ . \ . \quad (0)$$

For the free body in Fig. 292 we have, for equilibrium, the sum of horizontal components of forces $= 0$ (the shear J has no horizontal component); that is, remembering that below N no tensile forces are considered as acting on the concrete, but simply the total tensile stress $F'p'$ in the steel rods,

$$\int_0^e \frac{z}{e}\ pdF - F'p' = 0.$$

But here $\frac{p}{e}$ is a constant; and for the rectangular cross-section, $dF = b \,.\, dz$, and

$$\frac{pb}{e}\int_0^e z dz = \frac{pb}{e}\cdot\frac{e^2}{2};\ \therefore\ \frac{pbe}{2} = F'p' \quad . \ . \ . \quad (1)$$

But from the definition of modulus of elasticity (E for the concrete and E' for the steel), we have (§ 191)

$E = p \div$ (relat. elongation), or $E = p \div (d\lambda/dx)$; and similarly, $E' = p' \div (d\lambda'/dx)$; whence

$$\frac{d\lambda}{d\lambda'} = \frac{p}{p'}\cdot\frac{E'}{E} \quad . \ . \ . \ . \ . \ . \ . \quad (2)$$

But, from eq. (1), $p \div p' = 2F' \div be$, combining which with eqs. (0) and (2), and denoting the ratio $E' \div E$ by n,

we find
$$\frac{e}{a-e} = \frac{2F'n}{be} \quad . \ . \ . \ . \ . \ . \ . \quad (3)$$

The ratio n may have a value from 10 to 25 for "rock-concrete," and still higher for "cinder-concrete;" see § 284. Now solve eq. (3) for the distance e, obtaining

$$e = \frac{F'n}{b}\left(\sqrt{\frac{2ab}{F'n} + 1} - 1\right) \quad . \ . \ . \ . \quad (4)$$

This locates the neutral axis, N. [See, later, eq. (29), § 291.]

Returning to the free body ON in Fig. 292 above, we note that the resultant compression in the concrete between N and D, viz., $\frac{1}{2}\,p\,.\,be$, lbs. [see eq. (1)], is equal in value to the total tension $F'p'$, lbs., in the steel rods at G', and that they are parallel. Consequently they form a couple (the "stress-couple" of the section) whose moment is equal to the product of one of these forces, say $F'p'$, by the perpendicular distance $= a''$, between G' and a point G (see now Fig. 293) whose distance from the "outer fiber" D is one-third of e. The "arm" of this couple is $a'' = a - \frac{e}{3}$. For



Fig. 293.

equilibrium of the free body ON in Fig. 292 the shear J and the two forces V (reaction) and P_1 (load) must be equivalent to a couple of opposite and equal moment to that of the stress couple. Call this moment M [in this case it has a value of $Vx - P_1(x - x_1)$]; it is the "bending moment" of the section at DS. We may therefore write (see Fig. 293):

$$M = F'p'\,[a - \tfrac{1}{3}e]\text{; and } \therefore\ p' = \frac{M}{F'(a - \frac{1}{3}e)}\text{; .} \quad (5)$$

which will give the unit-stress p', induced in the steel rods at section DS. It is seen to depend on the position of the neutral axis N (i.e., upon e); upon the bending moment, M, at that section; upon the sectional area F' of the steel rods (aggregate); and on the distance, a, at which they are placed from the compression edge, D, of the beam.

But since the resultant compression, $\frac{1}{2}\,p\,.\,be$, is equal to the resultant tension, $F'p'$, we may also write

$$M = \tfrac{1}{2}\,p\,.\,be\,[a - \tfrac{1}{3}e] \text{ and } \therefore\ p = \frac{2M}{be\,(a - \frac{1}{3}e)}\text{; .} \quad (6)$$

which gives the unit-stress (compression) in the outer "fiber" at D, of the concrete, for this section DS.

286. Horizontal Shear in the Foregoing Case (Rectangular Section). The shear per sq. in. along the sides of the steel rods, and also along the horizontal "*Neutral Surface*," *NN''* (see Fig. 294), may be obtained as follows: — Let *dx* be the length of a small portion of the beam (of Fig. 290) situated between two vertical sections *DS* and *D''S''*. Fig. 294 shows this portion as a "free body." The forces acting consist of the tension *F'p'* on the left-hand end of the steel; the tension on the right-hand end of these rods [being something greater (say) and expressed by $F'(p' + dp')$ in which *dp* is the difference between the unit-tensions at the two ends of the steel "re-inforcement"]; the resultant compression, $\frac{1}{2}\,be\,.\,p$, in the concrete on the left; and that, $\frac{1}{2}\,be\,.\,(p + dp)$, on the right; and, finally, the two vertical shears, *J* and *J''*. Here *p* is the unit compressive stress (lbs. per sq. in.) in outer fiber of concrete at the left-hand extremity of the same, while $p + dp$ expresses the unit compressive stress in the same outer fiber at the right-hand extremity.



FIG. 294.

Evidently the difference between the total tensile stresses at the extremities of the steel rods will give the total horizontal shearing stress on the sides of those rods and this may be written $p_s' l_0 dx$ (lbs.), where p_s' = unit shearing stress between the steel and concrete and l_0 = aggregate perimeter of the steel rods (so that $l_0 dx$ = total area of the outside surface of rods in Fig. 294);

hence
$$p_s' l_0 dx = F'(p' + dp') - F'p' \quad . \quad . \quad . \quad . \quad (7)$$

But if, for the free body of Fig. 294, we put Σ moms. = 0 about the point *G* (a distance $\frac{1}{3}\,e$ from upper fiber)

we find
$$Jdx = [F'(p' + dp') - F'p'](a - \tfrac{1}{3}\,e); \quad . \quad . \quad (8)$$

and hence, see (7),
$$p_s' = \frac{J}{l_0\,(a - \frac{1}{3}\,e)} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (9)$$

Also, if we let p_s denote the unit shearing stress (or tendency to slide) along the horizontal surface NN'' or neutral surface, the total amount is $p_s b dx$ (lbs.).



Fig. 295.

In Fig. 295, which shows as a free body the portion $NN''S''S$ of Fig. 294, we see this horizontal force (of concrete on concrete) acting toward the left. The other forces acting on the free body are as shown in Fig. 295 and, by putting Σ horiz. compons. $= 0$,

we find $$F'(p' + dp') - F'p' = p_s b dx; \quad . \quad . \quad . \quad . \quad (9a)$$

and finally, see eq. (8), $$p_s = \frac{J}{b\,(a - \frac{1}{3}e)} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (10)$$

This (unit) shearing stress in the concrete along NN'', the "neutral surface," should nowhere exceed a certain value (e.g., 64 lbs. per sq. in.). For horizontal planes above NN'' it is smaller than along NN''. Similarly, the unit stress p_s' should not exceed a proper limit.

287. Numerical Example of a Concrete-Steel Beam of Rectangular Section. (See foregoing equations.)

Fig. 296 shows the section [8 by 11 inches] of the beam. Four round steel rods are imbedded near the under (tension) side, their centers being 10 in. from



Fig. 296.

the top of section ($a = 10$ in.). This beam is to be placed on two supports at the same level and 8 feet apart, and is to support a concentrated load P, lbs., at the middle of the span as well as its own weight, which is $W = 600$ lbs.

P is to be determined of such a safe value that the greatest stress in the steel rods shall not exceed 16,000 lbs. per sq. in. The compressive stress in concrete is not to exceed 700 lbs. per sq. in., nor the greatest shear either in the concrete or between the steel and the concrete, 64 lbs. per sq. in.

Each steel rod is continuous throughout the whole span and has a diameter of 0.45 in., from which we easily compute the aggregate perimeter of the rods

to be 5.65 inches ($= l_0$), and the aggregate sectional area to be 0.64 sq. in ($= F'$).

The ratio of the modulus of elasticity for steel to that of the concrete will be taken as 15 to 1; i.e., $n = 15$.

The first step is to locate the neutral axis by finding the value of e from eq. (4), thus:—

$$e = \frac{64}{100} \cdot \frac{15}{8} \left(\sqrt{\frac{2 \times 10 \times 8}{.64 \times 15} + 1} - 1 \right) = 3.84 \text{ in.}$$

Next, if for p' we write 16,000 (using inch and pound) and substitute in eq. (5), solving for M, we obtain the greatest bending moment to which any section of the beam should be exposed, so far as the steel is concerned, viz:—

$$M = p'F' \left(a - \frac{e}{3} \right) = 16{,}000 \times 0.64\,(10 - 1.28) = \left\{ \begin{matrix} 89{,}000 \\ \text{in.-lbs.} \end{matrix} \right.$$

i.e., max. moment is to be 89,300 in.-lbs.

For the mode of loading of the present beam the max. moment occurs at the section at the middle of the span and has a value (with l denoting the span, or 96 in.) of $\frac{Pl}{4} + \frac{Wl}{8}$. We therefore write

$$\frac{P \times 96}{4} + \frac{600 \times 96}{8} = 89{,}300. \quad \text{Hence } P = 3{,}420 \text{ lbs.}$$

To find the accompanying maximum compressive stress in the concrete, eq. (6) gives (for outer "fiber")

$$p = \frac{2M}{be\,(a - \frac{1}{3}\,e)} = \frac{2 \times 89{,}300}{8 \times 3.84 \times 8.72} = 666 \text{ lbs. per sq. in.,}$$

which is within the limit set (700 lbs. per sq. in.).

As for the max. *shearing* unit stresses p_s' and p_s, they are greatest where the vertical shear, J, is a max., which is close to one of the supports. Here we note that J is equal to $\frac{1}{2}$ of 3,420 + $\frac{1}{2}$ of 600 = 2,010 lbs. Hence, from eq. (9),

$$p_s' = \frac{2{,}010}{5.65 \times (10 - 1.28)} = \frac{2{,}010}{5.65 \times 8.72} = 40.8 \text{ lbs. per sq. in.,}$$

$$\left. \begin{matrix} \text{while} \\ \text{from (10)} \end{matrix} \right\} p_s = \frac{2{,}010}{8 \times 8.72} = 28.8 \text{ lbs. per sq. in.,}$$

These shearing stresses are seen to be well within the limit set, of 64 lbs. per sq. in. As to compressive stress, the building laws of most cities put 500 lbs. per sq. in. as max. safe limit for p, the compressive stress in concrete.

288. Concrete-Steel Beam of T-Form Section. See Fig. 297. In this form of beam, to secure simplicity in treatment, it will be considered that the flange (TK) alone is subjected to compressive stress [although strictly a small portion of "stem" between the flange and the neutral axis of a section is under that kind of stress]. The part of stem below the neutral axis (as before) is not considered to offer any tensile resistance, all

tension being borne by the steel rods or "re-inforcement." Fig. 297 shows a side view and also an end-view of a portion of the beam in Fig. 291 extending from the left-hand support up to any section DS (or up to W in Fig. 291). As before, sections plane before flexure are considered to be still plane during flexure, so that the elongations or shortenings of any horizontal "fiber," whether steel or concrete, are proportional to the dis-



FIG. 297.

tances from a neutral axis N, at some distance e from the top fiber of the flange, where the unit compressive stress has some value p.

Also, since the E for concrete in compression is to be taken as constant the stresses in the concrete will also be proportional to the distances of the "fibers" from N the neutral axis. Let p'' denote the unit-stress in the concrete at H, the bottom fiber of the flange; then, by proportion, $p : p'' :: e : e - d$, where d is the thickness of the flange. Since the compressive stresses in the concrete between H and D are distributed over a rectangle their average unit-stress is $(p + p'')/2$, and their resultant, which acts horizontally through some point G, has a value of $bd \,.\, (p + p'')/2$; or, as it may be written (see above for p''), $(p\,(2\,e - d)\,.\,bd) \div (2\,e)$.

The total tensile stress in the steel rods will be $F'p'$, as before, where F' is the aggregate sectional area of the rods and p' the unit stress in them at section DS. Besides the stresses just mentioned the other forces acting on the free body in Fig. 297 are all vertical; viz., the shear J and the pier reaction and certain loads between O and D; hence by summing the horizontal components we note that the compressive stress in the concrete is equal to the tensile stress $F'p'$ in the steel, so that this

tensile force $F'p'$ and the resultant compressive stress form a couple ("*stress-couple*" of the section; with an arm $= \overline{GG'}$, $= a''$), and we have

$$\frac{p\,(2\,e - d)\,bd}{2\,e} = F'p' \quad . \quad . \quad . \quad . \quad . \quad . \quad (11)$$

Consequently the shear and the other vertical forces acting on the free body form a couple also, and the moment of this couple (equal to that of the "stress-couple") will be called M. In the figure these vertical forces are not shown, but simply an equivalent couple (on the left).

If at this part of the beam a length dx of the steel has stretched an amount $d\lambda'$ and an equal length, dx, of the outer fiber at D has shortened an amount $d\lambda$, we have from eq. (2) of previous work

$$\frac{d\lambda}{d\lambda'} = \frac{p}{p'} \cdot \frac{E'}{E}; \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (12)$$

where E' and E are the moduli of elasticity of the steel and concrete, respectively. But, from (11),

$$\frac{p}{p'} = \frac{F'e}{(e - \frac{1}{2}d)\,bd}; \quad . \quad . \quad . \quad . \quad . \quad . \quad (13)$$

and from similar triangles $d\lambda : d\lambda' :: e : (a - e)$ . . . . (14)

Eqs. (13), (14), and (12), with $E' \div E = n$, give

$$e = \frac{F' \,.\, n \,.\, a + \dfrac{bd^2}{2}}{bd + F'n}, \quad . \quad . \quad . \quad . \quad . \quad . \quad (15)$$

and thus the neutral axis, N, is located.

It will now be necessary to locate the point of application, between H and D, of the resultant compressive stress on HD; that is, the point G in Fig. 298 which gives a side view of these stresses alone, forming, as they do, a trapezoidal figure whose center of gravity, U, projected horizontally on HD gives the desired point, G. The lower base HC'' of this trapezoid

represents the unit stress p''; the upper, DC''', represents the unit stress p. The distance, call it c, of G from N, is to be determined. Let the trapezoid be divided into a rectangle $DD'''C''H$ and a triangle $D'''C'''C''$. The center of gravity of the latter is at a vertical distance of $\frac{1}{6}d$ from a line $H''H'''$ drawn horizontally at distance $\frac{1}{2}d$ from D. $H''H'''$ passes through the center of gravity of the rectangle. Let us now find the distance $\overline{GH''}$ by writing the moment of the resultant stress about point H'' equal to the sum of those of its two parts, or components, represented by the rectangle and the triangle; whence we have



Fig. 298.

$$\tfrac{1}{2}(p+p'')\,.\,bd \times \overline{GH''} = 0 + \frac{(p-p'')\,bd}{2}\cdot\frac{d}{6} \quad . \quad (16)$$

Noting that $p'' = \left(\frac{e-d}{e}\right)p$, we have, solving,

$\overline{GH''} = \frac{1}{6}\cdot\frac{d^2}{2e-d}$, and therefore, measuring from N,

$$\overline{NG}, \text{ i.e., } c, = e - \frac{d}{2} + \frac{1}{6}\cdot\frac{d^2}{2e-d} \quad . \quad . \quad . \quad . \quad . \quad (17)$$

Now that both e and c have been determined in any given case it remains to find expressions for the unit stresses p' and p (in steel and fiber D of concrete).

Since G is the point of application of the resultant compression in flange, the arm of the stress-couple, a'' (Fig. 297), is the distance from G to G' (see Fig. 297); that is, $a'' = c + (a - e)$; and hence we may write

$$F'p'\,(c + a - e) = M;\ \therefore p' = \frac{M}{F'\,(c + a - e)} \quad . \quad (18)$$

Also, by eliminating the ratio $d\lambda : d\lambda'$ from eqs. (12) and (14) we have, solving for p,

$$p = \frac{p'e}{n\,(a-e)} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (19)$$

289. Shearing Stresses in T-Form Concrete-Steel Beams. As regards the unit shearing stress, p'_s induced on the sides of the steel rods, in this case of the concrete steel beam of T-form section, an analysis similar to the corresponding one in the case of the beam of rectangular section leads to the result

$$p'_s = \frac{J}{l_0(c+a-e)} \left\{ \begin{array}{l} \text{where } J \text{ is the total vertical shear at} \\ \text{the section } BS, \text{ and } l_0 \text{ the aggregate} \end{array} \right\} \quad (20)$$

perimeter of the steel rods.

And, similarly, for the unit shearing stress on the horizontal surface separating the flange from the "web" or "stem" (see Fig. 297) at H, where the width of the web is b'', we find for this unit horizontal shear, p_s,

$$p_s = \frac{J}{b''(c+a-e)} \quad . \quad . \quad . \quad . \quad . \quad (21)$$

290. Deflections of Concrete-Steel Beams. The deflection of a loaded *prismatic* concrete-steel beam resting on two supports at its extremities, may be obtained for the cases dealt with in §§ 233–236 inclusive, in connection with homogeneous beams; provided the product EI occurring in the expressions for these deflections be replaced by $\frac{E\,be^2}{2}\left(a-\frac{e}{3}\right)$, for concrete-steel beams of rectangular section; and by $E'F'(a-e)(c+a-e)$, for those of T-form section.

291. Practical Formulæ and Diagrams for use with Concrete-Steel Beams of Rectangular Section. The equations of the foregoing theory will now be put into convenient form for practical use in designing these beams. Let us denote the ratio of p' (stress in steel at section of max. moment) to p (stress in outer fiber of concrete) by r; i.e., $r = p'/p$; while $n = E'/E$, as before. Also let m, $= M \div b$, denote the max. bending moment *per inch* of width (b) of beam; and let F' (area of steel) $\div\, b$ be called f', i.e., steel area *per inch of width* (b). In other words, we have the notation



FIG. 299.

$$r = \frac{p'}{p};\ n = \frac{E'}{E};\ m = \frac{M}{b};\ \text{and}\ f' = \frac{F'}{b}; \quad . \quad . \quad . \quad . \quad (22)$$

If we now substitute $e = 2\,rf'$, from eq. (1), in eq. (3),

we have $$2\,rf'(r+n) = an \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (23)$$

Now $e = 2\,rf'$, which from (23) $= an \div (r+n)$; Hence eq. (5)

will give $$3\,m(r+n) = af'p'(3\,r+2\,n) \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (24)$$

REINFORCED CONCRETE BEAMS (rectangular).

DIAGRAM I.

$$S = \frac{n}{2\,r\,(r+n)};$$

in which

$$\left(S = \frac{f'}{a}, = \frac{F'}{a\,b}\right)$$



[To face page 350.


REINFORCED CONCRETE BEAMS (rectangular).
DIAGRAM II.
$Q = \frac{3r + 2n}{3(r + n)}$;
in the formula :—
$m = Q f' p' a$
or
$m = Q S p' a^2$
VALUES OF Q
VALUES OF r, $= p' \div p$
VALUES OF n, $= E' \div E$.
10 12 15 20 25 30 40 50 60
.75 .80 .85 .90 .95
30 25 20 15 12 10 7 5

[To face page 351.

If now S denote the quotient $f' \div a$ (i.e., S = area of steel section *per unit area of concrete section above the steel*), (23) may be written in the form

$$S = n \div [2\,r\,(r+n)] \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (25)$$

Again, let $\dfrac{3\,r+2\,n}{3\,(r+n)}$ be denoted by Q . . . . . (26)

From (24), (25) and (26) we may then derive

$M = QSp'a^2b$ . . . . (27); and $m = QSp'a^2$ . . . . . (28)

for practical use in design; in connection with Diagrams I and II (opp. pp. 350 and 351) from which we may obtain values of Q and S, respectively, for any given values of r and n.

As to unit *shearing stresses*, which should not exceed 64 lbs. per sq. in. (say), use is made of eqs. (9) and (10), § 286, in which the maximum total vertical shear J_m should be substituted. In computing "e" for use in (9) and (10), it is simplest to employ the relation [derived from eqs. (1), (23) and (25)]

$$e = 2\,Sra \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (29)$$

292. Numerical Examples. Rectangular Section. Let us suppose that in the cross-section of maximum moment the stresses in *both* materials are to attain their greatest safe values; viz., 16,000 lbs. per sq. in. tension for the steel, and 500 for the compressive stress in outer fiber of the (rock) concrete. Also suppose that $E' = 30{,}000{,}000$ and $E = 2{,}000{,}000$ lbs. per sq. in. That is, we have $n = 15$ and $r = 16{,}000 \div 500, = 32$; and from Diagram I find $S = 0.005$. In other words the necessary area of steel section is $\frac{1}{2}$ of one per cent. of the area of the concrete (above steel rods). We also find, from Diagram II, that $Q = 0.894$.

If now "a" be taken as 10 in., eq. (28) gives:—

$m = 0.894 \times 0.005 \times 16{,}000 \times 100, = 7{,}152$ inch-lbs. bending moment that could safely be withstood by each inch in the width b; so that if "b" were 8 inches we should have $M = mb = 7{,}152 \times 8 = 57{,}216$ inch-lbs., safe bending moment for the section of the beam.

Again, with r and n still equal to 32 and 15, respectively, and hence with Q and S as before, viz., 0.894 and 0.005, if b is assumed as 10 in., and the max. bending moment to be sustained is $M = 80{,}000$ inch-lbs. (so that $m = 8{,}000$), we find from eq. (28)

$$a = \sqrt{\frac{8{,}000}{0.894 \times 0.005 \times 16{,}000}} = 10.58 \text{ inches},$$

as necessary value of a; while the total area of steel section needed is

$$F', = S \,.\, a\,b = 0.005 \times 10.58 \times 10 = 0.5290 \text{ sq. in.}$$

which is seen to be one half of one per cent. of the area [10×10.58] of the concrete above steel (i.e., $S = 0.005$, as found from Diagram I originally).

293. Cost of Beams of Rectangular Section. While in a general sense economy in cost is favored by having the width "b" of the rectangular section small compared with the height "a," a limit to narrowness of width is set by the unit shearing stress in the neutral surface which would be found to exceed a safe limit if the beam were too narrow. The thickness "a'" of concrete below the steel rods (see Fig. 292) might be made $\frac{1}{10}$ of "a."

CHAPTER VI.

FLEXURE. COLUMNS AND HOOKS. OBLIQUE LOADS.

294. Oblique Prismatic Cantilever. In Fig. 301, at (*a*), (on p. 354) we have a prismatic beam built in at K, projecting out obliquely, and carrying a vertical load P at upper end; the line of action of P passing through the center of gravity of the upper base of the prism. In such a case the fibers of the beam where they cross any transverse plane mg will evidently be subjected to compressive stress (called a "*thrust*") due to the component of P parallel to the axis OK of the prism; to a *shear* J due to the component of P at right angles to that axis; and also to additional stresses, both tensile and compressive, forming a "*stress-couple*" due to the moment of P (i.e., Pu) about g, the center of gravity of the cross-section $m'm$.

More in detail, consider in Fig. 300 a portion AB of the prism, being the part lying above a cross-section mm' near the top, so that the portion gO of axis is practically perpendicular to the section mm' which is a plane both before and after flexure, g being the center of gravity of the plane figure formed by the cross-section.



FIG. 300.

Let the unit stress on the end of the extreme fiber at m be represented by the length sm and that [also compression (say)] on the other extreme fiber, at m', by $s'm'$. Draw the straight line ss'; then by the common theory of flexure the stress on any intermediate fiber, at c, would be the intercept, or ordinate, ac to this line. Now the unit stress p_1, on the fiber g at the center of gravity of cross-section, being $\overline{gr}$, draw through r a line $t'rt$

parallel to $m'm$, and we now have the stress on any fiber as c divided into two parts $\overline{bc}$, or p_1, the same for all the fibers; and $\overline{ab}$, different for the different fibers but *proportional to the distance z* of the fiber from g. Hence we have:
the unit stress on any fiber c is

$$p = p_1 + \frac{z}{e} p_2 \quad (lbs.\ per\ sq.\ in.) \quad . \quad . \quad . \quad . \quad (1)$$

where p_2 is $\overline{st}$ and e the distance of the extreme fiber m from g; and hence the total stress on fiber c is $pdF = p_1 dF + \frac{z}{e} p_2 dF$, *lbs.*; where dF is the area (sq. in.) of section of fiber, or element of area of the cross-section, F being the total area of the cross-section, mm'. Geometrically, we note that while the system of normal stresses on all the fibers forms a trapezoid, $m's'sm$ in this side-view, and that they are all compressive, they are equivalent to a rectangle, $m't'tm$, of stress of *uniform* compressive unit-stress p_1; and two *triangles*, one, rst, of compressive stress, and the other, $rs't'$, of *tensile* stress.* It will now be shown that the sum of the moments of the stresses of the rectangle about center g is *zero*, and that the two triangles of stress form a *couple.*

$$\Sigma(\text{moms.}) \text{ of stresses in triangle} = \int_{z=-e'}^{z=+e} (p_1 dF) z = p_1 \int dF z$$

$= p_1 F\bar{z} =$ *zero;* since $\bar{z} =$ zero, the z's being measured from the center of gravity, g, of section mm' [§ 23, eq. (4)].

Again, if we sum (algebraically) the stresses of the two triangles,

we have $$\int_{z=-e'}^{z=+e} \frac{z}{e} p_2 dF = \frac{p_2}{e} \int z dF = \frac{p_2}{e} F\bar{z}, = \text{zero}$$

that is, the resultant of the compressive stresses in rts equals that of the tensile stresses in $rs't'$; *hence they form a couple.*

If, therefore, we have occasion to sum the moments about g, of all the stresses acting on the fibers in section mm' we are to note that this moment-sum involves the stresses of *the triangles alone* (that is, of the couple), and is

$$\int_{-e'}^{e} \left(\frac{z}{e} p_2 dF\right) z, = \frac{p_2}{e} \int dF z^2 = \frac{p_2 I_g}{e} \quad . \quad . \quad . \quad (2)$$

in.-lbs.; where I_g is the "moment of inertia" of the cross-section

* These plane figures are the side views of geometric solids.

referred to an axis through g (its center of gravity) and perpendicular to the "force plane" (plane of paper here).

If, again, we sum the components of all the stresses (on plane mm') parallel to the axis gO we note that this sum is zero for the couple and also for the shear J and hence reduces simply to

$$\int p_1 dF = p_1 \int dF = p_1 F, \text{ lbs. (the } \textit{Thrust}) \quad . \quad . \quad (3)$$

(corresponding to the rectangle, $t'm$).

The sum of components perpendicular to axis gO is of course simply the *shear*, J, *lbs.*

Evidently the unit stress (normal) in fiber at m is expressed as $p_m = p_1 + p_2$; and that at m' as $p_{m'} = p_1 - \frac{e'}{e} p_2$. If in any case the latter is negative it indicates that the actual stress in this fiber is tension.

295. Oblique Cantilever. Fig. 301, (a) and (b). At (b) is shown as a "free body," a portion [of the cantilever at (a)] of any length x from top. The forces acting are the vertical load P at O, and the stresses on the ends of the fibers in the section $m'm$; and these stresses are now indicated as consisting of a *thrust*, T, of uniform intensity p_1, the total thrust being $p_1 F$, lbs., (where F is the total area of section); of a *stress-couple*, C, whose moment is $\frac{p_2 I}{e}$ in.-lbs., in which $p_2 = p_m - p_1$ and I is the "moment of inertia" of the cross-section (about an axis through its center of gravity g at right angles to the plane ("force plane") containing Og and force P; *the same I that has been used in previous cases of flexure*); and the *total shear*, J, lbs., parallel to force plane and perpendicular to gO. The lever arm of P about g is u which practically $= x \sin \alpha$ (unless the beam is considerably bent or is nearly vertical).



FIG. 301.

For this free body (in order to find p_1, p_2 and J)

$$\sum X = 0 \text{ gives: } P\cos a - p_1 F = 0\,;\ \therefore\ p_1 = \frac{P\cos a}{F} \quad . \quad (4)$$

$$\sum (\text{moms.})_g = 0\ .\ .\ \frac{p_2 I}{e} - Pu = 0\,;\ \therefore\ p_2 = \frac{Pue}{I} \quad . \quad . \quad (5)$$

and $$\sum Y = 0\ .\ .\ P\sin a - J = 0\,;\ \therefore J = P\sin a, \quad (6)$$

As x varies, from 0 to l, we note that p_1 and J remain unchanged but that p_2 *increases with* u; so that the maximum value of the unit stress p_m, which $= p_1 + p_2$, will be found in the section at K, where $x = l$; and if this stress is not to exceed a safe value, R', for the material, we put p_2 (at K) $+ p_1 = R'$, (as the *equation of safe loading*);

or, $$P\left[\frac{\cos a}{F} + \frac{le\sin a}{I}\right] = R' \quad . \quad . \quad . \quad . \quad (7)$$

(N. B. For a cross-section of unusual shape the stress $p_{m'} = p_1 - \frac{e'}{e}\, p_2$, at K, might happen to be numerically greater than $p_{m'}$, and thus govern the design).



Fig. 302.

296. Experimental Proof of Foregoing. A stick or test piece of straight-grained pine wood, 12 inches in length and of square cross-section (one inch square), originally straight and planed smooth and with bases perpendicular to the length, was placed in a testing machine; steel shoes, with (outside) spherical bearing surfaces, being centered on the ends. See Fig. 302, where AB is the stick and S, S', the two steel shoes. The stick was gradually compressed between the two horizontal plates B,B', of the machine and bent progressively in a smooth curve under increasing force. From the nature of the "end conditions," as the stick changed form, the line of action of the two end pressures P,P, always passed through the centers of gravity, a and b, of the respective bases.

When the force P had reached the value 4500 lbs. a fine wrinkle was observed to be forming on the right-hand surface

of the stick at the outside fiber m of the middle section gm. The other fibers of this section were evidently uninjured. At m then, the unit-stress must have been about 8000 lbs. per sq. in., the crushing stress (as known from previous experiments with sticks of similar material and equal section but only three or four inches long; these were too short to bend, and wrinkles formed around the *whole perimeter*, showing incipient crushing in *all* the fibers). The distance $\bar{gc}$ at this time was found to be $\frac{1}{8}$ in.; i.e., the lever arm, u, of the force P about g, the center of gravity of the section. In this case, then, it is to be noted that the value of u was *entirely due to the bending of the piece.*

Substituting, in eqs. (4) and (5) of § 295, the values $u = \frac{1}{8}$ in., $a = 0$, $\cos a = 1$, $e = e'$, $= \frac{1}{2}$ inch, $F = 1$ sq. in.,

$$\text{and } I, = \frac{bh^3}{12}, = \frac{1 \times 1^3}{12} = \frac{1}{12} \text{ in.}^4, \text{ we find } p_1 = 4500$$

lbs. per sq. in. and $p_2 = 3375$ lbs. per sq. in.
Hence stress at m, $= p_1 + p_2$, $= 7875$ lbs. per sq. in., which is about 8000, as should be expected. On the fiber at o, however, we find a stress of $p_1 - p_2$, or of only 1125 lbs. per sq. in. *compression.*

We find, then, that in the section om, when P reached the value of 4500 lbs., there was a *total-thrust* ($p_1 F$) of 4500 lbs.; a *unit-thrust* (p_1) of 4500 lbs. per sq. in.; and a stress-couple having a moment of $Pu, = \frac{p\,I}{e}$, $= 562.5$ in.-lbs., (implying a separate stress of $p_2 = 3375$ lbs. per sq. in. in the outer fibers, to be combined with that due to the thrust). Also that J, the shear, was zero.

297. Crane-Hooks. First (Imperfect) Theory. Fig. 303 shows a common crane-hook of iron or steel. Early writers (Brix and others) treated this problem as follows: —

The load being P, if we make a horizontal section at AB, about whose gravity axis, g, P has its greatest moment, and consider the lower portion C as a free body, in Fig. 304), we find, using the notation and subdivision of stresses already set forth in § 294 for an oblique prism, that the uniformly distributed pull (or "negative thrust") on the fibers is $p_1 F = P$, lbs.;

while the moment of the stress-couple is $\frac{p_2 I}{e} = Pa$ ft.-lbs.; and that the shear, J, is zero.

Hence on the extreme fiber at B we have a total unit tensile stress of $p_1 + p_2 = \frac{P}{F} + \frac{Pae}{I}$, which for safe design must not exceed the safe unit-stress for the material, R' lbs. per sq. in.; whence we should have



Fig. 303.



Fig. 304.



Fig. 305.

$$P\left[\frac{1}{F} + \frac{ae}{I}\right] = R' \quad . \quad . \quad . \quad . \quad . \quad . \quad (8)$$

as the equation of safe loading.*

Example: Safe P = ?, if section AB is a circle of radius 2 in., while a = 4 in.; the material being mild steel for which (in view of the imperfection of the theory) a low value, say 6000 lbs. per sq. in., should be taken for R'. With these data we obtain: —

$$P = 6000 \div \left[\frac{1}{12.56} + \frac{4 \times 2}{50.24}\right] = 25130 \text{ lbs.}$$

The simple crane in Fig. 305, being practically an inverted hook, may be treated in the same manner.

298. Crane-Hooks. Later, More Exact, Theories. The most exact and refined theory of hooks yet produced is that of Andrews and Pearson,† but it is very complicated in practical application and far too elaborate and extended to be given here.

The next best (and fairly satisfactory) treatment is that of Winkler and Bach, of which the principal practical features and results will now be presented.

* See experiments by Prof. Goodman, in *Engineering*, vol. 72, p. 537. Results are irregular, due probably to the use of this imperfect theory.

† Drapers' Company Research Memoirs. Technical Series I. London, 1904.

In *AB*, Fig. 306, we have again the free body of Fig. 304, but the vertical stresses acting on the cross-section *m'm* are proportional to the ordinates of a *curve* instead of a straight line. The imperfection of the early theories lies in the fact that the sides of a hook are curved, and not straight and parallel as in the prismatic body of Fig. 301; and the variation of stress from fiber to fiber on the cross-section must follow a different law, as may thus be illustrated:

As preliminary, the student should note, from the expression $\frac{P}{F} = \frac{E\lambda}{l}$ of p. 209, that in the case of two fibers under tension, with the same sectional area F, the unit-stress $P \div F$ (or p) is not proportional to the elongation λ of the fiber unless the two lengths l are equal. In Fig. 306 the center of gravity of the cross-section is g, and O is the center of curvature of the curved axis gk of this part of the hook (or other curved body). The two consecutive radial sections *m'm* and *t't* are assumed to remain plane during stress, and hence the changes of length, due to stress, of the (vertical) fiber lengths between them are proportional to the ordinates of a straight line; and if these fiber lengths were equal in length (as would be the case for a prismatic beam) the unit-stresses acting would also be proportional to the ordinates of a straight line (this is the case in Fig. 301).



Fig. 306.

But in the present case these fiber-lengths are *unequal*, so that the unit-stresses in action are (in general) proportional to the ordinates of a *curved* line. Such a curved line we note in *ve*, Fig. 306, the ordinates between which and the horizontal line *hi* represent the unit-stresses, p, acting on the upper ends

of the vertical fibers from m' to m. Thus, the stress on the fiber mt is $p_m = \overline{ei}$ (tension); and that on the other extreme fiber, (at m') is $p_{m'} = \overline{hv}$ (compression).

If now we compute the average unit-stress $p_1 = P \div F$ and lay it off, $= is$, upward from hi, and draw the horizontal bs, we thereby re-arrange the stresses into a uniformly distributed pull (or "negative thrust") $p_1 F$ lbs., represented by the rectangle $bsih$, and a stress-couple formed by the ordinates lying between the curve and the axis bs.

It will be noted in Fig. 306 that there is a fiber at some point n (on right of g) where the stress is zero; i.e., the "*neutral axis*" of the section is at n, ⌐ to paper. Also, at some point n', the actual stress is equal to the average, p_1, and an axis ⌐ to paper through this point would be the neutral axis if the forces acting on this free body, other than the fiber stresses, consisted, not of a single force P, but of a *couple*, with a moment $= Pa$. This axis through n' might be called the neutral axis for "pure bending", since then the whole system of fiber stresses would reduce to a couple and the stresses would be measured by the ordinates between bs and the curve.

299. Crane-Hooks. Winkler-Bach Theory. Formula for Stress. In Fig. 306, let F be the area of the plane figure formed by the section $m'm$, dF an element of this area, and z its distance (reckoned *positive toward the right*) from the gravity axis, g, of the section. The radius of curvature of gk is r, and a is the lever arm of P, the load, about g. Let $\overline{gm} = e$ and $\overline{gm'} = e'$ (distances of extreme fibers) and let

$$S \text{ denote the quantity } \left(\left[\frac{r}{F}\int_{z=-e'}^{z=+e}\left(\frac{dF}{r-z}\right)\right]-1\right); \quad . \quad (1)$$

an abstract number depending on the area, shape, and position, of the cross-section $m'm$; and upon the radius of curvature r. Its value may be obtained by the calculus (or Simpson's Rule) for ordinary cases. For instance, if the section is a rectangle of width b, and altitude $= h$, $= \overline{m'm}$, we find

$$S = \frac{r}{h}\left(\log_e \frac{2r+h}{2r-h}\right) - 1 \quad . \quad . \quad . \quad . \quad . \quad (2)$$

From the Winkler-Bach theory it results that the unit-stress on any fiber between m and m', at a distance z from the gravity axis g (on the right, *toward* the center of curvature, O; if on the left, z is negative) is

$$p = \frac{P}{F}\left[1 - \frac{a}{r}\left(1 - \frac{z}{r-z}\cdot\frac{1}{S}\right)\right]. \quad . \quad . \quad . \quad (3)$$

lbs. per sq. inch. A positive result from (3) indicates tension; a negative, compressive stress. Of course, for $P \div F$ we might write the symbol p_1, or "average stress." If p were set = zero, a solution of (3) for z would locate the neu-

tral axis, n, of Fig. 306; while by placing $p - p_1 = 0$, a solution for z would locate the point n', or neutral axis for "pure bending."

300. Numerical Example. Let the cross-section be a trapezoid, of base $b = 3$ in. at m, and upper base $b' = 1$ in. at m', both $\perp$ to paper; the altitude $h, = \overline{m'm}$, being 4 in. This brings g $\frac{5}{3}$ in. $(= e)$ from m and $\frac{7}{3}$ in. $(= e')$ from m'. Let N be in the same vertical as O and $\overline{Om} = 2$ in. Hence $r = a = 2 + \frac{5}{3} = \frac{11}{3}$ in. The material is mild steel and the load P is 8 tons; find p_m and $p_{m'}$.

From above dimensions we find area $F = 8$ sq. in., while from eq. (1), (using the calculus), $S = 0.0974$. For p_m we put $z = +\frac{5}{3}$ in. in eq. (3); and for $p_{m'}$, $z = -\frac{7}{3}$ in.; obtaining, finally, $p_m = 17{,}120$ lbs. per sq. in. (tension); and $p_{m'} = -7{,}980$ (compression). Evidently the elastic limit is not passed.

Using the imperfect theory of § 297, we should have obtained $p_m = 12{,}000$ lbs. per sq. in., only; which is seen to be about 30 per cent. in error, compared with the above value of 17,120. The reason for taking a low value for the safe unit-stress, R', in the example of § 297 is now apparent, an additional reason being the fact that loads are sometimes "suddenly applied" on hooks.

301. By "column" or "long column" is meant a straight beam, usually prismatic, which is acted on by two compressive forces, one at each extremity, and whose length is so great compared with its diameter that it gives way (or "fails") by buckling sideways, i.e. by flexure, instead of by crushing or splitting like a short block (see § 200). The pillars or columns used in buildings, the compression members of bridge-trusses and roofs, the "bents" of a trestle work, and the piston-rods and connecting-rods of steam-engines, are the principal practical examples of long columns. That they should be weaker than short blocks of the same material and cross-section is quite evident, but their theoretical treatment is much less satisfactory than in other cases of flexure, experiment being very largely relied on not only to determine the physical constants which theory introduces in the formulae referring to them, but even to modify the algebraic form of those formulae, thus rendering them to a certain extent empirical.

302. End Conditions.—The strength of a column is largely dependent on whether the ends are free to turn, or are fixed and thus incapable of turning. The former condition is attained by rounding the ends, or providing them with hinges or ball-and-socket-joints; the latter by facing off each end to an accurate plane surface, the bearing on which it rests being plane also, and incapable of turning. In the former condition the column is spoken of as having

round ends ;* Fig. 311, (*a*) ; in the latter as having fixed ends, (or flat bases ; or square ends), Fig. 311, (*b*).



FIG. 311. FIG. 312.

Sometimes a column is fixed at one end while the other end is not only round but *incapable of lateral deviation from the tangent line* of the other extremity; this state of end conditions is often spoken of as "Pin and Square," Fig. 311, (*c*).

If the rounding * of the ends is produced by a hinge or "pin joint," Fig. 312, both pins lying in the same plane and having immovable bearings at their extremities, the column is to be considered as round-ended as regards flexure in the plane ⌐ to the pins, but as square-ended as regards flexure in the plane containing the axes of the pins.

The "moment of inertia" of the section of a column will be understood to be referred to a gravity axis of the section which is ⌐ to the plane of flexure (and this corresponds to the "force-plane" spoken of in previous chapters), or plane of the axis of column when bent.

303. Euler's Formula.—Taking the case of a round-ended column, Fig. 313 (*a*), assume the middle of the length as an origin, with the axis X tangent to the elastic curve at that point. The flexure being slight, we may use the form $EI\, d^2y \div dx^2$ for the moment of the stress-couple in any

* With round ends, or pin ends, it should be understood that the force at each end must be so applied as to act through the *centre of gravity of the base* (plane figure) of the prismatic column at that end ; and continue to do so as the column bends.



FIG. 313.



FIG. 314.

section n, remembering that with this notation the axis X must be ‖ to the beam, as in the figure (313). Considering the free body nC, Fig. 313 (b), we note that the shear is zero, that the uniform thrust $=P$, and that $\Sigma(\text{moms.}_n)=0$ gives (a being the deflection at O)

$$EI\frac{d^2y}{dx^2}=P(a-y) \quad . \quad . \quad . \quad (1)$$

Multiplying each side by dy we have

$$\frac{EI}{dx^2}\,dy\,d^2y=Pa\,dy-Py\,dy \quad . \quad . \quad (2)$$

Since this equation is true for the y, dx, dy, and d^2y of any element of arc of the elastic curve, we may suppose it written out for each element from O where $y=0$, and $dy=0$, up to *any* element, (where $dy=dy$ and $y=y$) (see Fig. 314) and then write the sum of the left hand members equal to that of the right hand members, remembering that, since dx is assumed constant, $1\div dx^2$ is a common factor on the left. In other words, integrate between O and any point of the curve, n. That is,

$$\frac{EI}{dx^2}\int_{dy=0}^{dy=dy}[dy]d[dy]=Pa\int_0^y dy-P\int_0^y y\,dy \qquad (3)$$

The product $dy\,d^2y$ has been written $(dy)d(dy)$, (for d^2y is

the differential or increment of dy) and is of a form like xdx, or ydy. Performing the integration we have

$$\frac{EI}{dx^2} \cdot \frac{dy^2}{2} = Pay - P\frac{y^2}{2} \quad . \quad . \quad . \quad . \quad (4)$$

which is in a form applicable to any point of the curve, and contains the variables x and y and their increments dx and dy. In order to separate the variables, solve for dx, and we have

$$dx = \sqrt{\frac{EI}{P}} \frac{dy}{\sqrt{2ay - y^2}} \text{ or } dx = \sqrt{\frac{EI}{P}} \cdot \frac{d\left(\frac{y}{a}\right)}{\sqrt{2\,\frac{y}{a} - \left(\frac{y}{a}\right)^2}} \quad . \quad (5)$$

$$\therefore \int_0^x dx = \pm \sqrt{\frac{EI}{P}} \int_0^y \frac{d\left(\frac{y}{a}\right)}{\sqrt{2\,\frac{y}{a} - \left(\frac{y}{a}\right)^2}}$$

$$\text{i.e., } x = \pm\sqrt{\frac{EI}{P}} \left(\text{vers. } \sin^{-1}\frac{y}{a}\right) \quad . \quad . \quad . \quad (6)$$

(6) is the equation of the elastic curve DOC, Fig. 313 (a), and contains the deflection a. If P and a are both given, y can be computed for a given x, and vice versâ, and thus the curve traced out, but we would naturally suppose a to depend on P, for in eq. (6) when $x = \frac{1}{2}l$, y should $= a$. Making these substitutions we obtain

$$\frac{1}{2}l = \sqrt{\frac{EI}{P}} \left(\text{vers. } \sin^{-1} 1.00\right); \text{ i.e., } \frac{1}{2}l = \sqrt{\frac{EI}{P}} \cdot \frac{\pi}{2} \quad (7)$$

Since a has vanished from eq. (7) the value for P obtained from this equation, viz.:

$$P_0 = EI \frac{\pi^2}{l^2} \quad . \quad . \quad . \quad . \quad (8)$$

is independent of a, and is ∴ to be regarded as that force (at each end of the *round-ended* column in Fig. 313) which will *hold* the column at *any* small deflection at which it may previously have been set.

In other words, if the force is less than P_0 no flexure at all will be produced, and hence P_0 is sometimes called the force producing "incipient flexure." [This is roughly verified by exerting a downward pressure with the hand on the upper end of the flexible rod (a T-square-blade for instance) placed vertically on the floor of a room; the pressure must reach a definite value before a decided buckling takes place, and then a very slight increase of pressure occasions a large increase of deflection.]

It is also evident that a force slightly greater than P_0 would very largely increase the deflection, thus gaining for itself so great a lever arm about the middle section as to cause rupture. For this reason eq. (8) may be looked upon as giving the **Breaking Load** of a column with round ends, and is called *Euler's formula.*

Referring now to Fig. 311, it will be seen that if the three parts into which the flat-ended column is divided by its two points of inflection A and B are considered free, individually, in Fig. 315, the forces acting will be as there shown, viz.: At the points of inflection there is no stress-couple, and no shear, but only a thrust, $=P$, and hence the portion AB is in the condition of a round-ended column. Also, the tangents to the elastic curves at O and C being preserved vertical by the frictionless guide-blocks and guides (which are introduced here simply as a theoretical method of preventing the ends from turning, but do not interfere with vertical freedom) OA is in the same state of flexure as half of AB and under the same forces. Hence the length AB must = one half the total length l of the flat-ended column. In other words, the breaking load of a round-ended column of length $=\frac{1}{2}l$, is the same as that of a flat-ended column of length $=l$. Hence for the l of eq. (8) write $\frac{1}{2}l$ and we have as the breaking load of a column with flat-ends and of length $=l$.



Fig. 315.

$$P_1 = 4\,EI\frac{\pi^2}{l^2} \quad . \quad . \quad . \quad . \quad (9)$$

Similar reasoning, applied to the "pin-and-square" mode of support (in Fig. 311) where the points of inflection are at B, approximately $\frac{1}{3}\,l$ from C, and at the extremity O itself, calls for the substitution of $\frac{2}{3}\,l$ for l in eq. (8), and hence the breaking load of a "*pin-and-square*" column, of length $= l$, is

$$P_2 = \frac{9}{4}\,EI\,\frac{\pi^2}{l^2} \quad . \quad . \quad . \quad (10)$$

Comparing eqs. (8), (9), and (10), and calling the value of P_1 (flat-ends) unity, we derive the following statement:

The breaking loads of a given column are as the numbers

1	9/16	¼	according to the
flat-ends	*pin-and-square*	*round-ends*	mode of support.

These ratios are approximately verified in practice.

Euler's Formula [i.e., eq. (8) and those derived from it, (9) and (10)] when considered as giving the breaking load is peculiar in this respect, that it contains no reference to the stress per unit of area necessary to rupture the material of the column, but merely assumes that the load producing "incipient flexure", i.e., which produces any bending at all, will eventually break the beam because of the greater and greater lever arm thus gained for itself. In the cantilever of Fig. 241 the bending of the beam does not sensibly affect the lever-arm of the load about the wall-section, but with a column, the lever-arm of the load about the mid-section is almost entirely due to the deflection produced.

It is readily seen, from the form of eqs. (8), (9) and (10), that when l is taken quite small the values obtained for P_0, P_1, and P_2 become enormous, and far exceed what would be found from the formula for crushing load of a short block, viz., $P = FC$ (see p. 219), with F denoting the area of section of the prism and C the crushing unit-stress of the material. The degree of slenderness a column must have to justify the use of Euler's relations will appear in the next paragraph.

304. Euler's Formula Tested by Experiment.—Since the "moment of inertia," I, (referred to a certain axis) of the cross-section of the column may be written $I = Fk^2$, where k is the "*radius of gyration*" (see p. 91), and F the area of the plane figure, eq. (8), for "round ends," may be written

$$\left.\begin{array}{l}\text{"round}\\ \text{ends,"}\end{array}\right\} \quad \frac{P_0}{F} = \frac{\pi^2 E}{(l \div k)^2}. \quad \ldots\ldots\ldots \quad (11)$$

Here $P_0 \div F$ is the *average* unit-stress (compressive) on the cross-section and $l \div k$ is a ratio measuring the *slenderness* of the column. (Of course, when the column actually gives way by buckling, the unit-stress on the concave side at the middle of the length is much greater than the average). In the experiments by Christie, described on p. 112 of the *Notes and Examples*, the value of the ratio $l \div k$ ranges from 20 to 480.

As an **example** consider a $3'' \times 3'' \times \frac{1}{2}''$ angle-bar (or "angle") of wrought iron, with $l = 15$ ft., to be used as a column. Fig. 315*a* shows the cross-section of this shape, with dimensions. C is the center of gravity of this plane figure. Let the force be applied at each end of the column according to Christie's mode of "round ends," i.e., by a ball-bearing device, the force always passing through the point C of the section at each extremity of the column. Since the ends are free to turn in any plane, the axis of the column will deflect in the plane CN ⊥ to the axis 2...2 (of the plane figure) about which the values of I and of k are *least*. For this shape, we find from the handbook of the Cambria Steel Co., that k about axis 2...2 is the *least radius of gyration* and $= 0.58$ in.; also that



Fig. 315*a*.



Fig. 315*b*.

the area of the figure is $F = 2.75$ sq. in. Hence the "*slenderness-ratio*," $l \div k$, is $180'' \div 0.58'' = 310$; and from eq. (11) we have, with E for wrought iron taken as 25,000,000, lbs./in.^{2} (p. 279),

$$(P_0 \div F) = \pi^2 \times 25{,}000{,}000 \div (310)^2 = 2570 \text{ lbs./in.}^2;$$

while from the Christie experiments we find $(P_0 \div F) = 2650$ lbs./in.^{2} as the *average* unit-stress at rupture; a fairly close agreement with the Euler result. The total rupturing load would then be $P_0 = 2570 \times 2.75 = 7070$ lbs., and the *safe load*, with the "factor of safety" of 8 recommended in the Christie report, would be 884 lbs.

In this way it may be ascertained that for values of $l \div k$ from 200 to 400 for "round ends" and from 300 to 400 for fixed ends there is an approximate agreement between Euler's equations and the Christie experiments. But most of the columns used in engineering practice involve values of $l \div k$ less than 200, so that Euler's formulæ are not adapted to actual columns (though used to some extent in Germany). A formula of such nature as to be available for *all* degrees of slenderness has therefore been established (Rankine's, see next paragraph), based partly on theory and partly on experiment, which has obtained a very wide acceptance among engineers.

In Fig. 315*b* is shown a curve, E_r, resulting from plotting as abscissa and ordinate the values of $P_0 \div F$ and $l \div k$, as related in Euler's formula (8) for columns with round ends, for "medium" structural steel; with $E = 30{,}000{,}000$ lbs./in.^{2} E_f is a similar curve plotted from Euler's formula (9) for fixed ends for the same material. Each of these Euler curves is tangent to *both* axes at infinity. The other curves will be referred to later.

305. Rankine's Formula for Columns.—The formula of this name (some times called Gordon's, in some of its forms) has a somewhat more rational basis than Euler's, in that it introduces the maximum normal stress in the outer fibre and is applicable to a column or block of any length, but still contains assumptions not strictly borne out in theory, thus introducing some co-efficients requiring experimental determination. It may be developed as follows:

Since in the flat-ended column in Fig. 315 the middle portion AB, between the inflection points A and B, is acted on at each end by a thrust $= P$, not accompanied by any shear or stress-couple, it will be simpler to treat that

portion alone Fig. 316, (a), since the thrust and stress-couple induced in the section at R, the middle of AB, will be equal to those at the flat ends, O and C, in Fig. 315. Let a denote the deflection of R from the straight line AB. Now consider the portion AR as a free body in Fig. 316, (b), putting in the elastic forces of the section at R, which may be classified into a uniform thrust $= p_1F$, and a stress couple of moment $= \frac{p_2 I}{e}$, (see § 294). (The shear is evidently zero, from Σ(hor comps.) $= 0$). Here p_1 denotes the uniform pressure (per unit of area), due to the uniform thrust, and p_2 the pressure or tension (per unit of area), in the elastic forces constituting the stress-couple, on the outermost element of area, at a distance e from the gravity axis (⊥ to plane of flexure) of the section. F is the total area of the section. I is the moment of inertia about the said gravity axis, g



FIG. 316.

$$\Sigma \text{ (vert. comps.)} = 0 \text{ gives } P = p_1 F \quad . \quad . \quad (1)$$

$$\Sigma \text{ (moms.}_g\text{)} = 0 \text{ gives } Pa = \frac{p_2 I}{e} \quad . \quad . \quad . \quad . \quad (2)$$

For any section, n, between A and R, we should evidently have the same p_1 as at R, but a smaller p_2, since $Py < Pa$ while e, I, and F, do not change, the column being prismatic. Hence the max. (p_1+p_2) is on the concave edge at R and for safety should be no more than $C \div n$, where C is the Modulus of Crushing (§ 201) and n is a "factor of safety." Solving (1) and (2) for p_1 and p_2, and putting their sum $= C \div n$, we have

$$\frac{P}{F} + \frac{Pae}{I} = \frac{C}{n} \quad . \quad . \quad . \quad . \quad (3)$$

We might now solve for P and call it the safe load, but it

is customary to present the formula in a form for giving the *breaking load*, the factor of safety being applied afterward. Hence, we shall make $n=1$, and solve for P, calling it then the breaking load. Now the deflection a is unknown, but may be expressed approximately, as follows, in terms of e and l.

If we now consider ARB to be a circular arc, of radius $=\rho$, we have from geometry (similar triangles) $a=(l\div 4)^2\div 2\rho$; and if we equate the two expressions for the moment of the stress-couple at R there results $\frac{EI}{\rho}=\frac{p_2 I}{e}$ (see pp. 249 and 250). A combination of these two relations gives $ae=(p_2\div 32E)l^2$. Now under a safe load the total stress, p_1+p_2, in the outer fibre (concave side) at R will have reached a safe value, R', for the material, and is therefore constant for this material, and if the rude assumption is made that the portion p_2 of this stress is also constant, it follows that the fraction $(p_2\div 32E)$ $=$ a constant; which may be denoted by β, (an abstract number). Let us also write, for convenience, $I=Fk^2$, (k being the radius of gyration of the cross-section about a (gravity) axis through g ⊓ to paper). Hence finally, we have, from eq. (3),

$$\left.\begin{array}{l}\text{Breaking load}\\ \text{for flat ends}\end{array}\right\}=P_1=\frac{FC}{1+\beta(l\div k)^2}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

By the same reasoning as in § 303, for a round-ended column we substitute $2l$ for l; for a column with one end round and the other "flat" or "fixed" (i.e., for a "pin-and-square" column), $\frac{4}{3}l$ for l; and obtain

$$\left.\begin{array}{l}\text{Breaking load for a round-}\\ \text{ended column}\end{array}\right\}=P_0=\frac{FC}{1+4\beta(l\div k)^2}, \quad . \quad . \quad . \quad (5)$$

$$\left.\begin{array}{l}\text{Breaking load for a "pin-}\\ \text{and-square" column}\end{array}\right\}=P_2=\frac{FC}{1+1.78\beta(l\div k)^2}. \quad . \quad . \quad . \quad (6)$$

Each of these equations (4), (5), and (6), is known as *Rankine's Formula*, for the respective end-conditions mentioned. They find a very extended use among engineers in English-speaking countries; with some variation, however, in the

numerical values used for quantities C and β, which are constants for a given material; and also in the fraction of the breaking load which should be taken as the safe, or working, load (the reciprocal of this fraction being called the "factor of safety,") $=n$. A set of fair average values for these constants, as recommended by Rankine and others, is here presented:

	Hard Steel.	Medium Steel.	Soft Steel.	Wrought Iron.	Cast Iron.	Timber,
C (lbs./in.^{2})	70,000	50,000	45,000	36,000	70,000	7,200
β (abstract number)	$\frac{1}{25,000}$	$\frac{1}{36,000}$	$\frac{1}{36,000}$	$\frac{1}{36,000}$	$\frac{1}{6,400}$	$\frac{1}{3,000}$

The factor of safety, n, usually employed with the foregoing formulæ and constants, is $n=4$ for wrought iron and steel in quiescent structures; and 5 under moving loads, as in bridges; while $n=10$ should be used for timber and 8 for cast iron.

In Fig. 315*b* are two dotted curves, plotted for round ends (R_r) and fixed ends (R_f) in the case of *medium steel;* the above equations (Rankine), with the above values of C and β, having been used. The "slenderness ratio," $l \div k$, is the abscissa; and $P_0 \div F$, or $P_1 \div F$, (the average *breaking* unit-stress), is the ordinate, of any point. These curves may now be compared with the Euler curves, E_r and E_f, (in the same figure) already mentioned as having been plotted for structural steel (of modulus of elasticity $E=30,000,000$ lbs./in.^{2})

306. Examples; under the Rankine Formulæ.—EXAMPLE 1. Let it be required to compute the breaking load of a wrought-iron solid cylinder, used as a column, of length $l=8$ ft. and diameter, $=d$, $=2.4$ inches; with *round ends*, i.e., the pressure acting at each end at the center of the circular base, the ends being free to turn in any direction.

The "end conditions" call for the employment of the "least k," but here k is the same for any gravity axis of the circular section. That is we have

$$k^2 = I \div F = \tfrac{1}{4}\pi r^4 \div \pi r^2 = \tfrac{1}{4} r^2 = \tfrac{1}{4}(1.2)^2 = 0.36 \text{ in.}^2; \quad \therefore\ k = 0.6 \text{ in.}$$

and $(l \div k)$ = "slenderness-ratio" $= 96 \div 0.6 = 160$. Hence from eq. (5)

$$P_0 = \frac{\pi r^2 C}{1 + 4\beta(160)^2}; \text{ with } \beta = \frac{1}{36{,}000} \text{ and } C = 36{,}000 \text{ lbs./in.}^2; \text{ i.e.,}$$

$$P_0 = \frac{\pi(1.2)^2 36{,}000}{1 + 2.85} = \frac{162{,}800}{3.85} = 42{,}300 \text{ lbs.}$$

It is seen that, on account of the degree of slenderness of the column, the breaking load is about one quarter of what it would be for a short prism of same section.

With a factor of safety of 5 we should take $\frac{1}{5}$ of 42,300, i.e., 8460 lbs., as safe load.

Example 2.—It is required to compute the diameter, d, of a solid cast-iron cylinder, 16 ft. in length, to serve as a column with *flat ends*, whose safe load is to be 6 tons, the factor of safety being 6. This calls for the use of eq. (4) in which we put $P_1 = 6 \times 12{,}000 = 72{,}000$ lbs., the required breaking load; with $C = 70{,}000$ lbs./in.^{2} and $\beta = 1 \div 6400$. The least radius of gryation should be used, but in this case the k^2 is constant for all axes of the section, viz., $k^2 = \frac{1}{4}\pi r^4 \div \pi r^2 = d^2 \div 16$.

Hence from eq. (4) we have (for inch and pound)

$$P_1 = \frac{\frac{1}{4}\pi d^2 C}{1 + \pi(l \div k)^2} = \frac{54{,}980 d^2}{1 + \frac{1}{6400}[192 \div (\frac{1}{4}d)]^2} = 72{,}000 \text{ lbs.}$$

This on reduction leads to the bi-quadratic equation

$$d^4 - 1.309 d^2 = 120.7;$$

which being solved for d^2 gives $d^2 = 0.645 \pm 11.01$. The upper sign being taken we have, finally, $d = 3.41$ in. as the required diameter.

The "slenderness ratio," therefore, proves to be $192 \div 0.85 = 225$, which though seemingly high is not extreme for a flat-ended column; corresponding, as it does, to 112 for a round-ended column.

Example 3.—A prism of medium steel, of uniform rectangular section (solid) with dimensions $b = 3$ in. and $h = 1$ in., is to be subjected to a thrust (connecting-rod of a steam-engine). Its ends are provided with pins (see Fig. 312) capable of turning in firm bearings, the axis of each pin being ⊥ to

the "b" dimension of the rectangular section. The length between axes of pins, is $l=6$ ft. It is required to find the breaking load by the Rankine formulæ.

Since the end conditions would be "round-ends" if the axis of the column were to bend in a plane ⊥ to the axes of the pins (as in Fig. 312), but "flat-ends" [Fig. 311(b)] in case it bent in the plane containing the axes of the pins; and since the k of the section is different for the two cases, it will be necessary to make each supposition in turn and take the smaller of the two results for breaking load (i.e., as the one to which the factor of safety should be applied).

For round-ended buckling the value of k^2 is $I \div F = [hb^3 \div 12] \div bh = 0.75$ in.^{2}; and, with the values of C and β for medium steel, we have from eq. (5),

$$P_0 = \frac{50{,}000 \times 3.0}{1 + \frac{4}{36{,}000} \cdot \frac{(72)^2}{0.75}} = \frac{150{,}000}{1+0.768} = 84{,}800 \text{ lbs.};$$

while for flat-ended buckling, in the other plane, the k^2 to be used would be $k^2 = [bh^3 \div 12] \div bh = 0.0833$ in.^{2}, and hence from eq. (4)

$$P_1 = \frac{50{,}000 \times 3.0}{1 + \frac{1}{36{,}000} \cdot \frac{(72)^2}{0.0833}} = \frac{150{,}000}{1+1.73} = 54{,}933 \text{ lbs.}$$

It is seen that P_1 is smaller than P_0, so that with a factor of safety of 6 we have for the safe, or working, load, $\frac{1}{6}$ of 54,933, $= 9{,}155$ lbs.

307. Radii of Gyration.—The following table, taken from p. 523 of Rankine's Civil Engineering, gives values of k^2, the square of the *least* radius of gyration of the given cross-section about a gravity-axis. By giving the *least* value of k^2 it is implied that the plane of flexure is not determined by the end-conditions of the column (i. e., it is implied that the column has either flat ends or round ends). If either end (or both) is a *pin-joint* the column may need to be treated as having a flat-end as regards flexure in a plane containing the axis of the column and the axis of the pin, if the bearings of the pin are firm; while as regards flexure in a plane perpendicular to the pin it is to be considered round-ended at that extremity.

In the case of a "thin cell" the value of k^2 is strictly true for metal infinitely thin and of *uniform thickness*; still, if that thickness does not exceed $\frac{1}{8}$ of the exterior diameter, the form given is sufficiently near for practical purposes; similar statements apply to the branching forms.



FIG. 317.



FIG. 318.

Solid Rectangle. h= least side.	**Fig. 317 (*a*).**	$k^2 = \frac{1}{12}h^2$
Thin Square Cell. Side= h.	**Fig. 317 (*b*).**	$k^2 = \frac{1}{6}h^2$
Thin Rectangular Cell. h= least side.	**Fig. 317 (*c*).**	$k^2 = \frac{h^2}{12} \cdot \frac{h+3b}{h+b}$
Solid Circular Section. Diameter $=d$.	**Fig. 317 (*d*).**	$k^2 = \frac{1}{16}d^2$
Thin Circular Cell. Exterior diam. $= d$.	**Fig. 317 (*e*).**	$k^2 = \frac{1}{8}d^2$
Angle-Iron of Equal ribs	**Fig. 317 (*f*)**	$k^2 = \frac{1}{24} \cdot b^2$
Angle-Iron of unequal ribs.	**Fig. 318 (*a*).**	$k^2 = \frac{b^2h^2}{12(b^2+h^2)}$
Cross of equal arms.	**Fig. 318 (*b*).**	$k^2 = \frac{1}{24}b^2$
I-Beam as a pillar. Let area of web $=B$. " " " *both* flanges $=A$.	**Fig. 318 (*c*).**	$k^2 = \frac{b^2}{12} \cdot \frac{A}{A+B}$
Channel Iron.	**Fig. 318 (*d*).**	$k^2 = h^2 \left[\frac{A}{12(A+B)} + \frac{AB}{4(A+B)^2}\right]$

Let area of web $=B$; of flanges $=A$ (both). h extends from edge of flange to middle of web.

308. Built Columns.—The "compression members" of bridge trusses, and columns in steel framework buildings are generally composed of several pieces of structural steel riveted together, each column being thus formed of a combination of plates, channels, angles, Z-bars, etc. In Figs. 319 and 320



Fig. 319.



PHŒNIX COLUMN.

Fig. 320.

are shown examples of these compound shapes. The Phœnix column is seen to consist of four quadrantal segments riveted together. In Fig. 319 is a combination of two channels and one plate, these three pieces being continuous along the whole length of the column. On the side opposite to the plate are seen lattice bars, arranged in zig-zag, which serve to stiffen the column on that side. The center of gravity of the cross-section of this column is nearer to the edge carrying the plate than to the lattice edge; and if the ends of the column are provided with pins ⊣ to the webs of the channels the axis of each of these pins should be so placed as to contain the center of gravity of the cross-section of the column at that point.

The handbooks of the various steel companies present formulæ and tables enabling the breaking loads to be found for their various designs of built columns, and for single I-beams used as columns. For example, the tables given in the handbook of the Cambria Steel Co. for built columns of "medium steel" are stated to be computed from the following formulæ (which are evidently of the Rankine type).

The breaking load for a column of length l and with cross-section of area F and least radius of gyration k is (in pounds):

Square Bearing. Pin and Square Bearing. Pin Bearings.

$$P_1=\frac{50{,}000F}{1+\frac{1}{36{,}000}\cdot\left(\frac{l}{k}\right)^2};\quad P_2=\frac{50{,}000F}{1+\frac{1}{24{,}000}\cdot\left(\frac{l}{k}\right)^2};\quad P_0=\frac{50{,}000F}{1+\frac{1}{18{,}000}\left(\frac{l}{k}\right)^2}.$$

In these formulæ l and k should be in the same unit (both feet, or both inches; since $(l \div k)$ is a ratio) and the proper k to be used for the case of "pin and square bearing" (i.e., one end provided with a pin and the other with a square bearing) should be ascertained as in example 3, p. 371. To obtain the total safe load for the column: "For quiescent loads, as in buildings, divide by 4. For moving loads, as in bridges, divide by 5."

Considerable variety will be found among the formulæ of the Rankine type proposed by different engineers as best satisfying the results of experiment. For accounts of experiments beyond those already quoted in the author's "Notes and Examples in Mechanics," the reader is referred to special works. Kent's Pocket Book for Mechanical Engineers contains much valuable matter on the subject of columns. The handbooks of the Carnegie Steel Co., the Pencoyd Iron Works, and the Phœnix Iron Co., give extensive data relating to steel columns. Osborne's Tables of moments of inertia and radii of gyration of compound sections is a valuable book in this connection.

309. Moment of Inertia of Built Column. Example.—It is proposed to form a column by joining two I-beams by lattice-work, Fig. 321, (a). (While the lattice-work is relied upon to cause the beams to act together as one piece, it is not regarded in estimating the area F, or the moment of inertia, of the cross section). It is also required to find the proper distance apart $= x$, Fig. 321, at which these beams must be placed, from centre to centre of webs, that the liability to flexure shall be equal in all axial planes, i.e. that the I of the compound section shall be the same about all gravity axes. This condition will be fulfilled if I_Y can be made $= I_X$* (§ 89), O being the centre of gravity of the compound section, and X perpendicular to the parallel webs of the two equal I-beams.

Let F' = the sectional area of one of the I-beams, I'_Y (see Fig. 321(a) its moment of inertia about its web-axis, that about an axis ⌐ to web. (These quantities can be

* That is, with flat ends or ball ends; but with pin ends, Fig. 312, if the pin is ‖ to X, put $4I_Y = I_X$; if ‖ to Y, put $4I_X = I_Y$.

found in the hand-book of the iron company, for each size of rolled beam).

Then the

$$\text{total } I_X = 2I'_X; \text{ and total } I_Y = 2\left[I'_Y + F'\left(\frac{x}{2}\right)^2\right]$$

(see §88 eq. 4.) If these are to be equal, we write them so and solve for x, obtaining

$$x = \sqrt{\frac{4[I'_X - I'_Y]}{F'}} \quad \ldots\ldots \quad (1)$$

310. **Numerically**; suppose each girder to be a 10½ inch light I-beam, 105 lbs. per yard, of the N. J. Steel and Iron Co., in whose hand-book we find that for this beam $I'_X = 185.6$ biquad. inches, and $I'_Y = 9.43$ biquad. inches, while $F' = 10.44$ sq. inches. With these values in eq. (1) we have

$$x = \sqrt{\frac{4\ (185.6 - 9.43)}{10.44}} = \sqrt{67.5} = 8.21 \text{ inches.}$$



Fig. 321.

The square of the radius of gyration will be

$$k^2 = 2I'_X \div 2F' = 371.2 \div 20.88 = 17.7 \text{ sq. in.} \quad (2)$$

and is the *same for any gravity axis* (see § 89).

As an additional example, suppose the two I-beams united by plates instead of lattice. Let the thickness of the plate $= t$, Fig. 321, (*b*). Neglect the rivet-holes. The distance a is known from the hand-book. The student may derive a formula for x, imposing the condition that (total I_X) $= I_Y$.

310a. Design of Columns.—General considerations governing economy and efficiency in the design of built columns are that the various pieces, besides being continuous for the whole length, should be placed as far from the axis of the column as possible, in order to increase the value of k the (least) radius of gyration, thus leading to a larger value of the safe load for a given amount of material, or to a minimum amount of material for a given required safe load; and that the parts should be well fastened together by rivets, preventing all relative motion. The economy secured by placing the material as far from the center as possible also holds, of course, for single pieces used as columns. For example, if the safe load of a hollow cylindrical cast-iron flat-ended column, 20 ft. long, is to be 40 tons, i.e., 80,000 lbs., and the thickness of metal is not to be less than $\frac{7}{8}$ in., we find, after a few trials with Rankine's formula eq. (4), p. 369, taking a factor of safety of 8 (so that the breaking load would be 640,000 lbs.) that an outside diameter of $d=8$ in. is the largest permissible. Thus, taking the least k^2, $(=d^2 \div 8)$, from p. 373, for a thin cylindrical cell, with $l=240$ in., with the sectional area, F, as the quantity to be solved for, we have

$$\frac{70{,}000F}{1+\frac{1}{6400}\cdot\frac{(240)^2}{[8^2 \div 8]}} = 640{,}000 \text{ lbs.}; \quad \therefore F = 19.43 \text{ sq. in.}$$

Let d_2 denote the internal diameter of the section; then $\frac{\pi}{4}(8^2 - d_2^2) = 19.43$; whence $d_2 = 6.26$ in.; i.e., the thickness of metal $= \frac{1}{2}(d - d_2) = 0.87$ in., or practically $\frac{7}{8}$ in.

310b. The Merriman-Ritter-Formula for Columns was derived independently by Professors Merriman and Ritter (see *Engineering News*, July 19, 1894) and has a mathematical basis as follows. In Fig. 315*b* curves have been plotted for the Euler and Rankine formulæ for medium steel, both for flat and round ends; and it is seen that each of the Rankine curves is tangent to the horizontal line through V and is roughly parallel to, and not very distant from, the corresponding Euler curve on the extreme right. Professor Merriman derives the equation (of the same form as Rankine's) for a curve which has a horizontal tangent at V, and is *exactly* tangent

to the Euler curve at some point on the extreme right (at infinity, in fact) and thus secures a more rational value for the constant called β in Rankine's formula.

With P' denoting the *safe load* for the column and C' the *safe* compressive unit-stress for the material, this formula may be written . . . . $P' = \dfrac{FC'}{1 + \dfrac{nC''}{4\pi^2 E}\left(\dfrac{l}{k}\right)^2}$, ... (*M*)

where C'' denotes the unit compressive stress at *elastic limit*, E the modulus of elasticity, F the sectional area, and n an abstract number whose value (as before, in the Rankine formulæ) is 1, 16/9 (or 1.78), and 4, for flat ends, pin-and-square, and round ends, respectively.

If for Q we write P, the breaking load, and correspondingly C for C', and plot values of $P \div F$ and $l \div k$, the curve would not differ greatly from the Rankine curve in Fig. 120 for medium steel; and similarly for wrought iron; but for timber and cast iron the variation is considerable, and hence Prof. Merriman does not recommend the use of his formula for the latter two materials. (Crehore's formula differs from the above only in replacing C'' by C'.)

310c. The "Straight-Line Formula."—It will be noticed that in Fig. 315*b* the straight line connecting points A and C (medium steel, round ends) or A' and C' (medium steel, flat ends) would not vary widely from the Rankine curve, so that on account of its simplicity, when restricted to proper limiting values of the ratio $l \div k$, a straight line, or linear relation, between the quantity $P \div F$ and ratio $l \div k$ was proposed by Mr. T. H. Johnson (see Transac. Am. Soc. C. E., 1886, p. 530) for the breaking loads of columns of various materials. Among them are the following:

Wrought iron: Hinged ends, $P_0 = \left[42{,}000 - 157\left(\dfrac{l}{k}\right)\right]F$;

" " Flat ends, $P_1 = \left[42{,}000 - 128\left(\dfrac{l}{k}\right)\right]F$;

Mild steel: Hinged ends, $P_0 = \left[52{,}000 - 220\left(\dfrac{l}{k}\right)\right]F$;

" " Flat ends, $P_1 = \left[52{,}000 - 179\left(\dfrac{l}{k}\right)\right]F$.

In these formulæ P_0, or P_1, is *breaking load* in lbs., F = sectional area (in *sq. in.*), l = the length, and k is the least radius of gyration of the cross-section for flat ends (as for hinged ends, see example 3, § 306); l and k in same unit.

310d. The J. B. Johnson Parabolic Formula for Columns.—If in Fig. 315*a* a parabola be plotted with its axis vertical (and downward) and vertex at the point V of the two Rankine curves, and also made tangent to the Euler curve for the end conditions concerned, the points on such a curve for values of $l \div k$ between zero and the point of tangency to the Euler curve are found to agree fairly well with experiment; and the corresponding formula, or the equation to the curve, is of much simpler form than that of the Rankine types, being almost as simple as the straight line formula. Such a formula was proposed by the late Prof. J. B. Johnson, those for mild steel and wrought iron being given below (breaking load in lbs.).

Mild steel:

$$\text{Pin ends, } P_0 = \left[42{,}000 - 0.97\left(\frac{l}{k}\right)^2\right] F; \left(\frac{l}{k} \text{ not } > 150\right)$$

$$\text{Flat ends, } P_1 = \left[42{,}000 - 0.62\left(\frac{l}{k}\right)^2\right] F; \left(\frac{l}{k} \text{ not } > 190\right)$$

Wrought iron:

$$\text{Pin ends, } P_0 = \left[34{,}000 - 0.67\left(\frac{l}{k}\right)^2\right] F; \left(\frac{l}{k} \text{ not } > 170\right)$$

$$\text{Flat ends, } P_1 = \left[34{,}000 - 0.43\left(\frac{l}{k}\right)^2\right] F; \left(\frac{l}{k} \text{ not } > 210\right)$$

The notation is the same as in the preceding article. The limiting values mentioned for $l \div k$ refer to the points of tangency with the Euler curve. In Fig. 315*b* the curve VWX is a parabola fulfilling the above mathematical condition for medium steel, with flat ends.

311. Solid Wooden Columns and Posts. Formula of U. S. Dept. of Agriculture, Division of Forestry.—This formula was derived by Johnson from the results of experiments conducted by the Division of Forestry and applies to solid wooden columns provided with "*square ends*," the constraint due to which, however, is not to be considered as fully equivalent to that of "fixed ends." The breaking load being denoted by P_1,

the sectional area by F, the ratio of length l to the "*least dimension*," d, of the cross section, by m (i.e., $l \div d = m$), and the unit crushing stress for the material by C, the formula is

$$P_1 = \frac{(700+15m)FC}{700+15m+m^2}. \quad . \quad . \quad . \quad . \quad . \quad (F)$$

The values of C to be used for different kinds of timber are given as follows:

White oak and Georgia yellow pine	5000 lbs./in.^{2}
Douglas fir and short-leaf yellow pine	4500 "
Red pine, spruce, hemlock, cypress, chestnut, California redwood, and California spruce	4000 "
White pine and cedar	3500 "

The fraction of P_1 to be taken as the safe load depends on the wood and the degree of moisture present, four classes being designated in this respect; from Class A (18 per cent of moisture; timber exposed to weather), to Class D (10 per cent; timber at all times protected from the weather). For yellow pine the safe load should be from $0.20P_1$ for Class A to $0.31P_1$ for Class D. For all other timbers, from $0.20P_1$ for Class A to $0.25P_1$ for Class D.

312. Column under Eccentric Loading.—In Fig. 322 let the load P be applied at i, at a distance or "eccentricity" $= c$ from the center of gravity A of the upper base of the column, the reaction at the other end (at k) having an equal eccentricity from B; the ends of the column being free to turn. (In an extreme case Ai and Bk might be brackets fastened to the ends of the column.)



FIG. 322.

AOB is the elastic curve, or bent condition of the axis of the column, originally straight. With O as origin, any point n in the elastic curve has a vertical co-ordinate x and a horizontal co-ordinate y. The unknown lateral deflection of the point O from AB is a. With n *as any* point in the elastic curve, and nAi as free body, we have for the moment of the stress couple in section at n $EI[d^2y \div dx^2] = P(c+a-y)$; which is seen to differ from eq. (1) of p. 362 only in having the constant $c+a$ in place of the constant a. We may therefore use eq. (6) of p. 363 for the present case, after replacing a by $c+a$; and hence, denoting $\sqrt{P \div EI}$ by b, remembering that vers. sin. $= 1 - \cos$, we may write, as the equation to the elastic curve,

$$y = (c+a)[1 - \cos(bx)] \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

For $x = \frac{1}{2}l$, y should $=$ the deflection a; on substituting which values in (1) there results finally

$$a=c\left[\sec\left(\frac{bl}{2}\right)-1\right] \quad . \quad . \quad (2); \qquad \text{and} \qquad c+a=c\cdot\sec\left(\frac{bl}{2}\right). \quad . \quad . \quad (3)$$

Hence the moment of the stress couple at O is $M_0=P(c+a)=Pc\cdot\sec\left(\frac{bl}{2}\right)$ and the unit stress in outer fibre on concave side at O is

$$p=\frac{P}{F}+\frac{M_0e}{I}=\frac{P}{F}+\frac{Pc\sec(\frac{1}{2}bl)}{I}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

(In this case of eccentric loading, then, the deflection a is *not* indeterminate as was the case in deriving Euler's formula on p. 363. Note that $\frac{1}{2}bl$ is an angle in *radians*.)

Example.—Let the value of P be 10,000 lbs., the length of the column be $l=20$ ft. $=240$ in., and the cross-section be a square cell [see Fig. 317 (*b*)] 4 inches being the side of the outer square; area $F=7$ in.^{2} and $I=14.58$ in.^{4} Let the eccentricity be $c=2$ in., each force P being applied in the middle of a side of the 4 in. square. Let $E=30{,}000{,}000$ lbs./in.^{2}; material, medium steel. With this position of the force plane, $e=2$ in.

Here we have $\frac{1}{2}bl=\frac{1}{2}\left(\sqrt{\frac{10{,}000}{30{,}000{,}000\times14.58}}\right)\times240=0.5736$ radians, corresponding to 32° 52′, whose sec. $=1.190$; and therefore $a=2\times(1.190-1)=0.380$ in., and $M_0=10{,}000\times2\times1.190=23{,}800$ in.-lbs. Finally

$$p=\frac{10{,}000}{7}+\frac{23{,}800\times2}{14.58}=1430+3265=4695 \text{ lbs./in.}^2$$

With $P=20{,}000$ lbs., we should obtain $\frac{1}{2}bl=0.811$ radians (46° 30′), $a=0.906$ in., $M_0=57{,}120$ in.-lbs., and $p=2860+7835=10{,}695$ lbs./in.^{2}

This latter unit stress is seen to be only moderate in value for the material, leading to the conclusion that 20,000 lbs. for P is a safe load; but on account of the possible original lack of straightness in the column, and of lack of homogeneity, both of which causes might increase a and M_0, it would be better to limit the load to 15,000 lbs.; considering, also, the fact that Rankine's Formula for round ends (with a safety factor of 4) applied to this column for the case of *no* eccentricity would give about 22,000 lbs. as safe load.



FIG. 322*a*.

313. Beam or Column with Eccentric End Pressures and also under Uniform Transverse Loading.—For example, in Fig. 322*a* let AB be the bent axis of a beam, or column (originally straight), the longitudinal forces P and P being applied at an eccentricity c from A and B, while there is at the same time a vertical loading W, $=wl$, uniformly distributed along the

whole length at rate of w lbs. per running inch. The reactions of the two *end supports* will therefore be each $\frac{1}{2}W$. The ends of the column are free to turn. It is required to find the deflection a, the moment M_0 of the couple at middle section O, and the unit stress p on the concave side at O. Take the free body iAn, n being *any point* of the elastic curve AOB, with co-ordinates x and y referred to the horizontal and vertical axes through O as an origin, as shown. Then the moment of stress couple at n is

$$EI(d^2y \div dx^2) = P(c+a-y) + (\tfrac{1}{8})w(l^2-4x^2) \quad . \quad . \quad . \quad . \quad (5)$$

Since $(d^2y \div dx^2)$ is a variable, let us denote $(-EI \div P)(d^2y \div dx^2)$ by u, as an auxiliary variable; and eq. (5) will now read

$$y-u = c+a+[(\tfrac{1}{8})w(l^2-4x^2)] \div P \quad . \quad . \quad . \quad . \quad . \quad . \quad (6)$$

Differentiating (6) twice, with respect to x, we have

$$\frac{d^2y}{dx^2} - \frac{d^2u}{dx^2} = -\frac{w}{P}; \quad \text{that is,} \quad \frac{d^2u}{dx^2} = -\frac{P}{EI}u + \frac{w}{P}. \quad . \quad . \quad . \quad . \quad (7)$$

Multiplying (7) by $2du$, and denoting $P \div EI$ by b^2 and $2w \div P$ by h, we have by integration, (dx^2 is a constant, x being the independent variable), $(du)^2 \div (dx)^2 = -b^2u^2 + hu + C$, where C is a constant of integration; and hence $dx = du \div (\sqrt{C + hu - b^2u^2})$, which integrates into

$$x = \frac{1}{b} \cdot \sin^{-1}\left(\frac{2b^2u - h}{\sqrt{h^2 + 4Cb^2}}\right) + C', \quad . \quad . \quad . \quad . \quad . \quad . \quad (8)$$

where C' is a constant. Transformation of (8) gives

$$(\sqrt{h^2 + 4Cb^2}) \sin [b(x-C')] + h = 2b^2u \quad . \quad . \quad . \quad . \quad . \quad (9)$$

Eliminating u by aid of eqs. (6) and (9) we have

$$2b^2y = \sqrt{h^2 + 4Cb^2} \cdot \sin [b(x-C')] + h + 2b^2(c+a) + (\tfrac{1}{8})b^2h(l^2-4x^2) \quad (10)$$

from which

$$2b^2(dy/dx) = b\sqrt{h^2 + 4Cb^2} \cdot \cos [b(x-C')] - b^2hx \quad . \quad . \quad . \quad (11)$$

To determine the three constants C, C', and a, we now make use of the facts that in (10) when $x=0$, y also $=0$, and for $x=\frac{1}{2}l$, $y=a$; and that in (11) for $x=0$, dy/dx, must $=0$. The three equations thus obtained, containing constants only, enable us to determine C, C', and a, and insert their values in (10); thus giving us as *the equation to the elastic curve AOB*,

$$y = \left(c + \frac{h}{2b^2}\right)\left[\frac{1-\cos(bx}{\cos(\frac{1}{2}bl)}\right] - \tfrac{1}{4}hx^2; \quad . \quad . \quad . \quad . \quad . \quad (12)$$

as also the value of the deflection

$$a = [c + (h \div 2b^2)][\sec(\tfrac{1}{2}bl) - 1] - (\tfrac{1}{16})hl^2 \quad . \quad . \quad . \quad . \quad (13)$$

To find the moment of stress couple, M_0, at O, we have now only to substitute $x=0$ and $y=0$ in eq. (5), and for a its value from (13); and thus obtain

$$M_0 = P\left[\left(c + \frac{h}{2b^2}\right) \cdot \sec(\tfrac{1}{2}bl) - \frac{h}{2b^2}\right], \quad . \quad . \quad . \quad . \quad . \quad (14)$$

With F as the sectional area of the cross-section of the (prismatic) column (or beam, as it might also be called in this connection), and e as the distance of the outer fibre from the gravity axis of the section, we now have for p, the stress in outer fibre on concave side at O,

$$p = \frac{P}{F} + \frac{M_0e}{I} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (15)$$

Since b and h denote $\sqrt{P \div EI}$ and $2w \div P$, respectively, it is seen that when w is zero, h is zero and eq. (13) reduces to eq. (2) of the previous article. Again, if the two forces P are central, i.e., applied at A and B, we put $c=0$; in which case an approximate result may be reached by writing for the deflection a the value it would have if the end forces P were not present, i.e., $\frac{5}{384} \cdot \frac{Wl^3}{EI}$, as due to the uniform load W alone (see p. 260). On this basis the value of M_0 is $Pa + (\frac{5}{8})Wl$.

(In case the vertical load on the beam or column in Fig. 322*a* is a single load Q concentrated in the middle at O, a treatment similar to the foregoing may be applied, but is somewhat more complicated. For details of such a case the reader is referred to *Mecanique Appliquee*, by Bresse, Tome I. p. 384.)

314. Buckling of Web-Plates in Built Girders.—In §257 mention was made of the fact that very high web plates in built beams, such as *I* beams and box-girders, might need to be stiffened by riveting "angles" on the sides of the web. (The girders here spoken of are horizontal ones, such as might be used for carrying a railroad over a short span of 20 to 50 feet.

An approximate method of determining whether such stiffening is needed to prevent lateral buckling of the web, may be based upon Rankine's formula for a long column and will now be given.

In Fig. 323 we have, free, a portion of a bent I-beam, between two vertical sections at a distance apart $= h_1 =$ the height of the web. In such a beam under forces ⊥ to its axis it has been proved (§256) that we may consider the web to sustain all the shear, J, at any section, and the flanges to take all the tension and compression, which form the "*stress-couple*" of the section. These couples and the two shears are shown in Fig. 323, for the two exposed sections. There is supposed to be no load on this portion of the beam, hence the shears at the two ends are



Fig. 323.



Fig. 324.



Fig. 325.

equal. Now the shear acting between each flange and the horizontal edge of the web is equal in intensity per square inch to that in the vertical edge of the web; hence if the web alone, of Fig. 323, is shown as a free body in Fig. 324, we must insert two horizontal forces $= J$, in opposite directions, on its upper and lower edges. Each of these $= J$ since we have taken a horizontal length h_1 = height of web. In this figure, 324, we notice that the effect of the acting forces is to lengthen the diagonal BD and shorten the diagonal AC, both of those diagonals making an angle of 45° with the horizontal.

Let us now consider this buckling tendency along AC, by treating as free the strip AC, of small width $= b_1$. This is shown in Fig. 325. The only forces acting in the direction of its length AC are the components along AC of the four forces J' at the extremities. We may therefore treat the strip as a long column of a length $l = h_1\sqrt{2}$, of a sectional area $F = bb_1$, (where b is the thickness of the web plate), with a value of $k^2 = {}^1/_{12}\, b^2$ (see § 309), and with fixed (or flat) ends. Now the sum of the longitudinal components of the two J''s at A is $Q = 2\, J'\, {}^1/_2\, \sqrt{2} = J'\sqrt{2}$; but J' itself $= \frac{J}{bh_1}\, b\, {}^1/_2\, b_1\sqrt{2}$, since the small rectangle on which J' acts has an area $= b\, {}^1/_2\, b_1\sqrt{2}$, and the shearing stress on it has an intensity of $(J \div bh_1)$ per unit of area. Hence the longitudinal force at each end of this long column is

$$Q = \frac{b_1}{h_1} J \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

According to eq. (4) and the table in § 305, the *safe load* (factor of safety = 4) for a *medium steel* column of this form, with flat ends, would be (pound and inch)

$$P_1 = \frac{\frac{1}{4} bb_1 50{,}000}{1 + \frac{1}{36{,}000} \cdot \frac{2h_1^2}{{}^1/_{12} b^2}} = \frac{12{,}500 bb_1}{1 + \frac{1}{1{,}500} \cdot \frac{h_1^2}{b^2}} \quad . \quad . \quad (2)$$

If, then, in any particular locality of the girder (of *medium steel*) we find that Q is $> P_1$, i.e.

$$\text{if } \frac{J}{h_1} \text{ is } > \frac{12{,}500b}{1+\frac{1}{1{,}500}\cdot\frac{h_1^2}{b^2}} \text{ (pound and inch).} \quad . \quad (3)$$

then vertical stiffeners will be required laterally.

When these are required, they are generally placed at intervals equal to h_1, (the depth of web), along that part of the girder where Q is $>P_1$.

EXAMPLE Fig. 326.—Will stiffening pieces be required in a plate girder of 20 feet span, bearing a uniform load of 40 tons, and having a web 24 in. deep and $\frac{3}{8}$ in. thick?



FIG. 326.

From § 242 we know that the greatest shear, J max., is close to either pier, and hence we investigate that part of the girder first.

J max. $=\frac{1}{2}W=20$ tons $=40{,}000$ lbs.

$\therefore$ (inch and lb.), see (3),

$$\frac{J}{h_1}=\frac{40{,}000}{24}=1666.6 \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

while, see (3), (inch and pound),

$$\frac{12{,}500\times\frac{3}{8}}{1+\frac{1}{1{,}500}\cdot\frac{24^2}{(\frac{3}{8})^2}}=1270 \quad . \quad . \quad . \quad . \quad . \quad (5)$$

which is less than 1666.66.

Hence stiffening pieces will be needed near the extremities of the girder. Also, since the shear for this case of loading diminishes uniformly toward zero at the middle they will be needed from each end up to a distance of $\frac{1270}{1666}$ of 10 ft. from the middle.

CHAPTER VII.

LINEAR ARCHES (OF BLOCKWORK).

315. A Blockwork Arch is a structure, spanning an opening or gap, depending, for stability, upon the resistance to *compresssion* of its blocks, or *voussoirs*, the material of which, such as stone or brick, is not suitable for sustaining a tensile strain. Above the voussoirs is usually placed a load of some character, (e.q. a roadway,) whose pressure upon the voussoirs will *be considered as vertical*, only. This condition is not fully realized in practice, unless the load is of cut stone, with vertical and horizontal joints resting upon voussoirs of corresponding shape (see Fig. 327), but sufficiently so to warrant its assumption in theory. Symmetry of form about a vertical axis will also be assumed in the following treatment.



FIG. 327.

316. Linear Arches.—For purposes of theoretical discussion the voussoirs of Fig. 327 may be considered to become infinitely small and infinite in number, thus forming a "linear arch," while retaining the same shapes, their depth ⊓ to the face being assumed constant that it may not appear in the formulae. The joints between them are ⊓ to the curve of the arch, i.e., adjacent voussoirs can exert pressure on each other only in the direction of the tangent-line to that curve.

317. Inverted Catenary, or Linear Arch Sustaining its Own Weight Alone.—Suppose the infinitely small voussoirs to have weight, uniformly distributed along the curve, weighing q lbs. per running linear unit. The equilibrium of such a structure, Fig. 328, is of course unstable but theoretically possible. Required the form of the curve when equilibrium exists. The conditions of equilibrium are, obviously: 1st. The thrust or mutual pressure T between any two adjacent voussoirs at any point, A, of the curve must be tangent to the curve; and 2ndly, considering a portion BA as a free body, the resultant of H_0 the pres-



Fig. 328.



Fig. 329.



Fig. 330.

sure at B the crown, and T at A, must balance R the resultant of the ∥ vertical forces (i.e., weights of the elementary voussoirs) acting between B and A.

But the conditions of equilibrium of a flexible, inextensible and uniformly loaded cord or chain are the very same (weights uniform along the curve) the forces being reversed in direction. Fig. 329. Instead of compression we have tension, while the ∥ vertical forces act toward instead of away from, the axis X. Hence the curve of equilibrium of Fig. 328 is an inverted catenary (see § 48) whose equation is

$$y+c=\tfrac{1}{2}c\left[e^{\frac{x}{c}}+e^{-\frac{x}{c}}\right] \quad \ldots\ldots \quad (1)$$

See Fig. 330. $e = 2.71828$ the Naperian Base. The "parameter" c may be determined by putting $x = a$, the half span, and $y = OY$, the *rise*, then solving for c by successive

approximations. The "*horizontal thrust*," or H_0, is $= qc$, while if s = length of arch OA, along the curve, the thrust T at any point A is

$$T = \sqrt{H_0^2 + q^2 s^2} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (2.)$$

From the foregoing it may be inferred that a series of voussoirs of *finite dimensions*, arranged so as to contain the catenary curve, with joints ⊓ to that curve and of equal weights for equal lengths of arc will be in equilibrium, and moreover in *stable* equilibrium on account of friction, and the finite width of the joints; see Fig. 331.



Fig. 331.

318. **Linear Arches under Given Loading.**—The linear arches to be considered further will be treated as without weight themselves but as bearing vertically pressing loads (each voussoir its own).

Problem.—Given the form of the linear arch itself, it is required to find the law of vertical depth of loading under which the given linear arch will be in equilibrium. Fig. 332, given the curve ABC, i.e., the linear arch itself, required the form of the curve MON, or upper limit of loading, such that the linear arch ABC shall be in equilibrium under the loads lying between the two curves. The loading is supposed homogeneous and of constant depth ⊓ to paper; so that the ordinates z between the two curves are proportional to the *load per horizontal linear unit*. Assume a height of load z_0 at the crown, at pleasure; then required the z of any point m as a function of z and the curve ABC.



Fig. 332.



Fig. 333.

Practical Solution.—Since a linear arch under vertical pressures is nothing more than the inversion of the curve assumed by a cord loaded in the same way, this problem might be solved mechanically by experimenting with a light cord, Fig. 333, to which are hung other *heavy* cords, or bars of uniform weight per unit length, and at equal horizontal distances apart *when in equilibrium.* By varying the lengths of the bars, and their points of attachment, we may finally find the curve sought, *MON.* (See also § 343.)

Analytical Solution.—Consider the structure in Fig. 334. A number of rods of finite length, in the same plane, are in equilibrium, bearing the weights P, P_1, etc., at the con-



Fig. 334.



Fig. 335.

necting joints, each piece exerting a thrust T against the adjacent joint. The joint A, (the "pin" of the hinge), imagined separated from the contiguous rods and *hence free,* is held in equilibrium by the vertical force P (a load) and the two thrusts T and T', making angles $= \theta$ and θ' with the vertical; Fig. 335 shows the joint A free. From Σ(horizontal comps.)$=0$, we have

$$T \sin \theta = T' \sin \theta'.$$

That is, the horizontal component of the thrust in any rod is the same for all; call it H_0. $\therefore$

$$T = \frac{H_0}{\sin \theta} \qquad (1)$$

Now draw a line As ⌐ to T' and write Σ (compons. ∥ to As)$=0$; whence $P \sin \theta' = T \sin \beta$, and [see (1)]

$$\therefore P = \frac{H_0 \sin \beta}{\sin \theta \sin \theta'} \qquad (2)$$

Let the rods of Fig. 334 become infinitely small and infinite in number and the load continuous. The length of each rod becomes $=ds$ an element of the linear arch. β is the angle between two consecutive ds's, θ is the angle between the tangent line and the vertical, while P becomes the load resting on a single dx, or horizontal distance between the middles of the two ds's. That is, Fig. 336, if $\gamma =$ weight of a cubic unit of the loading, $P = \gamma z dx$. (The lamina of arch and load considered is unity, ⌐ to paper, in thickness.) $H_0 =$ a constant $=$ thrust at crown O; $\theta = \theta'$, and $\sin \beta = ds \div \rho$, (since the angle between two consecutive tangents is $=$ that between two consecutive radii of curvature). Hence eq. (2) becomes



Fig. 336.

$$\gamma z dx = \frac{H_0 ds}{\rho \sin^2 \theta} \text{ ; but } dx = ds \sin \theta,$$

$$\therefore \gamma z = \frac{H_0}{\rho \sin^3 \theta} \quad . \quad . \quad . \quad . \quad (3)$$

Call the radius of curvature at the crown ρ_0, and since there $z = z_0$ and $\theta = 90°$, (3) gives $\gamma z_0 \rho_0 = H_0$; hence (3) may be written

$$z = \frac{z_0 \rho_0}{\rho \sin^3 \theta} \quad . \quad . \quad . \quad . \quad (4)$$

This is the law of vertical depth of loading required. For a point of the linear arch where the tangent line is vertical, $\sin \theta = 0$ and z would $= \infty$; i.e., the load would be *in-*

finitely high. Hence, in practice, a full semi-circle, for instance, could not be used as a linear arch.

319. Circular Arc as Linear Arch.—As an example of the preceding problem let us apply eq. (4) to a circular arc, Fig. 337, as a linear arch. Since for a circle ρ is constant $=r$, eq. (4) reduces to

$$z = \frac{z_0}{\sin^3\theta} \quad . \quad (5)$$



FIG. 337.

Hence the depth of loading must vary inversely as the cube of the sine of the angle θ made by the tangent line (of the linear arch) with the vertical.

To find the depth z by **construction.**—Having z_0 given, C being the centre of the arch, prolong Ca and make $ab = z_0$; at b draw a ⌝ to Cb, intersecting the vertical through a at some point d; draw the horizontal dc to meet Ca at some point c. Again, draw ce ⌝ to Cc, meeting ad in e; then $ae = z$ required; a being any point of the linear arch. For, from the similar right triangles involved, we have

$$z_0 = \overline{ab} = \overline{ad}\,\sin\theta = \overline{ac}\,\sin\theta.\,\sin\theta = \overline{ae}\,\sin\theta\,\sin\theta\,\sin\theta$$

$$\therefore\ \overline{ae} = \frac{z_0}{\sin^3\theta};\ \text{i.e.,}\ \overline{ae} = z. \qquad \textit{Q.E.D.}$$

[see (5.)]

320. Parabola as Linear Arch.—To apply eq. 4 § 318 to a parabola (axis vertical) as linear arch, we must find values of ρ and ρ_0 the radii of curvature at any point and the crown respectively. That is, in the general formula,

$$\rho = \left[1 + \left(\frac{dy}{dx}\right)^2\right]^{\frac{3}{2}} \div \frac{d^2y}{dx^2}$$

we must substitute the forms for the first and second differential co-efficients, derived from the equation of the



FIG. 338.



FIG. 339.

curve (parabola) in Fig. 338, i.e. from $x^2 = 2py$; whence we obtain

$$\frac{dy}{dx}, \text{or } \cot\theta, = \frac{x}{p} \text{ and } \frac{d^2y}{dx^2} = \frac{1}{p}$$

$$\text{Hence } \rho = \frac{(\sqrt{1+\cot^2\theta})^3}{1 \div p} = p \operatorname{cosec}.^3\theta, \text{ i.e. } \rho = \frac{p}{\sin^3\theta} \quad . \quad . \quad . \quad (6)$$

At the vertex $\theta = 90^\circ \therefore \rho_0 = p$. Hence by substituting for ρ and ρ_0 in eq. (4) of § 318 we obtain

$$z = z_0 = \text{constant [Fig. 339]} \quad . \quad . \quad . \quad . \quad . \quad (7)$$

for a parabolic linear arch. Therefore the depth of homogeneous loading must be the same at all points as at the crown; i.e., the load is uniformly distributed with respect to the horizontal. This result might have been anticipated from the fact that a cord assumes the parabolic form when its load (as approximately true for suspension bridges) is uniformly distributed horizontally. See § 46 in Statics and Dynamics.

321. Linear Arch for a Given Upper Contour of Loading, the arch itself being the unknown lower contour. Given the upper curve or limit of load and the depth z_0 at crown, required the form of linear arch which will be in equilibrium under the homogenous load between itself and that upper curve. In Fig. 340 let *MON* be the given upper contour of load, z_0 is given or assumed, z' and z'' are the respective ordinates of the two curves *BAC* and *MON*. Required the eqation of *BAC*.



FIG. 340.



FIG. 341.

As before, the loading is homogenous, so that the weights of any portions of it are proportional to the corresponding areas between the curves. (Unity thickness ⊥ to paper.) Now, Fig. 341, regard two consecutive ds's of the linear arch as two links or consecutive blocks bearing at their junction m the load $dP = \gamma\,(z' + z'')\,dx$ in which γ denotes the heaviness of weight of a cubic unit of the loading. If T and T' are the thrusts exerted on these two blocks by their neighbors (here supposed removed) we have the three forces dP, T and T', forming a system in equilibrium. Hence from $\Sigma X = 0$,

$$T \cos \varphi = T' \cos \varphi' \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

and

$$\Sigma Y = 0 \text{ gives } T' \sin \varphi' - T \sin \varphi = dP \quad . \quad . \quad . \quad (2)$$

From (1) it appears that $T \cos \varphi$ is constant at all points of the linear arch (just as we found in § 318) and hence = the thrust at the crown, = H, whence we may write

$$T = H \div \cos \varphi \text{ and } T' = H \div \cos \varphi' \quad . \quad . \quad . \quad (3)$$

Substituting from (3) in (2) we obtain

$$H\,(\tan \varphi' - \tan \varphi) = dP \quad . \quad . \quad . \quad . \quad . \quad (4)$$

But $\tan \varphi = \dfrac{dz'}{dx}$ and $\tan \varphi' = \dfrac{dz' + d^2z'}{dx}$, ($dx$ constant)

while $dP = \gamma\,(z' + z'')\,dx$. Hence, putting for convenience $H = \gamma a^2$, (where a = side of an imaginary *square* of the

loading, whose thickness = unity and whose weight = H) we have.

$$\frac{d^2z'}{dx^2}=\frac{1}{a^2}(z'+z'') \quad \ldots\ldots\ldots \quad (5)$$

as a relation holding good for any point of the linear arch which is to be in equilibrium under the load included between itself and the given curve whose ordinates are z'', Fig. 340.

322. Example of Preceding. Upper Contour a Straight Line.— Fig. 342. Let the upper contour be a right line and horizontal; then the z'' of eq. 5 becomes zero at all points of ON. Hence drop the accent of z' in eq. (5) and we have

$$\frac{d^2z}{dx^2}=\frac{z}{a^2}$$

Multiplying which by dz we obtain

$$\frac{dz\ d^2z}{dx^2}=\frac{1}{a^2}zdz \quad \ldots\ldots\ldots \quad (6)$$

This being true of the z, dz, d^2z and dx of each element of the curve $O'B$ whose equation is desired, conceive it written out for each element between O' and *any point* m, and put the sum of the left-hand members of these equations = to that of the right-hand members, remembering that a^2 and dx^2 are the same for each element. This gives

$$\frac{1}{dx^2}\int_{dz=0}^{dz=dz} dz\ d^2z=\frac{1}{a^2}\int_{z=z_0}^{z=z} zdz;\ \text{i.e.,}\ \frac{1}{dx^2}\cdot\frac{dz^2}{2}=\frac{1}{a^2}\left[\frac{z^2}{2}-\frac{z_0^2}{2}\right]$$

$$\therefore\ dx=\frac{adz}{\sqrt{z^2-z_0^2}}=a\cdot\frac{d\left(\frac{z}{z_0}\right)}{\sqrt{\left(\frac{z}{z_0}\right)^2-1}} \quad \ldots\ldots \quad (7.)$$



FIG. 342.



FIG. 343

Integrating (7.) between O' and any point m

$$\left[_0^x = a\left[_{z_0}^z \log._e\left(\frac{z}{z_0}+\sqrt{\left(\frac{z}{z_0}\right)^2-1}\right)\right. \quad . \quad . \quad (8)'$$

i.e., $x = a \log._e \left[\frac{z}{z_0}+\sqrt{\left(\frac{z}{z_0}\right)^2-1}\right]$; . . . . (8.)

or $z = \frac{z_0}{2}\left[e^{\frac{x}{a}}+e^{\frac{-x}{a}}\right]$ . . . . . (9.)

This curve is called the **transformed catenary** since we may obtain it from a common catenary by altering all the ordinates of the latter in a constant ratio, just as an ellipse may be obtained from a circle. If in eq. (9) a were $= z_0$ the curve would be a common catenary.

Supposing z_0 and the co-ordinates x_1 and z_1 of the point B (abutment) given, we may compute a from eq. 8 by putting $x = x_1$ and $z = z_1$, and solving for a. Then the crown-thrust $H = \gamma a^2$ becomes known, and a can be used in eqs. (8) or (9) to plot points in the curve or linear arch. From eq. (9) we have

$$\left.\begin{matrix}\text{area}\\ OO'mn\end{matrix}\right\} = \int_0^x z\,dx = \frac{z_0}{2}\int_0^x \left[e^{\frac{x}{a}}\,dx + e^{\frac{-x}{a}}\,dx\right] = \frac{az_0}{2}\left[e^{\frac{x}{a}} - e^{\frac{-x}{a}}\right] \quad . \quad (10)$$

Fig. 343.

Call this area, A. As for the thrusts at the different joints of the linear arch, see Fig. 343, we have crown-thrust $= H = \gamma a^2$ . . . ; . . . . (11)
and at any joint m the thrust

$$T = \sqrt{H^2+(\gamma A)^2} = \gamma\sqrt{a^4+A^2} \quad . \quad . \quad . \quad . \quad (12)$$

323. Remarks.—The foregoing results may be utilized with arches of finite dimensions by making the arch-ring contain the imaginary linear arch, and the joints ⌐ to the curve of the same. Questions of friction and the resistance of the material of the voussoirs are reserved for a succeeding chapter, (§ 344) in which will be advanced a more practical theory dealing with approximate linear arches or "equilibrium polygons" as they will then be called. Still, a study of exact linear arches is valuable on many accounts. By inverting the linear arches so far presented we have the forms assumed by flexible and inextensible cords loaded in the same way.

CHAPTER VIII.

ELEMENTS OF GRAPHICAL STATICS.

324. Definition.—In many respects graphical processes have advantages over the purely analytical, which recommend their use in many problems where celerity is desired without refined accuracy. One of these advantages is that gross errors are more easily detected, and another that the relations of the forces, distances, etc., are made so apparent to the eye, in the drawing, that the general effect of a given change in the data can readily be predicted at a glance.

Graphical Statics is the system of geometrical constructions by which problems in Statics may be solved by the use of drafting instruments, forces as well as distances being represented in amount and direction by lines on the paper, of proper length and position, according to arbitrary scales; so many feet of distance to the linear inch of paper, for example, for distances; and so many pounds or tons to the linear inch of paper for forces.

Of course results should be interpreted by the same scale as that used for the data. The parallelogram of forces is the basis of all constructions for combining and resolving forces.

325. Force Polygons and Concurrent Forces in a Plane.—If a material point is in equilibrium under three forces P_1 P_2 P_3 (in the same plane of course) Fig. 344, any one of them,

as P_1, must be equal and opposite to R the resultant of the other two (diagonal of their parallelogram). If now we lay off to some convenient scale a line in Fig. 345 = P_1 and ∥ to P_1 in Fig. 344; and then from the *pointed* end of P_1 a line equal and ∥ to P_2 and laid off *pointing the same way*, we note that the line remaining to close the triangle in Fig. 345 must be = and ∥ to P_3, since that triangle is nothing more than the left-hand half-parallelogram of Fig. 344. Also, in 345, to *close* the triangle properly the directions of the arrows must be continuous *Point to Butt*, round the periphery. Fig. 345 is called a **force polygor**; of three sides only in this case. By means of it, given any two of the three forces which hold the point in equilibrium, the third can be found, being equal and ∥ to the side necessary to "close" the force polygon.



FIG. 344.



FIG. 345.

Similarly, if a number of forces in a plane hold a material point in equilibrium, Fig. 346, their force polygon,



FIG. 346.

FIG. 347.

Fig. 347, must close, whatever be the order in which its sides are drawn. For, if we combine P_1 and P_2 into a resultant Oa, Fig. 346, then this resultant with P_3 to form a resultant Ob, and so on; we find the resultant of P_1, P_2, P_3, and P_4 to be Oc, and if a fifth force is to produce equilibrium it must be equal and opposite to Oc, and would close the polygon $OdabcO$, in which the sides are equal and par-

allel respectively to the forces mentioned. To utilize this fact we can dispense with all parts of the parallelograms in Fig. 346 except the sides mentioned, and then proceed as follows in Fig. 347:

If P_5 is the unknown force which is to balance the other four (i.e, is their *anti-resultant*), we draw the sides of the force polygon from A round to B, making each line parallel and equal to the proper force and pointing the same way; then the line BA represents the required P_5 in amount and direction, since the arrow BA must follow the continuity of the others (point to butt).

If the arrow BA were pointed at the extremity B, then it gives, obviously, the amount and direction of the *resultant* of the four forces $P_1 \ldots P_4$. The foregoing shows that if a system of **Concurrent Forces in a Plane** is in equilibrium, its *force polygon must close.*

326. Non-Concurrent Forces in a Plane.—Given a system of non-concurrent forces in a plane, acting on a rigid body, required graphic means of finding their resultant and anti-resultant; also of expressing conditions of equilibrium. The resultant must be found in *amount* and *direction*; and also in *position* (i.e., its *line of action* must be determined). E. g., Fig. 348 shows a curved rigid beam fixed in a vise at T, and also under the action of forces P_1 P_2 P_3 and P_4 (*besides* the action of the vise); required the resultant of P_1, P_2, P_3, and P_4. By the ordinary parallelogram of forces we combine P_1 and P_2 at a, the intersection of their lines of action, into a resultant R_a; then R_a with P_3 at b, to form R_b; and finally R_b with P_4 at c to form R_c which is $\therefore$ the resultant required, i.e., of $P_1 \ldots P_4$; and $c \ldots F$ is its line of action.



FIG. 348.

The separate force triangles (half-parallelograms) by which the successive partial resultants R_a, etc., were found, are again drawn in Fig. 349. Now since R_c, acting in the line $c \ldots F$, Fig. 348, is the resultant of $P_1 \ldots P_4$, it is plain that a force R_c' equal to R_c and acting along $c \ldots F$, but in the opposite direction, would balance the system $P_1 \ldots P_4$, (is their anti-resultant). That is, the forces $P_1 P_2 P_3 P_4$ and R_c' would form a system in equilibrium. The force R_c' then, represents the action of the vise T upon the beam. Hence replace the vise by the force R_c' acting in the line $\ldots F \ldots c$; to do which requires us to imagine a rigid prolongation of that end of the beam, to intersect $F \ldots c$. This is shown in Fig. 350 where the whole beam is *free*, in equilibrium, under the forces shown, and in precisely the same state of stress, part for part, as in Fig. 348. Also, by combining in one force diagram, in Fig. 351, all the force triangles of Fig. 349 (by making their common sides coincide, and putting R_c' instead of R_c, and dotting all forces other than those of Fig. 350), we have a figure to be interpreted in connection with Fig. 350.



FIG. 349.



SPACE DIAGRAM
FIG. 350.



FORCE DIAGRAM
FIG. 351.

Here we note, first, that in the figure called a force-diagram, $P_1 P_2 P_3 P_4$ and R_c' form a closed polygon and that

their arrows follow a continuous order, point to butt, around the perimeter; which proves that one condition of equilibrium of a system of non-concurrent forces in a plane is that its force polygon must close. Secondly, note that *ab* is ‖ to *Oa'*, and *bc* to *Ob'*; hence if the force-diagram has been drawn (including the rays, dotted) in order to determine the amount and direction of R_c', or any other one force, we may then find its line of action in the space-diagram, as follows: (N. B.—By space diagram is meant the figure showing to a true scale the form of the rigid body and the lines of action of the forces concerned). Through *a*, the intersection of P_1 and P_2, draw a line ‖ to *Oa'* to cut P_3 in some point *b*; then through *b* a line ‖ to *Ob'* to cut P_4 at some point *c*; *cF* drawn ‖ to *Oc'* is the required line of action of R_c', the anti-resultant of P_1, P_2, P_3, and P_4.

abc is called an **equilibrium polygon**; this one having but two *segments*, *ab* and *bc* (sometimes the lines of action of P_1 and R_c' may conveniently be considered as segments.) *The segments of the equilibrium polygon are parallel to the respective rays of the force diagram.*

Hence for the equilibrium of a system of **non-concurrent forces** in a plane *not only must its force polygon close*, but also the first and last segments of the corresponding equilibrium polygon must coincide with the resultants of the first two forces, and of the last two forces, respectively, of the system. *E.g.*, *ab* coincides with the line of action of the resultant of P_1 and P_2; *bc* with that of P_4 and R'_c. Evidently the equil. polygon will be different with each different order of forces in the force polygon or different choice of a **pole**, *O*. But if the order of forces be taken as above, *as they occur along the beam*, or structure, and the pole taken at the "*butt*" of the first force in the force polygon, there will be only one; (and this one will be called the **special equilibrium polygon** in the chapter on arch-ribs, and the "true linear arch" in dealing with the stone arch.) After the **rays** (dotted in Fig. 351) have been added, by joining the pole to each

vertex with which it is not already connected, the final figure may be called the *force diagram.*

It may sometimes be convenient to give the name of rays to the two forces of the force polygon which meet at the pole, in which case the first and last segments of the corresponding equil. polygon will coincide with the lines of action of those forces in the **space-diagram** (as we may call the representation of the body or structure on which the forces act). This "space diagram" shows the real field of action of the forces, while the force diagram, which may be placed in any convenient position on the paper, shows the *magnitudes* and directions of the forces acting in the former diagram, its lines being interpreted on a scale of so many *lbs.* or *tons* to the inch of paper; in the space-diagram we deal with a scale of so many *feet* to the inch of paper.

We have found, then, that if any vertex or corner of the closed force polygon be taken as a pole, and rays drawn from it to all the other corners of the polygon, and a corresponding equil. polygon drawn in the space diagram, the first and last segments of the latter polygon must co-incide with the first and last forces according to the order adopted (or with the resultants of the first two and last two, if more convenient to classify them thus). It remains to utilize this principle.

327. To Find the Resultant of Several Forces in a Plane.—This might be done as in § 326, but since frequently a given set of forces are parallel, or nearly so, a special method will now be given, of great convenience in such cases. Fig. 352. Let P_1 P_2 and P_3 be the given forces whose resultant is required. Let us first find their *analytical resultant,* or force which will balance



FIG. 352.



FIG. 353.

them. This anti-resultant may be conceived as decomposed into two components P and P' *one of which*, say P, is arbitrary in amount and position. Assuming P, then, at convenience, in the space diagram, it is required to find P'. The five forces must form a balanced system; hence if beginning at O_1, Fig. 353, we lay off a line $O_1A = P$ by scale, then $A1$ = and ‖ to P_1, and so on (point to butt), the line BO_1 necessary to close the force polygon is $= P'$ required. Now form the corresponding equil. polygon in the space diagram in the usual way, viz.: through a the intersection of P and P_1 draw ab ‖ to the ray $O_1 \ldots 1$ (which connects the pole O_1 with the point of the last force mentioned). From b, where ab intersects the line of P_2, draw bc, ‖ to the ray $O_1 \ldots 2$, till it intersects the line of P_3. A line mc drawn through c and ‖ to the P' of the force diagram is the line of action of P'.

Now the resultant of P and P' is the anti-resultant of P_1, P_2 and P_3; $\therefore$ d, the intersection of the lines of P and P', is a point in the line of action of the anti-resultant required, while its direction and magnitude are given by the line BA in the force diagram; for BA forms a closed polygon both with P_1 P_2 P_3, and with PP'. Hence a line through d ‖ to BA, viz., de, is the line of action of the anti-resultant (and hence of the resultant) of P_1, P_2, P_3.

Since, in this construction, P is arbitrary, we may first choose O_1, arbitrarily, in a *convenient position*, i.e., in such a position that by inspection the segments of the resulting equil. polygon shall give fair intersections and not pass off the paper. If the given forces are parallel the device of introducing the oblique P and P' is quite necessary.

328.—The result of this construction may be stated as follows, (regarding Oa and cm as segments of the equil. polygon as well as ab and bc): *If any two segments of an equil. polygon be prolonged*, their intersection is a point in the line of action of the *resultant of those forces* acting at

the vertices intervening between the given segments. Here, the resultant of $P_1\ P_2\ P_3$ acts through d.

329. Vertical Reaction of Piers, etc.—Fig. 354. Given the vertical forces or loads $P_1\ P_2$ and P_3 acting on a rigid body (beam, or truss) which is supported by two piers having smooth horizontal surfaces (so that the reactions must be vertical), required the reactions V_0 and V_n of the piers. For an instant suppose V_0 and V_n known; they are in



FIG. 354.

equil. with $P_1\ P_2$ and P_3. The introduction of the equal and opposite forces P and P' in the same line will not disturb the equilibrium. Taking the seven forces in the order $P\ V_0\ P_1\ P_2\ P_3\ V_n$ and P', a force polygon formed with them will close (see (b) in Fig. where the forces which really lie on the same line are slightly separated). With O, the butt of P, as a pole, draw the rays of the force diagram OA, OB, etc. The corresponding equil. polygon begins at a, the intersection of P and V_0 in (a) (the space diagram), and ends at n the intersection of P' and V_n. Join an. Now since P and P' act in the same line, an must be that line and must be ‖ to P and P' of the force diagram. Since the amount and direction of P and P' are arbitrary, the position of the pole O is arbitrary, while P_1, P_2, and P_3 are the only forces known in advance in the force diagram.

Hence V_0 and V_n may be determined as follows: Lay off the given loads P_1, P_2, etc., in the order of their occurrence in the space diagram, to form a "load-line" AD

(see (*b*.) Fig. 354) as a beginning for a force-diagram; take any convenient pole O, draw the rays OA, OB, OC and OD. Then beginning at any convenient point a in the vertical line containing the unknown V_0, draw $ab \parallel$ to OA, $bc \parallel$ to OB, and so on, until the last segment (dn in this case) cuts the vertical containing the unknown V_n in some point n. Join an (this is sometimes called a *closing line*) and draw a $\parallel$ to it through O, in the force-diagram. This last line will cut the "load-line" in some point n', and divide it in two parts $n'A$ and Dn', which are respectively V_0 and V_n required.

Corollary.—Evidently, for a given system of loads, in given vertical lines of action, and for two given piers, or abutments, having *smooth horizontal surfaces*, the location of the point n' on the load line is *independent of the choice of a pole*.

Of course, in treating the stresses and deflection of the rigid body concerned, P and P' are left out of account, as being imaginary and serving only a temporary purpose.

330. Application of Foregoing Principles to a Roof Truss.—Fig. 355. W_1 and W_2 are wind pressures, P_1 and P_2 are loads, while the remaining external forces, viz., the re-



FIG. 355.

actions, or supporting forces, V_0, V_n and H_n, may be found by preceding §§. (We here suppose that the right abutment furnishes all the horizontal resistance; none at the left).

Lay off the forces (known) W_1, W_2, P_1, and P_2 in the usual way, to form a portion of the closed force polygon. To close the polygon it is evident we need only draw a horizontal through 5 and limit it by a vertical through 1. This determines H_n but it remains to determine n' the point of division between V_0 and V_n. Select a convenient pole O_1, and draw rays from it to 1, 2, etc. Assume a convenient point a in the line of V_0 in the space diagram, and through it draw a line $\parallel$ to $O_1 1$ to meet the line of W_1 in some point b; then a line $\parallel$ to $O_1 2$ to meet the line of W_2 in some point c; then through $c \parallel$ to $O_1 3$ to meet the line of P_1 in some point d; then through $d \parallel$ to $O_1 4$ to meet the line of P_2 in some point e, (e is identical with d, since P_1 and P_2 are in the same line); then $ef \parallel$ to $O_1 5$ to meet H_n in some point f; then $fg \parallel$ to $O_1 6$ to meet V_n in some point g.

abcdefg is an equilibrium polygon corresponding to the pole O_1.

Now join ag, the "closing-line," and draw a $\parallel$ to it through O_1 to determine n', the required point of division between V_0 and V_n on the vertical 1 6. Hence V_0 and V_n are now determined as well as H_n.

[The use of the arbitrary pole O_1 implies the temporary employment of a pair of opposite and equal forces in the line ag, the amount of either being $= O_1 n'$].

Having now all the external forces acting on the truss, and assuming that it contains no "redundant parts," i.e., parts unnecessary for rigidity of the frame-work, we proceed to find the pulls and thrusts in the individual pieces, on the following plan. The truss being *pin-connected*, no piece extending beyond a joint, and all loads being considered to act at joints, the action, pull or thrust, of each piece on the joint at either extremity will be in the direction of the piece, i.e., in a *known direction*, and the pin of each

joint is in equilibrium under a system of concurrent forces consisting of the loads (if any) at the joint and the pulls or thrusts exerted upon it by the pieces meeting there. Hence we may apply the principles of § 325 to each joint in turn. See Fig. 356. In constructing and interpreting the various force polygons, Mr. R. H Bow's convenient notation will be used; this is as follows: In the space diagram a capital letter [*ABC*, etc.] is placed in each triangular cell of the truss, and also in each angular space in the outside outline of the truss between the external forces and the adjacent truss-pieces. In this way we can speak of the force W_1 as the force *BC*, of W_2 as the force *CE*, the stress in the piece $a\beta$ as the force *CD*, and so on. That is, the stress in any one piece can be named from the letters in the spaces bordering its two sides. Corresponding to these capital letters in the *spaces* of the space-diagram, small letters will be used at the *vertices* of the closed force-polygons (one polygon for each joint) in such a way that the stress in the piece *CD*, for example, shall be the force *cd* of the force polygon belonging to any joint in which that piece terminates; the stress in the piece *FG* by the force *fg* in the proper force polygon, and so on.

In Fig. 356 the whole truss is shown free, in equilibrium under the external forces. To find the pulls or thrusts (i.e., tensions or compressions) in the pieces, consider that if all but two of the forces of a closed force polygon are known in magnitude and direction, while the directions, only, of those two are known, the *whole force polygon may be drawn*, thus determining *the amounts* of those two forces by the lengths of the corresponding sides.

We must ∴ begin with a joint where no more than two pieces meet, as at α; [call the joints α, β, γ, δ, and the corcorresponding force polygons α', β' etc. Fig. 356.] Hence at α' (anywhere on the paper) make $ab \parallel$ and $=$ (by scale) to the known force *AB* (i.e., V_0) *pointing it at the upper end*, and from this end draw $bc =$ and $\parallel$ to the known force *BC* (i.e., W_1) pointing this at the lower end.



FIG. 356.

To close the polygon draw through c a $\parallel$ to the piece CD, and through a a $\parallel$ to AD; their intersection determines d, and the polygon is closed. Since the arrows must be point to butt round the periphery, the force with which the piece CD acts on the pin of the joint α is a force of an amount $= cd$ and in a direction from c toward d; hence the piece CD is *in compression*; whereas the action of the piece DA upon the pin at a is from d toward a (direction of arrow) and hence DA is *in tension*. Notice that in constructing the force polygon α' a right-handed (or clock-wise) rotation has been observed in considering in turn the spaces A B C and D, round the joint α. A similar order will be found convenient in each of the other joints.

Knowing now the stress in the piece CD, (as well as in DA) all but two of the forces acting on the pin at the joint β are known, and accordingly we begin a force polygon, β', for that joint by drawing dc, $=$ and $\parallel$ to the dc of polygon α', *but pointed in the opposite direction*, since the action of CD on the joint β is equal and opposite to its action on the joint α (this disregards the weight of the piece). Through c draw ce $=$ and $\parallel$ to the force CE (i.e., W_2) and

pointing the same way; then ef, = and ∥ to the load EF (i.e. P_1) and pointing downward. Through f draw a ∥ to the piece FG and through d, a ∥ to the piece GD, and the polygon is closed, thus determining the stresses in the pieces FG and GD. Noting the pointing of the arrows, we readily see that FG is in compression while GD is in tension.

Next pass to the joint δ, and construct the polygon δ', thus determining the stress gh in GH and that ad in AD; this last force ad should check with its equal and opposite ad already determined in polygon α'. Another check consists in the proper closing of the polygon γ', all of whose sides are now known.

[A compound stress-diagram may be formed by superposing the polygons already found in such a way as to make equal sides co-incide; but the character of each stress is not so readily perceived then as when they are kept separate].

In a similar manner we may find the stresses in any pin-connected frame-work (in one plane and having no redundant pieces) under given loads, provided all the supporting forces or reactions can be found. In the case of a braced-arch (truss) as shown in Fig. 357, hinged to the abutments at both ends and not free to slide laterally upon them, the reactions at O and B depend, in amount and direction, not only upon the equations of Statics, but on *the form* and *elasticity* of the arch-truss. Such cases will be treated later under arch-ribs, or curved beams.



FIG. 357.

332. The Special Equil. Polygon. Its Relation to the Stresses in the Rigid Body.—Reproducing Figs. 350 and 351 in Figs. 358 and 359, (where a rigid curved beam is in equilibrium under the forces P_1, P_2, P_3, P_4 and R'_c) we call $a \ldots b \ldots c$

the *special equil. polygon* because it corresponds to a force diagram in which the same order of forces has been observed as that in which they occur along the beam (from left to right here). From the relations between the force



SPACE DIAGRAM

Fig. 358.



FORCE DIAGRAM

Fig. 359.

diagram and equil. polygon, this special equil. polygon in the space diagram has the following properties in connection with the corresponding rays (dotted lines) in the force diagram.

The stresses in any cross-section of the portion $O'A$ of the beam, are due to P_1 alone; those of any cross-section on AB to P_1 and P_2, i.e., to *their resultant* R, whose magnitude is given by the line Oa' in the force diagram, while its line of action is ab the first segment of the equil. polygon. Similarly, the stresses in BC are due to P_1, P_2 and P_3, i.e., to their resultant R_b acting along the segment bc, its magnitude being $= Ob'$ in the force diagram. E.g., if the section at m be exposed, considering $O'ABm$ as a free body, we have (see Fig. 360) the elastic stresses (or inter-



Fig. 360.



Fig. 361.

nal forces) at m balancing the exterior or "applied forces" P_1, P_2 and P_3. Obviously, then, the stresses at m are just

the same as if R_b the resultant of P_1, P_2 and P_3, acted upon an imaginary rigid prolongation of the beam intersecting *bc* (see Fig. 361). R_b might be called the "*anti-stress-resultant*" for the portion *BC* of the beam. We may ∴ state the following: *If a rigid body is in equilibrium under a system of* **Non-Concurrent Forces** *in a plane, and the special equilibrium polygon has been drawn, then each ray of the force diagram is the anti-stress-resultant of that portion of the beam which corresponds to the segment of the equilibrium polygon to which the ray is parallel; and its line of action is the segment just mentioned.*

Evidently if the body is not one rigid piece, but composed of a ring of uncemented blocks (or voussoirs), it may be considered rigid only so long as no slipping takes place or disarrangement of the blocks; and this requires that the "anti-stress-resultant" for a given joint between two blocks shall not lie outside the bearing surface of the joint, nor make too small an angle with it, lest tipping or slipping occur. For an example of this see Fig. 362, showing a line of three blocks in equilibrium under five forces.



FIG. 362.

The pressure borne at the joint *MN*, is $= R_a$ in the force-diagram and acts in the line *ab*. The construction supposes all the forces given except one, in amount and position, and that this one could easily be found in *amount*, as being the side remaining to close the force polygon, while its *position* would depend on the equil. polygon. But in practice the *two* forces P_1 and R'_c are generally unknown, hence the point *O*, or pole of the force diagram, can not be fixed, nor the special equil. polygon located, until other considerations, outside of those so far presented, are brought into play. In the progress of such a problem, as will be seen, it will be necessary to use arbitrary *trial* positions for the pole *O*, and corresponding *trial* equilibrium polygons.

CHAPTER IX.

GRAPHICAL STATICS OF VERTICAL FORCES.

333. Remarks.—(With the exception of § 378 *a*) in problems to be treated subsequently (either the stiff arch-rib, or the block-work of an arch-ring, of masonry) when the body is considered *free* all the forces holding it in equil. will be *vertical* (loads, due to gravity) except the reactions at the two extremities, as in Fig. 363; but for convenience each reaction will be replaced by its horizontal and vertical components (see Fig. 364). The two H's are of course equal, since they are the only horizontal forces in the system. *Henceforth, all equil. polygons under discussion will be understood to imply this kind of system of forces.* P_1, P_2,



Fig. 363.



Fig. 364.



Fig. 364*a*.

etc., will represent the "loads"; V_0 and V_n the vertical components of the abutment reactions; H the value of either horizontal component of the same. (We here suppose the pressures T_0 and T_n resolved along the horizontal and vertical.)

334. Concrete Conception of an Equilibrium Polygon.—Any equilibrium polygon has this property, due to its mode of construction, viz.: If the *ab* and *bc* of Fig. 358 were imponderable straight rods, jointed at *b* without friction, they would be in equilibrium under the system of forces there given. (See Fig. 364*a*). The rod *ab* suffers a compression equal to the R_a of the force diagram, Fig. 359, and *bc* a compression $= R_b$. In some cases these rods might be in tension, and would then form a set of links playing the part of a suspension-bridge cable. (See § 44).

335. Example of Equilibrium Polygon Drawn to Vertical Loads—Fig. 365. [The structure bearing the given loads is not shown, but simply the imaginary rods, or segments of an equilibrium polygon, which would support the given loads in equilibrium if the abutment points *A* and *B*, to which the terminal rods are hinged, were firm. In the present case this equilibrium is unstable since the rods form a *standing structure*; but if they were *hanging*, the equilibrium would be *stable*. Still, in the present case, a *very light bracing*, or a little friction at all joints would make the equilibrium stable.



FIG. 365.

Given three loads P_1, P_2, and P_3, and two "abutment verticals" A' and B', in which we desire the equil. polygon to terminate, lay off as a "*load-line*," to scale, P_1, P_2, and P_3 end to end in their order. Then selecting any pole,

O, draw the rays $O1$, $O2$, etc., of a force diagram (the V's and P's, though really on the same vertical, are separated slightly for distinctness; also the H's, which both pass through O and divide the load-line into V_0 and V_n). We determine a corresponding equilibrium polygon by drawing through A (any point in A') a line ∥ to O . . 1, to intersect P_1 in some point b; through b a ∥ to O . . 2, and so on, until B' the other abutment-vertical is struck in some point B. AB is the "*abutment-line*" or "*closing-line.*"

By choosing another point for O, another equilibrium polygon would result. As to which of the infinite number (which could thus be drawn, for the given loads and the A' and B' verticals) is the *special equilibrium polygon* for the arch-rib or stone-arch, or other structure, on which the loads rest, is to be considered hereafter. In any of the above equilibrium polygons the imaginary series of jointed rods would be in equilibrium.

336. Useful Property of an Equilibrium Polygon for Vertical Loads.—(Particular case of § 328). See Fig. 366. In any equil. polygon, supporting vertical loads, consider as free any number of consecutive segments, or rods, with the loads at their joints, e. g., the 5th and 6th and portions of the 4th and 7th which, we suppose cut and the compressive forces in them put in, T_4 and T_7, in order to consider 4 5 6 7 as a free body. For equil., according to Statics, the lines of action of T_4 and T_7 (the compression in those rods) must intersect in a point, C, in the line of action of the resultant of P_4, P_5, and P_6; i.e., of the loads occurring at the intervening vertices. That is, the point C must lie in the vertical containing the centre of gravity of those loads. Since the position of this vertical must be independent of the particular equilibrium polygon used, any other (dotted lines in Fig. 366) for the same loads will give the same re-



FIG. 366.

sults. Hence the vertical CD, containing the centre of gravity of any number of consecutive loads, is easily found by drawing the equilibrium polygon corresponding to any convenient force diagram having the proper load-line.

This principle can be advantageously applied to finding a gravity-line of any plane figure, by dividing the latter into parallel strips, whose areas may be treated as loads applied in their respective centres of gravity. If the strips are quite numerous, the centre of gravity of each may be considered to be at the centre of the line joining the middles of the two long sides, while their areas may be taken as proportional to the lengths of the lines drawn through these centres of gravity parallel to the long sides and limited by the end-curves of the strips. Hence the "load-line" of the force diagram may consist of these lines, or of their halves, or quarters, etc., if more convenient (§ 376).

USEFUL RELATIONS BETWEEN FORCE DIAGRAMS AND EQUILIBRIUM POLYGONS.

(for vertical loads.)

237. Résumé of Construction.—Fig. 367. Given the loads P_1, etc., their verticals, and the two abutment verticals A' and B', in which the abutments are to lie; we lay off a load-line 1 . . . 4, take any convenient pole, O, for a force-diagram and complete the latter. For a corresponding equilibrium polygon, assume any point A in the vertical A', for an abutment, and draw the successive segments $A1$, 2, etc., respectively parallel to the inclined lines of the force diagram (rays), thus determining finally the abutment B, in B', which (B) will not in general lie in the horizontal through A.

Now join AB, calling AB the abutment-line, and draw a parallel to it through O, thus fixing the point n' on the



FIG. 367.



FIG. 368.

load-line. This point n', as above determined, is *independent of the location of the pole, O,* (proved in § 329) and divides the load-line into two portions ($V'_0 = 1 \ldots n'$, and $V'_n = n' \ldots 4$) which are the vertical pressures which two supports in the verticals A' and B' *would sustain if the given loads rested on a horizontal rigid bar,* as in Fig. 368.

See § 329. Hence to find the point n' we may use *any convenient pole O.*

[N. B.—The forces V_0 and V_n of Fig. 367 are not identical with V'_0 and V'_n, but may be obtained by dropping a ⌐ from O to the load-line, thus dividing the load-line into two portions which are V_0 (upper portion) and V_n. However, if A and B be connected by a *tie-rod,* in Fig. 367, the abutments in that figure will bear vertical pressures only and they will be the same as in Fig. 368, while the tension in the tie-rod will be $= On'$.]

338. Theorem.—*The vertical dimensions of any two equilibrium polygons, drawn to the same loads, load-verticals, and abutment-verticals, are inversely proportional to their H's* (*or "pole distances"*). We here regard an equil. polygon and its abutment-line as a closed figure. Thus, in Fig. 369, we have two force-diagrams (with a common load-line, for convenience) and their corresponding equil. polygons, for the same loads and verticals. From § 337 we know that On' is ‖ to AB and O_0n' is ‖ to A_0B_0. Let CD be any vertical cutting the first segments of the two equil. polygons.

Denote the intercepts thus determined by z' and z'_0, respectively. From the parallelisms just mentioned, and others more familiar, we have the triangle $O\,1n'$ similar to the triangle Az' (shaded), and the triangle $O_0 1n'$ similar to the triangle $A_0 z'_0$. Hence



Fig. 369.

the proportions between bases and altitudes $\left\{ \frac{1n'}{H} = \frac{z'}{h} \text{ and } \frac{1n'}{H_0} = \frac{z''_0}{h} \right\}$

$\therefore z' : z'_0 :: H_0 : H.$ The same kind of proof may easily be applied to the vertical intercepts in any other segments, e. g., z'' and z''_0. Q. E. D.

339. **Corollaries** to the foregoing. It is evident that:

(1.) If the pole of the force-diagram be moved along a vertical line, the equilibrium polygon changing its form in a corresponding manner, the vertical dimensions of the equilibrium polygon remain unchanged; and

(2.) If the pole move along a straight line which contains the point n', the direction of the abutment-line remains constantly parallel to the former line, while the vertical dimensions of the equilibrium polygon change in inverse proportion to the pole distance, or H, of the force-diagram. [H is the ⌐ distance of the pole from the load-line, and is called the pole-distance].

§ 340. **Linear Arch as Equilibrium Polygon.**—(See § 316.) If the given loads are infinitely small with infinitely small horizontal spaces between them, any equilibrium polygon becomes a **linear arch.** Graphically we can not deal with these infinitely small loads and spaces, but from § 336 it is evident that if we replace them, in successive groups,

by finite forces, each of which = the sum of those composing one group and is applied through the centre of gravity of that group, we can draw an equilibrium polygon whose segments will be tangent to the curve of the corresponding linear arch, and indicate its position with sufficient exactness for practical purposes. (See Fig. 370). The successive points of tangency A, m, n, etc., lie vertically under the points of division between the groups. This relation forms the basis of the graphical treatment of voussoir, or blockwork, arches.



FIG. 370.

341. To Pass an Equilibrium Polygon Through Three Arbitrary Points.—(In the present case the forces are vertical. For a construction dealing with any plane system of forces see construction in § 378*a*.) Given a system of loads, it is required to draw an equilibrium polygon for them through any three points, two of which may be considered as abutments, outside of the load-verticals, the third point being between the verticals of the first two. See Fig. 371. The loads P_1, etc., are given, with their verticals, while A, p, and B are the three points. Lay off the load-line, and with any convenient pole, O_1, construct a force-diagram, then a corresponding preliminary equilibrium polygon beginning at A. Its right abutment B_1, in the vertical through B, is thus found. $O_1 n'$ can now be drawn ∥ to AB_1, to determine n'. Draw $n'O$ ∥ to BA. The pole of the required equilibrium polygon must lie on $n'O$ (§ 337).



FIG. 371.

Draw a vertical through p. The H of the required equilibrium polygon must satisfy the proportion $H : H_1 :: \overline{rs} : \overline{pm}$. (See § 338). Hence construct or compute H from the proportion and draw a vertical at distance H from the load-line (on the left of the load-line here); its intersection with n' O gives O the desired pole, for which a force diagram may now be drawn. The corresponding equilibrium polygon beginning at the first point A will also pass through p and B; it is not drawn in the figure.

342. Symmetrical Case of the Foregoing Problem.—If two points A and B are *on a level*, the third, p, on the middle vertical between them; and the loads (an *even* number) *symmetrically disposed both in position and magnitude*, about p, we may proceed more simply, as follows: (Fig. 372).



Fig. 372.

From symmetry n' must occur in the middle of the load-line, of which we need lay off only the upper half. Take a convenient pole O_1, in the horizontal through n', and draw a half force diagram and a corresponding half equilibrium polygon (both dotted). The upper segment bc of the latter must be horizontal and being prolonged, cuts the prolongation of the first segment in a point d, which determines the vertical CD containing the centre of gravity of the loads occurring over the half-span on the left. (See § 336). In the required equilibrium polygon the segment containing the point p must be horizontal, and its intersection with the first segment must lie in CD. Hence determine this intersection, C, by drawing the vertical CD and a horizontal through p; then join CA, which is the *first segment* of the required equil. polygon. A parallel to CA through 1 is the *first ray* of the corresponding force diagram, and determines the pole O on the horizontal through n'. Completing the force diagram for

this pole (half of it only here), the required equil. polygon is easily finished afterwards.

343. To Find a System of Loads Under Which a Given Equilibrium Polygon Would be in Equilibrium.—Fig. 373. Let AB be the given equilibrium polygon. Through any point O as a pole draw a parallel to each segment of the equilibrium polygon. *Any* vertical, as V, cutting these lines will have, intercepted upon it, a load-line 1, 2, 3, whose parts 1..2, 2..3, etc., are proportional to the successive loads which, placed on the corresponding joints of the equilibrium polygon would be supported by it in equilibrium (unstable).



FIG. 373.

One load may be assumed and the others constructed. A hanging, as well as a standing, equilibrium polygon may be dealt with in like manner, but will be in *stable* equilibrium. The problem in § 44 may be solved in this way, the various steps and final results being as follows (Fig. 50 is here repeated):—



FIG. 50.

Let weight G_1 be given, $=66$ lbs., and the positions of the cord segments be as in Fig. 50. We first lay off (see Fig. 373*a*) vertically, $ab=66$ lbs., by some convenient scale, and prolong this vertical line indefinitely downward. aO is then drawn parallel to 0 . . . 1 of Fig. 50, and bO parallel to 1 . . . 2. Their intersection determines a pole, O, through which Oc and Od, parallel respectively to 2 . . . 3 and 3 . . . n, are drawn, to intersect ad in c and d.



FIG. 373*a*.

We also draw the horizontal On, in Fig. 373*a*. By scaling, we now find the results:—$G_2=bc=42$ lbs.; $G_3=cd=50$ lbs.; $H=58.5$ lbs., ($=H_0$ and H_n of Fig. 50); while $V_0=an=100$ lbs. and $V_n=58$ lbs.

CHAPTER X.

RIGHT ARCHES OF MASONRY.

Note.—The treatment given in this chapter is by many engineers considered sufficiently exact for ordinary masonry arches, the more refined methods of the "elastic theory" being reserved for arches of fairly continuous material, such as those of metal and of concrete (reinforced or otherwise); and is accordingly retained in this revised edition.

344.—In an ordinary "right" stone-arch (i.e., one in which the faces are ⊓ to the axis of the cylindrical soffit, or under surface), the successive blocks forming the arch-ring are called *voussoirs*, the joints between them being planes which, prolonged, meet generally in one or more horizontal lines; e.g., those of a three-centred arch in three ∥ horizontal lines; those of a circular arch in one, the axis of the cylinder, etc. Elliptic arches are sometimes used. The inner concave surface is called the *soffit*, to which the radiating joints between the voussoirs are made perpendicular. The curved line in which the soffit is intersected by a plane



FIG. 374.

⊓ to the axis of the arch is the **Intrados.** The curve in the same plane as the intrados, and bounding the outer extremities of the joints between the voussoirs, is called the **Extrados.**

Fig. 374 gives other terms in use in connection with a

stone arch, and explains those already given. AB is the "springing-line."

345. Mortar and Friction.—As common mortar hardens very slowly, no reliance should be placed on its tenacity as an element of stability in arches of any considerable size; though hydraulic mortar and *thin* joints of ordinary mortar can sometimes be depended on. *Friction*, however, between the surfaces of contiguous voussoirs, plays an essential part in the stability of an arch, and will therefore be considered.

The stability of voussoir-arches must ∴ be made to depend on the resistance of the voussoirs to compresssion and to sliding upon each other; as also of the blocks composing the piers, the foundations of the latter being firm.

346. Point of Application of the Resultant Pressure between two consecutive voussoirs; (or pier blocks). Applying Navier's principle (as in flexure of beams) that the pressure per unit area on a joint varies uniformly from the extremity under greatest compression to the point of least compression (or of no compression); and remembering that negative pressures (i.e., tension) can not exist, as they might in a curved beam, we may represent the pressure per unit area at successive points of a joint (from the intrados toward the extrados, or vice versâ) by the ordinates of a straight line, forming the surface of a trapezoid or triangle, in which figure the foot of the ordinate of the centre of gravity is the *point of application of the resultant pressure*. Thus, where the least compression is supposed



Fig. 375.



Fig. 376.



Fig. 377.



Fig. 378.

to occur at the intrados A, Fig. 375, the pressures vary as the ordinates of a trapezoid, increasing to a maximum value at B, in the extrados. In Fig. 376, where the pressure is zero at B, and varies as the ordinates of a *triangle*, the resultant pressure acts through a point *one-third* the joint-length from A. Similarly in Fig. 377, it acts one-third the joint-length from B. Hence, when the pressure is not zero at either edge the resultant pressure acts within the **middle third** of the joint. Whereas, if the resultant pressure falls *without* the middle third, it shows that a portion Am of the joint, see Fig. 378, receives no pressure, i.e., the joint tends to open along Am.

Therefore that no joint tend to open, the resultant pressure must *fall within the middle third.*

It must be understood that the joint surfaces here dealt with are rectangles, seen edgewise in the figures.

347. Friction.—By experiment it has been found the angle of friction (see § 156) for two contiguous voussoirs of stone or brick is about 30°; i.e., the coefficient of friction is $f = \tan. 30°$. Hence if the direction of the pressure exerted upon a voussoir by its neighbor makes an angle α less than 30° with the *normal to the joint surface*, there is no danger of rupture of the arch by the sliding of one on the other. (See Fig. 379).

348. Resistance to Crushing.—When the resultant pressure falls at its extreme allowable limit, viz.: the edge of the middle third, the pressure per unit of area at n, Fig. 380, is double the mean pressure per unit of area. Hence, in designing an arch of masonry, we must be assured that at every joint (taking 10 as a factor of safety)



Fig. 379.



Fig. 380.

$$\left\{\begin{array}{l}\text{Double the mean pressure per unit of area}\end{array}\right\} \left\{\begin{array}{l}\text{must be less than } {}^1/_{10}\ C\end{array}\right.$$

C being the ultimate resistance to crushing, of the material employed (§ 201) (Modulus of Crushing).

Since a lamina *one foot* thick will always be considered in what follows, careful attention must be paid to the units employed in applying the above tests.

EXAMPLE.—If a joint is 3 ft. by 1 foot, and the resultant pressure is 22.5 tons the mean pressure per sq. foot is

$$p = 22.5 \div 3 = 7.5 \text{ tons per sq. foot}$$

$\therefore$ its double=15 tons per sq. foot=208.3 lbs. sq. inch, which is much less than $^1/_{10}$ of C for most building stones; see § 203, and below.

At joints where the resultant pressure falls at the middle, the max. pressure per square inch would be equal to the mean pressure per square inch; but for safety it is best to assume that, at times, (from moving loads, or vibrations) it may move to the edge of the middle third, causing the max. pressure to be double the mean (per square inch).

Gen. Gillmore's experiments in 1876 gave the following results, among many others:

NAME OF BUILDING STONE.	C IN LBS. PER SQ. INCH.
Berea sand-stone, 2-inch cube,	8955
" " 4 " "	11720
Limestone, Sebastopol, 2-inch cube (*chalk*),	1075
Limestone from Caen, France,	3650
Limestone from Kingston, N. Y.,	13900
Marble, Vermont, 2-inch cube,	8000 to 13000
Granite, New Hampshire, 2-inch cube,	15700 to 24000

349. The Three Conditions of Safe Equilibrium for an arch of uncemented voussoirs.

Recapitulating the results of the foregoing paragraphs, we may state, as follows, the three conditions which must be satisfied at every joint of arch-ring and pier, for each of any possible combination of loads upon the structure:

(1). The resultant pressure must pass within the middle-third.

(2). The resultant pressure must not make an angle $>$ 30° with the normal to the joint.

(3). The mean pressure per unit of area on the surface

of the joint must not exceed $^1/_{20}$ of the Modulus of crushing of the material.

350. The True Linear-Arch, or Special Equilibrium Polygon; and the resultant pressure at any joint. Let the weight of each voussoir and its load be represented by a vertical force passing through the centre of gravity of the two, as in Fig. 381. Taking any two points A and B, A being in the first joint and B in the last; also a third point, p, in the crown joint (supposing such to be there, although generally a key-stone occupies the crown), through these three points can be drawn [§ 341] an equilibrium polygon for the loads given; suppose this equil. polygon nowhere passes outside of the arch-ring (the arch-ring is the portion between the intrados, mn, and the (dotted) extrados $m'n'$) intersecting the joints at b, c, etc. Evidently if such be the case, and small metal rods (not round) were inserted at A, b, c, etc., so as to separate the arch-stones slightly, the arch would stand, though in unstable equilibrium, the piers being firm; and by a different choice of A, p, and B, it might be possible to draw other equilibrium polygons with segments cutting the joints within the arch-ring, and if the metal rods were shifted to these new intersections the arch would again stand (in unstable equilibrium).



FIG. 381.

In other words, if an arch stands, it may be possible to draw a great number of linear arches within the limits of the arch-ring, since three points determine an equilibrium polygon (or linear arch) for given loads. The question arises then: *which linear arch is the locus of the actual resultant pressures at the successive joints?*

[Considering the arch-ring as an elastic curved beam inserted in firm piers (i.e., the blocks at the springing-line

are incapable of turning) and having secured a close fit at all joints before the centering is lowered, the most satisfactory answer to this question is given in Prof. Greene's "Arches," p. 131; viz., to consider the arch-ring as an arch rib of fixed ends and no hinges; see § 380 of next chapter; but the lengthy computations there employed (and the method demands a simple algebraic curve for the arch) may be most advantageously replaced by Prof. Eddy's graphic method ("New Constructions in Graphical Statics," published in Van Nostrand's Magazine for 1877), which applies to arch curves of any form.

This method will be given in a subsequent chapter, on Arch Ribs, or Curved Beams; but for arches of masonry a much simpler procedure is sufficiently exact for practical purposes and will now be presented].

FIG. 382.



FIG. 383.

If two elastic blocks of an arch-ring touch at one edge, Fig. 382, their adjacent sides making a small angle with each other, and are then gradually pressed more and more forcibly together at the edge m, as the arch-ring settles, the centering being gradually lowered, the surface of contact becomes larger and larger, from the compression which ensues (see Fig. 383); while the resultant pressure between the blocks, first applied at the extreme edge m, has now probably advanced nearer the middle of the joint in the mutual adjustment of the arch-stones. With this in view we may reasonably deduce the following theory of the location of the **true linear arch** (sometimes called the "line of pressures" and "curve of pressure") in an arch under given loading and with *firm piers*. (Whether the piers are really unyielding, under the oblique thrusts at the springing-line, is a matter for subsequent investigation.

351. Location of the True Linear Arch.—Granted that the voussoirs have been closely fitted to each other over the

centering (sheets of lead are sometimes used in the joints to make a better distribution of pressure); and that the piers are firm; and that the arch can stand at all without the centering; then we assume that in the mutual accommodation between the voussoirs, as the centering is lowered, the resultant of the pressures distributed over any joint, if at first near the extreme edge of the joint, advances nearer to the middle as the arch settles to its final position of equilibrium under its load; and hence the following

352. Practical Conclusions.

I. If for a given arch and loading, with firm piers, an equilibrium polygon can be drawn (by proper selection of the points A, p, and B, Fig. 381) entirely within the *middle third* of the arch ring, not only will the arch stand, but the resultant pressure at every joint will be within the middle third (Condition 1, § 349); and among all possible equilibrium polygons which can be drawn within the middle third, that is the "true" one which most nearly coincides with the middle line of the arch-ring.

II. If (with firm piers, as before) no equilibrium polygon can be drawn within the middle third, and only one within the arch-ring at all, the arch may stand, but chipping and spawling are likely to occur at the edges of the joints. The design should ∴ be altered.

III. If no equilibrium polygon can be drawn within the arch-ring, the design of either the arch or the loading must be changed; since, although the arch may stand, from the resistance of the spandrel walls, such a stability must be looked upon as precarious and not countenanced in any large important structure. (Very frequently, in small arches of brick and stone, as they occur in buildings, the cement is so tenacious that the whole structure is virtually a single continuous mass).

When the "true" linear arch has once been determined, the amount of the resultant pressure on any joint is given by the length of the proper ray in the force diagram.

ARRANGEMENT OF DATA FOR GRAPHIC TREATMENT.

353. **Character of Load.**—In most large stone arch bridges the load (permanent load) does not consist exclusively of masonry up to the road-way but partially of earth filling above the masonry, except at the faces of the arch where the spandrel walls serve as retaining walls to hold the earth. (Fig. 384). If the intrados is a half circle or half-



FIG. 384.



FIG. 385.

ellipse, a compactly-built masonry backing is carried up beyond the springing-line to AB about 60° to 45° from the crown, Fig. 385; so that the portion of arch ring below AB may be considered as part of the abutment, and thus AB is the virtual springing-line, for graphic treatment.

Sometimes, to save filling, small arches are built over the haunches of the main arch, with earth placed over them, as shown in Fig. 386. In any of the preceding cases



FIG. 386.



FIG. 387.

it is customary to consider that, on account of the bonding of the stones in the arch *shell*, the loading at a given distance from the crown is *uniformly distributed over the width of the roadway*.

354. Reduced Load-Contour.—In the graphical discussion of a proposed arch we consider a lamina one foot thick, this lamina being vertical and ⊓ to the axis of the arch; i.e., the lamina is ‖ to the spandrel walls. For graphical treatment, equal areas of the elevation (see Fig. 387) of this lamina must represent equal weights. Taking the material of the arch-ring as a standard, we must find for each point p of the extrados an imaginary height z of the arch-ring material, which would give the same pressure (per running horizontal foot) at that point as that due to the actual load above that point. A number of such ordinates, each measured vertically upward from the extrados determine points in the "**Reduced Load-Contour**," i.e., the imaginary line, AM, the area between which and the extrados of the arch-ring represents a homogeneous load of the same density as the arch-ring, and equivalent to the actual load (above extrados), *vertical by vertical.*

355. Example of Reduced Load-Contour.—Fig. 388. Given an arch-ring of granite (heaviness = 170 lbs. per cubic foot) with a dead load of rubble (heav. = 140) and earth (heav. = 100), distributed as in figure. At the point p, of the extrados, the depth 5 feet of rubble is equivalent to a depth of $[\frac{140}{170} \times 5] = 4.1$ ft. of granite, while the 6 feet of earth is equivalent to $[\frac{100}{170} \times 6] = 3.5$ feet of granite. Hence the **Reduced Load-Contour** has an ordinate, above p, of 7.6 feet. That is, for each of several points of the arch-ring extrados reduce the rubble ordinate in the ratio of 170 : 140, and the earth ordinate in the ratio 170 : 100 and add the results, setting off the sum vertically from the points in the extrados*. In this way Fig. 389 is obtained and the area

This is most conveniently done by graphics, thus: On a right-line set off 17 equal parts (of any convenient magnitude.) Call this distance OA. Through O draw another right line at any convenient angle (30° to 60°) with OA, and on it from O set off OB equal to 14 (for the rubble; or 10 for the earth) of the same equal parts. Join AB. From O toward A set off all the rubble ordinates to be reduced, (each being set off from O) and through the other extremity of each draw a line parallel to AB. The reduced ordinates will be the respective lengths, from O, along OB, to the intersections of these parallels with OB.

* With the dividers.



FIG. 388.



FIG. 389.

there given is to be treated as representing homogeneous granite one foot thick. This, of course, now includes the arch-ring also. AB is the "reduced load-contour."

356. Live Loads.—In discussing a railroad arch bridge the "live load" (a train of locomotives, e.g., to take an extreme case) can not be disregarded, and for each of its positions we have a separate **Reduced Load-Contour.**

EXAMPLE.—Suppose the arch of Fig. 388 to be 12 feet wide (not including spandrel walls) and that a train of locomotives weighing 3,000 lbs. per running foot of the track covers one half of the span. Uniformly * distributed laterally over the width, 12 ft., this rate of loading is equivalent to a masonry load of one foot high and a heaviness of 250 lbs. per cubic ft., i.e., is equivalent to a height of 1.4 ft. of granite masonry [since $\frac{250}{170} \times 1.0 = 1.4$] over the half span considered. Hence from Fig. 390 we obtain Fig. 391 in an obvious manner. Fig. 391 is now ready for graphic treatment.



FIG. 390.



FIG. 391.

357. Piers and Abutments.—In a series of equal arches the pier between two consecutive arches bears simply the weight of the two adjacent semi-arches, plus the load im-

* If the earth-filling is shallow, the laminæ directly under the track probably receive a greater pressure than the others.

mediately above the pier, and ∴ does not need to be as large as the abutment of the first and last arches, since these latter must be prepared to resist the oblique thrusts of their arches without help from the thrust of another on the other side.

In a very long series of arches it is sometimes customary to make a few of the intermediate piers large enough to act as abutments. These are called "abutment piers," and in case one arch should fall, no others would be lost except those occurring between the same two abutment piers as the first. See Fig. 392. *A* is an abutment-pier.

FIG. 392.

GRAPHICAL TREATMENT OF ARCH.

358.—Having found the "reduced load-contour," as in preceding paragraphs, for a given arch and load, we are ready to proceed with the graphic treatment, i.e., the first given, or assumed, form and thickness of arch-ring is to be investigated with regard to stability. It may be necessary to treat, separately, a lamina under the spandrel wall, and one under the interior loading. The constructions are equally well adapted to arches of all shapes, to Gothic as well as circular and elliptical.

359.—Case I. Symmetrical Arch and Symmetrical Loading.—(The "steady" (permanent) or "dead" load on an arch is usually symmetrical). Fig. 393. From symmetry we need



FIG. 393.



FIG. 394.



FIG. 395.

deal with only one half (say the left) of the arch and load. Divide this semi-arch and load into six or ten divisions by vertical lines; these divisions are *considered* as *trapezoids* and should have the same horizontal width $= b$ (a convenient whole number of feet) except the last one, LKN, next the abutment, and this is a pentagon of a different width b_1, (the remnant of the horizontal distance LC). The weight of masonry in each division is equal to (the area of division)$\times$(unity thickness of lamina)$\times$(weight of a cubic unit of arch-ring). For example for a division having an area of 20 sq. feet, and composed of masonry weighing 160 lbs. per cubic foot, we have $20\times1\times160=3{,}200$ lbs., applied through the centre of gravity of the division. The area of a trapezoid, Fig. 394, is $\frac{1}{2}b(h_1+h_2)$, and its centre of gravity may be found, Fig. 395, by the construction of Prob. 6, in § 26; or by § 27*a*. The weight of the pentagon LN, Fig. 393, and its line of application (through centre of gravity) may be found by combining results for the two trapezoids into which it is divided by a vertical through K. See § 21.

Since the weights of the respective trapezoids (*excepting* LN) are proportional to their middle vertical intercepts [such as $\frac{1}{2}(h_1+h_2)$ Fig. 394] these intercepts (transferred with the dividers) may be used directly to form the load-line, Fig. 396, or proportional parts of them if more convenient. The force scale, which this implies, is easily computed, and a proper length calculated to represent the weight of the odd division LN; i.e., 1 . . . 2 on the load-line.

Now consider A, the middle point of the abutment joint, Fig. 396, as the starting point of an equilibrium polygon (or abutment of a linear arch) for a given loading, and require that this equilibrium polygon shall pass through p, the middle of the crown joint, and through the middle of the abutment joint on the right (not shown in figure).

Proceed as in § 342, thus determining the polygon Ap for the half-arch. Draw joints in the arch-ring through those points where the extrados is intersected by the ver-



FIG. 396.



FIG. 397.

tical separating the divisions (not the gravity verticals). The points in which these joints are cut by the segments of the equilibrium polygon, Fig. 397, are (very nearly, if the joint is not more than 60° from *p*, the crown) the points of application in these joints, respectively, of the resultant pressures on them, (if this is the "true linear arch" for this arch and load) while the amount and direction of each such pressure is given by the proper ray in the force-diagram.

If at any joint so drawn the linear arch (or equilibrium polygon) passes outside the middle third of the arch-ring, the point *A*, or *p*, (or both) should be judiciously moved (within the middle third) to find if possible a linear arch which keeps within limits at all joints. If this is found impossible, the thickness of the arch-ring may be increased at the abutment (giving a smaller increase toward the crown) and the desired result obtained; or a change in the distribution or amount of the loading, if allowable, may gain this object. If but one linear arch can be drawn within the middle third, it may be considered the "true" one; if several, the one most nearly co-inciding with the middles of the joints (see §§ 351 and 352) is so considered.

360.—Case II. Unsymmetrical Loading on a Symmetrical Arch; (e.g., arch with live load covering one half-span as in Figs. 390 and 391). Here we must evidently use a full force diagram, and the full elevation of the arch-ring and load.

See Fig. 398. Select three points A, p, and B, as follows, to determine a *trial equilibrium polygon*:

Select A at the *lower limit* of the middle third of the



FIG. 398.

abutment-joint at the end of the span which is the more heavily-loaded; in the other abutment-joint take B at the upper limit of the middle third; and take p in the middle of the crown-joint. Then by § 341 draw an equilibrium polygon (i.e., a linear arch) through these three points for the given set of loads, and if it does not remain within the middle third, try other positions for A, p, and B, within the middle third. As to the "true linear arch" alterations of the design, etc., the same remarks apply as already given in Case I. Very frequently it is not necessary to draw more than one linear arch, for a given loading, for even if one could be drawn nearer the middle of the arch-ring than the first, that fact is almost always apparent on mere inspection, and the one already drawn (if within middle third) will furnish values sufficiently accurate for the pressures on the respective joints, and their direction angles.

360a.—The design for the arch-ring and loading is not to be considered satisfactory until it is ascertained that for the dead load and any possible combination of live-load (in addition) the pressure at any joint is

1.) Within the middle third of that joint;

(2.) At an angle of $< 30°$ with the normal to joint-surface.

(3.) Of a *mean* pressure per square inch not $>$ than $^1/_{20}$ of the ultimate crushing resistance. (See § 348.)

§ 361. **Abutments.**—The abutment should be compactly and solidly built, and is then treated as a single rigid mass. The pressure of the lowest voussoir upon it (considering a lamina one foot thick) is given by the proper ray of the force diagram (O .. 1, e. g., in Fig. 396) in amount and direction. The stability of the abutment will depend on the amount and direction of the resultant obtained by combining that pressure P_a with the weight G of the abutment and its load, see Fig. 399. Assume a probable width RS for the abutment and compute the weight G of the corresponding abutment $OBRS$ and $MNBO$, and find the centre of gravity of the whole mass C. Apply G in the vertical through C, and combine it with P_a at their intersection D. The resultant P should not cut the base RS in a point beyond the middle third (or, if this rule gives too massive a pier, take such a width that the pressure per square-inch at S shall not exceed a safe value as computed from § 362.) After one or two trials a satisfactory width can be obtained. We should also be assured that the angle PDG is less than 30°. The horizontal joints above RS should also be tested as if each were, in turn, the lowest base, and if necessary may be inclined (like mn) to prevent slipping. On no joint should the maximum pressure per square inch be $>$ than $^1/_{10}$ the crushing strength of the cement. Abutments of firm natural rock are of course to be preferred where they can be had. If water penetrates under an abutment its buoyant effort lessens the weight of the latter to a considerable extent.



FIG. 399.

362. Maximum Pressure Per Unit of Area When the Resultant Pressure Falls at Any Given Distance from the Middle; according to Navier's theory of the distribution of the pressure; see § 346. Case I. Let the resultant pressure P, Fig. 400, (a).



FIG. 400.



FIG. 401.

fall within the middle third, a distance $= nd\ (< \frac{1}{6}\ d)$ from the middle of joint (d = depth of joint.) Then we have the following relations:

p (the mean press. per. sq. in.), p_m (max. press. per sq. in.), and p_n (least press. per sq. in.) are proportional to the lines h (mid. width), a (max. base), and c (min. base) respectively, of a trapezoid, Fig. 400, (b), through whose centre of gravity P acts. But (§ 26)

$$nd = \frac{d}{6}\cdot\frac{a-c}{a+c} \text{ i.e., } n = \tfrac{1}{6}\,\frac{a-h}{h} \text{ or } a = h\,(6n+1)$$

$\therefore\ p_m = p\,(6n+1)$. Hence the following table:

If $nd =$	$\frac{1}{6}\ d$	$\frac{1}{9}\ d$	$\frac{1}{18}\ d$	then the max.
press. $p_m =$	2	$\frac{5}{5}$	$\frac{4}{3}$	times the mean pressure.

Case II. Let P fall outside the mid. third, a distance $= nd\ (> \frac{1}{6}\ d)$ from the middle of joint. Here, since the joint is not considered capable of withstanding tension, we have a triangle, instead of a trapezoid. Fig. 401. First compute the mean press. per sq. in.

$$p = \frac{P\ (\text{lbs.})}{(1-2n)\ 18\ d\ \text{inches}} \text{ or from this table: (lamina one foot thick).}$$

For $nd =$	$\frac{4}{18}d$	$\frac{5}{18}d$	$\frac{6}{18}d$	$\frac{7}{18}d$	$\frac{8}{18}d$	$\frac{9}{18}d$
$p =$	$\frac{1}{10}\cdot\frac{P}{d}$	$\frac{1}{8}\cdot\frac{P}{d}$	$\frac{1}{6}\cdot\frac{P}{d}$	$\frac{1}{4}\cdot\frac{P}{d}$	$\frac{1}{2}\cdot\frac{P}{d}$	infinity.

(d in inches and P in lbs.; with arch lamina 1 ft. in thickness.)

Then the maximum pressure (at A, Fig. 401) p_m, $= 2p$, becomes known, in lbs. per sq. in.

362a. Arch-ring under Non-vertical Forces.—An example of this occurs when a vertical arch-ring is to support the pressure of a liquid on its extrados. Since water-pressures are always at right angles to the surface pressed on, these pressures on the extradosal surface of the arch-ring form a system of non-parallel forces which are normal to the curve of the extrados at their respective points of application and lie in parallel vertical planes, parallel to the faces of the lamina. We here assume that the extradosal surface is a cylinder (in the most general sense) whose rectilinear elements are ⊥ to the faces of the lamina. If, then, we divide the length of the extrados, from crown to each abutment, into from six to ten parts, the respective pressures on the corresponding surfaces are obtained by multiplying the area of each by the depth of its centre of gravity from the upper free surface of the liquid, and this product by the weight of a unit of volume of the liquid; and each such pressure may be considered as acting through the centre of the area. Finally, if we find the resultant of each of these pressures and the weight of the corresponding portion of the arch-ring, these resultants form a series of non-vertical forces in a plane, for which an equilibrium polygon can then be passed through three assumed points by § 378a, these three points being taken in the crown-joint and the two abutment-joints. As to the "true linear arch" see § 359.

As an extreme theoretic limit it is worth noting that if the extrados and intrados of the arch-ring are concentric circles; if the weights of the voussoirs are neglected; and if the rise of the arch is very small compared with the depth of the crown below the water surface, then the *circular centre-line of the arch-ring is the "true linear arch."*

CHAPTER XI.

ARCH-RIBS.

Note.—The methods used in this chapter for the treatment of the "elastic arch" are practically the equivalent of those based on the theory of "Least Work."

364. Definitions and Assumptions.—An arch-rib (or *elastic-arch*, as distinguished from a block-work arch) is a rigid curved beam, either solid, or built up of pieces like a truss (and then called a braced arch) the stresses in which, under a given loading and with prescribed mode of support it is here proposed to determine. The rib is supposed symmetrical about a vertical plane containing its axis or middle line, and the Moment of Inertia of any cross section is understood to be referred to a gravity axis of the section, which (the axis) is perpendicular to the said vertical plane. It is assumed that in its strained condition under a load, the shape of the rib differs so little from its form when unstrained that the change in the abscissa or ordinate of any point in the rib axis (a curve) may be neglected when added (algebraically) to the coordinate itself; also that the dimensions of a cross-section are small compared with the radius of curvature at any part of the curved axis, and with the span.

365. Mode of Support.—Either extremity of the rib may be *hinged* to its pier (which gives freedom to the end-tangent-line to turn in the vertical plane of the rib when a load is applied); or may be *fixed*, i.e., so built-in, or bolted rigidly to the pier, that the end-tangent-line is incapable of changing its direction when a load is applied. A hinge may be inserted anywhere along the rib, and of course

destroys the rigidity, or resistance to bending at that point. (A hinge having its pin horizontal ⊓ to the axis of the rib is meant). Evidently no more than three such hinges could be introduced along an arch-rib between two piers; unless it is to be a *hanging* structure, acting as a suspension-cable.

366. Arch Rib as a Free Body.—In considering the whole rib free it is convenient, for graphical treatment, that no section be conceived made at its extremities, if fixed; hence in dealing with that mode of support the end of the rib will be considered as having a rigid prolongation reaching to a point vertically above or below the pier junction, an unknown distance from it, and there acted on by a force of such unknown amount and direction as to preserve the actual extremity of the rib and its tangent line in the same position and direction as they really are. As an illustration of this Fig. 402 shows *free* an arch rib. *ONB*, with its extremities *O* and *B fixed* in the piers, with no hinges, and bearing two loads P_1 and P_2. The other forces of the system holding it in equilibrium are the horizontal and vertical components, of the pier reactions (H, V, H_n, and V_n), and in this case of fixed ends each of these two reactions is a single force not intersecting the end of the rib, but cutting the vertical through the end in some point F (on the left; and in G on the right) at some vertical distance c, (or d), from the end. Hence the utility of these imaginary prolongations OQF, and BRG, the pier being supposed removed. Compare Figs. 348 and 350.



FIG. 402.

The imaginary points, or hinges, F and G, will be called *abutments* being such for the special equilibrium polygon

(dotted line), while O and B are the real ends of the curved beam, or rib.

In this system of forces there are five unknowns, viz.: V, V_n, $H = H_n$, and the distances c and d. Their determination by analysis, even if the rib is a circular arc, is extremely intricate and tedious; but by graphical statics (Prof. Eddy's method; see § 350 for reference), it is comparatively simple and direct and applies to *any shape* of rib, and is sufficiently accurate for practical purposes. This method consists of constructions leading to the location of the "special equilibrium polygon" and its force diagram. In case the rib is hinged to the piers, the reactions of the latter act through these hinges, Fig. 403, i.e., the abutments of the special equilibrium polygon coincide with the ends of the rib O and B, and for a given rib and load the unknown quantities are only three V, V_n, and H; (strictly there are four; but $\Sigma X = 0$ gives $H_n = H$). The solution by analytics is possible only for ribs of simple algebraic curves and is long and cumbrous; whereas Prof. Eddy's graphic method is comparatively brief and simple and is applicable to any shape of rib whatever.



FIG. 403.

367. Utility of the Special Equilibrium Polygon and its force diagram. The use of locating these will now be illustrated [See § 332]. As proved in §§ 332 and 334 the compression in each "rod" or segment of the "special equilibrium polygon" is the anti-stress resultant of the cross sections in the corresponding portion of the beam, rib, or other structure, the value of this compression (in lbs. or tons) being measured by the length of the parallel ray in the force diagram. Suppose that in some way (to be explained subsequently) the special equilibrium polygon and its force diagram have been drawn for the arch-rib in Fig. 404 having fixed ends, O and B, and no hinges; required the elastic stresses in any cross-section of the rib as at m. Let the



FIG. 404.

scale of the force-diagram on the right be 200 lbs. to the inch, say, and that of the space-diagram (on the left) 30 ft. to the inch.

The cross section m lies in a portion TK, of the rib, corresponding to the rod or segment bc of the equilibrium polygon; hence its anti-stress-resultant is a force R_2 acting in the line bc, and of an amount given in the force-diagram. Now R_2 is the resultant of V, H, and P_1, which with the elastic forces at m form a system in equilibrium, shown in Fig. 405; the portion $FOTm$ being considered free. Hence



FIG. 405. FIG. 406.

taking the tangent line and the normal at m as axes we should have Σ (tang. comps.) $= 0$; Σ (norm. comps.) $= 0$; and Σ (moms. about gravity axis of the section at m) $= 0$, and could thus find the unknowns p_1, p_2, and J, which appear in the expressions p_1F the thrust, $\frac{p_2 I}{e}$ the moment of

the stress-couple, and J the shear. These elastic stresses are classified as in § 295, which see. p_1 and p_2 are *lbs. per square inch*, J is *lbs.*, e is the distance from the horizontal gravity axis of the section to the outermost element of area, (where the compression or tension is p_2 lbs. per sq. in., as due to the stress-couple alone) while I is the "moment of inertia" of the section about that gravity axis. [See §§ 247 and 295; also § 85]. Graphics, however, gives us a more direct method, as follows: Since R_2, in the line bc, is the equivalent of V, H, and P_1, the stresses at m will be just the same as if R_2 acted directly upon a lateral prolongation of the rib at T (to intersect bc Fig. 405) as shown in Fig. 406, this prolongation Tb taking the place of TOF in Fig. 405. The force diagram is also reproduced here. Let a denote the length of the ⌐ from m's gravity axis upon bc, and z the vertical intercept between m and bc. For this imaginary free body, we have,

$$\text{from } \Sigma(\text{tang. compons.})=0,\ R_2 \cos \alpha = p_1 F$$

$$\text{and from } \Sigma(\text{norm. compons.})=0,\ R_2 \sin \alpha = J$$

$$\left.\begin{array}{l}\text{while from } \Sigma(\text{moms. about})\\ \text{the gravity axis of } m)=0,\end{array}\right\} \text{ we have } R_2 a = \frac{p_2 I}{e}.$$

But from the two similar triangles (shaded; one of them is in force diagram) $a : z :: H : R_2$ $\therefore$ $R_2 a = Hz$, whence we may rewrite these relations as follows (with a general statement), viz.:

If the Special Equilibrium Polygon and Its Force Diagram Have Been Drawn for a given arch-rib, of given mode of support, and under a given loading, then in any cross-section of the rib, we have (F = area of section):

(1.) The Thrust, i.e., $p_1 F =$ { The projection of the *proper ray* (of the force diagram) upon the *tangent line* of the rib drawn at the given section.

(2.) The Shear, i.e., J, = (upon which depends the shearing stress in the web). (See §§ 253 and 256). } The projection of the proper ray (of the force diagram) upon the *normal* to the rib curve at the given section.

(3.) The Moment of the stress couple, i.e., $\frac{p_2 I}{e}$, = } The product (Hz) of the H (or pole-distance) of the force-diagram by the vertical distance of the gravity axis of the section from the spec. equilibrium polygon.

By the "proper ray" is meant that ray which is parallel to the segment (of the equil. polygon) immediately under or above which the given section is situated. Thus in Fig. 404, the proper ray for any section on TK is R_2; on KB, R_3; on TO, R_1. The *projection* of a ray upon any given tangent or normal, is easily found by drawing through each end of the ray a line ⌐ to the tangent (or normal); the length between these ⌐'s on the tangent (or normal) is the force required (by the scale of the force diagram). We may thus construct a shear diagram, and a thrust diagram for a given case, while the successive vertical intercepts between the rib and special equilibrium polygon form a moment diagram. For example if the z of a point m is ½ inch in a space diagram drawn to a scale of 20 feet to the inch, while H measures 2.1 inches in a force diagram constructed on a scale of ten tons to the inch, we have, for the moment of the stress-couple at m, $M=Hz=[2.1\times10]$ tons $\times[\frac{1}{2}\times20]$ ft.$=210$ ft. tons.

368.—It is thus seen how a location of the special equilibrium polygon, and the lines of the corresponding force diagram, lead directly to a knowledge of the stresses in all the cross-sections of the curved beam under consideration bearing a given load; or, vice versâ, leads to a statement of conditions to be satisfied by the dimensions of the rib for proper security.

It is here supposed that the rib has sufficient later

bracing (with others which lie parallel with it) to prevent buckling sideways in any part like a long column. Before proceeding to the complete graphical analysis of the different cases of arch-ribs, it will be necessary to devote the next few paragraphs to developing a few analytical relations in the theory of flexure of a curved beam, and to giving some processes in "graphical arithmetic."

369. Change in the Angle Between Two Consecutive Rib Tangents when the rib is loaded, as compared with its value before loading. Consider any small portion (of an arch rib) included between two consecutive cross-sections; Fig. 407. $KHGW$ is its unstrained form. Let EA, $= ds$, be the original length of this portion of the rib axis. The length of all the fibres ($\parallel$ to rib-axis) was originally $= ds$ (nearly) and the two consecutive tangent-lines, at E and A, made an angle $= d\theta$ originally, with each other. While under strain, however, all the fibres are shortened *equally* an amount $d\lambda_1$, by the uniformly distributed tangential thrust, but are *unequally* shortened (or lengthened, according as they are on one side or the other of the gravity axis E, or A, of the section) by the system of forces making what we call the "stress couple," among which the stress at the distance e from the gravity axis A of the section is called p_2 per square inch; so that the tangent line at A' now takes the direction $A'D$ ⌐ to $H'A'G'$ instead of $A'C$ (we suppose the section at E to remain fixed, for **conveni-**



FIG. 407.

ence, since the change of angle between the two tangents depends on the stresses acting, and not on the new position in space, of this part of the rib), and hence the angle between the tangent-lines at E and A (originally $= d\theta$) is now increased by an amount $CA'D = d\varphi$ (or $G'A'R = d\varphi$); $G'H'$ is the new position of GH. We obtain the value of $d\varphi$ as follows: That part ($d\lambda_2$) of the shortening of the fibre at G, at distance e from A due to the force $p_2 dF$, is § 201 eq. (1), $d\lambda_2 = \frac{p_2 ds}{E}$. But, geometrically, $d\lambda_2$ also $= e d\varphi$,

$$\therefore \quad E e d\varphi = p_2 ds \quad . \quad . \quad . \quad . \quad . \quad (1.)$$

But, letting M denote the moment of the stress-couple at section A (M depends on the loading, mode of support, etc., in any particular case) we know from § 295 eq. (6) that $M = \frac{p_2 I}{e}$, and hence by substitution in (1) we have

$$d\varphi = \frac{M ds}{EI} \quad . \quad . \quad . \quad . \quad (2)$$

[If the arch-rib in question has less than three hinges, the equal shortening of the due to the thrust (of the block in last figure) $p_1 F$, will have an indirect effect on the angle $d\varphi$. This will be considered later.]

370. Total Change $\left[\text{i.e. } \int d\varphi\right]$ **in the Angle Between the End Tangents of a Rib**, before and after loading. Take the example in Fig. 408 of a rib fixed at one end and hinged at



FIG. 408.

the other. When the rib is unstrained (as it is supposed to be, on the left, its own weight being neglected; it is not supposed *sprung* into place, but is entirely without strain) then the angle between the end-tangents has some value $\theta' = \int_0^B d\theta =$ the sum of the successive small angles $d\theta$ for each element ds of the rib curve (or axis). After loading, [on the right, Fig. 408], this angle has increased having now a value

$$\theta' + \int_0^B d\varphi, \text{ i.e., a value} = \theta' + \int_0^B \frac{Mds}{EI} \quad . \quad . \quad . \quad \text{(I.)}$$



FIG. 409.

There must be no hinge *between O* and *B*.

§ 371. **Example of Equation (I.) in Analysis.**—A *straight*, homogeneous, prismatic beam, Fig. 409, its own weight neglected, is fixed obliquely in a wall. After placing a load P on the free end, required the angle between the end-tangents. This was zero before loading ∴ its value after loading is

$$= 0 + \varphi' = 0 + \frac{1}{EI}\int_0^B Mds$$

By considering free a portion between O and any ds of the beam, we find that $M = Px =$ mom. of the stress couple. The flexure is so slight that the angle between any ds and its dx is still practically $= a$ (§ 364), and ∴ $ds = dx \sec a$. Hence, by substitution in eq. (I.) we have

$$\varphi' = \frac{1}{EI}\int_0^B Mds = \frac{P \sec a}{EI}\int_0^{l\cos a} xdx = \frac{P \sec a}{EI}\left[\frac{x^2}{2}\right]_0^{l\cos a};$$

$$\therefore \varphi' = \frac{P(\cos a)l^2}{2EI} \quad \text{[Compare with § 237].}$$

It is now apparent that if *both* ends of an arch rib are *fixed*, when unstrained, and the rib be then loaded (within elastic limit, and deformation slight) we must have

$$\int_0^B (Mds \div EI) = \text{zero, since } \varphi' = 0.$$

372. Projections of the Displacement of any Point of a Loaded Rib Relatively to Another Point and the Tangent Line at the Latter.—(There must be no hinge between O and B). Let O be the point whose displacement is considered and B the other point. Fig. 410. If B's tangent-line is fixed while the extremity O is not supported in any way (Fig. 410) then a load P put on, O is displaced to a new position O_n.



Fig. 410.



Fig. 411.



Fig. 412.

With O as an origin and OB as the axis of X, the *projection* of the displacement OO_n upon X, will be called Δx, that upon Y, Δy.

In the case in Fig. 410, O's displacement with respect to B and its tangent-line BT, is *also* its *absolute displacement in space*, since neither B nor BT has moved as the rib changes form under the load. In Fig. 411, however, the extremities O and B are both hinged to piers, or supports, the dotted line showing its form when deformed under a load. The hinges are supposed immovable, the rib being free to turn about them without friction. The dotted line is the changed form under a load, and the *absolute* displacement of O is zero ; but not so its displacement relatively to B and B's tangent BT, for BT has moved to a new position BT'. To find this relative displacement conceive the new curve of the rib superposed on the old in a way that B and BT may coincide with their original po-

sitions, Fig. 412. It is now seen that O's displacement relatively to B and BT' is not zero but $=OO_n$, and has a small Δx but a comparatively large Δy. In fact for this case of hinged ends, *piers immovable*, rib continuous between them, and deformation slight, we shall write $\Delta x=$ zero as compared with Δy, the *axis X passing through OB*).

373. Values of the X and Y Projections of O's Displacement Relatively to B and B's Tangent; the origin being taken at O. Fig. 413. Let the coordinates of the different points E, D, C, etc., of the rib, referred to O and an arbitrary X axis, be x and y, their *radial distances* from O being u (i.e., u for C, u' for D, etc.; in general, u). $OEDC$ is the *unstrained form* of the rib, (e.g., the form it would assume if it lay flat on its side on a level platform, under no straining forces), while $O_nE''D'CB$ is its form under some loading, i.e., under strain. (The superposition above mentioned (§ 372) is supposed already made if necessary, so that BT is tangent at B to both forms). Now conceive the rib OB to pass into its strained condition by the successive bending of each ds in turn. The straining or bending of the first ds, BC, through the small angle $d\varphi$ (dependent on the moment of the stress couple at C in the strained condition) causes the whole finite piece OC to turn about C as a centre through the same small angle $d\varphi$; hence the point O describes a small linear arc $OO'=\delta v$, whose radius $= u$ the hypothenuse of the x and y of C, and whose value $\therefore$ is $\delta v=ud\varphi$.



FIG. 413.

Next let the section D, now at D', turn through its proper angle $d\varphi'$ (dependent on its stress-couple) carrying

with it the portion $D'O'$, into the position $D'O''$, making O' describe a linear arc $O'O''=(\delta v)'=u'd\varphi'$, in which $u'=$ the hypothenuse on the x' and y' (of D), (the deformation is so slight that the co-ordinates of the different points referred to O and X are not appreciably affected). Thus, each section having been allowed to turn through the angle proper to it, O finally reaches its position, O_n, of displacement. Each successive δv, or linear arc described by O, has a shorter radius. Let δx, $(\delta x)'$, etc., represent the projections of the successive (δv)'s upon the axis X; and similarly δy, $(\delta y)'$ etc., upon the axis Y. Then the total X projection of the curved line $O \ldots . O_n$ will be

$$\Delta x = \int \delta x \text{ and similarly } \Delta y = \int \delta y \quad . \ . \ . \quad (1)$$

But $\delta v = u\, d\, \varphi$, and from similar right-triangles, $\delta x : \delta v :: y : u$ and $\delta y : \delta v :: x : u$ $\therefore \delta x = y d\varphi$ and $\delta y = x d\varphi$; whence, (see (1) and (2) of §369)

$$\Delta x = \int \delta x = \int y d\varphi = \int_0^B \frac{My ds}{EI} \quad . \ . \ . \quad \text{(II.)}$$

$$\text{and } \Delta y = \int \delta y = \int x d\varphi = \int_0^B \frac{Mx ds}{EI} \quad . \ . \ . \quad \text{(III.)}$$

If the rib is homogeneous E is constant, and if it is of constant cross-section, all sections being similarly cut by the vertical plane of the rib's axis (i.e., if it is a "curved prism") I, the moment of inertia is also constant.

374. **Recapitulation of Analytical Relations**, for reference. (*Not applicable if there is a hinge between O and B*)

Total Change in Angle between tangent-lines O and B $\Big\} = \int_0^B \frac{Mds}{EI}$ . . . . (I.)

The X-Projection of O's Displacement Relatively to B and B's tangent-line; (*the origin being at O*) and the axes X and Y ⌐ to each other) $\Big\} = \int_0^B \frac{Myds}{EI}$ . . . (II.)

$$\left.\begin{array}{l}\text{The Y-Projection of O's Displacement,}\\ \text{etc., as above.}\end{array}\right\} = \int_0^n \frac{M x ds}{EI} \quad . \quad . \quad \text{(III.)}$$

Here x and y are the co-ordinates of points in the rib-curve, ds an element of that curve, M the moment of the stress-couple in the corresponding section as induced by the loading, or constraint, of the rib.

(The results already derived for deflections, slopes, etc., for straight beams, could also be obtained from these formulae, I., II. and III. In these formulae also it must be remembered that no account has been taken of the shortening of the rib-axis by the thrust, nor of the effect of a change of temperature.)

374a. Résumé of the Properties of Equilibrium Polygons and their Force Diagrams, for Systems of Vertical Loads.—See §§ 335 to 343. Given a system of loads or vertical forces, P_1, P_2, etc., Fig. 414, and two abutment verticals, F' and G'; if we lay off, vertically, to form a "load-line," $1..2 = P_1$, $2...3 = P_2$, etc., select any Pole, O_1, and join O_1 . . . 1, O_1 . . . 2, etc.; also, beginning at any point F_1 in the vertical F', if we draw $F_1 \ldots a \parallel$ to $O_1..1$ to intersect the line of P_1; then $ab \parallel$ to $O_1..2$, and so on until finally a point G_1, in G', is determined; then the figure $F_1.abc\ G_1$ is an *equilibrium polygon* for the given loads and load verticals, and $O_1 \ldots 1234$ is its "force diagram." The former is so called because the short segments F_1a ab, etc., if considered to be rigid and imponderable rods, in a vertical plane, hinged to each other and the terminal ones to abutments F_1 and G_1, would be in equilibrium under the given loads hung at the joints. An infinite number of equilib-



FIG. 414.

rium polygons may be drawn for the given loads and abutment-verticals, by choosing different poles in the force diagram. [One other is shown in the figure; O_2 is its pole. (F_1 G_1 and F_2 G_2 are abutment lines.)] For all of these the following statements are true:

(1.) A line through the pole, ∥ to the abutment line cuts the load-line in the same point n', whichever equilibrium polygon be used (∴ any one will serve to determine n'

(2.) If a vertical CD be drawn, giving an intercept z' in each of the equilibrium polygons, the product Hz' is the same for all the equilibrium polygons. That is, (see Fig. 414) for any two of the polygons we have

$$H_1 : H_2 :: z_2' : z_1' ; \text{ or } H_2 z_2' = H_1 z_1'.$$

(3.) The compression in each rod is given by that "ray" (in the force diagram) to which it is parallel.

(4.) The "pole distance" H, or ┐ let fall from the pole upon the load-line, divides it into two parts which are the vertical components of the compressions in the abutment-rods *respectively* (the other component being horizontal); H is the horizontal component of each (and, in fact, of each of the compressions in all the other rods). The compressions in the extreme rods may also be called the abutment reactions (oblique) and are given by the extreme rays.

(5.) **Three Points** [not all in the same segment (or rod)] determine an equilibrium polygon for given loads. Having given, then, three points, we may draw the equilibrium polygon by §341.

375. Summation of Products. Before proceeding to treat graphically any case of arch-ribs, a few processes in graphical arithmetic, as it may be called, must be presented, and thus established for future use.

To make a summation of products of two factors in each by means of an equilibrium polygon.

Construction. Suppose it required to make the summation $\Sigma\,(x\,z)$ *i. e.*, to sum the series

$$x_1 z_1 + x_2 z_2 + x_3 z_3 + \ldots \text{ by graphics.}$$

Having first arranged the terms in the order of magnitude of the x's, we proceed as follows: Supposing, for illustration, that two of the z's (z_3 and z_4) are negative (dotted in figure) see Fig. 415. These quantities x and z may be of any nature whatever, anything capable of being represented by a length, laid off to scale.



Fig. 415.



Fig. 416.

First, in Fig 416, lay off the z's in their order, end to end, on a vertical load-line taking care to lay off z_3 and z_4 *upward* in their turn. Take any convenient pole O; draw the rays $O \ldots 1$, $O \ldots 2$, etc.; then, having previously drawn vertical lines whose horizontal distances from an extreme left-hand vertical F' are made $= x_1$, x_2, x_3, etc., respectively, we begin at any point F, in the vertical F', and draw a line $\parallel$ to $O \ldots 1$ to intersect the x_1 vertical in some point; then $1'\text{-}2' \parallel$ to $O \ldots 2$, and so on, following carefully the proper order. Produce the last segment ($6' \ldots G$ in this case) to intersect the vertical F' in some point K. Let $KF = k$ (measured on the same scale as the x's), then the summation required is

$$\Sigma_1^6\,(xz) = Hk.$$

H is measured on the scale of the z's, which need not be the same as that of the x's; in fact the z's may not be the same kind of quantity as the x's.

[Proof.—From similar triangles $H : z_1 :: x_1 : k_1$, $\therefore x_1 z_1 = Hk_1$;
and " " " $H : z_2 :: x_2 : k_2$, $\therefore x_2 z_2 = Hk_2$.

and so on. But $H(k_1+k_2+\text{etc.})=H\times\overline{FK}=Hk$].

376. **Gravity Vertical.**—From the same construction in Fig. 415 we can determine the line of action (or gravity vertical) of the resultant of the parallel vertical forces z_1, z_2, etc. (or loads); by prolonging the first and last segments to their intersection at C. The resultant of the system of forces or loads acts through C and is vertical in this case; its value being $= \Sigma\ (z)$, that is, it = the length 1 . . . 7 in the force diagram, interpreted by the proper scale. It is now supposed that the z's represent forces, the x's being their respective lever arms about F. If the z's represent the areas of small finite portions of a large plane figure, we may find a gravity-line (through C) of that figure by the above construction; each z being applied through the centre of gravity of its own portion.



FIG. 416 *a*.



FIG. 416 *b*.

FIG. 416 *c*.

Calling the distance $\bar{x}$ between the verticals through C and F, we have also $\bar{x}\ .\ \Sigma\ (z) = \Sigma\ (xz)$ because $\Sigma\ (z)$ is the resultant of the $\parallel$ z's. This is also evident from the proportion (similar triangles)

$$H : (1\ .\ .\ 7) :: \bar{x} : k.$$

376a. Moment of Inertia (of Plane Figure) by Graphics.*—Fig. 416*a*. $I_N = ?$ First, for the portion on right. Divide OR into equal parts each $= \Delta x$. Let z_1, z_2, etc., be the middle ordinates of the strips thus obtained, and x_1, etc. their abscissas (of middle points).

Then we have approximately

$$I_N \text{ for } OR = \Delta x.z_1x_1^2 + \Delta x.z_2x_2^2 + \ldots\ldots$$
$$= \Delta x[(z_1x_1)x_1 + (z_2x_2)x_2 + \ldots] \ldots (1)$$

But by §375 we may construct the products z_1x_1, z_2x_2, etc., taking a convenient H', (see Fig. 416, (*b*)), and obtain k_1, k_2, etc., such that $z_1x_1 = H'k_1$, $z_2x_2 = H'k_2$, etc. Hence eq. (1) becomes:

$$I_N \text{ for } OR \text{ approx.} = H'\Delta x[k_1x_1 + k_2x_2 + \ldots] \ldots (2)$$

By a second use of § 375 (see Fig. 416 *c*) we construct l, such that $k_1x_1 + k_2x_2 + \ldots = H''l$ [H'' taken at convenience]. ∴ from eq. (2) we have finally, (approx.),

$$I_N \text{ for } OR = H'H''l\Delta x \ldots . (3)$$

For example if $OR = 4$ in., with four strips, Δx would $=$ 1 in.; and if $H' = 2$ in., $H'' = 2$ in., and $l = 5.2$ in., then

$$I_N \text{ for } OR = 2\times2\times5.2\times1.0 = 20.8 \text{ biquad. inches.}$$

The I_N for OL, on the left of N, is found in a similar manner and added to I_N for OR to obtain the total I_N. The position of a gravity axis is easily found by cutting the shape out of sheet metal and balancing on a knife edge ; or may be obtained graphically by § 336 ; or 376.

377. Construction for locating a line vm (Fig. 417) at (*a*), in the polygon FG in such a position as to satisfy the two following conditions with reference to the vertical intercepts at 1, 2, 3, 4, and 5, between it and the given points 1, 2, 3, etc., of the perimeter of the polygon.

* Another graphic method for this purpose will be found in § 76 (p. 80), of the author's *Notes and Examples in Mechanics.*

Condition I.—(Calling these intercepts u_1, u_2, etc., and their horizontal distances from a given vertical F, x_1, x_2, etc.) $\Sigma\,(u)$ is to $= 0$; i.e., the sum of the positive u's must be numerically $=$ that of the negative (which here are at 1 and 5). An infinite number of positions of vm will satisfy condition I.

Condition II.—$\Sigma\,(ux)$ is to $= 0$; i.e., the sum of the moments of the positive u's about F must $=$ that of the negative u's. i.e., the moment of the resultant of the positive u's must $=$ that of the resultant of the negative; and $\therefore$ (Condit. I being already satisfied) these two resultants must be *directly opposed* and *equal*. But the ordinates u in (a) are individually equal to the difference of the *full* and *dotted* ordinates in (b) with the same x's $\therefore$ the conditions may be rewritten:



Fig. 417.

I. Σ (full ords. in (b)) $=$ Σ (dotted ords. in (b))

II. Σ [each full ord. in (b) $\times$ its x] $= \Sigma$ [each dotted ord. in (b) $\times$ its x] i.e., the centres of gravity of the full and of the dotted in (b) must lie in the *same vertical*.

Again, by joining vG, we may divide the dotted ordinates of (b) into two sets which are dotted, and broken, respectively, in (c) Then, finally, drawing in (d),

R, the resultant of full ords. of (c)
T, " " " broken " " "
T', " " " dotted " " "

we are prepared to state in still another and final form the conditions which vm must fulfil, viz.:

(I.) $T+T'$ must $= R$; and (II.) The resultant of T and T' must act in the same vertical as R.

In short, the quantities T, T', and R must form a balanced system, considered as forces. All of which amounts practically to this: that if the verticals in which T and T' act are known and R be conceived as a load supported by a horizontal beam (see foot of Fig. 417, last figure) resting on piers in those verticals, then T and T' are the respective *reactions of those piers*. It will now be shown that the verticals of T and T' are easily found, *being independent of the position* of vm; and that both the vertical and the magnitude of R, being likewise independent of vm, are determined with facility in advance. For, if v be shifted up or down, all the broken ordinates in (c) or (d) will change in the same proportion (viz. as vF changes), while the dotted ordinates, though shifted along their verticals, do not change in value; hence the shifting of v affects neither the vertical nor the value of T', nor the vertical of T. The *value* of T, however, is proportional to vF. Similarly, if m be shifted, up or down, T' will vary proportionally to mG, but its vertical, or line of action, remains the same. T is unaffected in any way by the shifting of m. R, depending for its value and position on the full ordinates of (c) Fig. 417, is independent of the location of vm. We may ∴ proceed as follows:

1st. Determine R graphically, in amount and position, by means of § 376.

2ndly. Determine the *verticals* of T and T' by *any trial* position of vm (call it v_2m_2), and the corresponding trial values of T and T' (call them T_2 and T'_2).

3rdly. By the fiction of the horizontal beam, construct (§ 329) or compute the true values of T and T', and then determine the true distances vF and mG by the proportions

$$vF : v_2F :: T : T_2 \text{ and } mG : m_2G :: T' : T'_2.$$

Example of this. Fig. 418. (See Fig. 417 for s and t.)

From A toward B in (e) Fig. 418, lay off the lengths (or lines proportional to them) of the full ordinates 1, 2, etc., of (f). Take any pole O_1, and draw the equilibrium polygon $(f)'$ and prolong its extreme segments to find C and thus determine R's vertical. R is represented by AB. In (g) [same as (f) but shifted to avoid complexity of lines] draw a trial v_2m_2 and join v_2G_2. Determine the sum T_2 of the broken ordinates (between v_2G_2 and F_2G_2) and its vertical line of application, precisely as in dealing with R; also T'_2 that of the dotted ordinates (five) and its vertical. Now the true $T=Rt\div(s+t)$ and the true $T'=Rs\div(s+t)$. Hence compute $\overline{vF}=(T\div T_2)\ \overline{v_2F_2}$ and $\overline{mG}=(T'\div T'_2)\ \overline{m_2G_2}$, and by laying them off vertically upward from F and G respectively we determine v and m, i.e., the line vm to fulfil the conditions imposed at the beginning of this article, relating to the vertical ordinates intercepted between vm and given points on the perimeter of a polygon or curve.



FIG. 418.

Note (a). If the verticals in which the intercepts lie are equidistant and quite numerous, then the lines of action of T_2 and T'_2 will divide the horizontal distance between F and G into three equal parts. This will be *exactly true* in the application of this construction to § 390.

Note (b). Also, if the verticals are symmetrically placed about a vertical line, (as will usually be the case) v_2m_2 is

best drawn parallel to FG, for then T_2 and T'_2 will be equal and equi-distant from said vertical line.

378. Classification of Arch-Ribs, or Elastic Arches, according to continuity and modes of support. In the accompanying figures the *full* curves show the *unstrained* form of the rib (before any load, even its own weight, is permitted to come upon it); the dotted curve shows its shape (much exaggerated) when bearing a load. For a given loading **Three Conditions** must be given to determine the special equilibrium polygon (§§ 366 and 367).

Class A.—Continuous rib, free to slip laterally on the piers, which have smooth horizontal surfaces, Fig. 420.

This is chiefly of theoretic interest, its consideration being therefore omitted. The pier reactions are necessarily vertical, just as if it were a straight horizontal beam.

Class B. Rib of Three Hinges, two at the piers and one intermediate (usually at the crown) Fig. 421. Fig. 36 also is an example of this. That is, the rib is discontinuous and of two segments. Since at each hinge the moment of the stress couple must be zero, the special equilibrium polygon must pass through the hinges. Hence as three points fully determine an equilibrium polygon for given load, the special equilibrium is drawn by § 341.



FIG. 420. FIG. 421.

[§ 378*a* will contain a construction for arch-ribs of three hinges, when the forces are not all vertical.]

Class C. Rib of Two Hinges, these being at the piers, the rib continuous between. The piers are considered immovable, i.e., the span cannot change as a consequence of loading. It is also considered that the rib is fitted to its

hinges at a definite temperature, and is then under no constraint from the piers (as if it lay flat on the ground), not even its own weight being permitted to act when it is finally put into position. When the "false works" or temporary supports are removed, stresses are induced in the rib both by its loading, including its own weight, and by a change of temperature. Stresses due to temperature may be ascertained separately and then combined with those due to the loading. [Classes A and B are not subject to temperature stresses.] Fig. 422 shows a rib of two hinges, at ends. Conceive the *dotted* curve (form and position under strain) to be superposed on the continuous curve (form before strain) in such a way that B and its tangent line (which has been displaced from its original position) may occupy their previous position. This gives us the broken curve O_nB. OO_n is $\therefore$ O's displacement relatively to B and B's tangent. Now the *piers being immovable* O_nB (right line)$=OB$; i.e., the X projection (or Δx) of OO_n upon OB (*taken as an axis of* X) is zero compared with its Δy. Hence as one condition to fix the special equilibrium polygon for a given loading we have (from § 373)



FIG. 422.

$$\int_0^B [Myds \div EI] = 0 \quad . \quad . \quad . \quad (1)$$

The other two are that the } must pass through O . (2)
special equilibrium polygon } " " " B . (3)

Class D. Rib with **Fixed Ends** and *no hinges*, i.e., continuous. Piers immovable. The ends may be *fixed* by being inserted, or built, in the masonry, or by being fastened to large plates which are bolted to the piers. [The St. Louis Bridge and that at Coblenz over the Rhine are of this class.] Fig. 423. In this class there being no hinges we

have no point given in advance through which the special equilibrium polygon must pass. However, since O's displacement relatively (and absolutely) to B and B's tangent is zero, both Δx and Δy [see § 373] = zero. Also the tangent-lines both at O and B being *fixed in direction*, the angle between them is the same under loading, or change of temperature, as when the rib was first placed in position under no strain and at a definite temperature.



FIG. 423.

Hence the conditions for locating the special equilibrium polygon are

$$\int_o^B \frac{Mds}{EI} = 0: \quad \int_o \frac{Myds}{EI} = 0; \quad \int_o^B \frac{Mxds}{EI} = 0.$$

In the figure the imaginary rigid prolongations at the ends are shown [see § 366].

Other designs than those mentioned are practicable (such as: one end fixed, the other hinged; both ends fixed and one hinge between, etc.), but are of unusual occurrence.

378a. Rib of Three Hinges, Forces not all Vertical.* If the given rib of three hinges upholds a roof, the wind-pressure on which is to be considered as well as the weights of the materials composing the roof-covering, the forces will not all be vertical. To draw the special equil. polygon in such a case the following construction holds: Required to draw an equilibrium polygon, for *any plane system* of forces, through three arbitrary points, A, p and B; Fig. 423a. Find the line of action of R_1, the resultant of all the forces occurring between A and p; also,



FIG. 423a.

* See p. 117 of the author's "Notes and Examples in Mechanics" for a detailed example of the following construction.

that of R_2, the resultant of all forces between p and B; also the line of action of R, the resultant of R_1 and R_2, [see § 328.] Join any point M in R with A and also with B, and join the intersections N and O. Then AN will be the direction of the first segment, OB that of the last, and NO itself is the segment corresponding to p (in the desired polygon) of an equilibrium polygon for the given forces. See § 328. If $AN'pO'B$ are the corresponding segments (as yet unknown) of the desired equil. polygon, we note that the two triangles MNO and $M'N'O'$, having their vertices on three lines which meet in a point [i.e., R meets R_1 and R_2 in C'], are homological [see Prop. VII. of Introduc. to Modern Geometry, in Chauvenet's Geometry,] and that ∴ the three intersections of their corresponding sides must lie on the same straight line. Of those intersections we already have A and B, while the third must be at C, found at the intersection of AB and NO. Hence by connecting C and p, we determine N' and O'. Joining $N'A$ and $O'B$, the first ray of the required force diagram will be ∥ to $N'A$, while the last ray will be ∥ to $O'B$, and thus the pole of that diagram can easily be found and the corresponding equilibrium polygon, beginning at A, will pass through p and B.

(This general case includes those of §§ 341 and 342.)

379. Arch-Rib of two Hinges; by Prof. Eddy's Method.* [It is understood that the hinges are at the ends.] Required the location of the *special equilibrium polygon*. We here suppose the rib homogeneous (i.e., the modulus of Elasticity E is the same throughout), that it is a "curved prism" (i.e., that the moment of inertia I of the cross-section is constant), that the piers are on a level, and that the rib-curve is symmetrical about a vertical line. Fig. 424. For each point m of the rib curve we have an x and y (both known, being the co-ordinates of the point), and also a z (intercept between rib and special equilibrium polygon) and a z' (intercept



FIG. 424.

*P. 25 of Prof. Eddy's book; see reference in preface of this work.

between the spec. eq. pol. and the axis X (which is OB).

The first condition given in § 378 for Class C may be transformed as follows, remembering [§ 367 eq. (3)] that $M = Hz$ at any point m of the rib (and that EI is constant).

$$\frac{1}{EI}\int_o^B Myds = 0, \text{ i.e., } \frac{H}{EI}\int_o^B zyds = 0 . \therefore \int_o^B zyds = 0$$

$$\left.\begin{matrix}\text{but} \\ z = y - z'\end{matrix}\right\} . \therefore \int_o^B (y - z')yds = 0; \text{ i.e., } \int_o^B yyds = \int_o^B yz'ds \quad . \quad (1)$$

In practical graphics we can not deal with infinitesimals; hence we must substitute Δs a small finite portion of the rib-curve for ds; eq. (1) now reads $\Sigma_o^B\, yy\, \Delta s = \Sigma_o^B\, yz'\, \Delta s$.

But if we take *all the* Δs's *equal*, Δs is a common factor and cancels out, leaving as a final form for eq. (1)

$$\Sigma_o^B(yy) = \Sigma_o^B(yz') \quad . \quad . \quad . \quad (1)'$$

The other two conditions are that the special equilibrium polygon begins at O and ends at B. (The subdivision of the rib-curve into an *even* number of *equal* Δs's will be observed in all problems henceforth.)

379a. Detail of the Construction. Given the arch-rib $O\,B$, Fig. 425, with specified loading. Divide the curve into



FIG. 425.

eight equal Δs's and draw a vertical through the middle of each. Let the loads borne by the respective Δs's be P_1, P_2, etc., and with them form a vertical load-line $A\,C$ to some convenient scale. With any convenient pole O'' draw a trial force diagram $O''\,AC$, and a corresponding trial equilibrium polygon $F\,G$, beginning at any point in the vertical F. Its ordinates z_1'', z_2'', etc., are proportional to those of the special equil. pol. sought (whose abutment line is OB) [§ 374a (2)]. We next use it to determine n' [see § 374a]. We know that OB is the "abutment-line" of the required special polygon, and that ∴ its pole must lie on a horizontal through n'. It remains to determine its H, or pole distance, by equation (1)′ just given, viz.: $\Sigma_1^8\, yy = \Sigma_1^8 yz'$. First by § 375 find the value of the summation $\Sigma_1^8(yy)$, which, from symmetry, we may write $= 2\Sigma_1^4(yy) = 2[y_1y_1 + y_2y_2 + y_3y_3 + y_4y_4]$



Hence, Fig. 426, we obtain

$$\Sigma_1^8\ (yy) = 2\ [H_0 k]$$

Next, also by § 375, see Fig. 427, using the same pole distance H_0 as in Fig. 426, we find

$$\Sigma_1^4\ (yz'') = H_0 k_1''\ ;\ \text{i.e.,}$$

$$y_1z_1'' + y_2z_2'' + y_3z_3'' + y_4z_4'' = H_0k_1''.$$

Again, since $\Sigma_5^8\ (yz'') = y_8z_8'' + y_7z_7'' + y_6z_6'' + y_5z_5''$ which from symmetry (of rib)

$$= y_1z_8'' + y_2z_7'' + y_3z_6'' + y_4z_5'',$$

we obtain, Fig. 428, $\Sigma_5^8\ (yz'') = H_0k_r''$, (same H_0); and ∴

$\Sigma_1^8\ (yz'') = H_0\ (k_1'' + k_r'')$. If now we find that $k_1'' + k_r'' = 2k$,

the condition $\Sigma_1^s(yy) = \Sigma_1^s(yz'')$ is satisfied, and the pole distance of our trial polygon in Fig. 425, is also that of the special polygon sought; i.e., the z'''s are identical in value with the z''s of Fig. 424. In general, of course, we do not find that $k_l''+k_r'' = 2k$. Hence the z'''s must all be increased in the ratio $2k : (k_l''+k_r'')$ to become equal to the z''s. That is, the pole distance H of the spec. equil. polygon must be

$$H = \frac{k_l''+k_r''}{2k} H''$$ (in which H'' = the pole distance of the trial polygon) since from §339 the ordinates of two equilibrium polygons (for the same loads) are inversely as their pole distances. Having thus found the H of the special polygon, knowing that the pole must lie on the horizontal through n', Fig. 425, it is easily drawn, beginning at O. As a check, it should pass through B.

For its utility see § 367, but it is to be remembered that the stresses as thus found in the different parts of the rib under a given loading, must afterwards be combined with those resulting from change of temperature and the shortening of the rib axis due to the tangential thrusts, before the actual stress can be declared in any part.

Note.—Variable Moment of Inertia. If the I of the rib section is different at different sections we may proceed as follows: For eq. (1), we now write $\int_0^B yy\frac{ds}{I} = \int_0^B yz'\frac{ds}{I}$. Taking the I of the crown section (say) as a standard of reference, denoting it by I', we may write for any other section $I = nI'$, where n is a variable ratio, or abstract number; whence eq. (1) becomes, after putting Δs for ds, $\frac{1}{I'}\sum_0^B yy\frac{\Delta s}{n} = \frac{1}{I'}\sum_0^B yz'\frac{\Delta s}{n}$. If now the length of each successive Δs, from the crown down, be made directly proportional to the number n at that part of the rib, the quantity $\Delta s \div n$ will have the same value in all the terms of each summation and may be factored out; and we then have a relation identical in form with eq. (1)′, but *with the understanding* that the y's and z''s concerned are those in the successive verticals drawn through the mid-points of the *unequal* Δs's, or subdivisions along the rib, obtained by *following the above plan* that each Δs is proportional to the value of the moment of inertia at that part of the rib. For instance, if the I of a section near the hinge O, or B, is three times that (I') at the crown, then the length of the Δs at the former point must be made three times the length of the Δs first assumed at the crown when the subdivision is begun. By a little preliminary investigation, a proper value for this crown Δs may be decided upon such that the total number of Δs's shall be sufficient for accuracy (sixteen or twenty in all)

380. Arch Rib of Fixed Ends and no Hinges.—Example of Class D. Prof. Eddy's Method.* As before, E and I are constant along the rib Piers immovable. Rib curve symmetrical about a vertical line. Fig. 429 shows such a rib under any loading. Its span is OB, which is taken as an axis X. The co-ordinates of any point m' of the rib curve are x and y, and z is the vertical intercept between m' and the special equilibrium polygon (as yet unknown, but to be constructed). Prof. Eddy's method will now be given for finding the special equil. polygon. The three conditions it must satisfy (see § 378, Class D, remembering that E and I are constant and that $M = Hz$ from § 367) are



Fig. 429.

$$\int_0^B z\,ds = 0\,;\ \int_0^B xz\,ds = ;\,0 \text{ and } \int_0^B yz\,ds = 0 \quad . \quad . \quad (1)$$

Now suppose the auxiliary reference line (straight) vm to have been drawn satisfying the requirements, with respect to the rib curve that

$$\int_0^B z'\,ds = 0\,;\text{ and } \int_0^B xz'\,ds = 0 \quad . \quad . \quad . \quad . \quad (2)$$

in which z' is the vertical distance of any point m' from vm and x the abscissa of m' from O.

From Fig. 429, letting z'' denote the vertical intercept (corresponding to any m') between the spec. polygon and the auxiliary line vm, we have $z = z' - z''$, hence the three conditions in (1.) become

$$\int_0^B (z' - z'')\,ds = 0\,;\ \text{i.e., see eqs. (2)}\ \int_0^B z''\,ds = 0 \quad . \quad . \quad (3)$$

* P. 14 of Prof. Eddy's book; see reference in preface of this work.

$$\int_0^B x\,(z'-z')ds=0\,;\ \text{i.e., see eqs. (2)}\ \int_0^B xz''ds=o \qquad (4)$$

$$\text{and}\ \int_0^B y(z'-z'')ds=\,;0\,\therefore\ \overset{\text{by trans-}}{\text{position}}\ \int_0^B yz'ds=\int_0^B yz''ds \quad . \quad (5)$$

provided vm has been located as prescribed.

For graphical purposes, having subdivided the rib curve into an *even* number of small equal Δs's, and drawn a vertical through the middle of each, we first, by § 377, locate *vm* to satisfy the conditions

$$\Sigma_0^B(z')=0 \text{ and } \Sigma_0^B(xz')=0 \qquad . \quad . \quad (6)$$

(see eq. (2); the Δs cancels out); and then locate the special equilibrium polygon, with *vm* as a reference-line, by making it satisfy the conditions.

$$\Sigma_0^B(z'')=0\ .\ (7)\,;\quad \Sigma_0^B(xz'')=0\ .\ (8)\,;\quad \Sigma_0^B(yz'')=\Sigma_0^B(yz')\ .\ (9)$$

(obtained from eqs. (3), (4), (5) by putting $ds=\Delta s$, and cancelling).

Conditions (7) and (8) may be satisfied by an infinite number of polygons drawn to the given loading. Any one of these being drawn, as a trial polygon, we determine for it the value of the sum $\Sigma_0^B(yz'')$ by § 375, and compare it with the value of the sum $\Sigma_0^B(yz')$ which is independent of the special polygon and is obtained by § 375. [N.B. It must be understood that the quantities (lengths) x, y, z, z', and z'', here dealt with are those pertaining to the verticals drawn through the middles of the respective Δs's, which must be sufficiently numerous to obtain a close result, and not to the verticals in which the loads act, necessarily, since these latter may be few or many according to circumstances, see Fig. 429]. If these sums are not equal, the pole distance of the trial equil. polygon must be altered in the proper ratio (and thus change the z'''s in the inverse ratio) necessary to make these sums equal and thus satisfy condition (9). The alteration of the z'''s, all in the same ratio, will

not interfere with conditions (7) and (8) which are already satisfied.

331. **Detail of Construction of Last Problem. Symmetrical Arch-Rib of Fixed Ends.**—As an example take a span of the St. Louis Bridge (assuming I constant) with "live load" covering the half span on the left, Fig. 430, where the vertical



FIG. 430.

scale is much exaggerated for the sake of distinctness*. Divide into eight equal Δs's. (In an actual example sixteen or twenty should be taken.) Draw a vertical through the

* Each arch-rib of the St. Louis bridge is a built up or trussed rib of steel about 520 ft. span and 52 ft. rise, in the form of a segment of a circle. Its moment of inertia, however, is not strictly constant, the portions near each pier, of a length equal to one twelfth of the span, having a value of I one-half greater than that of the remainder of the arc.

middle of each Δs. P_1, etc., are the loads coming upon the respective Δs's.

First, to locate vm, by eq. (6); from symmetry it must be horizontal. Draw a trial vm (not shown in the figure), and if the $(+z')$'s exceed the $(-z')$'s by an amount z_o', the true vm will lie a height $\frac{1}{n}z_o'$ above the trial vm (or below, if vice versâ); n = the number of Δs's.

Now lay off the load-line on the right (to scale), take any convenient trial pole O''' and draw a corresponding trial equil. polygon $F'''G'''$. In $F'''G'''$, by § 377, locate a straight line $v'''m'''$ so as to make $\Sigma_o^B(z''') = 0$ and $\Sigma_o^B(xz''') = 0$ (see Note (*b*) of § 377).

[We might now redraw $F'''G'''$ in such a way as to bring $v'''m'''$ into a horizontal position, thus: first determine a point n''' on the load-line by drawing $O'''n''' \parallel$ to $v'''m'''$, take a new pole on a horizontal through n''', with the same H''', and draw a corresponding equil. polygon; in the latter $v'''m'''$ would be horizontal. We might also shift this new trial polygon upward so as to make $v'''m'''$ and vm coincide. It would satisfy conditions (7) and (8), having the same z''''s as the first trial polygon; but to satisfy condition (9) it must have its z''''s altered in a certain ratio, which we must now find. But we can deal with the individual z''''s just as well in their present positions in Fig. 430.] The points E and L in vm, vertically over E''' and L''' in $v'''m'''$, are now fixed; they are *the intersections of the special polygon required, with vm.*

The ordinates between $v'''m'''$ and the trial equilibrium polygon have been called z''' instead of z''; they are proportional to the respective z'''s of the required special polygon.

The next step is to find in what ratio the (z''')'s need to be altered (or H''' altered in inverse ratio) in order to become the (z'')'s; i.e., in order to fulfil condition (9), viz.:



FIG. 431.

$$\Sigma_1^8(yz'') = \Sigma_1^8(yz') \quad . \quad (9)$$

This may be done precisely as for the rib with two hinges, but the negative (z''')'s must be properly considered (§ 375) See Fig. 431 for the detail. Negative z''s or z''''s point upward.

From Fig. 431*a*

$$\Sigma_1^4(yz') = H_o k$$

$\therefore$ from symmetry

$$\Sigma_1^8(yz') = 2H_o k.$$

From Fig. 431*b* we have

$$\Sigma_1^4(yz''') = H_o k_1$$

and from Fig. 431*c*

$$\Sigma_5^8(yz'') = H_o k_r$$

[The *same pole distance* H_o is taken in all these constructions] $\therefore$ $\Sigma_1^8(yz'') = H_o(k_1 + k_r)$.

If, then, $H_0\,(k_1 + k_r) = 2H_0 k$ condition (9) is satisfied by the $z''''s$. If not, the true pole distance for the special equil. polygon of Fig. 430 will be

$$H = \frac{k_1 + k_r}{2k} \cdot H'''$$

With this pole distance and a pole in the horizontal through n''' (Fig. 430) the force diagram may be completed for the required special polygon; and this latter may be constructed as follows: Beginning at the point E, in vm, through it draw a segment $\parallel$ to the proper ray of the force diagram. In our present figure (430) this "proper ray" would be the ray joining the pole with the point of meeting of P_2 and P_3 on the load-line. Having this one seg-

ment of the special polygon the others are added in an obvious manner, and thus the whole polygon completed. It should pass through L, but not O and B.

For another loading a different special equil. polygon would result, and in each case we may obtain the *thrust*, *shear*, and *moment* of stress couple for any cross-section of the rib, by § 367. To the stresses computed from these, should be added (algebraically) those occasioned by change of temperature and by shortening of the rib as occasioned by the thrusts along the rib. These "temperature stresses," and stresses due to rib-shortening, will be considered in a subsequent paragraph. They have no existence for an arch-rib of three hinges.

Note.—If the moment of inertia of the rib section is *variable*, instead of dividing the rib axis into equal Δs's, we should make them *unequal*, following the plan indicated in the note on p. 464, the Δs being made *proportional to the values of the moment of inertia along the rib*. After such subdivision is made, and a vertical drawn through the mid-point of each Δs, the various y's, z''s, etc., in these verticals are dealt with in the same manner as just shown for the case of constant moment of inertia.

381a. Exaggeration of Vertical Dimensions of Both Space and Force Diagrams.—In case, as often happens, the axis of the given rib is quite a flat curve, it is more accurate (for finding M) to proceed as follows:

After drawing the curve in its true proportions and passing a vertical through the middle of each of the equal Δs's, *compute* the ordinate (y) of each of these middle points from the equation of the curve, and multiply each y by four (say). These quadruple ordinates are then laid off from the span upward, each in its proper vertical. Also multiply each load, of the given loading, by four, and then with these quadruple loads and quadruple ordinates, and the upper extremities of the latter as points in an exaggerated rib-curve, proceed to construct a special equilibrium polygon, and the corresponding force diagram by the proper method (for Class B, C, or D, as the case may be) for this exaggerated rib-curve.

The moment, Hz, thus found for any section of the ex-

aggerated rib-curve, is to be divided by four to obtain the moment in the real rib, in the same vertical line. To find the thrust and shear, however, for sections of the real rib, besides employing tangents and normals of the real rib we must draw, and use, another force diagram, obtained from the one already drawn (for the exaggerated rib) by reducing its *vertical* dimensions (only), in the ratio of four to one. [Of course, any other convenient number besides four, may be adopted throughout.]

382. Stress Diagrams.—Take an arch-rib of Class *D*, § 378, i.e., of fixed ends, and suppose that for a given loading (including its own weight) the special equil. polygon and its force diagram have been drawn [§ 381]. It is required to indicate graphically the variation of the three stress-elements for any section of the rib, viz., the thrust, shear, and mom. of stress-couple. *I* is constant. If at any point *m* of the rib a section is made, then the stresses in that section are classified into three sets (Fig. 432). (See §§ 295 and 367) and from § 367 eq. (3) we see that the vertical intercepts between the rib and the special equil. polygon being proportional to the products *Hz* or moments of the stress-couples in the corresponding sections form a **moment diagram,** on inspection of which we can trace the change in this moment, $Hz = \frac{p_2 I}{e}$, and hence the variation of the stress per square inch, p_2, (as due to stress couple alone) in the outermost fibre of any section (tension or compression) at distance *e* from the gravity axis of the section), from section to section along the rib.



FIG. 432.

By drawing through *O* lines *On'* and *Ot'* parallel respectively to the tangent and normal at any point *m* of the rib axis [see Fig. 433] and projecting upon them, in turn, the proper ray (R_3 in Fig. 433) (see eqs. 1 and 2 of § 367)

we obtain the values of the thrust and shear for the section at m. When found in this way for a number of points along the rib their values may be laid off as vertical lines from a horizontal axis, in the verticals containing the respective points, and thus a **thrust diagram** and a **shear diagram** may be formed, as constructed in Fig. 433. Notice that where the moment is a maximum or minimum the shear changes sign (compare § 240), either gradually or



Fig. 433.

suddenly, according as the max. or min. occurs between two loads or in passing a load; see m', e. g.

Also it is evident, from the geometrical relations involved, that at those points of the rib where the tangent-line is parallel to the "proper ray" of the force diagram, the thrust is a maximum (a local maximum) the moment (of

stress couple) is either a maximum or a minimum and the shear is zero.

From the moment, $Hz = \frac{p_2 I}{e}$, $p_2 = \frac{Hze}{I}$

may be computed. From the thrust $= Fp_1$, $p_1 = \frac{\text{thrust}}{F}$, ($F$ = area of cross-section) may be computed. Hence the greatest compression per sq. inch ($p_1 + p_2$) may be found in each section. A separate stress-diagram might be constructed for this quantity ($p_1 + p_2$). Its max. value (after adding the stress due to change of temperature, or to rib-shortening, for ribs of less than three hinges), wherever it occurs in the rib, must be made safe by proper designing of the rib. The maximum shear J_m can be used as in §256 to determine thickness of web, if the section is I-shaped, or box-shaped. See § 295.

383. Temperature Stresses.—In an ordinary bridge truss and straight horizontal girders, free to expand or contract longitudinally, and in Classes A and B of § 378 of arch-ribs, there are no stresses induced by change of temperature; for the *form* of the beam or truss is under no constraint from the manner of support; but with the arch-rib of two hinges (hinged ends, Class C) and of fixed ends (Class D) having *immovable piers* which constrain the distance between the two ends to *remain the same* at all temperatures, stresses called "temperature stresses" are induced in the rib whenever the temperature, t, is not the same as that, t_0, when the rib was put in place. These may be determined, as follows, as if they were the only ones, and then combined, algebraically, with those due to the loading.

384. Temperature Stresses in the Arch-Rib of Hinged Ends.—(Class C, § 378.) Fig. 434. Let E and I be constant, with



FIG. 434.

other postulates as in § 379. Let t_o = temperature of erection, and t = any other temperature; also let l = length of span = OB (invariable) and η = co-efficient of linear expansion of the material of the curved beam or rib (see § 199). At temperature t there must be a horizontal reaction H at each hinge to prevent expansion into the form $O'B$ (dotted curve), which is the form *natural* to the rib for temperature t and without constraint. We may ∴ consider the actual form OB as having resulted from the unstrained form $O'B$ by displacing O' to O, i.e., producing a horizontal displacement $O'O = l\,(t-t_o)\eta$.

But $O'O = \Delta x$ (see §§ 373 and 374); (N.B. B's tangent has moved, but this does not affect Δx, if the axis X is horizontal, as here, coinciding with the span;) and the ordinate y of any point m of the rib is identical with its z or intercept between it and the spec. equil. polygon, which here consists of *one segment only*, viz.: OB. Its force diagram consists of a single ray $O_1 n'$; see Fig. 434. Now (§ 373)

$$\Delta x = \frac{1}{EI}\int_o^B My\,ds\,;\ \text{and}\ M = Hz = \text{in this case, } Hy$$

$$\therefore l\,(t-t_o)\,\eta = \frac{H}{EI}\int_o^B y^2 ds\,;\ \left\{\begin{array}{l}\text{hence for graphics, and}\\ \textit{equal}\ \Delta s\text{'s, we have}\end{array}\right.$$

$$EIl(t-t_o)\eta = H\,\Delta s\,\Sigma_o^B\,y^2 \quad . \quad . \quad . \quad . \quad (1)$$

From eq. (1) we determine H, having divided the rib-curve into from twelve to twenty equal parts each called Δs.

For instance, for wrought iron, t and t_o, being expressed in Fahrenheit degrees, $\eta = 0.0000066$. If E is expressed in lbs. per square inch, all linear quantities should be in inches and H will be obtained in pounds.

$\Sigma_o^B y^2$ may be obtained by § 375, or may be computed. H being known, we find the moment of stress-couple = Hy,

at any section, while the thrust and shear at that section are the projections of H, i.e., of O_1n' upon the tangent and normal. The stresses due to these may then be determined in any section, as already so frequently explained, and then combined with those due to loading.

385. Temperature Stresses in the Arch-Ribs with Fixed Ends.—See Fig. 435. (Same postulates as to symmetry, E and I constant, etc., as in § 380.) t and t_o have the same meaning as in § 384.



FIG. 435.

Here, as before, we consider the rib to have reached its actual form under temperature t by having had its span forcibly shortened from the length natural to temp. t, viz.: $O'B'$, to the actual length OB, which the immovable piers compel it to assume. But here, *since the tangents at O and B are to be the same in direction under constraint as before*, the two forces H, representing the action of the piers on the rib, must be considered as acting on imaginary rigid prolongations at an unknown distance d above the span. To find H and d we need two equations.

From § 373 we have, since $M=Hz=H(y-d)$,

$$\Delta x, \text{ i.e., } \overline{O'O}+\overline{BB'}, \text{ i.e., } l(t-t_o)\eta,=\frac{H}{EI}\int_o^B(y-d)y\,ds \quad . \quad (2)$$

or, graphically, with equal Δs's

$$EIl(t-t_o)\eta=H\Delta s\left[\Sigma_o^B y^2-d\,\Sigma_o^B y\right] \quad . \quad . \quad . \quad (3)$$

Also, since there has been no change in the angle between end-tangents, we must have, from § 374,

$$\frac{1}{EI}\int_o^B M\,ds=0\,; \quad \text{i.e., } \frac{H}{EI}\int_o^B z\,ds=0\,; \text{i.e., } \int_o^B(y-d)\,ds=0$$

or for graphics, with *equal* Δs's, $\Sigma_o^B y = nd$ . . . . (4)

in which n denotes the number of Δs's. From (4) we determine d, and then from (3) can compute H. Drawing the horizontal $F\,G$, it is the special equilibrium polygon (of but one segment) and the moment of the stress-couple at any section $= Hz$, while the thrust and shear are the projections of $H = O_1 n'$ on the tangent and normal respectively of any point m of rib.

For example, in one span, of 550 feet, of the St. Louis Bridge, having a rise of 55 feet and fixed at the ends, the force H of Fig. 435 is = 108 tons, when the temperature is 80° Fahr. higher than the temp. of erection, and the enforced span is 3¼ inches shorter than the span natural to that higher temperature. Evidently, if the actual temperature t is lower than that t_o, of erection, H must act in a direction opposite to that of Figs. 435 and 434, and the "thrust" in any section will be *negative*, i.e., a pull.

386. Stresses Due to Rib-Shortening.—In § 369, Fig. 407, the shortening of the element AE to a length $A'E$, due to the uniformly distributed thrust, $p_1 F$, was neglected as producing indirectly a change of curvature and form in the rib axis; but such will be the case if the rib has *less than three hinges*. This change in the length of the different portions of the rib curve, may be treated as if it were due to a change of temperature. For example, from § 199 we see that a thrust of 50 tons coming upon a sectional area of $F = 10$ sq. inches in an iron rib, whose material has a modulus of elasticity $= E = 30{,}000{,}000$ lbs. per sq. inch, and a coefficient of expansion $\eta = .0000066$ per degree Fahrenheit, produces a shortening equal to that due to a fall of temperature $(t_o - t)$ derived as follows: (See § 199) (units, inch and pound)

$$(t_o - t) = \frac{P}{FE\eta} = \frac{100{,}000}{10 \times 30{,}000{,}000 \times .0000066} = 50°$$

Fahrenheit.

Practically, then, since most metal arch bridges of classes C and D are rather flat in curvature, and the thrusts

due to ordinary modes of loading do not vary more than 20 or 30 per cent. from each other along the rib, an imaginary fall of temperature corresponding to an average thrust in any case of loading may be made the basis of a construction similar to that in § 384 or § 385 (according as the ends are *hinged*, or *fixed*) from which new thrusts, shears, and stress-couple moments, may be derived to be combined with those previously obtained for loading and for change of temperature.

387. **Resumé.**—It is now seen how the stresses per square inch, both shearing and compression (or tension) may be obtained in all parts of any section of a solid arch-rib or curved beam of the kinds described, by combining the results due to the three separate causes, viz.: the load, change of temperature, and rib-shortening caused by the thrusts due to the load (the latter agencies, however, coming into consideration only in classes *C* and *D*, see § 378). That is, in any cross-section, the stress in the outer fibre is, [letting T_h', T_h'', T_h''', denote the thrusts due to the three causes, respectively, above mentioned; $(Hz)'$, $(Hz)''$, $(Hz)'''$, the moments]

$$= \frac{T_h' \pm T_h'' - T_h'''}{F} \pm \frac{e}{I}\left[(Hz)' \pm (Hz)'' \pm (Hz)'''\right] \quad . \quad . \quad . \quad (1)$$

i.e., lbs. per sq. inch compression (if those units are used).



Fig. 436.

The double signs provide for the cases where the stresses in the outer fibre, due to a single agency, may be tensile. Fig. 436 shows the meaning of e (the same used heretofore) I is the moment of inertia of the section about the gravity axis (horizontal) C. F = area of cross-section. [$e_1 = e$; cross section symmetrical about C]. For a given loading we may find the maximum stress in a given rib, or design the rib so that this maximum stress shall be safe for the material employed. Similarly, the resultant shear (total, not

per sq. inch) $= J' \pm J'' \pm J'''$ is obtained for any section to compute a proper thickness of web, spacing of rivets, etc.

388 The Arch-Truss, or braced arch. An open-work truss, if of homogeneous design from end to end, may be treated as a beam of constant section and constant moment of inertia, and if curved, like the St. Louis Bridge and the Coblenz Bridge (see § 378, Class D), may be treated as an arch-rib.* The moment of inertia may be taken as

$$I = 2 F_1 \left(\frac{h}{2}\right)^2$$

where F_1 is the sectional area of one of the pieces ∥ to the curved axis midway between them, Fig. 437, and h = distance between them.



FIG. 438.



FIG. 437.

Treating this curved axis as an arch-rib, in the usual way (see preceding articles), we obtain the spec. equil. pol. and its force diagram for given loading. Any plane ⌐ to the rib-axis, where it crosses the middle m of a "web-member," cuts three pieces, A, B and C, the total com-

*The St Louis Bridge is not strictly of constant moment of inertia, being somewhat strengthened near each pier

pressions (or tensions) in which are thus found: For the point m, of rib-axis, there is a certain moment $= Hz$, a thrust $= T_h$, and a shear $= J$, obtained as previously explained. We may then write $P \sin \beta = J$ . . . . (1) and thus determine whether P is a tension or compression; then putting $P' + P'' \pm P \cos \beta = T_h$ . . . . . 2 (in which P is taken with a plus sign if a compression, and minus if tension), and

$$(P' - P'') \frac{h}{2} = Hz \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

we compute P' and P'', which are assumed to be *both compressions* here. β is the angle between the web member and the tangent to rib-axis at m, the middle of the piece. See Fig. 406, as an explanation of the method just adopted.

Circular Ribs and Hoops.

389. Deflections and Changes of Slope of Curved Beams. Analytical Method. For finding these quantities we may use eqs. (I.), (II.) and (III.) of § 374. For example, we have in Fig. 439, a curved beam of the form of the quadrant of a circle, fixed vertically at lower extremity A, and carrying a single concentrated load, P, at the free end O. [Its own weight neglected.]



Fig. 439.

As a consequence of the loading, the extremity O is displaced to some position, O_n, but the bending is slight. Required, the projections Δx and Δy of this displacement and also the angle OKO_n or ϕ, which the tangent-line at O_n makes with its former (horizontal) position OX. The beam is homogeneous and of constant cross-section; i.e., E and I are constants.

To use the equations for Δx and Δy we must *take O as an origin* (since O is the point whose displacement is under con-

sideration). Hence the co-ordinates x and y of any point, m, of the axis of the beam are as shown in the figure. Taking now polar co-ordinates, as shown, we note that $x = r \cos \theta$; $y = r\,(1 - \sin \theta)$; and $ds = rd\theta$. We must also put down the following integral forms for reference; viz.: —

$$\int \sin \theta . d\theta = -\cos \theta ; \qquad \int \theta . \cos \theta . d\theta = \theta . \sin \theta + \cos \theta ;$$

$$\int \cos \theta . d\theta = +\sin \theta ; \qquad \int \sin^2 \theta . d\theta = \tfrac{1}{2}\theta - \tfrac{1}{4}\sin 2\theta ;$$

$$\int \sin \theta . \cos \theta . d\theta = \tfrac{1}{2}\sin^2 \theta ; \qquad \int \cos^2 \theta . d\theta = \tfrac{1}{2}\theta + \tfrac{1}{4}\sin 2\theta .$$

Taking the portion $O_n m$ (m being any point on curved axis of beam) as a free body, we have, for the moment of the stress couple at m, $M = Px$, $= Pr \cos \theta$, and hence derive, for the angle ϕ,

$$\phi, = \frac{1}{EI}\int_O^B M . ds = \frac{Pr^2}{EI}\int_B^O \cos \theta . d\theta = \frac{Pr^2}{EI}\,(\sin \theta)\Big]_0^{\frac{\pi}{2}} = \frac{Pr^2}{EI} \quad . \ . \ . \quad (1)$$

Also

$$\Delta y, = \frac{1}{EI}\int_O^B M . xds, = \frac{Pr^3}{EI}\int_B^O \cos^2 \theta . d\theta = \frac{Pr^3}{EI}\left[\frac{\theta}{2} + \frac{\sin 2\theta}{4}\right]_0^{\frac{\pi}{2}} = \frac{\pi}{4} . \frac{Pr^3}{EI} \quad (2)$$

and

$$\Delta x, = \frac{1}{EI}\int_O^B M . yds, = \frac{Pr^3}{EI}\left[\int_0^{\frac{\pi}{2}} \cos \theta . d\theta - \int_0^{\frac{\pi}{2}} \cos \theta . \sin \theta . d\theta\right] = \frac{Pr^3}{2\,EI} . \quad (3)$$

It must be understood that the elastic limit is not passed in any fiber and that the bending is very slight. A simple curved crane and a ship's davit are instances of this problem, provided the cross-section has the same moment of inertia, I, about a gravity axis perpendicular to the plane of the paper in Fig. 439, at all parts of the beam.

390. Semi-Circular Arch-Rib. Hinged at the Two Piers or Supports, and Continuous Between. Fig. 440. The supports are at the same level. The arch-rib, or curved beam, is homogeneous and has a constant I at all sections. (It is a "curved prism".) It is stipulated that no constraint is necessary in fitting the rib upon the hinges at the piers before any load is placed on the rib; that is, that the distance apart of the piers (which are *unyielding*) is just equal to the distance between the ends of the rib when entirely free from strain. In other words, after the rib is in position it is under no stress until a load is put upon it. Its own weight is neglected and the load is a concentrated one of $2\,P$ lbs. placed at the "crown", B. As a conse-

quence of the gradual placing of the load the crown B settles slightly, but on account of symmetry the tangent-line to the curved axis at B remains horizontal. Also the extremities O and A tend to spread further apart, but this is prevented by the fact that the piers are immovable (or we may express it "the span is invariable"). Hence the reaction at each hinge support will have a horizontal component H as well as a vertical component, V, lbs. Fig. 2 shows the axis of the rib. Taking the whole rib as a free body we easily find (by putting Σ vert. comps. = zero, and from symmetry) that each $V = P$; the whole load being called $2P$; but for determining the value of H (same at each hinge; from Σ (horiz. comps.) = zero) we must have recourse to the theory of elasticity; i.e., must depend on the following fact, viz.: — that in the gradual settling of point B under the load, B remains in the same vertical, and the tang. line at B remains horizontal, and hence (since O moves neither horizontally nor vertically in actual space) the horizontal projection of O's displacement relatively to B and B's tangent is *zero* (or $\Delta x = 0$), while the vertical projection of O's displacement relatively to B and B's tangent (Δy) equals the distance B has settled in actual space. Here we must take O as origin for x and y (as in figure) for any point m between O and B; and note that the $x = r\ (1 - \cos\theta)$, and $y = r \sin\theta$; while $ds = r.\, d\theta$.



Fig. 440.

With Om as a free body (m being any point between O and B) we have for the moment of the stress couple at m, $M, = Vx - Hy, = Px - Hy$.

$$\Delta x, = \frac{1}{EI}\int_O^B My ds, = 0\ ;\ \therefore \int_0^{\frac{\pi}{2}} [P(r - r\cos\theta) - Hr\sin\theta]r^2 \sin\theta d\theta = 0\ ;$$

$$\therefore P\int_0^{\frac{\pi}{2}} \sin\theta . d\theta - P\int_0^{\frac{\pi}{2}} \sin\theta\cos\theta d\theta - H\int_0^{\frac{\pi}{2}} \sin^2\theta . d\theta = 0\ ;$$

and hence, (see integrals in § 389),

$$\left(P\left[-\cos\theta-\frac{\sin^2\theta}{2}\right]-H\left[\frac{\theta}{2}-\frac{\sin 2\theta}{4}\right]\right)_0^{\frac{\pi}{2}}=0.$$

Inserting the limits, we have

$$P\left[-0+1-\tfrac{1}{2}+0\right]-H\left[\frac{\pi}{4}-0-0-(-0)\right]=0;$$

$$\therefore H=\frac{2P}{\pi}=\frac{\text{load}}{\pi}.$$

Also we may obtain, for the settlement of the crown, at B

Δy of O relatively to B, $=\dfrac{1}{EI}\displaystyle\int_o^B Mxds=\frac{Pr^3}{EI}\left[\frac{3\pi}{4}-\frac{1}{\pi}-2\right]$

while the tangent-line at O, originally vertical, now makes with the vertical (on the outside)

$$\text{an angle}=\frac{1}{EI}\int_o^B Mds=\frac{Pr^2}{EI}\left[\frac{2}{\pi}+1-\frac{\pi}{2}\right].$$

This is a "*statically indeterminate structure*"; that is, one in which a solution is impossible by ordinary statics but must depend on the theory of the elastic change of form of the beam or body in question.

If the load were not placed at the crown, or highest point, we should be obliged to put

$$\frac{1}{EI}\int_o^A Myds=0$$

for the Δx of O relatively to A (instead of to B).

391. Cylindrical Pipe Loaded on Side. A cylindrical pipe of homogeneous material and small uniform thickness of pipe-wall, t, and length l, (so that the moment of inertia of the cross-section of wall is for present purposes $I=lt^3\div 12$) rests in a horizontal position on a firm horizontal floor and bears a concentrated load of $2P$ at the highest point, or crown, B. See Fig. 441. It is to be considered as a continuous curved beam or "hoop", without hinges. We neglect the weight of the pipe itself. The dotted circle shows the original unstrained form of the pipe-wall, or hoop, while the full line is its (slightly deformed) shape when it bears the load. The elastic limit is of course not to be passed. The upward force $2P$ at N is the reaction of the floor. *Required*, the maximum moment of stress-couple; and also the increase in the length of the horizontal diameter, and the decrease in that of the vertical diameter.

Consider as a free body the upper left-hand quadrant of the hoop, viz., OB, in Fig. 442, cutting just on the left of the load at B, a horizontal section being made at O. At each end of this body we must indicate a stress-couple, a shear, and a thrust. But at O it is evident, after a little consideration, that the shear (which would be horizontal) must be *zero;* there being at O, $\therefore$ only

a thrust T_0 and a stress-couple of unknown moment M_0. At the other section the shear must be equal to one half of the load $2P$ (from considerations of symmetry) i.e., J at $B = P$; while the thrust at B is soon shown to be zero (since Σ (horiz. compons.) must = zero, and this thrust if it existed would be



Fig. 441.



Fig 442.



Fig. 443.

the only horiz. force besides those forming the stress-couple at B). At B, therefore, we find only a stress-couple, of an unknown moment M_B, and a shear J_B of direction shown in Fig. 442. By writing Σ (vert. compons.) = zero for this free body we find that the thrust, T_0, at O, must have a value P.

To determine M_0 we make use of the fact (evident from Fig. 441) that in the deformed condition of the "hoop" the tangent-lines at points O and B are still vertical and horizontal, respectively; in other words that the angle between them has not changed, i.e., is still 90°. Hence the value of ϕ, or *change of angle* between tangents at O and B is *zero*. Apply this fact to Fig. 442. Take O as origin for the x and y of any point m on OB (using θ later). From a consideration of the free body Om shown in Fig. 443 we have for the stress-couple-moment M at any section m the value $M = Px - M_0$. We have also $x = r\ (1 - \cos\theta)$; $y = r \sin\theta$; and $ds = rd\theta$.

Since $$\phi, = \frac{1}{EI}\int_O^B Mds, = 0, \quad \therefore \int_O^B [Pr^2 - Pr^2\cos\theta - M_0 r]\, d\theta = 0;$$

i.e., $$(Pr^2\,[\theta - \sin\theta] - M_0 r\theta)\Big|_0^{\frac{\pi}{2}} = 0;\ \text{or, } Pr^2\left[\frac{\pi}{2} - 1\right] - M_0 r\frac{\pi}{2} = 0;$$

whence, finally, we have $$M_0 = Pr\left[1 - \frac{2}{\pi}\right] \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

Now that M_0 is known, we may find M_B by taking moments about the lower section, O, in Fig. 442, with OB as free body whence $M_B = (2 \div \pi)\ Pr$, which is greater than M_0. Hence the equation for safe loading is $(R'I \div e) = 2Pr \div \pi$, where R' is the maximum safe unit-stress for the material, and e the distance of the extreme fiber from the gravity axis of a section. (If, however, the radius, r, of the cylinder is not large compared with the radial thickness of the section, see §§ 298 and 299.)

Evidently the horizontal diameter has been lengthened by an amount $2\Delta x$, if Δx denote the horiz. proj. of O's displacement relatively to B and B's tangent; and similarly, the shortening of the vertical diameter is $2\Delta y$, if Δy denote the vert. proj. of O's displacement with regard to B and B's tangent-line.

Hence

$$\Delta x = \frac{1}{EI}\int_O^B My ds = \frac{1}{EI}\int_0^{\frac{\pi}{2}} [Pr^3 \sin\theta \,.\, d\theta - Pr^3 \cos\theta \sin\theta d\theta - M_0 r^2 \sin\theta d\theta];$$

from which we have, with $M_0 = Pr\,[1 - (2 \div \pi)]$,

$$\Delta x = \frac{Pr^3}{EI} \cdot \frac{4-\pi}{2\pi}; \text{ while}$$

$$\Delta y = \frac{1}{EI}\int_O^B Mx ds, = \frac{1}{EI}\int_0^{\frac{\pi}{2}} [Pr^3 (1 - \cos\theta)^2 d\theta - M_0 r^2 (d\theta - \cos\theta d\theta)],$$

$$\text{i.e.,} \quad \Delta y = \frac{Pr^3}{EI} \cdot \frac{\pi^2 - 8}{4\pi} .$$

It will be noted that the results obtained in this problem apply also to the case where the hoop is a circular link of a chain under a tension $2P$, except that the moments will be of opposite character and shears and thrusts of opposite direction. Also, the change of length $2\Delta x$ of the horiz. diameter will be a *shortening*, that of the vertical diameter, a *lengthening*. (See Prof. Filkins' article on p. 99 of Vol. IV of the Transac. of Assoc. C. E. of Cornell Univ. and Engineering News, Dec. 1904, p. 547.)

Numerical Example. Fig. 441. The length of a cast iron pipe is 10 ft., the thickness of wall $\frac{1}{2}$ inch, and the radius of the pipe (measured to the middle of the thickness) is 6 inches. Required, the value of the safe load at crown, $2P$ when the pipe is supported horizontally on a firm smooth bed or floor; the max. safe unit-stress being taken at the low figure 2000 lbs. per sq. inch.

Solution. We have only to substitute these values in $M_B = R'I \div e$ and obtain (since $I = l.\, t^3 \div 12$), $\frac{2000 \times 120 \times (\frac{1}{2})^3}{(\frac{1}{2}) \times (\frac{1}{2}) \times 12} = (0.6366\, P \times 6)$; hence *safe load* $= 2P$, $= 5236$. lbs.; that is, 43.63 lbs. per running inch of pipe length.

If now the thickness be doubled, i.e., $t = 1''$, with other data unchanged, we find the safe load to be four times as great, i.e., $2P = 20{,}944$ lbs.; or 174.5 lbs. per running inch of pipe-length.

Although the load is called "concentrated" as regards the *end-view* of the pipe, it must be understood to be uniformly distributed along the length.

CHAPTER XII.

FLEXURE OF BEAMS; BOTH SIMPLE AND CONTINUOUS. GEOMETRICAL TREATMENT.

392. By Geometrical Treatment is meant making use of the properties of geometrical figures to deduce algebraic relations. This *does not necessitate the use of drafting instruments;* but the graphic ideas involved greatly simplify the algebraic detail of finding deflections, angles, moments, shears, etc., in the case of horizontal beams originally straight and slightly bent under vertical loads and reactions. In the case of "continuous beams", or "girders", (p. 320), this mode of treatment leads to conceptions and methods which are remarkably clear and simple.

393. Angle Between End-Tangents of a Portion of a Bent Beam. If the cantilever beam of Fig. 443*a* (slender and originally



FIG. 443*a*. FIG. 443*b*.

straight) be loaded as shown, and the beam thus slightly bent, the two cross-sections, AH and CD, at the two ends of any dx of the axis of beam, are no longer parallel but become inclined at a small angle $d\phi$ which is also the angle between the normals to these sections, in their new (relative) position (see now Fig. 443*b*). AH now occupies the position $A'H'$ (relatively to CD). The outer fiber AC (originally of length $= dx$) is longer by some amount $d\lambda$; and evidently the value of angle $d\phi$ may be written $= d\lambda \div e$. But, by the definition of the modulus of elasticity of the material, E, we have also

$$E = p \div \frac{d\lambda}{dx}, \text{ (p. 209); whence } d\phi = \frac{p dx}{Ee} \quad . \quad . \quad . \quad . \quad . \quad (1)$$

Now if M denote the moment of the stress-couple to which the tensions and compressions on the ends of the fibers in the section $A'H'$ are equivalent (M would equal Px in this simple case) we may combine the relation, (§ 229), $M = pI \div e$ with eq. (1) and thus derive, as

a fundamental relation: . . . $d\phi = \dfrac{M dx}{EI}$ . . . . . (2)

for the angle between two tangents to the elastic curve, one at each end of the elementary length, dx, of the curve; since the two normals to the sections $A'H'$ and $C\ D$ in Fig. 443*b* are tangents to the ends of the short length dx of the elastic curve. (This value of the angle $d\phi$ is in π-measure; i.e., *radians*.)

It follows, therefore, that when the cantilever of Fig. 443*a* is gradually bent from its original condition (in which the tangent lines at the two extremities O and B were coincident, i.e., made with each other an angle of zero) into its final form, by the gradual application of the load P at O, the angle between the tangent to elastic curve at O_n (the final position of O) and that at B (which tangent, in this case, has not moved) will have a value obtained by summing up all the small values of $d\phi$, one for each of the dx's between O and B (these dx's making up the length of curve between those points).



Fig. 444.

Or, **in general**, if O_n and B are **any two points** of an elastic curve (of axis of bent beam, originally straight and now only slightly bent, x being measured along the beam) we have for the

angle between the tangents at O_n and B $\Big\} = \phi = \int_o^B \dfrac{M dx}{EI}$ . . . . . (3)

(See Fig. 444 for case of cantilever.) This may be called the *angle between end-tangents* of any portion of such elastic curve. The beam must be *continuous* between these two points and only slightly bent. Usually the beam in question is homogeneous and then E may be taken outside of the integral sign. Also, if the beam be prismatic in form (i.e., sides parallel to a central axis, originally straight) the moment of inertia,

I, of the cross-section is the same for each dx, and may be placed outside of the $\int$ sign.

394. (Relative) Displacement of any Point, O, of Elastic Curve of a Bent Beam. In the case of the simple cantilever of Fig. 443a let us consider that the axis of the beam, originally straight and in position OB, passes gradually into its final form or elastic curve $O_n\,A'''\,A''\,\ldots\,B$ by the *successive* change of form of each small block, or elementary length dx; beginning



Fig. 444a.

at the end B. When the section at A' turns through its angle $d\phi_1$, as due to the lengthening and shortening of the fibers forming the block (i.e., to the stress-couple in section A', of moment M') it carries with it all the portion OA' (still straight) into position O_1A' so that the extremity O describes a small distance (practically vertical) $\overline{OO_1} = \overline{OA'} \cdot d\phi_1$. Similarly when, next in order, the section at A'' turns through its small angle $d\phi_2$, the left-hand end of the beam describes a further small distance $\overline{O_1O_2} = \overline{OA''} \cdot d\phi_2$; and so on; until finally the extremity O has arrived at its final position O_n, having executed a total (vertical) displacement $\overline{OO_n}$, which will be called Δy.

If, now, any one of the elementary vertical displacements (like $\overline{O_1O_2}$, as typical) be called δy, we note that Δy is the sum of all these small δy's, each of which is practically a small circular arc described with a radius x swinging through a small angle $d\phi$, (the successive x's being successively smaller for the δy's lower in the series), so that $\delta y = x d\phi$; hence

$$\Delta y, = \int \delta y, = \int x d\phi. \quad \text{But, from eq. (2), } d\phi = M dx \div EI;$$

$$\therefore \left\{\begin{matrix}\text{Displacement of point } O \\ \text{relatively to } B\text{'s tangent}\end{matrix}\right\} = \Delta y = \int_0^B \frac{M x dx}{EI} \quad . \quad . \quad . \quad (4)$$

(N.B. *In the use of this relation the x of each dx must be measured from the point O whose displacement is desired.*)

Although the special case of the cantilever has been in mind in the figure used in this connection, this result in eq. (4) may be generalized by stating that it gives the displacement Δy of any point O from the tangent-line drawn at any other point, B, of the elastic curve formed by the axis of a beam originally straight and slightly bent under the action of vertical forces and reactions. In order to use it, the value of the moment M of the stress-couple in each successive dx must be expressed as a function of x. If, in addition, the beam has a constant moment of inertia, I, of the cross-sections, the "I" may be taken outside of the sign of integration. An integration is then generally possible. (For example, in the above cantilever, for M we should write Px.)

395. Deflections and Slopes of Straight Homogeneous Prismatic Beams Slightly Bent under Vertical Loads and Reactions. (Beam Horizontal.)

If the beam is a *prism* and homogeneous, both E and I are constant along its length and may be taken outside of the integral sign in eqs. (3) and (4), and these two equations may now be applied to a portion of a beam situated between any two points O and B of the elastic curve assumed by the (originally straight) axis of the beam (Fig. 444*b*) under some load. The tangent-lines at O_n and B were originally coincident, and hence the angle between these tangents when the beam is bent is the *total change* in angle between the tangents, and consequently may be written $\phi = \frac{1}{EI}\int_0^B M dx$ and is $O_n CO$ in the figure. Again, if a vertical be drawn through the point O_n to B's tangent-line OB, the length $\overline{OO_n}$ is evidently O's displacement relatively to B's tangent-line, since originally the point O_n was situated in B's tangent itself.



FIG. 444*b*.

That is, $\overline{OO_n}$, or $\Delta y, = \frac{1}{EI}\int_0^B M x dx$, in which M is the mo-

ment of the stress-couple in the cross-section at any distance, x, from O. Note that in general M is a *variable*; also that the x must be measured from the point O whose displacement is under consideration.

Example I. *Simple cantilever* (Fig. 444_1), *built in horizontally at B and bearing a concentrated load = P lbs. at the free extremity.* Both E and I are constant (homogeneous prism). Find the deflection $\overline{OO}_n$ and the slope ϕ.

Solution. From the free body $O_n m$ (m being any point between O and B) we have $M = Px$ as mom. of stress-couple at m.

$$\phi = \frac{1}{EI}\int_0^B M\,dx = \frac{P}{EI}\int_0^l x\,dx = \frac{Pl^2}{2EI} = \text{the "slope" at } O_n. \quad \text{For } \Delta y$$

we have $$\Delta y, = \overline{OO}_n, = \frac{1}{EI}\int_0^B Mx\,dx = \frac{P}{EI}\int_0^l x^2 dx = \frac{Pl^3}{3EI}.$$



Fig. 444_1.



Fig. 444_2.

Example II. *Prismatic beam on two end-supports. Concentrated load P, lbs., in middle*, Fig. 444_2. The two supports being at same level we note that from symmetry the tangent at the middle point B of the elastic curve is horizontal. Hence the displacement $\overline{OO}_n$ of the extremity O from this tangent is equal to the deflection of B itself below the horizontal line O_nC. To find $\overline{OO}_n$ or Δy,

$$\Delta y = \frac{1}{EI}\int_O^B Mx\,dx = \frac{1}{EI}\int_O^B \left[\frac{P}{2}\,x\right] x\,dx = \frac{P}{2EI}\int_{x=0}^{x=\frac{l}{2}} x^2 dx = \frac{Pl^3}{48EI}$$

Example III. *Prismatic beam on two end-supports at same level, the load being uniformly distributed over the whole span, l.* Fig. 444_3. That is, $W = wl$,



Fig. 444_3.



Fig. 444_4.

w being the load per running inch. As before, the tangent-line at middle point B of the elastic curve must be horizontal, so that the displacement of extremity O_n from this tangent will also give the deflection of B from the horizontal O_nC. Measuring x from O (as must always be done in these cases) we note that M at any point $m = \frac{W}{2}x - \frac{wx^2}{2}$.

$$\overline{OO}_n = \frac{1}{EI}\int_O^B \left[\frac{Wx^2}{2}dx - \frac{wx^3}{2}dx\right] = \frac{1}{EI}\left[\frac{Wx^3}{6} - \frac{wx^4}{8}\right]_0^{\frac{l}{2}} = \frac{5}{384}\cdot\frac{Wl^3}{EI}.$$

Example IV. *Prismatic beam on end-supports, bearing two equal loads, each* $= P$, *symmetrically placed on the span.* Fig. 444_4. Required, the deflection of the middle point, B, of the elastic curve, below the horizontal O_nC. Length $= 4a$.

Solution. In previous problems of this article the expression for M, the mom. of stress-couple for any point m between the points O and B, has been a single function of x, applying to all such points m. But in the present problem, having found the reaction at O to be $= P$ lbs., we note by considering a free body O_nm (where m is any point between O_n and D) that the value of M is $M = Px$; whereas if the free body extends into the portion DB the expression for M (the free body being now O_nm') is $M = Px - P(x - a)$ which reduces to $M = Pa$, a *different* function of x; (in fact a constant). Therefore, in making the summation $OO_n = (1 \div EI) \int Mx\, dx$ for all the dx's between O and B, this summation must be divided into two parts, viz.: one from O to D, involving for x the limits $x = 0$ and $x = a$; and the other from D to B, for which the limits for x are $x = a$ and $x = 2a$. Hence

$$\overline{OO_n} = \frac{1}{EI}\int_0^B Mx\, dx = \frac{1}{EI}\left[\int_{x=o}^{x=a} Px^2 dx + \int_{x=a}^{x=2a} Pa \,.\, x\, dx\right] = \frac{11}{6} \cdot \frac{Pa^3}{EI}. \quad (1)$$

(The student should verify all details of this operation, noting that each summation or integral contains the proper value of M, *as a function of* x, for the proper portion of the elastic curve. As before, it should be said that on account of symmetry the tangent-line at the middle point B is horizontal, and parallel to O_nC. *Otherwise* O_nO *would not be equal to the deflection of* B.)

396. Non-prismatic Beam. Variable Moment of Inertia, I. If the I is variable, (e.g., if the beam tapers) it must be retained on the right of the integral sign in the expressions for ϕ and Δy and then expressed as a function of x before the integration can be proceeded with. In some cases I may be constant within the limits of definite portions of the beam and then the procedure is simple. For instance, if the beam in Fig. 444_4 has a constant value, $= I_1$, for the portions OD and FC, and a larger (but constant) value, of I_2, $= \frac{3}{2} I_1$, for all the sections from D to F, the following takes the place of eq. (1) above:

$$\overline{OO_n} = \frac{P}{EI_1}\int_0^a x^2 dx + \frac{Pa}{EI_2}\int_a^{2a} x dx = \frac{4}{3} \cdot \frac{Pa^3}{EI_1} \quad . \quad . \quad . \quad . \quad (1a)$$

397. Properties of Moment Diagrams (Moment-Areas and Centers of Gravity). Prismatic Beams in Horizontal Position. Vertical Loads and Reactions. In Fig. 445 let AD be the bent condition (i.e., elastic curve) of the axis of a straight prismatic homogeneous beam supported on supports at, or nearly at, the same level (so that all tangent lines to the elastic curve deviate but slightly from the horizontal. That is, the bending is slight). Also, let $A''D''B'''O'''$ be the corresponding *moment diagram* (as defined and illustrated on pp. 265 to 309). For instance, for any point m of the elastic curve the moment of stress-couple (or "bending moment") in that section of the bent beam is repre-

sented (to scale) by the ordinate $m''m'''$ or M, in the same vertical as m.

If now a small horiz. distance dx, or $m''r$, be laid off from m'' and a vertical $r\,..\,s$ be drawn through r, the product $M\,.\,dx$ would be proportional to, and may be represented by, the area of the vertical strip $m''rsm'''$. Now dx being inches (say) and M being inch-lbs., this product might be called so many "sq. inch-lbs." of *moment-area* (as it will be called). But the angle ϕ between the tangent-lines drawn at any two points O_n and B of the elastic curve is equal to $\frac{1}{EI}\int_o^B Mdx$; and hence we may write



FIG. 445.

$$\phi = \begin{bmatrix}\text{total "moment-area"}\\ \text{between } O \text{ and } B\end{bmatrix} \div EI \quad . \quad . \quad . \quad . \quad . \quad . \quad (1a)$$

or, for brevity, $\phi = (A_o^B) \div EI \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$

This "moment-area," then, between O and B is the product of the base $O''B''$ (inches) by the average moment between O and B regarded as the average altitude of the figure, $O''B''B'''O'''$, this altitude being inch-lbs.

Again, if the elementary "moment-area" Mdx be multiplied by x, its horizontal distance from O'' (i.e. from O and O_n), and these products summed up for all the dx's between O and B, there results the expression $\int_o^B (M\,.\,dx)\,.\,x$ which may be written $(A_o^B)\,.\,\bar{x}$, where $\bar{x}$ denotes the horiz. distance of the *center of gravity* of the moment-area $O''B'''$ from $O''O'''$ (since, from the theory of the center of gravity, the sum of the products of each *strip* of an area by its x co-ordinate is equal to the product of the whole area by the distance of its center of gravity from the same axis). In the figure the center of gravity of the moment-area $O''B'''$ is shown at C'', and the corresponding $\bar{x}$ is marked.

But we have

$$\Delta y, \text{ or } \overline{OO}_n, = \left[\int_o^B Mxdx\right] \div EI = \left[\int_o^B Mdx \,.\, x\right] \div EI;$$

and hence we may write

$$\overline{OO}_n, \text{ or } \Delta y, = [(A_o^B) \,.\, \bar{x}] \div EI \quad . \quad . \quad . \quad . \quad (2)$$

which furnishes us with a simple means of determining the displacement of any point O_n in the elastic curve of the bent beam from the tangent-line at any other point B in that elastic curve.

Evidently, from equations (1) and (2) we have $\Delta y, = \overline{OO}_n, = \phi\bar{x}$; and can therefore state that the *intersection of the two tangent-lines, one drawn at O, the other at B, lies in the same vertical as the center of gravity of the intervening moment-area.*

(N.B. Instead of the product $(A_o^B).\bar{x}$, we may, of course, use the algebraic sum of similar products for any component parts into which it may be convenient to subdivide the total moment-area.)

398. Examples of Use of Eqs. (1) and (2) of Preceding Paragraph.

Example I. Simple Cantilever. *Concentrated load at free end.* Fig. 444_1. Constant E and I. (*Prism.*) Here the moment-diagram for whole length is a *triangle* (§ 249) whose base is l inches and whose altitude is Pl inch-lbs.



FIG. 445_1.

Hence, with O and B taken as in Fig. 445_1, we note that

$$A_o^B = \left(l \,.\, \frac{Pl}{2}\right), \text{ and that } \bar{x} = \frac{2}{3}l.$$

$$\therefore \phi = \left[l \,.\, \frac{Pl}{2}\right] \div E \,.\, I. = \frac{Pl^2}{2\,EI}; \text{ for the slope at } O_n; \text{ while } \overline{OO}_n = \frac{1}{EI}(A_o^B).\,\bar{x},$$

$$\text{i.e., } \overline{OO}_n = \frac{1}{EI}\left[l \,.\, \frac{Pl}{2}\right] \cdot \frac{2}{3}\,l = \frac{Pl^3}{3\,.\,EI}.$$

Example II. Prismatic Beam on Two End-Supports. *Load Uniformly distributed over the whole span or length, l; $W = wl$.* From p. 268 we know that the moment-diagram (Fig. 445_2) is a symmetrical segment of a parabola with axis vertical, and that the moment at the middle section is $Wl \div 8$. Also, from p. 12 of Notes, etc., in Mechanics, we find the $\bar{x}$ of the left-hand half of this moment-figure, measured from the left-hand extremity O_n, is $\frac{1}{2}\,l - \frac{3}{8}$ of $\frac{1}{2}\,l$; i.e., $\bar{x} = \frac{5}{8}$ of $\frac{1}{2}\,l$.

The area of this semi-parabolic-segment is two-thirds that of the circumscribing rectangle. From symmetry, the tangent-line drawn at B, the middle point of the elastic curve, is parallel to $O_n\,D$, so that the displacement $\overline{O_nO}$ of O from that tangent is equal to the deflection of B from O_nD. Hence

$$\overline{O_nO}, = \frac{(A_o^B).\,\bar{x}}{EI}, = \left[\frac{2}{3}\cdot\frac{l}{2}\cdot\frac{Wl}{8}\cdot\frac{5}{8}\cdot\frac{l}{2}\right] \div EI = \frac{5}{384}\cdot\frac{Wl^3}{EI}.$$

Example III. *Prismatic Beam. Ends Supported. Two Concentrated Loads Equidistant from Supports.* Fig. 445_3.

Here, as before, from symmetry the tangent at B is horizontal, parallel to



Fig. 445_2.



Fig. 445_3.

O_nD; so that O_nO equals the deflection of B from C (its position before loading of beam). Each load P is in middle of a half-span. Required $\overline{O_nO}$; i.e., $CB = ?$

In this case the moment-diagram is easily shown to consist of a triangle at each end with a central rectangle of altitude $= Pa$ (inch-lbs.). To find $\overline{O_nO}$ we need the product $(A_O^B).\bar{x}$. But this A_O^B consists of the triangle $O''A''N$ with its center of gravity distant $\frac{2}{3}$ of a from O and of the rectangle $A''B''KN$ whose center of gravity is at a distance of $\frac{1}{2}$ of a from O. Utilizing, therefore the principle stated in the N.B. of § 397, we write

$$\overline{O_nO}_O = \frac{(A)_O^B.\bar{x}}{EI} = \frac{1}{EI}\left[a\cdot\frac{Pa}{2}\cdot\frac{2}{3}a + a.Pa\frac{3}{2}a\right] = \frac{11}{6}\cdot\frac{Pa^3}{EI}.$$

Example IV. *Prismatic Beam on End Supports. Single Eccentric Load, P.* Fig. 445_4. Here a tangent drawn to the elastic curve at the load-point B, not being horizontal, is *not parallel to* O_nC_n, and hence $\overline{O_nO}$ does *not* = the deflection, δ, of B.



Fig. 445_4.

However, the displacements ($= d_1$ and d_2), of O from B's tangent and of C from B's tangent, are easily found, the moment-diagram $O''NC''$ having been drawn, in which $\overline{B''N} = (Pa_1a_2 \div l)$ inch-lbs. (§ 260). Call the "moment-area" of triangle $O''B''N$, A'; and that on right of load, viz. of $C''B''N$, A''.

Then, from eq. (2) of § 397, we may write

$$EId_1 = A'\bar{x}_1; \text{ and } EId_2 = A''\bar{x}_2.$$

If now we draw a horizontal line, HD, through the point B of the elastic curve, we note, from the similar triangles thus formed, the proportion $\frac{d_1 - \delta}{\delta - d_2} = \frac{a_1}{a_2}$. From these three equations d_1 and d_2 may be eliminated and δ

obtained; (since $A = \frac{1}{2} Pa_1{}^2a_2 \div l$, and $A'' = \frac{1}{2} Pa_2{}^2a_1 \div l$; while $\bar{x}_1 = \frac{2}{3} a_1$, and $\bar{x}_2 = \frac{2}{3} a_2$.)

We thus obtain $\delta = (\frac{1}{3} Pa_1{}^2a_2{}^2) \div (EI.l)$ . . . . . (3)

This is for the load-point. For the *maximum* deflection see next example.

Example V. *Maximum Deflection of Prismatic Beam. End Supports. Single Eccentric Load.* Fig. 445$_5$. To locate the lowest point D of elastic curve and determine its deflection, d, below the horizontal O_nB.



Fig. 445$_5$.

Draw a tangent at D, also at B whose distance n from D is, as yet, unknown. Note that the tangent at D is *horizontal*.

The moment-diagram is a triangle of altitude M'; ($M' = Pab \div l$); denote the moment at D by m'. We have $m' = (n \div b) . M'$. Now the angle $\phi = d' \div l$, and

$$d' = (A_v^B) . \bar{x} \div EI = \tfrac{1}{2} M'l \,(a + \tfrac{2}{3}\,[\tfrac{1}{2}\,(a+b) - a]) \div EI.$$

$\therefore 6\,EI\phi = M'(2a + b)$. But $\phi_1 = (A_D^B) \div EI = n . m' \div 2EI$, and $\phi = \phi_1$; $\therefore$, finally, we have $n = \sqrt{\frac{1}{3} b\,(2a + b)}$, which locates the point R.

Now note that the intersection C lies in the vertical through the center of gravity of the shaded triangle (§ 397). Hence $\overline{CD} = \frac{1}{3} n$ and therefore from similar triangles $\overline{DS} = \frac{1}{3}\overline{RS}$. But $\overline{RD}$, $= d$, $= \overline{RS} - \overline{DS}$, and $\overline{DS} = \phi_1 . \overline{CD} = \phi . \frac{1}{3} n$. Hence $d = \frac{2}{3}\phi n$ and finally by substitution, and with M' placed $= Pab \div l$, we have (with $b > a$)

$$d = \frac{1}{9} \cdot \frac{Pab}{EI.l} [2a + b] \sqrt{\tfrac{1}{3} b\,(2a + b)} \quad . \quad \left\{ \begin{matrix} \text{same as} \\ \text{on page 258} \end{matrix} \right\}$$

399. The "Normal Moment Diagram." If a portion, OB, of a horizontal beam carrying loads, be conceived separated from the remainder of beam and placed on two supports at its extremities O and B, while carrying the loads [say P_1 and P_2] originally lying between O and B, the corresponding moment-diagram, $O'''TB'''$ of Fig. 446 may be called the "**normal-moment diagram**" for portion OB (of original beam) and its load. If V_0 is the pier reaction at left, we have for any section t (say between P_1 and P_2) x ft. from O, the moment of stress-couple [call it M_n or "**normal moment**"]

$$M_n = V_0x - P_1(x - a) \quad . \quad . \quad . \quad . \quad . \quad (1)$$

Now consider OB in its original condition (see lower part of Fig. 446) when forming part of a much longer beam sup-

ported in *any manner*. If we consider OB, *now*, as a "free body," we must put in, besides the loads P_1 and P_2, a shear J_0 and a stress-couple of moment M_0 in section at O, and J_B and couple of moment M_B at B. The moment in any section t of OB is now $M = M_0 + J_0 x - P_1 (x - a)$. Let V = difference between J_0 and V_0,

i.e., $$J_0 = V_0 + V;$$

then $$M = M_0 + Vx + [V_0 x - P_1 (x - a)] \quad . \quad (2)$$

i.e. [see (1)], $$M = M_0 + Vx + M_n \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

Hence the moment M ($= kw$ in Fig. 446) of any section of OB is made up of a constant part M_0, a part proportional to x, and a third part equal to the "*normal moment*" of that section. Therefore, if, in the moment-diagram $O'B'B''wO''$ for OB we join O'' and B'' by a straight line, and also draw a horizontal through O'', the vertical intercepts [such as uw] between the line $O''B''$ [or "chord"] and the broken line $O''wB''$ are the *normal moments* for OB and its load, and the area (mom.-area) of the figure formed by these intercepts is equal to that of the *normal moment diagram*.



Fig. 446.

It is also evident that the center of gravity of the figure $O''B''w$ lies in the same vertical as that of the *normal moment diagram*.

(In the next paragraph the trapezoid $O'B'B''O''$ will be divided into two triangles, instead of into a triangle and a rectangle.)

400. The Theorem of Three Moments. Let O, B, and C, Fig. 446*a*, be any three points in the elastic curve of a homogeneous, *continuous*, and *prismatic* beam, originally straight and horizontal but now slightly bent under vertical forces (some of which are reactions of supports; no loads or forces are shown in the figure).



FIG. 446*a*.

Let M_0, M_1, and M_2 be the moments of the couples in sections O, B, and C. The moment-diagram for portion OBC is $O'C'C''T_2B''T_1O''$. Join $O''B'$ and $C''B'$; also $O''B''$ and $C''B''$. At the point B of elastic curve draw a tangent m_0m_2 and join OC. Then $\overline{Om}_0$, or d_0, is the displacement of point O from B's tangent, and $d_2 = \overline{Cm}_2$, is the displacement of C from the same tangent; while δ is the *deflection of B from the straight line joining O and C*.

Now the vertical displacement $d_0 =$ [mom.-area $O'B'T_1 \times$ distance of its cent. grav. from OO''] $\div EI$. But the moment-figure $O'B'T_1$, under OB, is composed of the two triangles shown and the "*normal moment-diagram*" *for OB*, viz.: $O''B''T_1$, whose mom.-area may be called A_1 and whose center of gravity is $\bar{x}_1$ ft. from OO'', while the corresponding distances for the triangles are $\frac{1}{3}\ a_1$ and $\frac{2}{3}\ a_1$.

Hence, from eq. (2), § 397, we have:

$$EId_0 = \tfrac{1}{2}\ M_0a_1 \cdot \tfrac{1}{3}\ a_1 + \tfrac{1}{2}\ M_1a_1 \cdot \tfrac{2}{3}\ a_1 + A_1\bar{x}_1; \quad . \ . \quad (1)$$

and similarly, with corresponding notation, for the right-hand portion, or segment, BC, of OBC (denoting the "normal mom.-area" $C''B''T_2$ by A_2 and reckoning $\bar{x}_2$, etc., from CC''),

$$EId_2 = \tfrac{1}{2}\ M_2a_2 \cdot \tfrac{1}{3}\ a_2 + \tfrac{1}{2}\ M_1a_2 \cdot \tfrac{2}{3}\ a_2 + A_2\bar{x}_2. \quad . \ . \quad (2)$$

If now a straight line be conceived to be drawn through B parallel to OC, we have, from the similar triangles so formed,

(as in Fig. 445$_4$), $(d_0 - \delta) \div a_1 = (\delta - d_2) \div a_2$. Combining this with eqs. (1) and (2) we have finally

$$\frac{M_0 a_1}{6} + \frac{M_1(a_1 + a_2)}{3} + \frac{M_2 a_2}{6} + \frac{A_1\bar{x}_1}{a_1} + \frac{A_2\bar{x}_2}{a_2} = EI\delta\left[\frac{1}{a_1} + \frac{1}{a_2}\right] \quad (4)$$

which is the "**Theorem of Three Moments.**"

E is the modulus of elasticity of material of beam, I the "moment of inertia" of its cross-section; M_0, M_1, M_2, the moments of stress-couples ("bending-moments") at O, B, and C, respectively. Distances a_1 and a_2 are shown in Fig. 446a, while A_1, A_2, $\bar{x}_1$, and $\bar{x}_2$ are as above; δ being the deflection of point B from the straight line joining O and C.

N.B. It should be carefully noted that eq. (4) does not apply unless the part of beam from O to C is *continuous* and *prismatic;* also that in its derivation, the elastic curve is considered *concave upward* throughout; hence if a negative number is obtained for M_0, M_1, or M_2, in any example by the use of eq. (4), it implies that at that section the beam is *convex* upward, instead of concave; in other words that the upper fibers are in tension and the lower in compression (instead of the reverse, as in Fig. 446a).

401. Values of $A_1\bar{x}_1$ and $A_2\bar{x}_2$ in Special Cases. The Theorem of Three Moments involves the use of the (imaginary) *normal mom.-area* of each of the two portions (left and right "spans", or "panels"), OB and BC; i.e. of the products $A_1\bar{x}_1$ and $A_2\bar{x}_2$, where $\bar{x}_1$ is measured from the *left* end of the *left* panel, and $\bar{x}$ from the *right* end of the *right* panel. We are now to determine values of $A_1\bar{x}_1$ and $A_2\bar{x}_2$ for several ordinary cases of loading.

Case I. *Single Central Concentrated Load, P*, Fig. 446$_1$. Here, for a left-hand panel,

$$A_1\bar{x}_1 = \frac{Pl}{4} \cdot \frac{l}{2} \cdot \frac{l}{2} = \frac{Pl^3}{16};$$ and for a right-hand panel,

$$A_2\bar{x}_2 = \frac{Pl^3}{16}.$$



Fig. 446$_1$.



Fig. 446$_2$.

Case II. *Single Non-central Concentrated Load, P.* Fig. 446$_2$. For this case as a left-hand panel,

$$A_1\bar{x}_1 = \left[\frac{Pbc}{l} \cdot \frac{l}{2}\right]\left[\frac{l}{2} - \frac{1}{3}\left(\frac{l}{2} - b\right)\right] = \frac{Pbc\,(l + b)}{6};$$ while, as a right-hand panel, $A_2\bar{x}_2 = \frac{Pbc\,(l + c)}{6}$

Case III. *Two* (or more) *Concentrated Loads.* Fig. 446_3.

$A_1\bar{x}_1 = \frac{1}{6}[P'b'c'\ (l+b') + P''b''c''\ \ (l+b'')]$; and for each load more than two add a proper term in the bracket.

For $A_2\bar{x}_2$ interchange b' and c', b'' and c'', etc.



Fig 446_3.



Fig. 446_4.

Case IV. *Any Continuous Load over a Part or the Whole of the Span;* of w lbs. per linear foot, w being variable or constant. Fig. 446_4. The load on a length dx (of loaded part) is wdx lbs.; comparing which with the P of Case II, (or one of the P's of Case III), we note that x corresponds to b, and $l-x$ to c;

hence $$A_1\bar{x}_1 = \frac{1}{6}\int_{x=b_1}^{x=c_1} wdx\,(l-x)\,x\,(l+x) = \frac{1}{6}\int_{b_1}^{c_1} wx\,(l^2-x^2)\,dx.$$

If w is variable it must first be expressed in terms of x. (For $A_2\bar{x}_2$ we measure x from the right-hand end, B.)

Case V. *Uniformly Distributed Load over Whole Span;* (i. e., w is *constant*). Let W, $= wl$, = whole load, lbs. Fig. 446_5.



Fig. 446_5.

Fig. 446_6.

$$A_1\bar{x}_1 = A_2\bar{x}_2$$
$$= \tfrac{2}{3}\,.\,l\,.\,\frac{Wl}{8}\,.\,\frac{l}{2}$$
$$= \frac{Wl^3}{24}.$$

Case VI. *Uniformly Distributed Load Adjoining one End of Span;* (left end for example). Fig. 446_6. Total load $= W = wb$. Applying method of Case IV, with $c_1 = b$, and $b_1 = 0$, we have $A_1\bar{x}_1 = \frac{1}{12}\,W\,b\,(l^2 - \frac{1}{2}\,b^2)$. Also from Case IV, now measuring x from B, $A_2\bar{x}_2 = \frac{1}{24}\,W\,(l^2 - c^2)\,(l+c)$.

Case VII. *Uniformly Distributed Load Not Adjoining either End of the Span.* Fig. 446. Whole load $= W = w(e-b)$. By Case IV, we find

$$A_1\bar{x}_1 = \frac{W(e+b)}{12}\left[l^2 - \frac{e^2+b^2}{2}\right];$$

$$A_2\bar{x}_2 = \frac{W(k+f)}{12}\left[l^2 - \frac{k^2+f^2}{2}\right].$$

It is now seen how $A_1\bar{x}_1$ and $A_2\bar{x}_2$ may be obtained for any loading.



FIG. 446$_7$.

402. Continuous Girders Treated by the Theorem of Three Moments. This theorem is of special advantage in solving continuous beams (p. 271); and examples will now be given.

Example I. Fig. 447$_1$. A straight, homogeneous, *prismatic* beam or girder, 35 feet long, is placed upon three supports at the *same level*, forming two spans of 15′ and 20′; two concentrated loads in the left span, a uniformly distributed load on part of right span. Required the maximum moment, and maximum shear. (Neglect weight of beam.)

Take O, B, and C, as the three sections where the three moments M_0, M_1, and M_2 are situated [respectively] used in the theorem of § 400. But both M_0 and M_2 are *zero* in this case, and δ (deflection of point B from line joining O and C) is also zero (since the supports are on the same level). Hence M_1 (i.e., at B) is the only unknown quantity in applying the theorem of § 400 (eq. (4)) to this problem.

Taking the $A_1\bar{x}_1$ from Case III, and $A_2\bar{x}_2$ from Case VII (with $f = 0$), of § 398, we obtain (using the *foot* and *ton* as units),

$$0 + \frac{M_1(15+20)}{3} + 0 + \frac{1}{6\times 15}[6\times 4\times 11\times 19 + 8\times 10\times 5\times 25]$$

$$+ \frac{16\times 16}{12\times 20}\left[\overline{20}^2 - \frac{\overline{16}^2}{2}\right] = 0; \text{ and } \therefore M_1 = -39.2 \text{ ft.-tons.}$$

The negative sign shows that at section B the elastic curve is *convex* on its upper side (see N. B. in § 400). To follow up the solution from this point, let us draw the actual moment-diagram somewhat differently from that in Fig. 446*a*, (which see), where the actual moment for any section is measured from

a continuous horizontal line, $O'C'$, as an axis. Let the "chords" $O''B''$ and $B''C''$ of the two normal moment figures, $O''B''T_1$ and $C''B''T_2$, be made a continuous horizontal line by an upward shifting (*each in its own vertical*) of the intercepts of those figures. The intercepts $O''O'$, $B''B'$, and $C''C'$, and the four triangles involved with them, now extend upward from that horizontal line. But in our present problem both M_0 and M_2 are *zero;* hence the two upper triangles disappear and the two inner triangles project above the horizontal line, with M_1 as a common base. The actual moments of the points of the elastic curve are now measured (in general) by the vertical intercepts between the lower boundary of the normal moment figures and the upper edges of the two triangles; but since in the present case M_1 is negative, M_1 must be laid off below the (new) horizontal line so that the lines $O''B''$ and $C''B''$ will *cross* the lower boundaries of the normal figures; *the actual moments being now measured by the vertical intercepts between these two oblique lines and the curved (or broken) boundaries of the normal figures.*



FIG. 447$_1$.

This re-arrangement has been observed in the moment-diagram $O''B''C''$ of Fig. 447$_1$, where *line-shaded* areas correspond to the parts of the elastic curve which are *concave upward;* and the *dot-shaded* areas, to parts *convex upward* (or upper fibers in tension).

Before determining the shears, J, along the beam, we must first determine the reactions at the support, viz. V_O, V_B, and V_C. Consider the portion OB as a "free body", cutting just on left

of support B, and put $\sum$ (moments) $= 0$ about the neutral axis of section at B; deriving
$6 \times 11 + 8 \times 5 - 39.2 - V_O \times 15 = 0$; and $\therefore V_O = 4.5$ tons.

Similarly, with BC as free body, taking moments about B, $16 \times 12 - 39.2 - V_C \times 20 = 0$; and $\therefore V_O = 7.6$ tons; and hence, since $V_O + V_B + V_C = 30$ tons, $V_B = 17.9$ tons. The shear-diagram is now easily formed (see Fig. 447_1); the maximum shear being evidently 9.55 tons, occurring in the section just on the *left* of support B.

We note that the shear changes sign three times, corresponding to the three (local) maximum moments (at E, B, and K). To locate, and determine, M_K, note that the change of sign of the shear at D is *gradual* and that hence the shear is exactly zero at K; which requires that the load between K and the support C be equal to the reaction at C, (from the free body concerned). Since w along HC is one ton per foot, the distance KC must be 7.64 tons $\div$ 1.00, $= 7.6$ ft. From this free body, KC, we now find, by moments, that $M_K = 29.2$ ft.-tons.

As to the other maximum moment, i.e., at E, we note that the moment at E in the normal moment-figure would be $E'''\ E'' = 28.2$; from which by deducting $\frac{4}{15}$ of M_B (i.e., of 39.2) we obtain M_E, $= 17.7$ ft.-tons. Hence, the greatest moment to be found in the beam is that at B, viz. 39.2 ft.-tons, and upon this depends the choice of a safe and economical beam.

Example II. Fig. 447_2, Continuous prismatic beam OC. Three supports at same level. Find maximum moment, etc., under given loading, the 12 tons being uniformly distributed over whole of right-hand span. Neglect weight of beam.

M max. $= M_B = 16.6$ ft.-tons. Ans.



Fig. 447_2.



Fig. 447_3.

Example III. Continuous prismatic beam on three supports O, B, C, at same level. Three concentrated loads. Neglect weight of beam. Find M_B and maximum moment, etc.

$M_B = -92.6$ ft.-tons. Max. $M = 116$ ft.-tons, at D. Ans.

Example IV. Continuous prismatic beam, 40 ft. long and extending over *four* supports at the *same level.* The loading is *symmetrical*, as shown (Fig. 447$_4$). Here we note that from symmetry M_B must $= M_C$; also M_O and M_D each $= 0$. Applying the *Three-Moment Theorem* to O, B, and C, (with $\delta = 0$) we find



Fig. 447$_4$.

$$0 + \frac{1}{3}\, M_B \times 26 + \frac{1}{6}\, M_B \times 12 + \frac{1}{24} \cdot \frac{20}{14} \times \overline{14}^3 + \frac{10}{16} \cdot \frac{1}{12} \times \overline{12}^3 = 0;$$

and $\therefore M_B = -23.7$ ft.-tons, $(= M_C$, also).

Completing the mom.-diagram we find that $M_B (= M_C)$, or 23.7, is greater than any other moment along the beam; $\therefore M$ max. $= 23.7$ ft.-tons. The reactions of the supports are found to be: V_O (and V_D) $= 8.3$ tons; and V_B (and V_C) $= 16.6$ tons. Evidently the elastic curve is *convex up*, over both B and C. The maximum shear is 11.8 tons, close on the left of support B, (or close on right of C).



Fig. 447$_5$.

Example V. Continuous prismatic beam, 38 ft. long, on three supports *at the same level.* Fig. 447$_5$. Uniformly distributed loads over portions of the length. Find the maximum moment and maximum shear, (J).

$$\left.\begin{array}{l}\text{Max. } M = -39.6 \text{ ft.-tons (at } B);\\ \text{Max. } J = 10.2 \text{ tons (close at right of } B)\end{array}\right\} \text{Ans.}$$

Example VI. Fig. 447$_6$. Continuous prismatic beam, 50 ft. long, on *four* supports *at same level;* but the arrangement of loading and span-lengths is *non-symmetrical.* Fig. 447$_6$. Find the max. M and max. J. In this case M_O and M_D are each $= 0$, but M_B is not $= M_C$. We are therefore compelled to apply the Theorem of Three Moments *twice*, viz.: first to the three points O, B, and C; and then to the three points B, C, and D; whence we have

$$0 + \frac{M_B\,(14 + 20)}{3} + \frac{M_C \times 20}{6} + \frac{16 \times 6 \times 8\,(14 + 6)}{6 \times 14} + \frac{20 \times \overline{20}^3}{24 \times 20} = 0;$$

$$\frac{M_B \times 20}{6} + \frac{M_C\,(20 + 16)}{3} + 0 + \frac{20 \times \overline{20}^3}{24 \times 20} + \frac{15 \times 7 \times 9\,(16 + 7)}{6 \times 16} = 0;$$

or, $68\,M_B + 20\,M_C + 1097.1 + 2000 = 0$; . . . . . (1)

and $20\,M_B + 72\,M_C + 2000 + 1358.3 = 0$; . . . . . (2)

two simultaneous equations, for determining M_B and M_C.

Solving, we find $M_B = -34.6$, and $M_C = -37.0$, ft.-tons.

The three "normal mom.-diagrams" having been drawn to the common base $O''B''C''D''$ in the figure, we lay off $B''B'$ downward from B'' and



FIG. 447b.

$= 34.6$ ft.-tons; and $C''C'$, also downward, $= 37.0$; and draw the straight lines $O''B'$, $B'C'$, and $C'D''$; thus completing the mom.-diagram, in which, as before, the differently shaded portions show whether the elastic curve is concave up (line-shading), or convex up (dot-shading), in the corresponding part of beam.

The four reactions of supports are then found, viz.: V_O, V_B, V_C, and V_D, $= 6.7$, 19.2, 19.0, and 6.1 tons, respectively. Shears are now easily found and are shown in the shear diagram, the max. J being 9.8 tons, occurring just on the right of support B. The max. M is found to occur at E, and to have a value of 42.7 ft.-tons.

402a. Continuous Beam with One Span Unloaded. In Fig. 448 we have a continuous prismatic beam supported at three points O, B, and C at the same level; but the support at O is *above* the beam, instead of below; since that end tends to *rise*, there being *no load in the left-hand span.* (Case of a *drawbridge* with the left-end "latched down"). Neglect weight of beam. By the Theorem of Three Moments applied to O, B, and C, with M_0 and $M_C = 0$, and M_B unknown, we find $M_B = -4.9$ ft.-tons. In forming the moment-diagram here, we note that since there is no load from O to B the lower edge of the "normal mom.-diagram"

for OB coincides with its upper edge, i.e., with the axis itself, viz. $O''B''$. The "normal mom.-diagram" for BC is a triangle, with $B''C''$ as base. Laying off $B''B' = 4.9$ *downward* from B', and joining $O''B'$ and $B'C''$, we complete the actual (shaded) mom.-diagram, as shown. Max. moment is found under the load and = + 9.55 ft.-tons.



Fig. 448.

To find the reaction at O, take OB as "free body", cutting close on left of B. (See (F) in the figure. Note the position of stress-couple at right-hand end of this body.) By moments about B we have $V_O \times 10 - 4.9 = 0$, whence $V_O =$ (say) 0.5 tons. The other reactions and the shear diagram are now easily determined.

403. Supports out of Level. In the foregoing examples the quantity δ has been zero in each instance of the application of the Theorem of Three Moments; but when such is not the case the quantities E and I are brought into play. In this connection it must be remembered that any unequal settling of the supports (originally at same level) after the beam has been put in place, may cause considerable changes in the values of the various moments and shears, and consequent stresses in the material. (See lower half of p. 323.)

404. Continuous Beam with "Built-in" Ends. Fig. 449. As a case for illustration take the prismatic beam in Fig. 449, "*built-in*" or clamped, horizontally, at B and at C; at the same level. A load P is placed as shown. On account of the mode of support the tangents to the elastic curve at B and C will be horizontal and are coincident; so that portions of the curve near the ends are convex up. Now conceive the beam to be sustained at B by a simple



Fig. 449.

support underneath and to extend toward the left a length a_o at the end of which a support, O, is placed *above* the beam, and at *same level as* B and C (allowing for thickness of beam). This makes an additional span (with M_o = zero); and the tangent to elastic curve at B will no longer be horizontal. But *it may be made as nearly horizontal as we please, by taking* a_o *small enough* (supposing no limit to strength of beam). When a_o = *zero* the tangent at B will be in its actual position (horizontal). We may therefore apply the Theorem of Three Moments (§ 400) to O, B, and C, [noting that there is no load on $O\,B$], if we write both M_O, and a_o, = 0, whence (see also Case II of § 401),

$$0 + \frac{M_B\,(0 + 3a)}{3} + \frac{M_C\,3a}{6} + 0 + \frac{P2a\,.\,a(3a + 2a)}{6 \times 3a} = 0.$$

Similarly, by conceiving the beam extended to the right, a distance a' to a point D, for another support, etc., we may apply the theorem to the three points, B, C, and D in like fashion, with M_D and $a' = 0$, obtaining

$$\frac{M_B\,3a}{6} + \frac{M_C\,(3a + 0)}{3} + 0 + \frac{P2a\,.\,a\,(3a + a)}{6 \times 3a} + 0 = 0.$$

Elimination gives $M_B = -\frac{4}{9}Pa$, and $M_C = -\frac{2}{9}Pa$, ft.-tons.

405. Deflections found by the Theorem of Three Moments for Prismatic Beams. Since this theorem contains δ (see Fig. 446*a*) the deflection of the point B of the elastic curve of a continuous *prismatic* beam from the line joining the two others, O and C, we may use the theorem in many cases for determining deflections *when the three moments are known.*



FIG. 450.

Example I. Fig. 450. Case of two end-supports and a single non-central load, P; (with weight of beam neglected). Taking O, B, C, as the three points (i.e., OB is the left-hand, and BC the right-hand, span: *with no load on either span*) we have, with M_O and M_C = 0, and $M_B = Pa_1a_2 \div l$,

$$0 + \frac{Pa_1a_2}{l}\frac{l}{3} + 0 + 0 + 0 = EI\delta\left[\frac{1}{a_1} + \frac{1}{a_2}\right]; \therefore \delta = \frac{Pa_1^2a_2^2}{3\,EI}.$$

Example II. If n is any point between O and B, at x ft. from O, and O, n, and C are taken as the three points for the theorem, we may find δ_n, the deflection of n below OC. That is, with M_O and $M_C = 0$ and $M_n = P(a_2 + l)\,x$,

$$0 + \frac{Pa_2x \,.\, l}{3l} + 0 + 0 + \frac{Pa_2(a_1 - x)[(l - x) + a_2]}{6(l - x)}$$

$$= EI\delta_n\left[\frac{1}{x} + \frac{1}{l - x}\right]$$

or, after reduction,

$$\delta_n = \frac{Pa_2}{6EI \,.\, l}\,[l^2 - a_2{}^2 - x^2]x \quad . \quad . \quad . \quad . \quad . \quad (4)$$

Now if $a_1 > a_2$, we may find the distance x', from O, of the point of maximum deflection, by putting $\frac{d\,(\delta_n)}{dx} = 0$; whence is obtained

$$x' = \sqrt{\tfrac{1}{3}\,(l^2 - a_2{}^2)} \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

and this substituted in (4) gives

$$\text{max. deflection, } = \frac{\cdot Pa_2}{9EI \,.\, l}\,(l^2 - a_2{}^2)\,\sqrt{\tfrac{1}{3}\,(l^2 - a_2{}^2)} \quad . \quad . \quad . \quad (6)$$

(Compare with pp. 258 and 494.)

(The following example is the one referred to at the foot of page 514.)

Example.—A hollow sphere of mild steel, of thickness 2 in. and internal radius of $r_0 = 4$ in., contains fluid at a pressure of 2 tons/in.^{2} Find max. stress and max. strain; with $E = 15{,}000$ tons/in.^{2} and $k = 0.30$. Here $n = 1.5$; and by substitution in eq. (30) we obtain max. hoop stress to be $q_0 = -2.26$ tons/in.^{2} (tension), while from eqs. (22) and (23) the tangential, or hoop strain, at inner surface is found to be $\varepsilon_2 = -0.000145$ (elongation), and the radial strain to be $\varepsilon_1 = +0.000224$ (shortening).

The latter strain, ε_1, is seen to be the greater and the ideal "*equivalent simple stress*" (see § 405*b*) is $E\varepsilon_1 = +3.35$ tons/in.^{2}, compression, i.e., *much larger than the actual max. stress* (2.26) *in this case*. On the "elongation theory" (see § 405*b*), the 3.36, and not the 2.26, tons/in.^{2}, is the figure that, for safety, should not pass a prescribed unit stress as inferred from compressive tests with an ordinary testing machine.

CHAPTER XIII.

THICK HOLLOW CYLINDERS AND SPHERES.

405a. General Relations between Stress and Strain.—(*Elastic limit not passed.*) If a small cube of homogeneous and isotropic material, dx inches long on each edge, is subjected to a compressive stress of p_1 lbs./in.^{2} on two opposite faces, not only is its length in direction of the stress diminished, and by an amount $d\lambda$, but its lateral dimensions are *increased* by an amount $d\lambda''$ which is a certain fraction (from 0.20 to 0.35 for metals) of $d\lambda$. This ratio, or fraction, is called *Poisson's Ratio*, and will be denoted by k. Thus, in Fig. 450*a* we have such a cube, AD being its unstrained form. Axes 1 and 2 are in the plane of the paper while axis 3 is ⊥ to the paper. On the left and right faces is shown acting the compressive unit-stress p_1 lbs./in.^{2}, $A'D$ being the form of the cube under this stress. If now E represent the modulus of elasticity (Young's) of the material, we have (see p. 203) denoting the ratio $d\lambda \div dx$, or relative decrease in length, by ε_1, $\varepsilon_1 = p_1 \div E$; so that if $d\lambda''$ is the *increase* in length of the vertical edges we have $d\lambda'' \div dx$ (call this ratio $\varepsilon_2 = -kp_1 \div E$; while the relative increase of length in the horizontal edges ⊥ to paper will be an equal amount, viz., $\varepsilon_3 = -kp_1 \div E$. These ratios ε_1, ε_2, and ε_3 are called the *strains* along the three axes 1, 2, and 3, respectively, and are abstract numbers. Hence the three strains produced by the stress p_1 *acting alone* are



FIG. 450*a*.

$$\varepsilon_1 = \frac{p_1}{E}; \quad \varepsilon_2 = -\frac{kp_1}{E}; \quad \text{and} \quad \varepsilon_3 = -\frac{kp_1}{E}. \quad . \quad . \quad (1)$$

Now if while p_1 is still in action a compressive stress of p_2 lbs./in.^{2} acts on the two horizontal faces, and also a compressive stress of p_3 on the two vertical faces which are parallel to the paper, the *total strain* in the direction of axis 1 (that is, the relative shortening of the cube in that direction) will be, by superposition, $\varepsilon_1 = \frac{p_1}{E} - \frac{k(p_2+p_3)}{E}$; and similarly, in the directions of the other two axes, we have

$$\varepsilon_2 = \frac{p_2}{E} - \frac{k(p_1+p_3)}{E}; \quad \text{and} \quad \varepsilon_3 = \frac{p_3}{E} - \frac{k(p_1+p_2)}{E}. \quad . \quad (2)$$

(This form of stress-strain relation is due to Grashof.) Note that if either p_1, p_2, or p_3 is a *tensile* stress, a negative number must be substituted for it; and that if a negative number is obtained for ε_1, ε_2, or ε_3, in any problem, it indicates a lengthening instead of a shortening. Similarly, if the condition is imposed that the strain ε_2 (say) shall be a relative *elongation* of 0.00020, -0.00020 must be substituted for it in above relation.

405b. **"Elongation Theory" of Safety.**—In all preceding chapters the criterion of safety has been that the unit-stress in the element of the elastic body where the stress is highest, regardless of stress on the side faces, should not exceed a certain value, or working stress, $=R'$ lbs./in.^{2}, as determined upon by a consideration of the stress at "elastic limit;" this "elastic limit" being itself determined by the ordinary experiments on "simple" tension or compression of rods of the material in question, there being *no stress* on the *sides* of the rod. In such experiments, however, an element with four faces parallel to the axis is subjected to stress, say p, on two (end) faces only; and the question naturally arises whether the elastic limit would be reached for the same value of p as before, in case there were also present tensile or compressive stress acting on the *side faces* of the element. Experiments which would throw much light on this point are unfortunately wanting, and some authorities, notably on the continent of Europe, contend that the extreme limit of safety, as regards state of stress in isotropic materials, is when the greatest relative *strain* (elongation or shortening), say ε_1, is as great as would be produced at the elastic limit in an experiment involving only "simple" tension, or compression (as above described), in an ordinary testing machine. This view would make the greatest "strain," or deformation (change of form), the criterion of safety instead of the greatest stress. Now if a stress of "simple" tension, $=p'$, (no side stresses) acts on an element, the highest strain produced is in the direction of this stress and has a value $\varepsilon' = p' \div E$, since Young's modulus, E, is determined by experiments of this very nature; that is, $p' = E\varepsilon'$. Hence if the greatest strain in an element in some compound state of stress, as in § 405*a*, is ε_1, and it is desired to place it equal to $\frac{3}{4}$ (say) of the ε_1 in simple tension at elastic limit, we may write $\varepsilon_1 = \frac{3}{4}\varepsilon' = \frac{3}{4}(p' \div E)$; or $E\varepsilon_1 = \frac{3}{4}p'$. If now we

denote $\frac{3}{4}p'$ by p'' we may write $E\varepsilon_1 = p''$ and describe p'', or $E\varepsilon_1$, as the *ideal* tensile stress which would produce a strain, or relative elongation, equal to ε_1 *in case there were no side stresses;* Cotterill calls this ideal stress ($E\varepsilon_1$) the "*equivalent simple stress.*"

For instance, if on an element of the shell of a cylindrical steam-boiler of soft steel the "hoop stress" (p. 537) is p_1 on two end faces and the stress on two of the other faces is p_2, $= \frac{1}{2}p_1$, (the stress on the remaining two opposite faces being p_3 = practically zero in this connection) we have for the strain in direction 1, by eq. (2), $E\varepsilon_1 = p_1 - k(\frac{1}{2}p_1 + 0)$. . . . (2′)

Let p'', $= -15{,}000$ lbs./in.^{2}, tension, be the safe working stress for the metal in simple tension; with $E = 30{,}000{,}000$ lbs./in.^{2}, and Poisson's ratio $= k = 0.30$. Then according to the view of preceding chapters the greatest safe value for the stress p_1 would be $-15{,}000$ lbs./in.^{2} But according to the new view now being illustrated the safe value of p_1 must be determined by limiting the strain ε_1 to a value which would be produced by 15,000 lbs./in.^{2} in simple tension, i.e., -0.00050, (which $= p'' \div E$); which amounts to the same thing as requiring that the "equivalent simple stress" shall $= 15{,}000$ lbs./in.^{2} Hence, substituting in eq. (2′), we have

$-15{,}000 = p_1(1 - \frac{1}{2} \cdot (0.30))$; i.e., $p_1 = -17{,}600$ lbs./in.^{2} tension; which is considerably greater than the 15,000 allowed by the older theory. The relation thus brought out in this case that the tenacity of a material is *increased* by the presence of lateral tension "can hardly be considered as intrinsically probable, and such direct experimental evidence as exists is against the supposition" (Cotterill).

But in many cases the results of this "elongation theory" are more probable than those based on the older theory; hence the former is much favored by continental writers.

405c. Thick Hollow Cylinder. Stresses and Strains.—Fig. 450*b* shows a longitudinal section of a thick hollow cylinder of homogeneous and isotropic material (say steel or iron) provided with end stoppers (no friction nor leakage); and Fig. 450*c* a transverse section, giving dimensions. r_0 is the inner



FIG. 450*b*.



FIG. 450*c*.

radius and nr_0 the outer radius (n is a ratio). Fig. 450*c* also shows (dotted lines) an elementary hoop, or shell, of inner radius r and outer radius $r+dr$. The interior of the cylinder is filled with fluid under a high pressure, p_0 lbs./in.^{2}; and it is required to determine the stresses and strains in a cubic element in *any* elementary hoop or sign such as ABC, Fig. 450*c*. Let the half hoop ABC of Fig. 450*c* be considered as a "free body" in Fig. 450*d*, showing also at 3 a small cubic element, as mentioned above. The compressive stress on the inner surface of the hoop is p (radial), exerted on it by the adjacent inner hoop; while on the outer surface of the elementary hoop, and exerted on it by the adjacent outer hoop, is the compressive stress $p+dp$. The thickness of the hoop is dr. The stress on the edges, A and C, of this free body (half hoop), will be taken as compressive at first, of intensity q lbs./in.^{2} Let the hoop or thin shell have a length $=l$, ⊥ to paper i.e., longitudinally (see Fig. 450*b*).



FIG. 450*d*.

Now for this free body put $\Sigma X=0$ and we have (see pp. 525 and 526)

$$(p+dp)(2r+2dr)l-2ql\,.\,dr-p(2rl)=0 \quad . \quad .(3)$$

i.e.,

$$pr+r\,.\,dp+p\,.\,dr+dp\,.\,dr-q\,.\,dr-pr=0 \quad . \quad . \quad (4)$$

and hence, omitting the term $dp\,.\,dr$ of the second order,

$$r\,.\,dp+p\,.\,dr=q\,.\,dr \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

which is a differential equation of stress. Next consider the relations of stress and strain to be found in the small cube at 3, Fig. 450*d*. It is subjected to a compressive stress p along the radial axis 1; to a compressive stress q a long the tangential axis 2; while on the front and back faces the stress is $p_3=$ zero, parallel to axis 3 (⊥ to paper). Let now $_{01}$ denote the radial strain, ε_2 the tangential, and ε_3 the axial strain, this latter being parallel to the axis of the cylinder. All of these strains are supposed to be *shortenings* for the present; and from the circumstances of the case the third strain ε_3 (axial) is considered constant (i.e., the same for all values of the variable r), since the cylinder is under no constraint as to longitudinal change of form.

We may therefore write the relations (see § 405a)

$$E\varepsilon_1=p-k\,.\,q, \quad (6); \quad E\varepsilon_2=q-k\,.\,p, \quad (7); \quad E\varepsilon_3=0-k(p+q), \quad (8)$$

From (8) we have $q=-p-(E\varepsilon_3 \div k)$, which in (5) gives

$$r \,.\, dp+2pr \,.\, dr=-(E\varepsilon_3 \div k)dr \quad . \quad . \quad . \quad . \quad (9)$$

Now multiply by r (integrating factor) and denote $E_{03} \div k$ by A, an unknown constant, (unknown since it contains the strain ε_3) and we have

$$r^2 . dp+2pr \,.\, dr=-Ar \,.\, dr; \quad . \quad . \quad . \quad (10)$$

that is to say,

$$d[r^2p]=-Ar \,.\, dr; \quad . \quad . \quad . \quad (11)$$

which may be integrated, giving, $r^2p=-\frac{1}{2}Ar^2+C; \quad . \quad . \quad (12)$

where C is a constant of integration. The two constants A and C may now be determined by substituting in (11) the values r_0 and p_0 which the two variables r and p assume at the inside surface of the cylinder. Similarly, at the outside surface r and p have the values nr_0 and 0 (atmospheric pressure relatively small and hence neglected); which being placed in (11) give rise to a second equation, which like the first contains constants only. From these two equations we easily find

$$A=\frac{2p_0}{n^2-1}; \quad \text{and} \quad C=\frac{n^2r_0^2p_0}{n^2-1};$$

and hence finally, from equations (12) and (8),

$$p=\frac{p_0}{n^2-1}\left[\frac{n^2r_0^2}{r^2}-1\right]. \quad (13); \text{ and } q=-\frac{p_0}{n^2-1}\left[\frac{n^2r_0^2}{r^2}+1\right]. \quad (14)$$

From (13) and (14) we may find the stresses p and q for any value of the variable distance, r, from the axis. The negative sign for q shows that it is in reality a *tensile* stress, the reverse of the character assigned to it at first; i.e., it is a "negative compressive" stress for this case of fluid pressure acting *inside* the cylinder. Both p and q have maximum values at the inner surface and diminish toward the outside.

Example.—With inner radius $r_0=4$ in.; and outer, $=5$ in. (hence $n=5/4$ or 1.25); and $p_0=800$ lbs./in.^{2}; we find q max. (or q_0), at inner surface, to be 3644 lbs./in.^{2}; while at outer surface $q=-2844$ lbs./in.^{2}, tension. If the metal is cast iron we may put $k=0.23$ (see p. 230) and $E=15{,}000{,}000$ lbs./in.^{2}, and thus obtain for the radial strain at the inner surface, $\varepsilon_1=+0.000109$, indicating a shortening; and for the "hoop" strain (or tangential strain) at the same place, $\varepsilon_2=-0.000255$, i.e., a relative *elongation* of about $2\frac{1}{2}$ parts in 10,000. (The student should verify all the details of this example, carefully noting the proper signs to be used).

405d. Thick Hollow Cylinder under External Fluid Pressure.—If the cylinder is surrounded by fluid under high pressure, p_n lbs./in.^{2}, the internal pressure p_0 being practically zero (atmosphere) in comparison, we must determine the constants A and C of eq. (12) on the basis that $p=0$ for $r=r_0$ and that $p=p_n$ for $r=nr_0$; whence, finally, we obtain

$$p=\frac{n^2p_n}{n^2-1}\left(1-\frac{r_0^2}{r^2}\right); \quad . \quad . \quad . \quad (15) \qquad q=+\frac{n^2p_n}{n^2-1}\left(1+\frac{r_0^2}{r^2}\right). \quad . \quad . \quad . \quad (16)$$

for the stresses at any distance r from the axis. Here *both* p and q are com-

pressive stresses; the latter increasing, and the former diminishing, toward the center. Evidently if the cylinder were not hollow, but *solid*, r_0 would $=0$, and $n=\infty$; and both p and q would be constant, $=p_n$, at all points.

405e. Approximate equalization of the tensile hoop stress in successive rings of a thick hollow cylinder under internal fluid pressure may be brought about by using two or more separate cylinders of which the outer ones are successively "shrunk on" before the fluid is introduced. For instance, with only two cylinders, the outer one is first heated to such an extent that it barely fits over the inner one, the latter being cold. When the compound cylinder has cooled the outer one has shrunk and is in a state of hoop *tension*, while the inner one is in a state of hoop *compression*. The radial pressure between them, at their surface of contact, is an internal or bursting pressure for the outside cylinder, and an external or collapsing pressure for the inside cylinder. The original and final temperatures being known, we are able to make use of the foregoing equations [(6) to (16)] to compute all stresses and strains thus induced before the fluid is introduced into the interior of the smaller cylinder. When the internal pressure is eventually produced, the hoop stresses in the smaller cylinder, initially compressive, will be converted into moderate tensions and the tensile stresses in the external cylinder will be increased; but the maximum tension is not so great as if the complete cylinder had been originally continuous. (See Prof. Ewing's Strength of Materials).

In the case of thick hollow cylinders subjected to the severe internal pressures needed in the manufacture of lead pipe, to produce "flow" of the metal, it is well known (Cotterill) that a permanent increase in the internal diameter takes place, showing that in the inner layers of the cylinder the elastic limit has been passed. In this way an approach is made to equalization in the hoop stresses of all the layers and the above formulæ no longer hold; but the cylinder as a whole is not injured, having simply adapted itself better to its function. Cast-iron hydraulic press cylinders are sometimes subjected to the high internal pressure of 3 tons/in.^{2} If the cylinder is short, its resistance is doubtless much increased by connection with the end plates, or "domes."

405f. Equation of Continuity for Thick Hollow Cylinder under Stress.—(Cotterill.) In Fig. 450e we have in $ABCD$ the form and position of a "cubical" element (of an elementary hoop) between the two radial planes ABO and DCO, in its con-

dition of *no stress*. After it is subjected to stress it will still be found *between the same radial planes* and will occupy some position $A'B'C'D'$. The radial thickness $\overline{AB}=dr$, or t, will have changed to t', BC has changed to $B'C'$, etc. With axes 1 and 2 as shown, 1 being radial, and 2 tangential (or circumferential), we note that the whole circumference of which BC is a part has shortened from a length $2\pi r$ to $2\pi s$, so that $2\pi s=2\pi r(1-\varepsilon_2)$, ε_2 being the value of the tangential strain, or "hoop" strain, at distance r from center O; and similarly $2\pi s'=2\pi r'(1-\varepsilon_2')$, where ε_2' is the hoop strain at distance r' (i.e., $r+dr$) from O. But ε_2 varies with r, so $\varepsilon_2'=\varepsilon_2+t\,.\,\frac{d\varepsilon_2}{dr}$. Hence, subtracting,



FIG. 450e.

$$s'-s=(r'-r)(1-\varepsilon_2)-r't\frac{d\varepsilon_2}{dr}. \quad . \quad . \quad . \quad . \quad . \quad . \quad (17)$$

i.e., $$t'=t-t\varepsilon_2-r't\frac{d\varepsilon_2}{dr}; \quad \text{or,} \quad t(1-\varepsilon_1)=t-t\varepsilon_2-r't\frac{d\varepsilon_2}{dr}; \quad . \quad . \quad . \quad (18)$$

whence $$\varepsilon_1-\varepsilon_2=r\frac{d\varepsilon_2}{dr}; \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (19)$$

which is the "equation of continuity of substance," of the cylinder.

Since in the foregoing cases of thick hollow cylinder, under bursting or collapsing fluid pressure, both ε_1 and ε_2 may be expressed as functions of r, it is a simple matter for the student to show that (19) is verified in those cases, and that hence *the solutions given are adequate.*

Evidently eq. (19) also holds in the case of the thick hollow sphere, where there is a hoop strain ε_3, ⊥ to paper in Fig. 450, equal to that, ε_2, along axis 2.

405g. Thick Hollow Sphere under Internal Fluid Pressure. — (For thin-walled spheres see p. 536). As thick hollow spheres are sometimes used to hold fluids under high pressure, and the halves of such spheres frequently form the ends of thick hollow cylinders, the following treatment will be of practical value. In Fig. 450*f* we have a cross-section of the sphere through the center. The inner radius is r_0; the outer, nr_0 (where n is a ratio); while the (variable) r is the inner radius of any thin spherical shell,



FIG. 450f.



FIG. 450g.



FIG. 450h.

of thickness dr, an infinite number of which make up the complete sphere. Though each of these shells is under a "hoop tension," when the internal fluid pressure is in action, we shall at first deal with this stress as if compressive, for uniformity in applying the principles of § 450*a*.

Consider as a free body any hemispherical shell as shown in Fig. 450*g*. The pressure (radial) on the inside, from the adjacent shell, is p lbs./in.^{2}; and that from the adjacent shell on the outside is $p+dp$, or p'. The radius of the outside will be called r', $(=r+dr)$. The "hoop compression" on the thin edge of the shell is q lbs./in.^{2} These three quantities, p, r, and q, are *variables*, i.e., refer to any infinitesimal shell of the sphere. The strains affecting any small "cubical" block in any shell are p, radial; q, tangential; and q_3, $=q$, along a tangent ⊓ to the first mentioned.

Taking an axis X through the center and ⊓ to sectional plane AB, and putting $\Sigma(X\text{-components})=0$, for equilibrium, we have

$$\pi r'^2p'-\pi r^2p-2\pi r\,.\,dr\,.\,q=0; \qquad \text{i.e.,} \qquad r'^2p'-r^2p=2qr\,.\,dr.$$

But the difference, $r'^2p'-r^2p$, is nothing more than the increment accruing to the product r^2p when r takes the increment dr, and is therefore the *differential* of the quantity or product r^2p; hence we may write

$$d(r^2p)=2qr\,.\,dr; \quad \text{or,} \quad r^2\,.\,dp+2pr\,.\,dr=2qr\,.\,dr\,. \quad . \quad . \quad (20)$$

We next consider the relations of stress and strain in the small cubical element shown in Fig. 450*h*, having four radial and two tangential faces. The unit stresses on the faces are as there shown; p on the two tangential, and q on the four radial, faces. Radial strain $=\varepsilon_1$ and hoop strain (tangential) $=\varepsilon_2=$same for any tangent. It has already been proved in § 405*f* that

$$\varepsilon_1-\varepsilon_2=r\,.\,\frac{d\varepsilon_2}{dr}; \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (21)$$

and we also have, from § 405*a*,

$$E\varepsilon_1=p-2kq; \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (22)$$

and

$$E\varepsilon_2=q-k(p+q) \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (23)$$

From the four equations, (20), (21), (22) and (23), containing the five variables p, q, ε_1, ε_2, and r, we may by elimination and integration finally determine p and q, each as a function of r; as follows: (C', C'', C_1, C_2, etc., will denote constants of integration, or, constant products involving E and k.

From (22) and (23) we obtain a value for $\varepsilon_1-\varepsilon_2$ which in (21) gives rise to an expression for $p-q$. Another expression for $p-q$ is obtained from (20). Equating these two expressions we derive $-dp=C_1\,.\,d\varepsilon_2$; that is, by integration,

$$-p=C_1\varepsilon_2+C_2 \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (24)$$

By elimination of ε_2 between (24) and (23) we obtain q in terms of p which substituted in (20) produces

$$r^2\,.\,dp+3pr\,.\,dr=C_3r\,.\,dr \quad . \quad . \quad . \quad . \quad (25)$$

Eq. (25) is made integrable by multiplying by r (integrating factor); whence

$$r^3\,.\,dp+3pr^2\,.\,dr=C_3r^2\,.\,dr$$

The left-hand member is evidently $d[r^3p]$. Therefore $d[r^3p]=C_3r^2\,.\,dr$; or, integrating,

$$r^3p=\tfrac{1}{3}C_3r^3+C_4; \qquad \text{that is,} \qquad p=C'+\frac{C''}{r^3}, \quad . \quad . \quad (26)$$

whence, also, $\dfrac{dp}{dr}=-\dfrac{3C''}{r^4}$; which in (20) gives rise to $q=C'-\dfrac{C''}{2r^3}$. . (27)

We may now determine the two constants C' and C'' substituting in eq. (26), first $p=p_0$ and $r=r_0$; and then $p=0$ with $r=nr_0$. The values of C' and C'' so obtained are placed in (26) and (27), resulting finally in the relations

$$p=\frac{p_0}{n^3-1}\left(\frac{n^3r_0^3}{r^3}-1\right); \quad . \quad (28) \qquad \text{and} \qquad q=-\frac{p_0}{n^3-1}\left(\frac{n^3r_0^3}{2r^3}+1\right). \quad . \quad (29)$$

The negative sign of q shows that it is a tensile stress, or "hoop tension." It is evidently a maximum for $r=r_0$, this maximum value being

$$q_0, =q \text{ max.}, =-\frac{p_0}{n^3-1}\left(\frac{n^3}{2}+1\right). \quad . \quad . \quad . \quad . \quad . \quad (30)$$

(For a numerical example see foot of p. 506).

PART IV.

HYDRAULICS.

CHAPTER I.

DEFINITIONS—FLUID PRESSURE—HYDROSTATICS BEGUN.

406. A Perfect Fluid is a substance the particles of which are capable of moving upon each other with the greatest freedom, absolutely without friction, and are destitute of mutual attraction. In other words, the stress between any two contiguous portions of a perfect fluid is always one of *compression* and *normal* to the dividing surface at every point; i.e., *no shear* or tangential action can exist on any imaginary cutting plane.

Hence if a perfect fluid is contained in a vessel of rigid material the pressure experienced by the walls of the vessel is *normal to the surface of contact at all points.*

For the practical purposes of Engineering, water, alcohol, mercury, air, steam, and all gases may be treated as perfect fluids within certain limits of temperature.

407. Liquids and Gases.—A fluid a definite mass of which occupies a definite volume at a given temperature, and is incapable both of expanding into a larger volume and of being compressed into a smaller volume at that temperature, is called a **Liquid**, of which water, mercury, etc., are common examples; whereas a **Gas** is a fluid a mass of which is capable of almost indefinite expansion or compression, according as the space within the confining vessel is made larger or smaller, and always tends to fill the vessel, which must therefore be closed in every direction to prevent its escape.

Liquids are sometimes called *inelastic* fluids, and gases *elastic* fluids.

408. Remarks.—Though practically we may treat all liquids as incompressible, experiment shows them to be compressible to a slight extent. Thus, a cubic inch of water under a pressure of 15 lbs. on each of its six faces loses only fifty millionths (0.000050) of its original volume, while remaining at the same temperature; if the temperature be sufficiently raised, however, its bulk will remain unchanged (provided the initial temperature is over 40° Fahr.). Conversely, by heating a liquid in a rigid vessel completely filled by it, a great bursting pressure may be produced. The slight cohesion existing between the particles of most liquids is too insignificant to be considered in the present connection.*

The property of indefinite expansion, on the part of gases, by which a confined mass of gas can continue to fill a confined space which is progressively enlarging, and exert pressure against its walls, is satisfactorily explained by the "Kinetic Theory of Gases," according to which the gaseous particles are perfectly elastic and in continual motion, impinging against each other and the confining walls. Nevertheless, for practical purposes, we may consider a gas as a continuous substance.

Although by the abstraction of heat, or the application of great pressure, or both, all known gases may be reduced to liquids (some being even solidified); and although by converse processes (imparting heat and diminishing the pressure) liquids may be transformed into gases, the range of temperature and pressure in all problems to be considered in this work is supposed kept within such limits that no extreme changes of state, of this character, take place. A gas approaching the point of liquefaction is called a **Vapor**.

Between the solid and the liquid state we find all grades of intermediate conditions of matter. For example, some substances are described as soft and plastic solids, as soft putty, moist earth, pitch, fresh mortar, etc.; and others as viscous and sluggish liquids, as molasses and glycerine. In sufficient bulk,

* Water has recently been subjected to a pressure of 65,000 lbs./in.^{2}; resulting in a reduction of 10 per cent in the volume. See *Engineering News*, Oct. 1900, p. 236.

however, the latter may still be considered as perfect fluids. Even water is slightly viscous.

409. Heaviness of Fluids.—The weight of a cubic unit of a homogeneous fluid will be called its *heaviness*,* or rate of weight (see § 7), and is a measure of its density. Denoting it by γ, and the volume of a definite portion of the fluid by V, we have, for the weight of that portion,

$$G = V\gamma. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

This, like the great majority of equations used or derived in this work, is of *homogeneous form* (§ 6), i.e., admits of any system of units. E.g., in the metre-kilogram-second system, if γ is given in kilos. per cubic metre, V must be expressed in cubic metres, and G will be obtained in kilos.; and similarly in any other system. The quality of γ, $= G \div V$, is evidently one dimension of force divided by three dimensions of length.

In the following table, in the case of gases, the temperature and pressure are mentioned at which they have the given heaviness since under other conditions the heaviness would be different; in the case of liquids, however, for ordinary purposes the effect of a change of temperature may be neglected (within certain limits).

HEAVINESS OF VARIOUS FLUIDS.*

[In ft. lb. sec. system; γ = weight in lbs. of a cubic foot.]

Liquids.		Gases { At temp. of melting ice; and 14.7 lbs. per sq. in. tension.	
Fresh water,	$\gamma =$ 62.5	Atmospheric Air	0.08076
Sea water	64.0	Oxygen	0.0892
Mercury	848.7	Nitrogen	0.0786
Alcohol	49.3	Hydrogen	0.0056
Crude Petroleum, about	55.0	Illuminating Gas, { from	0.0300
(N.B.—A cubic inch of water weighs 0.0361 lbs.; and a cubic foot 1000 av. oz.)		Gas, { to	0.0400
		Natural Gas, about	0.0500

* Sometimes called "specific weight;" while its reciprocal, or $1 \div \gamma$ may be styled the "specific volume" of the substance, i.e., the volume of a unit of weight.

For use in problems where needed, values for the heaviness of pure fresh water are given in the following table (from Rossetti) for temperatures ranging from freezing to boiling; as also the relative density, that at the temperature of maximum density, 39°.3 Fahr. being taken as unity. The temperatures are Fahr., and γ is in lbs. per cubic foot.

Temp.	Rel. Dens.	γ.	Temp.	Rel. Dens.	γ.	Temp.	Rel. Dens.	γ.
32°	.99987	62.416	60°	.99907	62.366	140°	.98338	61.386
35°	.99996	62.421	70°	.99802	62.300	150°	.98043	61.203
39°.3	1.00000	62.424	80°	.99669	62.217	160°	.97729	61.006
40°	.99999	62.423	90°	.99510	62.118	170°	.97397	60.799
43°	.99997	62.422	100°	.99318	61.998	180°	.97056	60.586
45°	.99992	62.419	110°	.99105	61.865	190°	.96701	60.365
50°	.99975	62.408	120°	.98870	61.719	200°	.96333	60.135
55°	.99946	62.390	130°	.98608	61.555	212°	.95865	59.843

From D. K. Clark's "Manual."	for temp. =	230°	250°	270°	290°	298°	338°	366°	390°
	γ =	59 4	58.7	58.2	57.6	57.3	56.1	55.3	54.5

Example 1. What is the heaviness of a gas, 432 cub. in. of which weigh 0.368 ounces? Use ft.-lb.-sec. system.

432 cub. in. $= \frac{1}{4}$ cub. ft. and 0.368 oz. $= 0.023$ lbs.

$$\therefore \gamma = \frac{G}{V} = \frac{0.023}{\frac{1}{4}} = 0.092 \text{ lbs. per cub. foot.}$$

Example 2. Required the weight of a right prism of mercury of 1 sq. inch section and 30 inches altitude.

$V = 30 \times 1 = 30$ cub. in. $= \frac{30}{1728}$ cub. feet; while from the table, γ for mercury $= 848.7$ lbs. per cub. ft.

$$\therefore \text{its weight} = G = V\gamma = \frac{30}{1728} \times 848.7 = 14.73 \text{ lbs.}$$

410. **Definitions.**—By *Hydraulics* we understand the mechanics of fluids as utilized in Engineering. It may be divided into

Hydrostatics, treating of fluids at rest; and

Hydrokinetics, which deals with fluids in motion. (The name *Pneumatics* is sometimes used to cover both the statics and kinetics of gaseous fluids.)

411. Pressure per Unit Area, or Intensity of Pressure.—As in § 180 in dealing with solids, so here with fluids we indicate the pressure per unit area between two contiguous portions of fluid, or between a fluid and the wall of the containing vessel, by p, so that if dP is the total pressure on a small area dF, we have

$$p = \frac{dP}{dF} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

as the pressure per unit area, or intensity of pressure (often, though ambiguously, called the *tension* in speaking of a gas) on the small surface dF. If pressure of the *same intensity* exists over a finite plane surface of area $= F$, the total pressure on that surface is

$$\left.\begin{aligned} P = \int p\,dF = p\int dF = Fp, \\ \text{or} \qquad p = \frac{P}{F}. \end{aligned}\right\} \quad . \quad . \quad . \quad . \quad (2)$$

(N.B.—For brevity the single word "pressure" will sometimes be used, instead of intensity of pressure, where no ambiguity can arise.) Thus, it is found that, under ordinary conditions at the sea level, the atmosphere exerts a normal pressure (normal, because fluid pressure) on all surfaces, of an intensity of about $p = 14.7$ lbs. per sq. inch ($= 2116.$ lbs. per sq. ft.). This intensity of pressure is called *one atmosphere*. For example, the total atmospheric pressure on a surface of 100 sq. in. is [inch, lb., sec.]

$$P = Fp = 100 \times 14.7 = 1470 \text{ lbs. } (= 0.735 \text{ tons.})$$

The quality of p is evidently one dimension of force divided by two dimensions of length.

By one "*atmosphere*," then (or "standard atmosphere;" an arbitrary unit), is to be understood a unit-pressure of 14.70 lbs./sq. in., or 2116.8 lbs./sq. ft. This would be the weight of a prismatic column of water one sq. in. in section and 33.9 ft. high (commonly considered 34 ft. for ordinary computations); or of a prismatic column of mercury 30 in. high and one sq. in. section. These numbers, 14.70, 34,

and 30, with their meanings as above, should be memorized by the student; as they are to be of very frequent service in this study.

At high altitudes the actual pressure of the air is much smaller than the conventional "atmosphere." E.g. (see p. 621) at 7000 ft. above the sea the height of a mercury column measuring the air pressure is only about 24 in., instead of the 30 in. above cited; varying somewhat, of course, with the weather.

412. Hydrostatic Pressure; per Unit Area, in the Interior of a Fluid at Rest.—In a body of fluid of uniform heaviness, at rest, it is required to find the mutual pressure per unit area between the portions of fluid on opposite sides of any imaginary cutting plane. As customary, we shall consider portions of the fluid as free bodies, by supplying the forces exerted on them by all contiguous portions (of fluid or vessel wall), also those of the earth (their weights), and then apply the conditions of equilibrium.

First, cutting plane horizontal.—Fig. 451 shows a body of homogeneous fluid confined in a rigid vessel closed at the top with a small air-tight but frictionless piston (a horizontal disk) of weight $= G$ and exposed to atmospheric pressure ($= p_a$ per unit area) on its upper face. Let the area of piston-face be $= F$. Then for the equilibrium of the piston the total pressure between its under surface and the fluid at O must be



FIG. 451.

$$P = G + Fp_a,$$

and hence the intensity of this pressure is

$$p_0 = \frac{G}{F} + p_a. \quad \ldots\ldots \quad (1)$$

It is now required to find the intensity, p, of fluid pressure between the portions of fluid contiguous to the horizontal cutting plane BC at a vertical distance $= h$ vertically below the piston O. In Fig. 452 we have as a free body the right parallelo-

piped OBC of Fig. 451 with vertical sides (two $\parallel$ to paper and four $\neg$ to it). The pressures acting on its six faces are normal to them respectively, and the weight of the prism is $=$ vol. $\times \gamma = Fh\gamma$, supposing γ to have the same value at all parts of the column (which is practically true for any height of liquid and for a small height of gas). Since the prism is in equilibrium under the forces shown in the figure, and would still be so were it to become rigid, we may put (§ 36) Σ (vert. compons.) $= 0$ and hence obtain



Fig. 452.

$$Fp - Fp_0 - Fh\gamma = 0. \quad . \quad . \quad (2)$$

(In the figure the pressures on the vertical faces $\parallel$ to paper have no vertical components, and hence are not drawn.) From (2) we have

$$p = p_0 + h\gamma. \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

($h\gamma$, being the weight of a column of homogeneous fluid of unity cross-section and height h, would be the total pressure on the base of such a column, if at rest and with no pressure on the upper base, and hence might be called *intensity due to weight*.)

Secondly, cutting plane oblique.—Fig. 453. Consider free an infinitely small right triangular prism bcd, whose bases are $\parallel$ to the paper, while the three side faces (rectangles), having areas $= dF$, dF_1, and dF_2, are respectively horizontal, vertical, and oblique; let angle $cbd = \alpha$. The surface bc is a portion of the plane BC of Fig. 452. Given p ($=$ intensity of pressure on dF) and α, required p_2, the intensity of pressure on the oblique face bd, of area dF_2. [N. B.—The prism is taken very small in order that the intensity of pressure may be considered constant over any one face; and also that the weight of the prism may be neglected, since it involves the volume (three dimen-



Fig. 453.

sions) of the prism, while the total face pressures involve only two, and is hence a differential of a higher order.]

From Σ (*vert. compons.*) $= 0$ we shall have

$$p_2 dF_2 \cos\alpha - p dF = 0\,;\ \text{but}\ dF \div dF_2 = \cos\alpha\,;$$

$$\therefore \qquad p_2 = p, \quad . \ . \ . \ . \ . \ . \ . \ . \quad (4)$$

which is independent of the angle α.

Hence, *the intensity of fluid pressure at a given point is the same on all imaginary cutting planes containing the point.* This is the most important property of a fluid, and is true whether the liquid is at rest or has *any kind of motion;* for, in case of rectilinear accelerated motion, *e.g.*, although the sum of the force-components in the direction of the acceleration does not in general $= 0$, but $=$ mass $\times$ acc., still, the mass of the body in question is $=$ *weight* $\div\, g$, and therefore the term mass $\times$ acc. is a differential of a higher order than the other terms of the equation, and hence the same result follows as when there is no motion (or uniform rectilinear motion).

413. The Intensity of Pressure is Equal at all Points of any Horizontal Plane in a body of homogeneous fluid at rest. If we consider a right prism of the fluid in Fig. 451, of small vertical thickness, its axis lying in any horizontal plane BC, its bases will be vertical and of equal area dF. The pressures on its sides, being normal to them, and hence to the axis, have no components $\parallel$ to the axis. The weight of the prism also has no horizontal component. Hence from Σ (hor. comps. $\parallel$ to axis) $= 0$, we have, p_1 and p_3 being the pressure-intensities at the two bases,

$$p_1 dF - p_3 dF = 0\,; \quad \therefore p = p_3\,, \quad . \ . \ . \ . \quad (1)$$

which proves the statement at the head of this article.

It is now plain, from this and the preceding article, that the pressure-intensity p at any point in a homogeneous fluid *at rest* is *equal to that at any higher point, plus the weight*

($h\gamma$) *of a column of the fluid of section unity and of altitude* (h) = *vertical distance between the points.*

i.e., $$p = p_0 + h\gamma, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

whether they are in the same vertical or not, and whatever be the shape of the containing vessel (*or pipes*), *provided the fluid is continuous between the two points;* for, Fig. 454, by considering a series of small prisms, alternately vertical and horizontal, *obcde*, we know that



FIG. 454.

$$p_b = p_0 + h_1\gamma; \qquad p_c = p_b;$$
$$p_d = p_c - h_2\gamma; \text{ and } p_e = p_d;$$

hence, finally, by addition we have

$$p_e = p_0 + h\gamma$$

(in which $h = h_1 - h_2$).

If, therefore, upon a small piston at o, of area $= F_0$, a force P_0 be exerted, and an inelastic fluid (liquid) completely fills the vessel, then, for equilibrium, the force to be exerted upon the piston at e, viz., P_e, is thus computed: For equilibrium of fluid $p_e = p_0 + h\gamma$; and for equil. of piston o, $p_0 = P_0 \div F_0$; also, $p_e = P_e \div F_e$;

$$\therefore P_e = \frac{F_e}{F_0} P_0 + F_e h\gamma. \quad . \quad . \quad . \quad . \quad . \quad (3)$$

From (3) we learn that if the pistons are at the same level ($h = 0$) the total pressures on their inner faces are *directly proportional to their areas.*

If the fluid is gaseous (2) and (3) are practically correct if h is not $>$ 100 feet (for, gas being compressible, the lower strata are generally more dense than the upper), but in (3) the pistons must be fixed, and P_e and P_0 refer solely to the interior pressures.

Again, if h is small or p_0 very great, the term $h\gamma$ may be omitted altogether in eqs. (2) and (3) (especially with gases, since for them γ (heaviness) is usually small), and we then have, from (2),

$$p = p_0; \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

being the algebraic form of the statement: *A body of fluid at rest transmits pressure with equal intensity in every direction and to all of its parts.* [Principle of "Equal Transmission of Pressure."]

414. Moving Pistons.—If the fluid in Fig. 454 is *inelastic* and the vessel walls rigid, the motion of one piston (o) through a distance s_0 causes the other to move through a distance s_e determined by the relation $F_0 s_0 = F_e s_e$ (since the volumes described by them must be equal, as liquids are incompressible); but on account of the inertia of the liquid, and friction on the vessel walls, equations (2) and (3) no longer hold exactly, still are approximately true if the motion is very slow and the vessel short, as with the cylinder of a water-pressure engine.

But if the fluid is compressible and elastic (gases and vapors; steam, or air) and hence of small density, the effect of inertia and friction is not appreciable in short wide vessels like the cylinders of steam- and air-engines, and those of air-compressors; and eqs. (2) and (3) still hold, practically, even with high piston-speeds. For example, in the space AB, Fig. 455, between the piston and cylinder-head of a steam-engine (piston moving toward the right) the intensity of pressure, p, of the steam against the moving piston B is practically equal to that against the cylinder-head A at the same instant.



FIG. 455.

415. An Important Distinction between gases and liquids (i.e., between elastic and inelastic fluids) consists in this:

A liquid can exert pressure against the walls of the containing vessel only by its weight, or (when confined on all sides) by transmitted pressure coming from without (due to piston pressure, atmospheric pressure, etc.); whereas—

A gas, confined, as it must be, on all sides to prevent diffusion, exerts pressure on the vessel not only by its weight, but by its elasticity or tendency to expand. If pressure from without is also applied, the gas is compressed and exerts a still greater pressure on the vessel walls.

416. Component, of Pressure, in a Given Direction.—Let $ABCD$, whose area $= dF$, be a small element of a surface, plane or curved, and p the intensity of fluid pressure upon this element, then the total pressure upon it is pdF, and is of course normal to it. Let $A'B'CD$ be the projection of the element dF upon a plane CDM making an angle α with the element, and let it be required to find the value of the component of pdF in a direction normal to this last plane (the other component being understood to be $\parallel$ to the same plane). We shall have



FIG. 455.

$$\textit{Compon. of } pdF \urcorner \textit{ to } CDM = pdF \cos\alpha = p(dF.\cos\alpha). \quad (1)$$

But $dF.\cos\alpha =$ area $A'B'CD$, the projection of dF upon the plane CDM.

$$\therefore \textit{ Compon.} \urcorner \textit{ to plane } CDM = p \times (\textit{project. of } dF \textit{ on } CDM);$$

i.e., *the component of fluid pressure* (on an element of a surface) *in a given direction* (the other component being $\urcorner$ to the first) *is found by multiplying the intensity of the pressure by the area of the projection of the element upon a plane* $\urcorner$ *to the given direction.*

It is seen, as an example of this, that if the fluid pressures on the elements of the inner surface of one hemisphere of a hollow sphere containing a gas are resolved into components $\urcorner$ and $\parallel$ to the plane of the circular base of the hemisphere, the sum of the former components simply $= \pi r^2 p$, where r is the radius of the sphere, and p the intensity of the fluid pressure; for, from the foregoing, the sum of these components is just the same as the total pressure would be, having an intensity p,

on a great circle of the sphere, the area, πr^2, of this circle being the sum of the areas of the projections, upon this circle as a base, of all the elements of the hemispherical surface. (Weight of fluid neglected.)

A similar statement may be made as to the pressures on the inner curved surface of a right cylinder.

417. Non-planar Pistons.—From the foregoing it follows that the sum of the components $\parallel$ to the piston-rod, of the fluid pressures upon the piston at A, Fig. 457, is just the same as at B, if the cylinders are of equal size and the steam, or air, is at the same tension. For the sum of the projections of all the elements of the curved surface of A upon a plane $\neg$ to the piston-rod is always $= \pi r^2 =$ area of section of cylinder-bore.



FIG. 457.

If the surface of A is symmetrical about the axis of the cylinder the other components (i.e., those $\neg$ to the piston-rod) will neutralize each other. If the line of intersection of that surface with the surface of the cylinder is not symmetrical about the axis of the cylinder, the piston may be pressed laterally against the cylinder-wall, but the thrust along the rod or "*working force*" (§ 128) is the same (except for friction induced by the lateral pressure), in all instances, as if the surface were plane and $\neg$ to piston-rod.

418. Bramah, or Hydraulic, Press.—This is a familiar instance of the principle of transmission of fluid pressure. Fig. 458. Let the small piston at O have a diameter $d = 1$ inch $= \frac{1}{12}$ ft., while the plunger E, or large piston, has a diameter $d' = AB = CD = 15$ in. $= \frac{5}{4}$ ft. The lever MN weighs $G_1 = 3$ lbs., and a weight $G = 40$ lbs. is hung at M. The lever-arms of these forces about the fulcrum N are given in the figure. The apparatus being full of water (oil is often used), the fluid pressure P_0 against the small piston is found by putting

Σ(moms. about N) $= 0$ for the equilibrium of the lever; whence [ft., lb, sec.]

$$P_0 \times 1 - 40 \times 3 - 3 \times 2 = 0. \quad \therefore P_0 = 126 \text{ lbs.}$$



FIG. 458.

But, denoting atmospheric pressure by p_a, and that of the water against the piston by p_0 (per unit area), we may also write

$$P_0 = F_0 p_0 - F_0 p_a = \tfrac{1}{4}\pi d^2(p_0 - p_a).$$

Solving for p_0, we have, putting $p_a = 14.7 \times 144$ lbs. per sq. ft.,

$$p_0 = \left[126 \div \frac{\pi}{4}\left(\tfrac{1}{12}\right)^2\right] + 14.7 \times 144 = 25236 \text{ lbs. per sq. ft.}$$

Hence at e the press. per unit area, from § 409, and (2), § 413, is

$$p_e = p_0 + h\gamma = 25236 + 3 \times 62.5 = 25423 \text{ lbs. per sq. ft.}$$

$= 175.6$ lbs. per sq. inch or 11.9 atmospheres, and the total upward pressure at e on base of plunger is

$$P = F_e p_e = \pi \frac{d'^2}{4} p_e = \tfrac{1}{4}\pi\left(\tfrac{5}{4}\right)^2 \times 25423 = 31194 \text{ lbs.},$$

or almost 16 tons (of 2000 lbs. each). The compressive force upon the block or bale, C, $= P$ less the weight of the plunger and total atmos. pressure on a circle of 15 in. diameter.

419. The Dividing Surface of Two Fluids (which do not mix) in Contact, and at Rest, is a Horizontal Plane.—For, Fig. 459, supposing any two points e and O of this surface to be at different levels (the pressure at O being p_0, that at e p_e, and the heavinesses of the two fluids γ_1 and γ_2 respectively), we would have, from a consideration of the two elementary prisms eb and bO (vertical and horizontal), the relation



FIG. 459.

$$p_e = p_0 + h\gamma_1;$$

while from the prisms ec and cO, the relation

$$p_e = p_0 + h\gamma_2.$$

These equations are conflicting, hence the above supposition is absurd. Therefore the proposition is true.

For stable equilibrium, evidently, the heavier fluid must occupy the lowest position in the vessel, and if there are several fluids (which do not mix), they will arrange themselves vertically, in the order of their densities, the heaviest at the bottom, Fig. 460. On account of the property called *diffusion* the particles of two gases placed in contact soon intermingle and form a uniform mixture. This fact gives strong support to the "Kinetic Theory of Gases" (§ 408).

FIG. 460.

420. Free Surface of a Liquid at Rest.—The surface (of a liquid) not in contact with the walls of the containing vessel is called a *free surface*, and is necessarily horizontal (from § 419) when the liquid is at rest. Fig. 461. (A gas, from its tendency to indefinite expansion, is incapable of having a free surface.) This is true even if the space above the liquid is vacuous, for if the surface were inclined or curved, points in the body of the liquid and in the same horizontal plane would have different heights (or "heads") of liquid



FIG. 461.

between them and the surface, producing different intensities of pressure in the plane, which is contrary to § 413.

When large bodies of liquid like the ocean are considered, gravity can no longer be regarded as acting in parallel lines; consequently the free surface of the liquid is curved, being ⊓ to the direction of (apparent) gravity at all points. For ordinary engineering purposes (except in Geodesy) the free surface of water at rest is a horizontal plane.

421. Two Liquids (which do not mix) at Rest in a Bent Tube open at Both Ends to the Air, Fig. 460; water and mercury, for instance. Let their heavinesses be γ_1 and γ_2 respectively. The pressure at e may be written (§ 413) either

$$p_e = p_{0_1} + h_1\gamma_1 \quad . \quad . \quad . \quad (1)$$

or

$$p_e = p_{0_2} + h_2\gamma_2 \quad . \quad . \quad . \quad (2)$$



FIG. 462.

according as we refer it to the water column or the mercury column and their respective free surfaces where the pressure $p_{0_1} = p_{0_2} = p_a$ = atmos. press. e is the surface of contact of the two liquids. Hence we have

$$p_a + h_1\gamma_1 = p_a + h_2\gamma_2; \quad \text{i.e., } h_1 : h_2 :: \gamma_2 : \gamma_1. \quad . \quad (3)$$

i.e., *the heights of the free surfaces of the two liquids above the surface of contact are inversely proportional to their respective heavinesses.*

EXAMPLE.—If the pressure at $e = 2$ atmospheres (§ 396) we shall have from (2) (inch-lb.-sec. system of units)

$$h_2\gamma_2 = p_e - p_a = 2 \times 14.7 - 14.7 = 14.7 \text{ lbs. per sq. inch.}$$

$$\therefore h_2 \text{ must} = 14.7 \div [848.7 \div 1728] = 30 \text{ inches}$$

(since, for mercury, $\gamma_2 = 848.7$ lbs. per cub. ft.). Hence, from (3),

$$h_1 = \frac{h_2\gamma_2}{\gamma_1} = \frac{30 \times [848.7 \div 1728]}{62.5 \div 1728} = 408 \text{ inches} = 34 \text{ feet.}$$

i.e., for equilibrium, and that p_e may = 2 atmospheres, h_2 and h_1 (of mercury and water) must be 30 in. and 34 feet respectively.

422. City Water-pipes.—If h = vertical distance of a point B of a water-pipe below the free surface of reservoir, and the water be at rest, the pressure on the inner surface of the pipe at B (per unit of area) is

$$p = p_0 + h\gamma\,; \text{ and here } p_0 = p_a = \text{atmos. press.}$$

EXAMPLE.—If $h = 200$ ft. (using the inch, lb., and second)

$$p = 14.7 + [200 \times 12][62.5 \div 1728] = 101.5 \text{ lbs. per sq. in.}$$

The term $h\gamma$, alone, = 86.8 lbs. per sq. inch, is spoken of as the *hydrostatic pressure* due to 200 feet height, or "**Head**," of water. (See Trautwine's Pocket Book for a table of hydrostatic pressures for various depths.)

If, however, the water is *flowing* through the pipe, the pressure against the interior wall becomes less (a problem of Hydrokinetics to be treated subsequently), while if that motion is suddenly checked, the pressure becomes momentarily much greater than the hydrostatic. This shock is called "water-ram" and "water-hammer," and may be as great as 200 to 300 lbs. per sq. inch.*

423. Barometers and Manometers for Fluid Pressure.—If a tube, closed at one end, is filled with water, and the other extremity is temporarily stopped and afterwards opened under water, the closed end being then a (vertical) height = h above the surface of the water, it is required to find the intensity, p_0, of fluid pressure at the top of the tube, supposing it to remain filled with water. Fig. 463. At E inside the tube the pressure is 14.7 lbs. per sq. inch, the same as that outside at the same level (§ 413); hence, from $p_E = p_0 + h\gamma$,



FIG. 463.

$$p_0 = p_E - h\gamma \ldots\ldots\ldots \quad (1)'$$

* See pp. 203–214 of the author's "*Hydraulic Motors.*"

EXAMPLE.—Let $h = 10$ feet (with inch-lb.-sec. system); then

$$p_0 = 14.7 - 120 \times [62.5 \div 1728] = 10.4 \text{ lbs. per sq. inch},$$

or about $\frac{2}{3}$ of an atmosphere. If now we inquire the value of h to make $p_0 =$ zero, we put $p_E - h\gamma = 0$ and obtain $h =$ 408 inches, $= 34$ ft., which is called *the height of the water-barometer*. Hence, Fig. 463*a*, ordinary atmospheric pressure will not sustain a column of water higher than 34 feet. If mercury is used instead of water the height supported by one atmosphere is

$$b = 14.7 \div [848.7 \div 1728] = 30 \text{ inches},$$

$= 76$ centims. (about), and the tube is of more manageable proportions than with water, aside from the advantage that no vapor of mercury forms above the liquid at ordinary temperatures. [In fact, the water-barometer height $b = 34$ feet has only a theoretical existence since at ordinary temperatures (40° to 80° Fahr.) vapor of water would form above the column and depress it by from 0.30 to 1.09 ft.] Such an apparatus is called a *Barometer*, and is used not only for measuring the varying tension of the atmosphere (from 14.5 to 15 lbs. per sq. inch, according to the weather and height above sea-level), but also that of any body of gas. Thus, Fig. 464, the gas in D is put in communication with the space above the mercury in the cistern at C; and we have $p = h\gamma$, where $\gamma =$ heav. of mercury, and p is the pressure on the liquid in the cistern. For delicate measurements an attached thermometer is also used, as the heaviness γ varies slightly with the temperature.



FIG. 463*a*.



FIG. 464.

If the vertical distance CD is small, the tension in C is considered the same as in D.

For gas-tensions greater than one atmosphere, the tube may be left open at the top, forming an *open ma-*

nometer, Fig. 465. In this case, the tension of the gas above the mercury in the cistern is



Fig. 465.

$$p = (h + b)\gamma \quad . \quad . \quad . \quad . \quad . \quad (1)$$

in which b is the height of mercury (about 30 in.) to which the tension of the atmosphere above the mercury column is equivalent.

Example.—If $h = 51$ inches, Fig. 465, we have (ft., lb., sec.)

$$p = [4.25 \text{ ft.} + 2.5 \text{ ft.}]\ 848.7 = 5728 \text{ lbs. per sq. foot}$$

$$= 39.7 \text{ lbs. per sq. inch} = 2.7 \text{ atmospheres.}$$

Another form of the open manometer consists of a U tube, Fig. 464, the atmosphere having access to one branch, the gas to be examined, to the other, while the mercury lies in the curve. As before, we have

$$p = (h + b)\gamma = h\gamma + p_a, \quad . \quad (2)$$



Fig. 466.

where p_a = atmos. tension, and b as above. The tension of a gas is sometimes spoken of as measured by so many *inches of mercury*. For example, a tension of 22.05 lbs. per sq. inch ($1\frac{1}{2}$ atmos.) is measured by 45 inches of mercury in a vacuum manometer (i.e., a common barometer), Fig. 464. With the open manometer this tension ($1\frac{1}{2}$ atmos.) would be indicated by 15 inches of actual mercury, Figs. 465 and 466. An ordinary steam-gauge indicates the *excess* of tension over one atmosphere; thus "40 lbs. of steam" implies a tension of $40 + 14.7 = 54.7$ lbs. per sq. in.

The *Bourdon* steam-gauge in common use consists of a curved elastic metal tube of flattened or elliptical section (with the long axis ⊥ to the plane of the tube), and has one end fixed. The movement of the other end, which is free and

closed, by proper mechanical connection gives motion to the pointer of a dial. This movement is caused by any change of tension in the steam or gas admitted, through the fixed end, to the interior of the tube. As the tension increases the elliptical section becomes less flat, i.e., more nearly circular, causing the two ends of the tube to separate more widely, i.e., the free end moves away from the fixed end; and *vice versâ*.

Such gauges, however, are not always reliable. They are graduated by comparison with mercury manometers; and should be tested from time to time in the same way.*

424. The Differential Manometer.—In Fig. 467 $OO'NK$ is a portion of a pipe with the upper wall OO' horizontal. In this pipe water is flowing from left to right in so called "steady flow;" that is, there is no change, as time goes on, in the velocity or internal pressure of the water at a given section, as at O or O'. At O' the velocity is greater than at O, since the sectional area is smaller and the pressure p_0' is smaller than that, p_0, at O; (as explained later) (p. 654).

The U-tube $dmca$ contains mercury weighing γ_m lbs./c.ft. in its lower part and is connected by the tubes aO and bO', as shown, with holes in the upper wall of the pipe at O and O'. Air previously contained in these tubes has been expelled through the cocks a and b, which are now closed. The water columns Oac and dbO' and the mercury in cm have adjusted themselves to a state of rest and are therefore in a *hydrostatic* condition. The water in the pipe exerts an upward pressure, p_0, as it flows by, against the base of the *stationary* liquid in tube Oa; and at O' a smaller upward pressure, p_0', against the base O' of the stationary water column $O'b$. If the height h (between summits of the mercury columns) be read from a scale, we are enabled to compute the value of the *difference*, $p_0 - p_0'$, of the pressures at O and O'; as may thus be shown (with p_c and p_d denoting the pressures at c and d, respectively):—



FIG. 467.

Since between O and c we find *stationary* and *continuous* water (heaviness $= \gamma$), we have $p_0 = p_c + x\gamma$. . . . (1)

* Of late years gauges have come into use constructed of boxes with corrugated sides of thin metal like the aneroid barometer. Motion of the sides, under varying internal fluid pressure, causes movement of a pointer on a dial.

Similarly, between O' and d, $\quad p_0' = p_d + (h+x)\gamma$; . (2)
while between d and c we have, for the mercury,

$$p_c = p_d + h\gamma_m. \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

By elimination there easily results

$$p_0 - p_0' = h(\gamma_m - \gamma); \quad \text{or} \quad \frac{p_0}{\gamma} - \frac{p_0'}{\gamma} = h\left(\frac{\gamma_m}{\gamma} - 1\right). \quad . \quad (4)$$

Evidently, if in place of the mercury we use a liquid only slightly heavier than water and that does not mix with the latter, h would be quite large for a small value of $p_0 - p_0'$; i.e., the instrument would be *more sensitive*. If kerosene oil, which is a little *lighter* than water, were used instead of mercury, an arrangement of tubes like that in Fig. 467*a* would be necessary, and similar analysis, (if γ_k denote the heaviness of kerosene) gives rise to the formula,



Fig. 467*a*.

$$p_0 - p_0' = h(\gamma - \gamma_k); \quad \text{or} \quad \frac{p_0}{\gamma} - \frac{p_0'}{\gamma} = h\left(1 - \frac{\gamma_k}{\gamma}\right). \quad . \quad (5)$$

425. Safety-valves.—Fig. 468. Required the proper weight G to be hung at the extremity of the horizontal lever AB, with fulcrum at B, that the flat disk-valve E shall not be forced upward by the steam pressure, p', until the latter reaches a given value $= p$. Let the weight of the arm be G_1, its centre of gravity being at C, a distance $= a$ from B; the other horizontal distances are marked in the figure.



Fig. 468.

Suppose the valve on the point of rising; then the forces acting on the lever are the fulcrum-reaction at B, the weights G and G_1, and the two fluid-pressures on the disk, viz.: Fp_a (atmospheric) downward, and Fp (steam) upward. Hence, from $\Sigma(\text{moms.}_B) = 0$,

$$Gb + G_1 c + Fp_a a - Fpa = 0. \quad . \quad . \quad . \quad (1)$$

Solving, we have

$$G = \frac{a}{b} F(p - p_a) - G_1 \frac{c}{b}. \quad . \quad . \quad . \quad . \quad . \quad (2)$$

EXAMPLE.—With $a = 2$ inches, $b = 2$ feet, $c = 1$ foot $G_1 = 4$ lbs., $p = 6$ atmos., and diam. of disk $= 1$ inch; with the foot and pound,

$$G = \frac{2}{24} \cdot \frac{\pi}{4} \left(\frac{1}{12}\right)^2 [6 \times 14.7 \times 144 - 1 \times 14.7 \times 144] - 4 \times \tfrac{1}{2}.$$

$$\therefore G = 2.81 \text{ lbs.}$$

[Notice the cancelling of the 144; for $F(p - p_a)$ is *pounds*, being one dimension of force, if the pound is selected as the unit of force, whether the inch or foot is used in both factors.] Hence when the steam pressure has risen to 6 atmos. (= 88.2 lbs. per square inch) (corresponding to 73.5 lbs. per sq. in. by steam gauge) the valve will open if $G = 2.81$ lbs., or be on the point of opening.

426. Proper Thickness of Thin Hollow Cylinders (i.e., Pipes and Tubes) to Resist Bursting by Fluid Pressure.

CASE I. *Stresses in the cross-section due to End Pressure;* Fig. 469.—Let AB be the circular cap closing the end of a cylindrical tube containing fluid at a tension $= p$. Let $r =$ internal radius of the tube or pipe. Then considering the cap free, neglecting its weight, we have three sets of || forces in equilibrium in the figure, viz.: the internal fluid pressure $= \pi r^2 p$; the external fluid pressure $= \pi r^2 p_a$; while the total stress (tensile) on the small ring, whose area now exposed is $2\pi rt$ (nearly), is $= 2\pi rtp_1$, where t is the thickness of the pipe, and p_1 the tensile stress per unit area induced by the end-pressures (fluid).



FIG. 469.

For equilibrium, therefore, we may put Σ(hor. comps.) $= 0$; i.e.,

$$\pi r^2 p - \pi r^2 p_a - 2\pi r t p_1 = 0;$$

$$\therefore p_1 = \frac{r(p - p_a)}{2t}. \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

(Strictly, the two circular areas sustaining the fluid pressures are different in area, but to consider them equal occasions but a small error.)

Eq. (1) also gives the tension in the central section of a *thin hollow sphere*, under bursting pressure.

Case II. *Stresses in the longitudinal section of pipe, due to radial fluid pressures.**—Consider free the half (semi-circular) of any length l of the pipe, between two cross-sections. Take an axis X (as in Fig. 470) ⊥ to the longitudinal section which has been made. Let p_2 denote the tensile stress (per unit area) produced in the narrow rectangles exposed at A and B (those in the half-ring edges, having no X components, are not drawn in the figure). On the internal curved surface the fluid pressure is considered of equal intensity $= p$ at all points (practically true even with liquids, if $2r$ is small compared with the head of water producing p). The fluid pressure on any dF or elementary area of the internal curved surface is $= p\,dF$. Its X component (see § 416) is obtained by multiplying p by the projection of dF on the vertical plane ABC, and since p is the same for all the dF's of the curved surface, the sum of all the X components of the internal fluid pressures must $= p$ multiplied by the area of rectangle $ABCD$, $= 2rlp$; and similarly the X components of the



Fig. 470.

* Analytically this problem is identical with that of the smooth cord on a smooth cylinder, § 169, and is seen to give the same result.

external atmos. pressures $= 2rlp_a$ (nearly). The tensile stresses ($\parallel$ to X) are equal to $2ltp_2$; hence for equilibrium, $\Sigma X = 0$ gives

$$2ltp_2 - 2rlp + 2rlp_a = 0;$$

$$\therefore p_2 = \frac{r(p - p_a)}{t} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

This tensile stress, called *hoop tension*, p_2, opposing rupture by longitudinal tearing, is seen to be double the tensile stress p_1 induced, under the same circumstances, on the annular cross-section in Case I. Hence eq. (2), and not eq. (1), should be used to determine a safe value for the thickness of metal, t, or any other one unknown quantity involved in the equation.

For safety against rupture, we must put $p_2 = T'$, a safe tensile stress per unit area for the material of the pipe or tube (see §§ 195 and 203);

$$\therefore t = \frac{r(p - p_a)}{T'} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

(For a *thin hollow sphere*, t may be computed from eq. (1); that is, need be only half as great as with the cylinder, other things being equal.)

EXAMPLE.—A pipe of twenty inches internal diameter is to contain water at rest under a head of 340 feet; required the proper thickness, if of cast-iron.

340 feet of water measures 10 atmospheres, so that the internal fluid pressure is 11 atmospheres; but the external pressure p_a being one atmos., we must write (inch, lb., sec.)

$(p - p_a) = 10 \times 14.7 = 147.0$ lbs. per sq. in., and $r = 10$ in.,

while (§ 203) we may put $T' = \frac{1}{2}$ of $9000 = 4500$ lbs. per sq. in.; whence

$$t = \frac{10 \times 147}{4500} = 0.326 \text{ inches.}$$

But to insure safety in handling pipes and imperviousness to the water, a somewhat greater thickness is adopted in practice than given by the above theory.*

Thus, Weisbach recommends (as proved experimentally also) for

Not homogen.

Pipes of sheet iron,	$t = [0.00172\ rA + 0.12]$	inches;
" " cast "	$t = [0.00476\ rA + 0.34]$	"
" " copper	$t = [0.00296\ rA + 0.16]$	"
" " lead	$t = [0.01014\ rA + 0.21]$	"
" " zinc	$t = [0.00484\ rA + 0.16]$	"

in which t = thickness in inches, r = radius in inches, and A = excess of internal over external fluid pressure (i.e., $p - p_a$) expressed in *atmospheres*.

For instance, for the example just given, we should have (cast-iron), $t = .00476 \times 10 \times 10 + 0.34 = 0.816$ in.

With *riveted steel pipes*, if the longitudinal seams are provided with two rows of rivets, a value of 10,000 lbs./in.^{2} may be used for the T' of eq. (3). This makes a fair allowance for the weakening of the steel plates by the rivet holes. The East Jersey Water Co. uses such pipes $2r = 4$ ft. in diameter, with a thickness of $t = \frac{3}{8}$ in., under a head of 340 ft. At the Mannesmann Works in Hungary, special steel tubes 4 in. in diameter and $\frac{1}{4}$ in. thick have been made, safely withstanding an internal fluid pressure of 2000 lbs./in.^{2}

Water Ram.—When water flowing in pipes is subject to sudden arrest of motion, a high bursting pressure, called "*water ram*," or "*water hammer*," may be produced. See pp. 204–211 of the writer's *Hydraulic Motors*.

In **thick hollow cylinders**, on account of the thickness of the walls, the stress in the metal is not uniformly distributed. See pp. 507, etc., of this book.

427. Collapsing of Tubes under Fluid Pressure. (Cylindrical boiler-flues, for example.)—If the external exceeds the internal fluid pressure, and the thickness of metal is small compared with the diameter, the slightest deformation of the tube or pipe gives the external pressure greater capability to produce a further change of form, and hence possibly a final collapse; just as with long columns (§ 303) a slight bending gives great advantage to the terminal forces. Hence the theory of § 426

is inapplicable. According to Sir Wm. Fairbairn's experiments (1858) a thin wrought-iron cylindrical (circular) tube will not collapse until the excess of external over internal pressure is

$$p(\text{in lbs. per sq. in.}) = 9672000\frac{t^2}{ld}. \quad . \quad . \ (1) \ . \quad . \ (\text{not homog.})$$

(t, l, and d must all be expressed in the same linear unit.) Here $t =$ thickness of the wall of the tube, d its diameter, and l its length; the ends being understood to be so supported as to preclude a local collapse.

EXAMPLE.—With $l = 10$ ft. $= 120$ inches, $d = 4$ in., and $t = \frac{1}{10}$ inch, we have

$$p = 9672000\left[\frac{1}{100} \div (120 \times 4)\right] = 201.5 \text{ lbs. per sq. inch.}$$

For safety, $\frac{1}{5}$ of this, viz. 40 lbs. per sq. inch, should not be exceeded; e.g., with 14.7 lbs. internal and 54.7 lbs. external.

[NOTE.—For simplicity the power of the thickness used in eq. (1) above has been given as 2.00. In the original formula it is 2.19, and then all dimensions must be expressed in *inches*. A discussion of the experiments of Mr. Fairbairn will be found in a paper read by Prof. Unwin before the Institute of Civ. Engineers (Proceedings, vol xlvi.). See also Prof. Unwin's "Machine Design," p. 66. It is contended by some that in the actual conditions of service, boiler-flues are subjected to such serious straining actions due to unequal expansion of the connecting parts as to render the above formula quite unreliable, thus requiring a large allowance in its application.]

427a. Collapsing Pressure of Steel Tubes.—Recent experiments by Prof. R. T. Stewart (see *Engineering News* of May 10, 1906, p. 528) on Bessemer steel lap-welded tubes of $8\frac{5}{8}$ in. in diameter and all commercial thicknesses of wall and in lengths of $2\frac{1}{2}$, 5, 10, 15, and 20 ft.; and also on single lengths of 20 ft. (between end connections) in seven sizes from 3 to 10 inches outside diameter and in all commercial thicknesses obtainable; have shown that length has practically no influence on the strength, if the length is greater than six times the diameter. From these experiments Prof. Stewart has deduced the following formulæ in which p is the collapsing unit-pressure in lbs. per sq. inch, d the outside diameter of the tube in inches, and t the thickness of wall of tube, also in inches:—

$$p = 1000\left(1 - \sqrt{1 - 1600\frac{t^2}{d^2}}\right), \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

$$p = 86670\frac{t}{d} - 1386.0. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

Eq. (4) is for use where $t \div d$ is less than 0.023, and eq. (5) for larger values of that ratio.

CHAPTER II.

HYDROSTATICS (*Continued*)—PRESSURE OF LIQUIDS IN TANKS AND RESERVOIRS.

428. Body of Liquid in Motion, but in Relative Equilibrium.—By relative equilibrium it is meant that the particles are not changing their relative positions, i.e., are not moving among each other. On account of this relative equilibrium the following problems are placed in the present chapter, instead of under the head of *Hydrodynamics*, where they strictly belong. As *relative equilibrium* is an essential property of rigid bodies, we may apply the equations of motion of rigid bodies to bodies of liquid in relative equilibrium.

CASE I. *All the particles moving in parallel right lines with equal velocities; at any given instant* (i.e., a motion of *translation*.)—If the common velocity is *constant* we have *a uniform translation*, and all the forces acting on any one particle are balanced, as if it were not moving at all (according to Newton's Laws, § 54); hence the relations of internal pressure, free surface, etc., are the same as if the liquid were at rest. Thus, Fig. 471, if the liquid in the moving tank is at rest relatively to the tank at a given instant, with *its free surface horizontal*, and the motion of the tank be one of translation with a uniform velocity, the liquid will remain in this condition of relative rest, as the motion proceeds.



FIG. 471.

But if the velocity of the tank is *accelerated* with a *constant acceleration* $= p$ (this symbol must not be confused with p for pressure), the free surface will begin to oscillate, and finally come to relative equilibrium at some angle α with the horizontal, which is thus found, when the motion is horizontal. See Fig. 472, in which the position and value of α are the same, whether the motion is uniformly accelerated from left to right

or uniformly retarded from right to left. Let O be the lowest point of the free surface, and Ob a small prism of the liquid with its axis horizontal, and of length $= x$; nb is a vertical prism of length $= z$, and extending from the extremity of Ob to the free surface. The pressure at both O and n is $p_a =$ atmos. pres. Let the area of cross-section of both prisms be $= dF$.



FIG. 472.

Now since Ob is being accelerated in direction X (horizont.), the difference between the forces on its two ends, i.e., its ΣX, must = its mass × accel. (§ 109).

$$\therefore p_b dF - p_a dF = [x dF . \gamma \div g]\bar{p}. \quad . \quad . \quad . \quad (1)$$

($\gamma =$ heaviness of liquid; $p_b =$ press. at b); and since the vertical prism nb has no vertical acceleration, the Σ(vert. compons.) for it must $= 0$.

$$\therefore p_b dF - p_a dF - z dF . \gamma = 0. \quad . \quad . \quad . \quad . \quad (2)$$

From (1) and (2),

$$\frac{x\gamma}{g}.\bar{p} = z\gamma; \quad \therefore \frac{z}{x} = \frac{\bar{p}}{g}. \quad . \quad . \quad . \quad . \quad (3)$$

Hence On is a right line, and therefore

$$\tan \alpha, \text{ or } \frac{z}{x}, = \frac{\bar{p}}{g}. \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

[Another, and perhaps more direct, method of deriving this result is to consider free a small particle of the liquid lying in the surface. The forces acting on this particle are two: the first its weight $= dG$; and the second the resultant action of its immediate neighbor-particles. Now this latter force (pointing obliquely upward) must be normal to the free surface of the liquid, and therefore must make the unknown angle α with the vertical. Since the particle has at this instant a rectilinear accelerated motion in a horizontal direction, the resultant of the two forces mentioned must be horizontal and have a value = mass × acceleration. That is, the diagonal formed on the two

forces must be horizontal and have the value mentioned, $= (dG \div g)\bar{p}$; while from the nature of the figure (let the student make the diagram for himself) it must also $= dG \tan \alpha$.

$$\therefore dG \tan \alpha = \frac{dG}{g}.\bar{p}; \text{ or, } \tan \alpha = \frac{\bar{p}}{g}. \quad . \quad . \quad . \quad . \quad \text{Q. E. D.}]$$

If the translation were *vertical*, and the acceleration *upward* [i.e., if the vessel had a uniformly accelerated upward motion or a uniformly retarded downward motion], the free surface would be horizontal, but the pressure at a depth $= h$ below the surface instead of $p = p_a + h\gamma$ would be obtained as follows: Considering free a small vertical prism of height $= h$ with upper base in the free surface, and putting Σ(vert. compons.) = mass $\times$ acceleration, we have

$$dF \,.\, p - dF \,.\, p_a - hdF \,.\, \gamma = \frac{hdF.\gamma}{g}.\bar{p};$$

$$\therefore p = p_a + h\gamma\left[\frac{g+\bar{p}}{g}\right]. \quad . \quad . \quad . \quad . \quad . \quad (5)$$

If the acceleration is downward (not the velocity necessarily) we make $\bar{p}$ negative in (5). If the vessel falls freely, $\bar{p} = -g$ and $\therefore p = p_a$, in all parts of the liquid.

Query: Suppose $\bar{p}$ downward and $> g$.

Case II. *Uniform Rotation about a Vertical Axis.*—If the narrow vessel in Fig. 473, open at top and containing a liquid, be kept rotating at a uniform angular velocity ω (see § 110) about a vertical axis Z, the liquid after some oscillations will be brought (by friction) to relative equilibrium (rotating about Z, as if rigid). Required the form of the free surface (evidently a surface of revolution) at each point of which we know $p = p_a$.



Fig. 473.

Let O be the intersection of the axis Z with the surface, and n any point in the surface; b being

a point vertically under n and in same horizontal plane as O. Every point of the small right prism nb (of altitude $= z$ and sectional area dF) is describing a horizontal circle about Z, and has therefore no vertical acceleration. Hence for this prism, free, we have $\Sigma Z = 0$; i.e.,

$$dF.p_b - dF.p_a - zdF.\gamma = 0. \quad . \quad . \quad . \quad . \quad (1)$$

Now the horizontal right prism Ob (call the direction $O \ldots b$, X) is rotating uniformly about a vertical axis through one extremity, as if it were a rigid body. Hence the forces acting on it must be equivalent to a single horizontal force, $-\omega^2 M\bar{\rho}$, (§122a,) coinciding in direction with X. [M = mass of prism = its weight $\div g$, and $\bar{\rho}$ = distance of its centre of gravity from O; here $\bar{\rho} = \frac{1}{2}x = \frac{1}{2}$ length of prism]. Hence the ΣX of the forces acting on the prism Ob must $= -\omega^2 \frac{xdF}{g}\gamma\frac{1}{2}x$. But the forces acting on the two ends of this prism are their own X components, while the lateral pressures and the weights of its particles have no X compons.;

$$\therefore dF.p_a - dF.p_b = \frac{-\omega^2 x^2 dF.\gamma}{2g}. \quad . \quad . \quad (2)$$

From (1) and (2) we have

$$z = \frac{(\omega x)^2}{2g} = \frac{v^2}{2g}; \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

where $v = \omega x$ = linear velocity of the point n in its circular path.

[As in Case I, we may obtain the same result by considering a single surface particle free, and would derive for the resultant force acting upon it the value $dG \tan \alpha$ in a horizontal direction and intersecting the axis of rotation. But here α is different for particles at different distances from the axis, $\tan \alpha$ being the $\frac{dz}{dx}$ of the curve On. As the particle is moving uniformly in a circle the resultant force must point toward the

centre of the circle, i.e., horizontally, and have a value $\frac{dG}{g} \cdot \frac{v^2}{x}$, where x is the radius of the circle [§ 74, eq. (5)];

$$\therefore dG \tan \alpha = \frac{dG}{g} \frac{(\omega x)^2}{x}; \text{ or } \tan \alpha, = \frac{dz}{dx}, = \frac{\omega^2 x}{g};$$

$$\therefore \int_0^z dz = \frac{\omega^2}{g} \int_0^x x dx; \text{ or, } z = \frac{\omega^2}{g} \cdot \frac{x^2}{2}. \quad \text{Q. E. D.}$$

Hence any vertical section of the free surface through the axis of rotation Z is a parabola, with its axis vertical and vertex at O; i.e., the free surface is a *paraboloid of revolution*, with Z as its axis. Since ωx is the linear velocity v of the point b in its circular path, $z =$ "height due to velocity" v [§ 52].

Example.—If the vessel in Fig. 473 makes 100 revol. per minute, required the ordinate z at a horizontal distance of $x =$ 4 inches from the axis (ft.-lb.-sec. system). The angular velocity $\omega = [2\pi\ 100 \div 60]$ *radians* per sec. [N. B.—A *radian* = the angular space of which 3.1415926 . . . make a half-revol., or angle of 180°]. With $x = \frac{1}{3}$ ft. and $g = 32.2$,

$$z = \frac{\omega^2 x^2}{2g} = \left(\frac{10\pi}{3}\right)^2 \left(\frac{1}{3}\right)^2 \frac{1}{64.4} = 0.188 \text{ ft.} = 2\tfrac{1}{4} \text{ inches,}$$

and the pressure at b (Fig. 473) is (now use inch, lb., sec.)

$$p_c = p_a + z\gamma = 14.7 + 2\tfrac{1}{4} \times \frac{62.5}{1728} = 14.781 \text{ lbs. per sq. in.}$$

Prof. Mendelejeff of Russia has recently utilized the fact announced as the result of this problem, for forming perfectly true paraboloidal surfaces of plaster of Paris, to receive by galvanic process a deposit of metal, and thus produce specula of exact figure for reflecting telescopes. The vessel containing the liquid plaster is kept rotating about a vertical axis at the proper uniform speed, and the plaster assumes the desired shape before solidifying. A fusible alloy, melted, may also be placed in the vessel, instead of liquid plaster.

Remark.—If the vessel is quite full and closed on top, except at O' where it communicates by a stationary pipe with a reservoir, Fig. 474, the free surface cannot be formed, but the pressure at any point in the water is just the same during uniform rotation, as if a free surface were formed with vertex at O;



Fig. 474.

i.e., $$p_b = p_a + (h_0 + z)\gamma. \quad . \quad (4)$$

See figure for h_0 and z. (In subsequent paragraphs of this chapter the liquid will be at rest.)

428a. Pressure on the Bottom of a Vessel containing Liquid at Rest.—If the bottom of the vessel is plane and horizontal, the intensity of pressure upon it is the same at all points, being



Fig. 475.



Fig. 476.

$p = p_a + h\gamma$ (Figs. 475 and 476), and the pressures on the elements of the surface form a set of parallel (vertical) forces. This is true even if the side of the vessel overhangs, Fig. 476, the resultant fluid pressure on the bottom in both cases being

$$P = Fp - Fp_a = Fh\gamma. \quad . \quad . \quad . \quad . \quad . \quad (1)$$

(Atmospheric pressure is supposed to act under the bottom.) It is further evident that if the bottom is a rigid homogeneous plate and has no support at its edges, it may be supported at a

single point (Fig. 477), which in this case (horizontal plate) is its centre of gravity. This point is called the **Centre of Pressure**, or the point of application of the resultant of all the fluid pressures acting on the plate. The present case is such that these pressures reduce to a single resultant, but this is not always practicable.



FIG. 477.

EXAMPLE.—In Fig. 476 (cylindrical vessel containing water), given $h = 20$ ft., $h_1 = 15$ ft., $r_1 = 2$ ft., $r_2 = 4$ ft., required the pressure on the bottom, the vertical tension in the cylindrical wall CA, and the hoop tension (§ 426) at C. (Ft., lb., sec.) Press. on bottom $= Fh\gamma = \pi r_2^2 h\gamma = \pi 16 \times 20 \times 62.5 = 62857$ lbs.; while the upward pull on $CA =$

$$(\pi r_2^2 - \pi r_1^2)h_1\gamma = \pi(16 - 4)15 \times 62.5 = 35357 \text{ lbs.}$$

If the vertical wall is $t = \frac{1}{10}$ inch thick at C this tension will be borne by a ring-shaped cross-section of area $= 2\pi r_2 t$ (nearly) $= 2\pi 48 \times \frac{1}{10} = 30.17$ sq. inches, giving $(35357 \div 30.17) =$ about 1200 lbs. per sq. inch tensile stress (vertical).

The *hoop* tension at C is horizontal and is

$$p'' = r_2(p - p_a) \div t \text{ (see § 426), where } p = p_a + h_1\gamma;$$

$$\therefore p'' = \frac{48 \times 15 \times 12 \times (62.5 \div 1728)}{\frac{1}{10}} = 3125 \text{ lbs. per sq. in.}$$

(using the inch and pound).

429. Centre of Pressure.—In subsequent work in this chapter, since the atmosphere has access both to the free surface of liquid and to the outside of the vessel walls, and p_a would cancel out in finding the resultant fluid pressure on any elementary area dF of those walls, we shall write:

The resultant fluid pressure on any dF of the vessel wall is normal to its surface and is $dP = pdF = z\gamma dF$, in which z is the vertical distance of the element below the free surface of the liquid (i.e., $z =$ the "head of water"). If the surface pressed on is plane, these elementary pressures form a system of parallel forces, and may be replaced by a single resultant

(if the plate is rigid) which will equal their sum, and whose point of application, called the **Centre of Pressure**, may be located by the equations of § 22, put into calculus form.

If the surface is *curved* the elementary pressures form a system of forces in space, and hence (§ 38) cannot in general be reduced to a single resultant, but to *two*, the point of application of one of which is arbitrary (viz., the arbitrary origin, § 38).

Of course, the object of replacing a set of fluid pressures by a single resultant is for convenience in examining the equilibrium, or stability, of a rigid body the forces acting on which include these fluid pressures. As to their effect in *distorting* the rigid body, the fluid pressures must be considered in their true positions (see example in § 264), and cannot be replaced by a resultant.

430. Resultant Liquid Pressure on a Plane Surface forming Part of a Vessel Wall. Co-ordinates of the Centre of Pressure.—Fig. 478. Let AB be a portion (of any shape) of a plane surface at any angle with the horizontal, sustaining liquid pressure. Prolong the plane of AB till it intersects the free surface of the liquid. Take this intersection as an axis Y, O being any point on Y. The axis X, ⊓ to Y, lies in the given plane. Let α = angle between the plane and the free surface. Then x and y are the co-ordinates of any elementary area dF of the surface, referred to X and Y. z = the "head of water," below the free surface, of any dF. The pressures are parallel.



FIG. 478.

The normal pressure on any $dF = z\gamma dF$; hence the *sum of these*, = their resultant,

$$= P, = \gamma \int z dF = F\bar{z}\gamma; \quad . \quad . \quad . \quad . \quad . \quad (1)$$

in which $\bar{z}$ = the "mean z," i.e., the z of the centre of gravity G of the plane figure AB, and F = total area of AB [$F\bar{z} = \int z dF$, from eq. (4), § 23]. γ = heaviness of liquid (see § 409).

That is, *the total liquid pressure on a plane figure is equal to the weight of an imaginary prism of the liquid having a base = area of the given figure and an altitude = vertical depth of the centre of gravity of the figure below the surface of the liquid.* For example, if the figure is a rectangle with one base (length = b) in the surface, and lying in a vertical plane,

$$P = bh \cdot \tfrac{1}{2}h\gamma = \tfrac{1}{2}bh^2\gamma.$$

Evidently, if the altitude be increased, P varies as its *square.*

From (1) it is evident that the total pressure *does not depend on the horizontal extent of the water in the reservoir.*

Now let x_c and y_c denote the co-ordinates, in plane YOX, of the *centre of pressure*, C, or *point of application of the resultant pressure* P, and apply the principle that the sum of the moments of each of several parallel forces, about an axis ⊥ to them, is equal to the moment of their resultant about the same axis [§ 22]. First taking OY as an axis of moments, and then OX, we have

$$Px_c = \int_A^B (z\gamma dF)x, \quad \text{and} \quad Py_c = \int_A^B (z\gamma dF)y. \quad . \quad (2)$$

But $P = F\bar{z}\gamma = F\bar{x}(\sin\alpha)\gamma$, and the z of any $dF = x \sin\alpha$. Hence eqs. (2) become (after cancelling the constant, $\gamma \sin\alpha$)

$$x_c = \frac{\int x^2 dF}{F\bar{x}} = \frac{I_Y}{F\bar{x}}, \text{ and } y_c = \frac{\int xy dF}{F\bar{x}}; \quad . \quad . \quad (3)$$

in which I_Y = the "*mom. of inertia*" of the plane figure referred to Y (see § 85). [N. B.—The centre of pressure as thus found is identical with the *centre of oscillation* (§ 117) and the *centre of percussion* [§ 113] of a thin homogeneous plate, referred to axes X and Y, Y being the axis of suspension.]

Evidently, if the plane figure is vertical $\alpha = 90°$, $x = z$ for

all dF's, and $\bar{x} = \bar{z}$. It is also noteworthy that the position of the centre of pressure is independent of α.

NOTE.—Since the pressures on the equal dF's lying in any horizontal strip of the plane figure form a set of equal parallel forces *equally spaced along the strip*, and are therefore equivalent to their sum applied in the *middle* of the strip, it follows that for rectangles and triangles with horizontal bases, the centre of pressure must lie on the straight line on which the middles of all horizontal strips are situated.

431. Centre of Pressure of Rectangles and Triangles with Bases Horizontal.—Since all the dF's of one horizontal strip have the same x, we may take the area of the strip for dF in the summation $\int x^2 dF$. Hence for the *rectangle* AB, Fig 479, we have from eq. (3), § 430, with $dF = b\,dx$,



FIG. 479.

$$x_c = \overline{KC} = \frac{b\int_{h_1}^{h_2} x^2 dx}{b(h_2 - h_1)\dfrac{h_1 + h_2}{2}} = \frac{2}{3}\cdot\frac{h_2^3 - h_1^3}{h_2^2 - h_1^2}; \quad (1)$$

while (see note, § 430) $y_c = \frac{1}{2}b$.

When the upper base lies in the surface, $h_1 = 0$, and $x_c = \frac{2}{3}h_2 = \frac{2}{3}$ *of the altitude.*

For a *triangle with its base horizontal and vertex up*, Fig. 480, the length u of a horizontal strip is variable and $dF = u\,dx$. From similar triangles $u = \dfrac{b}{h_2 - h_1}(x - h_1)$; therefore



FIG. 480.

$$x_c = \frac{\int_{h_1}^{h_2} x^2 dF}{F\bar{x}} = \frac{\dfrac{b}{h_2 - h_1}\int_{h_1}^{h_2} x^2(x - h_1)dx}{\frac{1}{2}b(h_2 - h_1)[h_1 + \frac{2}{3}(h_2 - h_1)]}.$$

But $\int_{h_1}^{h_2} x^2(x - h_1)dx = \left[\left(\frac{x^4}{4} - h_1\frac{x^3}{3}\right)\right]_{h_1}^{h_2}$

$$= \tfrac{1}{12}(3h_2^4 + h_1^4 - 4h_1h_2^3)$$

$$= \tfrac{1}{12}(h_2 - h_1)^2(3h_2^2 + 2h_1h_2 + h_1^2);$$

$$\therefore x_c = \tfrac{1}{2}\cdot\frac{3h_2^2 + 2h_1h_2 + h_1^2}{2h_2 + h_1}. \quad \ldots \quad (2)$$

Also, since the centre of pressure must lie on the line AB joining the vertex to the middle of base (see note, § 430), we easily determine its position.

Evidently for $h_1 = 0$, i.e., when the vertex is in the surface, $x_o = \frac{3}{4}h_2$. Similarly, *for a triangle with base horizontal and vertex down*, Fig. 481, we find that



Fig. 481.

$$x = \frac{1}{2} \cdot \frac{3h_1^2 + 2h_1h_2 + h_2^2}{2h_1 + h_2}. \quad . \quad (3)$$

If the base is in the surface, $h_1 = 0$ and (3) reduces to $x_o = \frac{1}{2}h_2$.

It is to be noticed that in the case of the triangle the value of x_o is the same whatever be its shape, so long as h_1 and h_2 remain unchanged and the base is horizontal. If the base is not horizontal, we may easily, by one horizontal line, divide the triangle into two triangles whose bases are horizontal and whose combined areas make up the area of the first. The resultant pressure on each of the component triangles is easily found by the foregoing principles, as also its point of application. The resultant of the two parallel forces so determined will act at some point on the line joining the centres of pressures of the component triangles, this point being easily found by the method of moments, while the amount of this final resultant pressure is the sum of its two components, since the latter are parallel. An instance of this procedure will be given in Example 3 of § 433. Similarly, the rectangle of Fig. 479 may be distorted into an oblique parallelogram with horizontal bases without affecting the value of x_o, nor the amount of resultant pressure, so long as h_1 and h_2 remain unchanged.

432. Centre of Pressure of Circle.—Fig. 482. It will lie on the vertical diameter. Let r = radius. From eq. (3), § 430,



Fig. 482.

$$x_o = \frac{I_v}{F\bar{x}}; \quad = \frac{I_g + F\bar{x}^2}{F\bar{x}} = \frac{\frac{1}{4}\pi r^4 + \pi r^2\bar{x}^2}{\pi r^2\bar{x}}$$

(See eq. (4), § 88, and also § 91.)

$$\therefore x_o = \bar{x} + \frac{1}{4} \cdot \frac{r^2}{\bar{x}}. \quad . \quad . \quad . \quad (4)$$

433. Examples.—It will be noticed that although the total pressure on the plane figure depends for its value upon the head, $\bar{z}$, of the centre of gravity, its point of application is always *lower* than the centre of gravity.

Example 1.—If 6 ft. of a vertical sluice-gate, 4 ft. wide, Fig. 483, is below the water-surface, the total water pressure against it is (ft., lb., sec.; eq. (1), § 430)



Fig. 483.

$$P = Fz\bar{y} = 6 \times 4 \times 3 \times 62.5 = 4500 \text{ lbs.},$$

and (so far as the pressures on the vertical posts on which the gate slides are concerned) is equivalent to a single horizontal force of that value applied at a distance $x_c = \frac{2}{3}$ of $6 = 4$ ft. below the surface (§ 431).

Example 2.—To (begin to) lift the gate in Fig. 483, the gate itself weighing 200 lbs., and the coefficient of friction between the gate and posts being $f = 0.40$ (abstract numb.) (see § 156), we must employ an upward vertical force at least

$$= P' = 200 + 0.40 \times 4500 = 2000 \text{ lbs.}$$

Example 3.—It is required to find the resultant hydrostatic pressure on the trapezoid in Fig. 483*a* with the dimensions there given and its bases horizontal; also its point of application, i.e., the centre of pressure of the plane figure in the position there shown. From symmetry the C. of P. will be in the middle vertical of the figure, as also that of the rectangle $BCFE$, and that of the two triangles ABE and CDF taken together (conceived to be shifted horizontally so that CF and BE coincide on the middle vertical, thus forming a single triangle of 5 ft. base, and having the same total pressure and C. of P. as the two actual triangles taken together). Let P_1 = the total pressure, and x_c' refer to the C. of P., for the rectangle; P_2 and x_c'', for the 5 ft. tri-



Fig. 483*a*.

angle; $h_1 = 4$ ft. and $h_2 = 10$ ft. being the same for both. Then from eq. (1), § 430, we have (with the ft., lb., and sec.)

$$P_1 = 30 \times 7\gamma = 210\gamma; \quad \text{and} \quad P_2 = \tfrac{1}{2} \times 6 \times 5 \times 6\gamma = 90\gamma;$$

while from eqs. (1) and (3) of § 431 we have also (respectively)

$$x_c' = \frac{2}{3} \cdot \frac{1000 - 64}{100 - 16} = \frac{2}{3} \cdot \frac{936}{84} = 7.438 \text{ feet};$$

$$x_c'' = \frac{1}{2} \cdot \frac{48 + 80 + 100}{8 + 10} = \frac{228}{2 \times 18} = 6.333 \text{ feet}.$$

The total pressure on the trapezoid, being the resultant of P_1 and P_2, has an amount $= P_1 + P_2$ (since they are parallel), and has a lever-arm x_c about the axis OY to be found by the principle of moments, as follows:

$$x_c = \frac{P_1 x_c' + P_2 x_c''}{P_1 + P_2} = \frac{(210 \times 7.438 + 90 \times 6.33)\gamma}{(210 + 90)\gamma} = 7.09 \text{ ft.}$$

The total hydrostatic pressure on the trapezoid is (for fresh water)

$$P = P_1 + P_2 = [210 + 90]\ 62.5 = 18750 \text{ lbs.}$$

Example 4.—Required the horizontal force P', Fig. 484, to be applied at N (with a leverage of $a' = 30$ inches about the fulcrum M) necessary to (begin to) lift the circular disk AB of radius $r = 10$ in., covering an opening of equal size. $NMAB$ is a single rigid lever weighing $G' = 210$ lbs. The centre of gravity, G, of disk, being a vertical distance $\bar{z} = O'G = 40$ inches from the surface, is 50 inches (viz., the sum of $OM = k = 20''$ and $MG = 30''$) from axis OY; i.e., $\bar{x} = 50$ inches. The centre of gravity of the whole lever is a horizontal distance $b' = 12$ inches, from M.



Fig. 484.

For impending lifting we must have, for equilibrium of the lever,

$$P'a' = G'b' + P(x_c - k); \quad \ldots \quad (1)$$

where P = total water pressure on circular disk, and $x_c = OC$. From eq. (1), § 430, (using inch, lb., and sec.,)

$$P = F\bar{z}\gamma = \pi r^2 \bar{z}\gamma = \pi 100 \times 40 \times \frac{62.5}{1728} = 454.6 \text{ lbs.}$$

From § 432, $x_c = \overline{OC} = \bar{x} + \frac{1}{4}\frac{r^2}{\bar{x}} = 50 + \frac{1}{4} \cdot \frac{100}{50} = 50.5$ in.

$$\therefore P' = \frac{1}{a'}\left[G'b' + P(x_c - k)\right]$$

$$= \frac{1}{30}\left[210 \times 12 + 454.6 \times 30.5\right] = 546 \text{ lbs.}$$

434. Example of Flood-gate.—Fig. 485. Supposing the rigid double gate AD, 8 ft. in total width, to have four hinges; two at e, and two at f, 1 ft. from top and bottom of water channel; required the pressures upon them, taking dimensions from the figure (ft., lb., sec.).



FIG. 485.

Wat. press. $= P = F\bar{z}\gamma$

$= 72 \times 4\frac{1}{2} \times 62.5 = 20250$

pounds, and its point of application (cent. of press.) is a distance $x_c = \frac{2}{3}$ of $9' = 6'$ from O (§ 431). Considering the whole gate free and taking moments about e, we shall have

(press. at f) $\times 7' = 20250 \times 5$; $\therefore$ press. at $f = 14464$ lbs.

(half on each hinge at f), and

$\therefore$ press. at e = P — press. at $f = 5875$ lbs.

(half coming on each hinge).

If the two gates do not form a single rigid body, and hence are not in the same plane when closed, a wedge-like or toggle-joint action is induced, producing much greater thrusts against the hinges, and each of these thrusts is not ⌐ to the plane of the corresponding gate. Such a case forms a good exercise for the student.

435. Stability of a Vertical Rectangular Wall against Water Pressure on One Side.—Fig. 486. All dimensions are shown in the figure, except l, which is the length of wall ⌐ to paper. Supposing the wall to be a single rigid block, its weight $G' = b'h'l\gamma'$ (γ' being its heaviness (§ 7), and l its length). Given the water depth $= h$, required the proper width b' for stability. For proper security:



FIG. 486.

First, the resultant of G' and the water-pressure P must fall within the base BD (or, which amounts to the same thing), the moment of G' about D, the outer *toe* of the wall, must be numerically greater than that of P; and

Secondly, P must be less than the sliding friction fG' (see § 156) on the base BD.

Thirdly, the maximum pressure per unit of area on the base must not exceed a safe value (compare § 348).

Now $P = F\bar{z}\gamma = hl\,\frac{h}{2}\,\gamma = \frac{1}{2}h^2l\gamma$, ($\gamma$ = heaviness of water);

and $x_0 = \frac{2}{3}h$.

Hence for stability against tipping about D,

$$P\tfrac{1}{3}h \text{ must be } < G'\tfrac{1}{2}b'; \text{ i.e., } \tfrac{1}{6}h^3l\gamma < \tfrac{1}{2}b'^2h'l\gamma'; \quad . \quad (1)$$

while, as to sliding on the base,

$$P \text{ must be } < fG'; \text{ i.e., } \tfrac{1}{2}h^2l\gamma < fb'h'l\gamma'. \quad . \quad . \quad (2)$$

As for values of the coefficient of friction, f, on the base of wall, Mr. Fanning quotes the following among others, from various authorities:

For point-dressed granite on dry clay,		$f = 0.51$
" " " " "	moist clay,	0.33
" " " " "	gravel,	0.58
" " " " "	smooth concrete,	0.62
" " " " "	similar granite,	0.70
For dressed hard limestone on like limestone,		0.38
" " " "	brickwork,	0.60
For common bricks on common bricks,		0.64

To satisfactorily investigate the third condition requires the detail of the next paragraph.

436. Parallelopipedical Reservoir Walls. More Detailed and Exact Solution.—If (1) in the last paragraph were an exact equality, instead of an inequality, the resultant R of P and G' would pass through the corner D, tipping would be impending, and the pressure per unit area at D would be theoretically *infinite*. To avoid this we wish the wall to be wide enough that the resultant R, Fig. 487,* may cut BD in such a point, E', as to cause the pressure per unit area, p_m, at D to have a definite safe value (for the pressure p_m at D, or quite near D, will evidently be greater than elsewhere on BD; i.e., it is the maximum pressure to be found on BD). This may be done by the principles of §§ 346 and 362.



FIG. 487.

First, assume that R cuts BD *outside of the middle third;* i.e., that

$$VE', = nb', > \tfrac{1}{6}b' (\text{or } n > \tfrac{1}{6});$$

where n denotes the ratio of the distance of E' from the middle of the base to the whole width, b', of base. Then the pressure (per unit area) on small equal elements of the base BD (see § 346) may be considered to vary as the ordinates of a triangle MND (the vertex M being within the distance BD), and $\overline{E'D}$ will $= \frac{1}{3}\overline{MD}$; i.e.,

* The student should note that Fig. 487 only shows the *lower part* of the wall of Fig. 486; and that the resultant R, *now applied at* E', is *there* decomposed into its original components P and G'.

$$\overline{MD} = 3(\tfrac{1}{2} - n)b'.$$

The mean pressure per unit area, on MD,

$$= G' \div (l \,.\, \overline{MD}),$$

and hence the maximum pressure (viz., at D), being double the mean, is

$$p_m = 2G' \div [3b'l(\tfrac{1}{2} - n)]; \quad . \quad . \quad . \quad . \quad (0)$$

and if p_m is to equal C' (see §§ 201 and 203), a safe value for the crushing resistance, per unit area, of the material, we shall have

$$b'l(\tfrac{1}{2} - n)C' = \tfrac{2}{3}G' = \tfrac{2}{3}b'h'l\gamma',$$

$$\therefore \; n = \frac{1}{2} - \frac{2}{3}\frac{h'\gamma'}{C'}; \quad . \quad . \quad . \quad . \quad . \quad (1)$$

To find b', knowing n, we put the Σ(moms.) of the G' and P at E, about E', = zero (for the only other forces acting on the wall are the pressures of the foundation against it, along MD; and since the resultant of these latter passes through E', the sum of their moments about E' is already zero); i.e.,

$$G'nb' - P\tfrac{1}{3}h = 0; \quad \text{or,} \quad nb'^2h'l\gamma' = \tfrac{1}{3}h \,.\, \tfrac{1}{2}h^2l\gamma;$$

$$\therefore \; b' = h \,.\, \sqrt{\frac{h\gamma}{6nh'\gamma'}}. \quad . \quad . \quad . \quad . \quad . \quad (2)$$

Having obtained b', we must also ascertain if P is $< fG'$, the friction; i.e., if P is $< fb'h'l\gamma'$. If not, b' must be still further increased. (Or, graphically, the resultant of G' and P must not make an angle $> \phi$, the angle of friction, with the vertical.

If n, computed from (1), should prove to be $< \frac{1}{6}$, our first assumption is wrong, and we therefore assume $n < \frac{1}{6}$, and proceed thus:

Secondly, n being $< \frac{1}{6}$ (see §§ 346 and 362), we have a

trapezoid of pressures, instead of a triangle, on BD. Let the pressure per unit area at D be p_m (the maximum on base). The whole base now receives pressure, the mean pressure (per unit area) being $= G' \div [b'l]$; and therefore, from § 362, Case I, we have

$$p_m = [6n + 1]\frac{G'}{b'l}; \quad . \quad . \quad . \quad . \quad . \quad (0a)$$

and since, here, $G' = b'h'l\gamma'$, we may write

$$p_m = (6n + 1)h'\gamma'.$$

For safety as to crushing resistance we put

$$(6n + 1)h'\gamma' = C'; \text{ whence } n = \frac{1}{6}\left[\frac{C'}{h'\gamma'} - 1\right]. \quad . \quad (1a)$$

Having found n from eq. (1a), we determine the proper width of base b' from eq. (2), in case the assumption $n < \frac{1}{6}$ is verified.

Example.—In Fig. 486, let $h' = 12$ ft., $h = 10$ ft., while the masonry weighs $(\gamma' =)$ 150 lbs. per cub. ft. Supposing it desirable to bring no greater compressive stress than 100 lbs. per sq. inch $(= 14400$ lbs. per sq. ft.) on the cement of the joints, we put $C' = 14400$, using the ft.-lb.-sec. system of units.

Assuming $n > \frac{1}{6}$, we use eq. (1), and obtain

$$n = \frac{1}{2} - \frac{2}{3} \cdot \frac{12 \times 150}{14400} = \frac{5}{12},$$

which is $> \frac{1}{6}$; hence the assumption is confirmed, also the propriety of using eq. (1) rather than (1a).

Passing to eq. (2), we have

$$b' = 10 \times \sqrt{\frac{62.5 \times 10}{\frac{5}{2} \times 12 \times 150}} = 3.7 \text{ feet.}$$

But, as regards frictional stability, we find that, with $f = 0.30$, a low value, and $b' = 3.7$ ft. (ft., lb., sec.),

$$\frac{P}{fG'} = \frac{\frac{1}{2}h'l\gamma}{fb'h'l\gamma'} = \frac{100 \times 62.5}{2 \times 0.3 \times 3.7 \times 12 \times 150} = 1.5;$$

which is greater than unity, showing the friction to be insufficient to prevent sliding (with $f = 0.30$); a greater width must therefore be chosen, for frictional stability.

If we make $n = \frac{1}{6}$, i.e., make R cut the base at the outer edge of middle third (§ 362), we have, from eq. (2),

$$b' = 10 \times \sqrt{\frac{62.5 \times 10}{\frac{3}{6} \times 12 \times 150}} = 5.89 \text{ feet};$$

and the pressure at D is now of course well within the safe limit; while as regards friction we find

$$P \div fG' = 0.92, < \text{unity},$$

and therefore the wall is safe in this respect also.

With a width of base = 3.7 feet first obtained, the portion MD, Fig. 487, of the base which receives pressure [according to Navier's theory (§ 346)] would be only 0.92 feet in length, or about one fourth of the base, the portion BM tending to open, and perhaps actually suffering tension, if capable (i.e., if cemented to a rock foundation), in which case these tensions should properly be taken into account, as with beams (§ 295), thus modifying the results.

It has been considered safe by some designers of high masonry dams, to neglect these possible tensile resistances, as has just been done in deriving $b' = 3.7$ feet; but others, in view of the more or less uncertain and speculative character of Navier's theory, when applied to the very wide bases of such structures, prefer, in using the theory (as the best available), to keep the resultant pressure within the middle third at the base (and also at all horizontal beds above the base), and thus avoid the chances of tensile stresses.

This latter plan was favored by Messrs. Church and Fteley, as engineers of the proposed Quaker Bridge Dam in connection with the New Croton Aqueduct of New York City, in their report of 1887. See § 439.

437. Wall of Trapezoidal Profile. Water-face Vertical.—Economy of material is favored by using a trapezoidal profile, Fig. 488. With this form the stability may be investigated in a corresponding manner. The portion of wall above each horizontal bed should be examined similarly. The weight G' acts through the centre of gravity of the whole mass.



FIG. 488.

Detail.—Let Fig. 488 show the vertical cross-section of a trapezoidal wall, with notation for dimensions as indicated; the portion considered having a length $= l$, ⊥ to the paper. Let γ = heaviness of water, γ' that of the masonry (assumed homogeneous), with n as in § 436.

For a *triangle of pressure*, MD, on the base, i.e., with $n > \frac{1}{6}$, or resultant falling outside the middle third (neglecting possibility of tensile stresses on left of M), if the intensity of pressure p_m at D is to $= C'$ (§ 201), we put, as in § 436,

$$b'l[\tfrac{1}{2} - n]C' = \tfrac{2}{3}G', \text{ i.e., } = \tfrac{2}{3}lh' \cdot \tfrac{1}{2}(b' + b'')\gamma',$$

whence

$$n = \frac{1}{2} - \frac{1}{3}\frac{h'\gamma'}{C'} \cdot \frac{b' + b''}{b'}. \quad \ldots \quad (1)'$$

For a *trapezoid of pressure*, i.e. with $n < \frac{1}{6}$, or the resultant of P and G' falling within the middle third, we have, as before (§ 362, Case I),

$$p_m, \text{ or } C', = (6n + 1)\frac{G'}{b'l};$$

whence

$$n = \frac{1}{6}\left[\frac{C'b'l}{G'} - 1\right]; \text{ i.e., } n = \frac{1}{6}\left[\frac{2C'b'}{h'\gamma'(b' + b'')} - 1\right]. \quad (1a)'$$

From the geometry of the figure, having joined the middles of the two bases, we have

$$\bar{y}, = \overline{gO}, = \frac{h'}{3} \cdot \frac{b' + 2b''}{b' + b''}$$

(§ 26, Prob. 6), and, by similar triangles, $\overline{OV} : \overline{KV} :: \overline{gO} : h'$, whence

$$\overline{OV} = \frac{\bar{y}}{h'} \cdot \frac{1}{2}[b' - b''];$$

$$\therefore \overline{OE'}, = \overline{OV} + \overline{VE'}, = \frac{1}{6} \cdot \frac{(b' + 2b'')(b' - b'')}{b' + b''} + nb' \ldots (a)$$

The lines of action of G' and P meet at E, and their resultant cuts the base in some point E'. The sum of their moments about E' should be zero, i.e., $P \cdot \frac{1}{3}h = G' \cdot \overline{OE'}$; that is, (see eq. (*a*) above, and eq. (1), § 430,)

$$\tfrac{1}{6}h^3 l\gamma = lh'\gamma' \tfrac{1}{2}(b' + b'')\left[\frac{1}{6} \cdot \frac{(b' + 2b'')(b' - b'')}{b' + b''} + nb'\right]; \quad (b)$$

i.e., cancelling,

$$h^3\gamma = \tfrac{1}{2}h'\gamma'\left[(b' + 2b'')(b' - b'') + 6nb'(b' + b'')\right]. \quad (2)'$$

Hence we have two equations for finding two unknowns viz.: (1)′and (2)′ when $n > \frac{1}{6}$; and (1a)′ and (2)′ when $n < \frac{1}{6}$.

For dams of small height (less than 40 ft., say), if we immediately put $n = \frac{1}{6}$, thus restricting the resultant pressure to the edge of middle third, and solve (2)′ for b', b'' being assumed of some proper value for a coping, foot-walk, or roadway, while h' may be taken enough greater than h to provide against the greatest height of waves, from 2.5 to 6 ft., the value of p_m at D will probably be $< C'$. In any case, for a value of $n =$, or $<$, $\frac{1}{6}$ we put p_m for C' in equation (1a)′ and solve for p_m, to determine if it is no greater than C'.

Mr. Fanning recommends the following values for C' (*in lbs.*

per sq. foot) with coursed rubble masonry laid in strong mortar:

	For Limestone.	Sandstone.	Granite.	Brick.
C' =	50,000	50,000	60,000	35,000
Av. heaviness of the masonry in lbs. per cub. ft.	152	132	154	120

As to *frictional resistance*, P must be $< fG'$; i.e.,

$$\tfrac{1}{2}h'^2 l\gamma < fh'\gamma'\tfrac{1}{2}(b' + b''). \quad . \quad . \quad . \quad . \quad . \quad (3)'$$

If the base is cemented to a *rock foundation* with good material and workmanship throughout, Messrs. Church and Fteley (see § 436) consider that the wall may be treated as amply safe against sliding on the base (or any horizontal bed), provided the other two conditions of safety are already satisfied.

438. Triangular Wall with Vertical Water-face.—Making $b'' = 0$ in the preceding article, the trapezoid becomes a *right triangle*, and the equations reduce to the following:

$$p_m = \frac{2h'\gamma'}{3 - 6n} \text{ for } n > \tfrac{1}{6}, \quad . \quad . \quad . \quad . \quad (1)''$$

and

$$p_m = \tfrac{1}{2}h'\gamma'[6n + 1] \text{ for } n < \tfrac{1}{6} \quad . \quad . \quad . \quad (1a)''$$

(p_m not to exceed C' in any case); while to determine the breadth of base, b', after n is computed [or assumed, for small height of wall], we have from eq. (2)',

$$h'^3\gamma = \tfrac{1}{2}h'b'^2\gamma'[6n + 1]. \quad . \quad . \quad . \quad . \quad (2)''$$

Also, for frictional stability,

$$\tfrac{1}{2}h'^2 l\gamma \text{ must be } < \tfrac{1}{2}fh'b'l\gamma'. \quad . \quad . \quad . \quad . \quad (3)''$$

439. High Masonry Dams.—Although the principle of the arch may be utilized for vertical stone dikes of small height (30 to 50 feet) and small span, for greater heights and spans the formula for hoop tension, § 426 (or rather, here, "hoop compression"), on the vertical radial joints of the horizontal arch rings, Fig. 489, calls for so great a radial thickness of joint in the lower courses, that straight dikes (or "gravity dams") are usually built instead, even where firm rock abutments are available laterally.



FIG. 489.

For example, at a depth of 100 feet, where the hydrostatic pressure is $hy = 100 \times 62.5 = 6250$ lbs. per sq. ft., if we assume for the voussoirs a (radial, horizontal) thickness $= 4$ ft., with a (horizontal) radius of curvature $r = 100$ feet, we shall find a compression between their vertical radial faces of (ft., lb., sec.)

$$p'' = \frac{r(p - p_a)}{t} = \frac{100 \times 6250}{4} = 156250 \text{ lbs. per sq. ft.},$$

or 1085 lbs. per sq. inch; far too great for safety, even if there were no danger of collapse, the dike being short. If now the thickness is increased, in order to distribute the pressure over a greater surface, we are met by the fact that the formula for "hoop compression" is no longer strictly applicable, the law of distribution of pressure becoming very uncertain; and even supposing a uniform distribution over the joint, the thickness demanded for proper safety against crushing is greater than for a straight dam ("*gravity dam*") at a very moderate depth below the water surface, unless the radius of curvature of arch can be made small. But the smaller the radius the more does the dam encroach on the storage capacity of the reservoir, while in no case, of course, can it be made smaller than half the span.

Another point is, that as masonry is not destitute of elasticity, the longer the span the more unlikely is it that the parts of the arch will "close up" properly, and develop the

abutment reactions when the water is first admitted to the reservoir; which should occur if it is to act as an arch instead of by gravity resistance.

For these reasons the engineers of the proposed Quaker Bridge Dam reported unfavorably to the plan of a curved design for that structure, and recommended that a straight dam be built. See reference in § 436. According to their designs this dam was to be 258 feet in height (exceeding by about 90 feet the height of any dam previously built), about 1400 feet in length at the top, and 216 feet in width at the lowest point of base, joining the bed-rock.

More recently, however (1888), a board of experts, specially appointed for the purpose, having examined a number of different plans, reported favorably to the adoption of a curved form for the dam, as offering greater resistance under extraordinary circumstances (impact of ice-floes, earthquakes, etc.), on account of its arched form (though resisting by gravity action under usual conditions) than a straight structure; and also as more pleasing in appearance.

Fig. 490 shows the profile of a straight high masonry dam as designed at the present day. Assuming a width $b'' =$ from 6 to 22 feet at the top, and a sufficient h'' (see figure) to exceed the maximum height of waves, the up-stream outline ACM is made nearly vertical and perhaps somewhat concave, while the down-stream profile BDN, by computation or graphical trial, or both, is so formed that *when the reservoir is full* the resultant R, of the weight G of the portion $ABCD$ of masonry above *each* horizontal bed, as CD, and the hydrostatic pressure P on the corresponding up-stream face AC, shall cut the bed CD in such a point E' as not to cause too great compression p_m at the outer edge D (not over 85 lbs. per sq. inch according to M. Krantz in "Reservoir Walls"). p_m being computed by one of the equations [(0) and (0a) of § 436]



FIG. 490.

For E' outside the middle third and neglecting tension $\Big\}$ $\ldots p_m = \dfrac{2G}{3.\overline{CD}\,.\,l(\frac{1}{2} - n)}$; $(1)''''$

For E' inside middle third $\Big\}$ $\ldots p_m = \dfrac{(6n + 1)G}{\overline{CD}\,.\,l}$; $(1a)'''$

where l = length of wall ⊓ to paper, usually taken = one foot, or one inch, according to the unit of length adopted; for n, see § 436.

Nor, *when the reservoir is empty* and the water pressure lacking, must the weight G resting on each bed, as CD, cut the bed in a point E'' so near the edge C as to produce excessive pressure there (computed as above). The figure shows the general form of profile resulting from these conditions. The masonry should be of such a character, by irregular bonding in every direction, as to make the wall a monolith.

440. The New Croton Dam * (completed in Feb. 1906).—Attempts, by strict analysis, to determine the equation of the curve BN, AM being assumed straight, so as to bring the point E' at the outer edge of the middle third of its joint, or to make the pressure at D constant below a definite joint, have failed, up to the present time; but approximate and tentative methods are in use which serve all practical purposes. As an illustration the method set forth in the report on the Quaker Bridge Dam will be briefly outlined; *this method confines E' to the middle third.*

The width $AB = b''$ is taken = 22′ for a roadway, and $h'' =$ 7 ft. The profile is made a vertical rectangle from A down to a depth of 33 ft. below the water surface (*reservoir full*). Combining the weight of this rectangle of masonry with the corresponding water pressure (for a length of wall = one foot), we find the resultant pressure comes a little within the outer edge of the middle third of the base of the rectangle, while p_m is of course small.

* This dam was built across the Croton River (see foot of p. 558) about a mile above the site chosen (in 1884) for the proposed "Quaker Bridge" Dam (which was not built). The profile and plan adopted were based entirely upon the plans prepared for the Quaker Bridge Dam. See Mr. Wegmann's paper on the New Croton Dam in vol. lvii (June, 1907) of *Transac. Am. Soc. Civil Engineers;* also his book on *Construction of Masonry Dams,* which gives an analytical treatment to replace the tentative graphic method originally used, and described in the report on the Quaker Bridge Dam.

The rectangular form of profile might be continued below this horizontal joint, as far as complying with the middle third requirement, and the limitation of pressure-intensity, is concerned; but, not to make the widening of the joints too abrupt in a lower position where it would be absolutely required, a beginning is made at the joint just mentioned by forming a trapezoid between it and a joint 11 ft. farther down, making the lower base of the latter of some trial width, which can be altered when the results to which it gives rise become evident. Having computed the weight of this trapezoid and constructed its line of action through the centre of gravity of the trapezoid, the value of the resultant G of this weight and that of the rectangle is found (by principle of moments or by an equilibrium polygon) in amount and position, and combined with the water pressure of the corresponding 44 ft. of water to form the force R, whose point of intersection with the new joint or bed (lower base of trapezoid) is noted and the value of p_m computed. These should both be somewhat nearer their limits than in the preceding joint. If not, a different width should be chosen, and changed again, if necessary, until satisfactory. Similarly, another layer, 11 ft. in height and of trapezoidal form, is added below and treated in the same way; and so on until in the joint at a depth of 66 ft. from the water surface a width is found where the point E' is very close upon its limiting position, while p_m is quite a little under the limit set for the upper joints of the dam, 8 tons per square foot. For the next three 11 ft. trapezoidal layers the chief governing element is the middle-third requirement, E' being kept quite close to the limit, while the increase of p_m to 7.95 tons per sq. ft. is unobjectionable; also, we begin to move the left-hand edge to the left of the vertical, so that when the reservoir is empty the point E'' shall not be too near the up-stream edge C.

Down to a depth of about 200 ft. the value of p_m is allowed to increase to 10.48 tons per sq. ft., while the position of E'' gradually retreats from the edge of its limit. Beyond 200 ft. depth, to prevent a rapid increase of width and consequent extreme flattening of the down-stream curve, p_m is allowed to mount rapidly to 16.63 tons per sq. ft. (= 231 lbs. per sq. in.), which value it reaches at the point N of the base of

the dam, which has a width = 216 ft., and is 258 feet below the water surface when the reservoir is full.

The heaviness of the masonry is taken as $\gamma' = 156.25$ lbs. per cubic foot, just $\frac{5}{2}$ of $\gamma = 62.5$ lbs. per cub. foot, the heaviness taken for water.

When the *reservoir is empty*, we have the weight G of the superincumbent mass resting on any bed CD, and applied through the point E''; the pressure per unit area at C can then be computed by eq. $(1a)'''$, § 439, n being the quotient of $(\frac{1}{2}\overline{CD} - CE'') \div \overline{CD}$ for this purpose. In the present case we find E'' to be within middle third at all joints, and the pressures at C to be under the limit.

For further details the reader is referred to the report itself (reprinted in *Engineering News*, January, 1888, p. 20). The graphic results were checked by computation, Wegmann's method, applied to each trapezoid in turn.*

441. Earthwork Dam, of Trapezoidal Section.†—Fig. 491. It is required to find the conditions of stability of the straight earthwork dam $ABDE$, whose length $= l$, ⊥ to paper, as regards sliding horizontally on the plane AE; i.e., its frictional stability. With the dimensions of the figure, γ and γ' being the heavinesses of the water and earth respectively (see § 7), we have



FIG. 491.

$$\text{Weight of dam} = G_1 = \text{vol.} \times \gamma' = lh_1[b + \tfrac{1}{2}(a_1 + c)]\gamma'. \quad (1)$$

$$\text{Resultant water press.} = P = F\bar{z}\gamma = \overline{OA} \times l \times \tfrac{1}{2}h\gamma. \quad (2)$$

$$\text{Horiz. comp. of } P = H = P \sin \alpha$$

$$= [\overline{OA} \sin \alpha]\tfrac{1}{2}hl\gamma = \tfrac{1}{2}h^2l\gamma. \quad . \quad . \quad . \quad (3)$$

From (3) it is evident that the horizontal component of P is just the same, viz., $= hl \,.\, \frac{1}{2}h\gamma$, as the water pressure would be

* See the *Engineering Record* of Dec. 30, 1899, for a description of the Assuan Dam across the river Nile; also the issue of April 22, 1905, for mention of Mr. Atcherley's paper on masonry dams, etc.

† Mr. Bassell's "Earth Dams" is a recent publication; New York, 1904.

on a vertical rectangle equal to the vertical projection of OA and with its centre of gravity at the same depth ($\frac{1}{2}h$). Compare § 416. Also,

Vert. comp. of $P = V = P \cos \alpha$

$$= [\overline{OA} \cos \alpha]\tfrac{1}{2}hl\gamma = \tfrac{1}{2}ahl\gamma, \quad . \ . \ . \quad (4)$$

and is the same as the water pressure on the horizontal projection of OA if placed at a depth $= O'G = \frac{1}{2}h$.

For stability against sliding, the horizontal component of P must be less than the friction due to the total vertical pressure on the plane AE, viz., $G_1 + V$; hence if f is the coefficient of friction on AE, we must have $H < f\,[G_1 + V]$, i.e. (see above),

$$\tfrac{1}{2}h^2l\gamma \text{ must be } < f\Big[lh_1[b + \tfrac{1}{2}(a_1 + c)]\gamma' + \tfrac{1}{2}ahl\gamma\Big]. \ . \quad (5)$$

However, if the water leak under the dam on the surface AE, so as to exert an upward hydrostatic pressure

$$V' = [a_1 + b + c]lh\gamma,$$

(to make an extreme supposition,) the friction will be only

$$= f[G_1 + V - V'],$$

and (5) will be replaced by

$$H < f[G_1 + V - V']. \ . \ . \ . \ . \ . \quad (6)$$

Experiment shows (Weisbach) that with $f = 0.33$ computations made from (6) (treated as a bare equality) give satisfactory results.

Example.—(Ft., lb., sec.) With $f = 0.33$, $h = 20$ ft., $h_1 = 22$ ft., $a = 24$ ft., $a_1 = 26.4$ ft., and $c = 30$ ft., we have, making (6) an equality, with $\gamma' = 2\gamma$,

$$\tfrac{1}{2}h^2l\gamma = f\left[\gamma' lh_1\left(b + \frac{a_1 + c}{2}\right) + \tfrac{1}{2}ahl\gamma - (a_1 + b + c)lh\gamma\right];$$

$$\therefore \ \tfrac{1}{2}(400) = \tfrac{1}{3}[22(b + 28.2)2 + \tfrac{1}{2}(24 \times 20) - (26.4 + b + 30)20];$$

whence, solving for b, the width of top, $b = 10.3$ feet.

442. Liquid Pressure on Both Sides of a Gate or Rigid Plate.—The sluice-gate AB, for example, Fig. 492, receives a pressure, P_1, from the "head-water" M, and an opposing pressure P_2 from the "tail-water" N. Since these two horizontal forces are not in the same line, though parallel, their resultant R, which $= P_1 - P_2$, acts horizontally in the same plane, but at a distance below $O_1 = u$, which we may find by placing the moment of R about O_1, equal to the algebraic sum of those of P_1 and P_2 about O_1.



FIG. 492.

$$\therefore \quad Ru = P_1 x_c' - P_2(x_c'' + h). \quad . \quad . \quad . \quad . \quad (1)$$

$$\therefore \quad u = \frac{[P_1 x_c' - P_2(x_c'' + h)]}{P_1 - P_2}. \quad . \quad . \quad . \quad (2)$$

C_1 and C_2 are the respective centres of pressure of the surfaces O_1B and O_2B, and $u =$ distance of R from O_1, while $h =$ difference of level between head and tail waters. If the surfaces O_1B and O_2B are both rectangular,

$$x_c' = \tfrac{2}{3}h_1 \quad \text{and} \quad x_c'' = \tfrac{2}{3}h_2.$$

EXAMPLE.—Let the dimensions be as in Fig. 493, both surfaces under pressure being rectangular and 8 ft. wide. Then (ft., lb., sec.) $R = P_1 - P_2$, or (§ 430)



FIG. 493.

$$R = [12 \times 8 \times 6 - 8 \times 8 \times 4]62.5$$

$$= 20000 \text{ lbs.} = 10 \text{ tons};$$

while from ex. (2)

$$u = \frac{[12 \times 8 \times 6 \times 8 - 8 \times 8 \times 4(9\tfrac{1}{3})]62.5}{20000}.$$

That is, $u = 6.93$ feet, which locates C. Hence the pressure of the gate upon its hinges or other support is the same (aside

from its own weight), provided it is rigid, as if the single horizontal force $R = 10$ tons acted at the point C, 2.93 ft. below the level of the tail-water surface.

443. If the plate, or gate, is entirely below the tail-water surface, the resultant pressure is applied in the centre of gravity of the plate.—Proof as follows: Conceive the surface to be divided into a great number of small equal areas, each $= dF$; then, the head of water of any dF being $= x_1$ on the head-water side, and $= x_2$ on the tail-water side, the resultant pressure on the dF is $\gamma dF(x_1 - x_2) = \gamma h dF$, in which h is the difference of level between head and tail water. That is, the resultant pressures on the equal dF's are *equal*, and hence form a system of equal parallel forces distributed over the plate in the same manner as the weights of the corresponding portions of the plate; therefore their single resultant acts through the centre of gravity of the plate; Q. E. D. This single resultant $= \int \gamma h dF = \gamma h \int dF = Fh\gamma$.

EXAMPLE.—Fig. 494. The resultant pressure on a circular disk ab of radius $= 8$ inches, (in the vertical partition OK,) which has its centre of gravity 3 ft. below the tail-water surface, with $h = 2$ ft., is (ft., lb., sec.)

$$R = Fh\gamma = \pi r^2 h\gamma$$

$$= \pi\, 8^2 \times 24 \times \frac{62.5}{1728} = 174.6 \text{ lbs.},$$



FIG. 494.

and is applied through the *centre of gravity* of the circle. *Evidently R is the same for any depth below the tail-water surface, so long as $h = 2$ ft.* [Let the student find a graphic proof of this statement.]

444. Liquid Pressure on Curved Surfaces.—If the rigid surface is curved, the pressures on the individual dF's, or elements of area, do not form a system of parallel forces, and the single resultant (if one is obtainable) is not equal to their sum. In

general, the system is not equivalent to a single force, but can always be reduced to two forces (§ 38) the point of application of *one of which* is arbitrary (the arbitrary origin of § 38) and its amount $= \sqrt{(\Sigma X)^2 + (\Sigma Y)^2 + (\Sigma Z)^2}$.

A single **Example** will be given ; that of a thin rigid shell having the shape of the curved surface of a right cone, Fig. 495, its altitude being h and radius of base $= r$. It has no bottom, is placed on a smooth horizontal table, vertex up, and is filled with water through a small hole in the apex O, which is left open (to admit atmospheric pressure). What load, besides its own weight G', must be placed upon it to prevent the water from lifting it and escaping under the edge A ? The pressure on each dF of the inner curved surface is $z\gamma dF$ and is normal to the surface. Its vertical compon. is $z\gamma dF \sin\alpha$, and horizontal compon. $= z\gamma dF \cos\alpha$. The dF's have all the same α, but different z's (or heads of water). The lifting tendency of the water on the thin shell is due to the vertical components forming a system of $\parallel$ forces, while the horizontal components, radiating symmetrically from the axis of the cone, neutralize each other. Hence the resultant lifting force is



FIG. 495.

$$V = \Sigma(\text{vert. comps.}) = \gamma \sin\alpha \int z dF = \gamma \sin\alpha \, F\bar{z}\,; \quad (1)$$

where $F =$ total area of curved surface, and $\bar{z} =$ the "head of water" of its centre of gravity. Eq. (1) may also be written thus:

$$V = \gamma F_b \bar{z}\,; \quad \ldots\ldots\ldots \quad (2)$$

in which $F_b = F \sin\alpha =$ area of the circular base $=$ area of the *projection of the curved surface upon a plane* $\perp$ to the vertical, i.e., upon a horizontal plane. Hence we may write

$$V = \tfrac{2}{3}\gamma\pi r^2 h, \quad \ldots\ldots\ldots \quad (3)$$

since $\bar{z} = \frac{2}{3}h$, being the z of the centre of gravity of the curved

surface *and not that of the base.* γ = heaviness of water. If G' = weight of the shell and is $< V$, an additional load of $V - G'$ will be needed to prevent the lifting. If the shell has a bottom of weight $= G''$, forming a base for the cone and rigidly attached to it, we find that the vertical forces acting on the whole rigid body, base and all, are: V upward; G' and G'' downward; and the liquid pressure on the base, viz., $V' = \pi r^2 h\gamma$ (§ 428*a*) also downward. Hence the resultant vertical force to be counteracted by the table is downward, and

$$= G' + G'' + V' - V, \text{ which} = G' + G'' + \tfrac{1}{3}\pi r^2 h\gamma\,; \quad (4)$$

i.e., the total weight of the rigid vessel and the water in it, as we know, of course, in advance.

CHAPTER III.

EARTH PRESSURE AND RETAINING WALLS.

[NOTE.—This chapter was outlined and written mainly by Prof. C. L. Crandall, and is here incorporated with his permission. The theory of earth pressure is arranged from Baumeister.]

445. Angle of Repose.—Granular materials, like dry sand, loose earth, soil, gravel, pease, shot, etc., on account of the friction between the component grains, occupy an intermediate position between liquids and large rigid bodies. When heaped up, the side of the mass cannot be made to stand at an inclination with the horizontal greater than a definite angle called the *angle of natural slope*, or *angle of repose*, different for each material; so that if the side of the mass is to be retained permanently at some greater angle, a *Retaining Wall* (or "*Revetment Wall*," in military parlance) becomes necessary to support it. If the material is somewhat moist it may be made to stand alone at an inclination greater than that of the natural slope, on account of the cohesion thus produced, but only as long as the degree of moisture remains; while if much water is present, it assumes the consistency of mud and may require a much thicker wall, if it is to be supported laterally, than if dry.

In dealing with earth to be supported by a retaining wall, we consider the former to have lost any original cohesion which may have existed among its particles, or that it will eventually lose it through the action of the weather; and hence treat it as a granular material.

A few approximate values of the angle of natural slope are

given below, being taken from Fanning, p. 345; see reference on p. 538 of this work.

Material.	Angle of Repose.	Coefficient of Friction.	Ratio of Slope.
			Horiz. to vert.
Dry sand, fine	28°	.532	1.88 to 1
" " coarse	30°	.577	1.73 " 1
Damp clay	45°	1.000	1.00 " 1
Wet clay	15°	.268	3.73 " 1
Clayey gravel	45°	1.000	1.00 " 1
Shingle	42°	.900	1.11 " 1
Gravel	38°	.781	1.28 " 1
Firm loam	36°	.727	1.38 " 1
Vegetable soil	35°	.700	1.43 " 1
Peat	20°	.364	2.75 " 1

The angle of repose, or natural slope, is also, evidently, the angle of friction between two masses of the same granular material.

446. Earth Pressure, and Wedge of Maximum Thrust.—Fig. 496. Let AB be a retaining wall, having a plane face AB in contact with a mass of earth ABD, both wall and earth being of indefinite extent ⊣ to the paper.

Let AD be the natural slope of the earth, making an angle β with the vertical (β is the complement of the angle of repose; see preceding table). Since AB, making an angle α with the vertical, is more nearly vertical than AD, the retaining wall is necessary, to keep the mass ABD in the position shown. The profile BCD may be of *any form* in this general discussion. Suppose the wall to be on the point of giving way; then the following motions are impending:

1st. Sliding is impending between some portion $ABC'A$ of the mass of earth and the remainder $C'AD$, the *surface of rupture* AC' (C' not shown in figure because not found yet, but lying somewhere on the profile $BCID$) being assumed plane, and making some angle ϕ' (to be determined) with the vertical. At this instant the resultant pressure N' of $AC'D$ on the plane AC' of the mass ABC' (a wedge) must *make an angle* $= \beta$ ($=$ comp. of angle of friction) with AC' on the upper side.

2d. A downward sliding of the mass ABC' along the back face AB of the wall. That is, the resultant pressure P' of the wall against the mass BAC' at this instant *makes an angle*



FIG. 496.

θ (= complement of angle of friction between the earth and wall) with the plane AB *and on the upper side.* The weight of the wedge of earth BAC' will be called G', and we desire to find the pressure P' against the wall.

Let BAC be a wedge (of the earth-mass), in which AC makes *any* angle ϕ with AV, and suppose *it* to be on the point of moving down and forcing out the wall; thus encountering friction both on the plane AC and the plane AB. Then the forces acting on it are three, acting in known directions; viz.: G, its own weight, vertical; N, the resultant pressure of the earth below it, making an angle β with AC on upper side; and P, the resultant pressure of the wall, at angle θ with AB (see Fig. 496 for positions of N and P). If now we express the force P in terms of ϕ and other quantities, and find that value ϕ', of ϕ, for which P is a maximum, we thereby determine the "*wedge of maximum thrust*," $ABC'A$; while this maximum thrust, P', is the force which the wall must be designed to withstand. [If the wall is overturned, the earth will sink with it until this part of its surface gradually assumes the natural slope.]

Let G = weight of prism of base ABC, and altitude = unity ⊥ to paper; then $G = \gamma \times$ area ABC, where $\gamma =$ "heaviness" = wgt. per cub. unit, of earth. Now P, G, and N balance; therefore, in triangle abc, if ab and ac are drawn ||

and $= G$ and N respectively, bc is $=$ and $\|$ to P; and from Trigonometry we have

$$P = G\frac{\sin[\beta-\phi]}{\sin[\beta+\delta-\phi]}; \quad \ldots \quad (1)$$

in which δ stands for $\alpha + \theta$, for brevity, being the angle which P makes with the vertical. N makes an angle $= \beta - \phi$ with the vertical.

The value, ϕ', of ϕ, which makes P a maximum is found by placing $\frac{dP}{d\phi} = 0$. From eq. (1), remembering that G is a function of ϕ, and that β and δ are constants, we have

$$\frac{dP}{d\phi} = \frac{\sin(\beta+\delta-\phi)\left[\frac{dG}{d\phi}\sin(\beta-\phi) - G\cos(\beta-\phi)\right] + G\sin(\beta-\phi)\cos(\beta+\delta-\phi)}{\sin^2[\beta+\delta-\phi]}.$$

For P to be a maximum we must put

$$\textit{numerator of above} = 0. \quad \ldots \quad (a)$$

To find a geometrical equivalent of $\frac{dG}{d\phi}$, denote $\overline{AC}$ by L, and draw AE, making an angle $= d\phi$ with AC. Now the area $ACI = \overline{AI} \times \frac{1}{2}\overline{CE} = (L + dL)\frac{1}{2}Ld\phi = \frac{1}{2}L^2d\phi$ . . . (neglecting infinitesimal of 2d order). Now

$dG = \gamma \times$ area $ACI \times$ unity; $\therefore \frac{dG}{d\phi} = \frac{1}{2}\gamma L^2$; $\therefore$ (a) becomes

$$\sin(\beta+\delta-\phi)\tfrac{1}{2}\gamma L^2\sin(\beta-\phi) - \sin(\beta+\delta-\phi)G\cos(\beta-\phi)$$

$$+ G\sin(\beta-\phi)\cos(\beta+\delta-\phi) = 0;$$

i.e., $G =$

$$\frac{\frac{1}{2}\gamma L^2\sin(\beta-\phi)\sin(\beta+\delta-\phi)}{\sin(\beta+\delta-\phi)\cos(\beta-\phi) - \cos(\beta+\delta-\phi)\sin(\beta-\phi)}$$

when P is a maximum; and hence, calling G' and ϕ' and L' the values of G, ϕ, and L, for max. P, we have

$$G' = \tfrac{1}{2}\gamma L'^2 \frac{\sin(\beta - \phi')\sin(\beta + \delta - \phi')}{\sin \delta}, \quad . \quad . \quad (2)$$

and therefore from (1) P max. itself is

$$P' = \tfrac{1}{2}\gamma L'^2 . \frac{\sin^2(\beta - \phi')}{\sin \delta}. \quad . \quad . \quad . \quad . \quad (3)$$

447. Geometric Interpretation and Construction.—If in Fig. 496 we draw CF, making angle δ with AD, C being any point on the ground surface BD, we have

$$\overline{CF} = L \frac{\sin(\beta - \phi)}{\sin \delta}.$$

Drop a perpendicular FH from F to AC, and we shall have

$$\overline{FH} = \overline{CF} . \sin(\beta + \delta - \phi), = L . \frac{\sin(\beta - \phi)\sin(\beta + \delta - \phi)}{\sin \delta}.$$

From this it follows that the weight of prism of base ACF and unit height

$$= \tfrac{1}{2}\gamma L . \overline{FH} = \tfrac{1}{2}\gamma L^2 . \frac{\sin(\beta - \phi)\sin(\beta + \delta - \phi)}{\sin \delta}. \quad (4)$$

When AC (as ϕ varies) assumes the position and value AC', bounding the prism of maximum thrust, Fig. 497. L becomes $= L'$, and $\phi = \phi'$; and eq. (4) gives the weight of the prism $AC'F'$. This weight is seen to be equal to that of the prism (or wedge) of maximum thrust ABC', by comparing eq. (4) with eq. (2); that is, *AC' bisects the area $ABC'F'$, and hence may be determined by fixing such a point C', on the upper profile BD, as to make the triangular area $AC'F'$ equal to the sectional area of the wedge $BC'A$*; $C'F'$ being drawn at an angle $= \delta$ with AD.

This holds for any form of ground surface BD, or any

values of the constants β, α, or θ. C' is best found graphically by trial, in dealing with an irregular profile BD.



FIG. 497.

Having found $AC' = L'$, P' can be found from (3), or *graphically* as follows: (Fig. 497) With F' as a centre and radius $= C'F'$, describe an arc cutting AD in J', and join $C'J'$. The weight of prism with base $C'J'F'$ and unit height will $= P'$. For that prism has a weight

$$= \tfrac{1}{2}\gamma \,.\, \overline{F'J'} \,.\, \overline{C'H'};$$

but $$\overline{F'J'} = \overline{F'C'} = \frac{L' \sin(\beta - \phi')}{\sin \delta},$$

and $$\overline{C'H'} = L' \sin(\beta - \phi');$$

$\therefore$ weight of prism $C'J'F = \tfrac{1}{2}\gamma L'^2 \dfrac{\sin^2(\beta - \phi')}{\sin \delta}; = P'.$

[See eq. (3).]

448. Point of Application of the Resultant Earth Thrust.— This thrust (called P' throughout this chapter *except in the present paragraph*) is now known in magnitude and direction, but not in position; i.e., we must still determine its line of action, as follows:

Divide AB into a number of equal parts, ab, bc, cd, etc.; see Fig. 498. Treat ab as a small retaining wall, and find the magnitude P' of the thrust against it by § 447; treat ac similarly, thus finding the thrust, P'', against it; then ad, ae, etc., the thrusts against them being found to be P''', P^{IV}, etc.; and so on. Now the pressure

P' on ab is applied nearly at middle of ab,
$P'' - P'$ " " " " bc,
$P''' - P''$ " " " " cd,

and so on. Erect perpendiculars at the middle points of ab, bc, cd, etc., equal respectively to P', $P'' - P'$, $P''' - P''$, etc., and join the ends of the perpendiculars. The perpendicular through the centre of gravity of the area so formed (Fig. 498) will give, on AB, the required point of application of the thrust or earth pressure on AB, and this, with the direction and magnitude already found in § 447, will completely determine the thrust against the wall AB.



FIG. 498.

449. Special Law of Loading.—If the material to be retained consists of loose stone, masses of masonry, buildings, or even moving loads, as in the case of a wharf or roadway, each can be replaced by the same *weight* of earth or other material which will render the bank homogeneous, situated on the *same verticals*, and the profile thus reduced can be treated by §§ 447 and 448.

Should the solid mass extend below the plane of rupture, AC', and the plane of natural slope, it will become a retaining wall for the material beyond, if strong enough to act as such (limiting the profile $ABCD$ of Fig. 496 to the front of the mass, or to the front and line of rupture for maximum thrust above it, if it does not reach the surface); if not strong enough, or if it does not reach below the plane of natural slope, its presence is better ignored, probably, except that the increased weight must be considered.

The spandrel wall of an arch may present two of these special cases; i.e., the profile may be enlarged to include a moving load, while it may be limited at the back by the other spandrel.

If the earth profile starts at the front edge of the top of wall, instead of from the back as at B, Fig. 496, eq. (3) would only apply to the portion behind AB prolonged, leaving the part on the wall (top) to be treated as a part of the wall to aid in resisting the thrust.

If the wall is stepped in from the footings, or foundation

courses, probably the weak section will be just above them; if stepped at intervals up the back of the wall, the surface of separation between the wall and filling, if it is plane, will probably pass through the first step and incline forward as much as possible without cutting the wall.

450. Straight Earth-profile.—The general case can be simplified as follows (the earth-profile BD being straight, at angle $= \zeta$ with vertical, $= DET$): Since the triangles ABC' and



FIG. 499.

$C'AF'$ are equal, from § 447, and AC' is common, therefore $BS = F'H$ (both being drawn ⌐ to AC'). Draw AE and BM ∥ to $F'C'$ (i.e., at angle δ with AD), cutting DB, prolonged, in E. We have

$$\frac{\overline{DE}}{\overline{C'E}} = \frac{\overline{EA}}{\overline{EA} - \overline{C'F'}}, \text{ and } \frac{\overline{C'E}}{\overline{BE}} = \frac{\overline{EA}}{\overline{EA} - BM}.$$

But $C'F' = BM$ (since $\overline{BS} = \overline{H'F'}$);

therefore $$\frac{\overline{DE}}{\overline{C'E}} = \frac{\overline{C'E}}{\overline{BE}}; \text{ i.e., } \overline{DE} \cdot \overline{BE} = \overline{C'E}^2,$$

which justifies the following construction for locating the desired point C' on BD, and thus finding $\overline{AC'} = L'$ and the angle ϕ': Describe a circle on ED as a diameter, and draw

$BX \perp$ to BD, thus fixing X in the curve. With centre E describe a circular arc through X, cutting BD in C', required.

Having $\overline{AC'}$ (i.e., L'), ϕ' is known; hence from eq. (3) we obtain the earth thrust or pressure P': or, with F' as centre and radius $= C'F'$, describe arc $C'J'$; then the triangle $C'F'J'$ is the base of a prism of unity height whose weight $= P'$ (as in § 447).

Centre of Pressure.—Applying the method of § 448, Fig. 498, to this case, we find that the successive L''s are proportional to the depths ab, ac, ad, etc., and that the successive I''s are proportional [see (3)] to the squares of the depths; hence the area in Fig. 498 must be triangular in this case, and the point of application of the resultant pressure on AB is *one third* of AB from A: just as with liquid pressure.

451. Resistance of Retaining Walls.—(Fig. 500.) Knowing the height of the wall we can find its weight, $= G_1$, for an assumed thickness, and unity width $\perp$ to paper. The resultant of G_1, acting through the centre of gravity of wall, and P', the thrust of the embankment, in its proper line of action, should cut the base AV within the middle third and make an angle with the normal (to the base) less than the angle of friction.



FIG. 500.

For the straight wall and straight earth-profile of Fig. 499 and § 450, the length L', $= AC'$, can be expressed in terms of the (vertical) height, h, of wall, thus:

$$\overline{AB} = \frac{h}{\cos \alpha},$$

and $$L' = \overline{AC'} = \overline{AB} \cdot \frac{\sin(\zeta - \alpha)}{\sin(\zeta - \phi')} = \frac{h}{\cos \alpha} \cdot \frac{\sin(\zeta - \alpha)}{\sin(\zeta - \phi')};$$

$\therefore$ eq. (3) becomes

$$P' = \tfrac{1}{2}\gamma \frac{h^2}{\cos^2 \alpha} \cdot \frac{\sin^2(\beta - \phi') \sin^2(\zeta - \alpha)}{\sin \delta \sin^2(\zeta - \phi')} = \tfrac{1}{2}\gamma \frac{h^2}{\cos^2 \alpha} \cdot A. \quad (5)$$

[A representing the large fraction for brevity.]

This equation will require, for a wall of rectangular section, that the thickness, d, increase as h, in order that its weight may increase as h^2 (i.e., as P') and that its resisting moment may increase with the overturning moment.

By this equality of moments is meant that $P' a = G_1 b$; where a and b are the respective lever-arms of the two forces about the front edge of the middle third. (AB is the back of the wall.) In other words, their resultant will pass through this point.

The following table is computed on the basis just mentioned, viz., *that the resultant of P' and G shall pass through the front edge of the midde third.*

The symbols of eq. (5) and the table are all shown in Fig. 499, except γ, θ, and δ. γ = weight of a cubic foot of earth, here assumed = $\frac{2}{3}$ that of masonry (e.g., if earth weighs 100 lbs., masonry is assumed to weigh 150 lbs. per cubic foot); θ = angle which the thrust P' makes with the back of the wall; and $\delta = \alpha + \theta$, $= \theta$ in this case as *the wall is vertical*, or $\alpha = 0$. d is the proper safe thickness to be given to the wall, of rectangular section, to prevent overturning, as stated above; h is the altitude, and A is the fraction shown in eq. (5).

Whether the wall is safe against sliding on its base, and whether a safe compression per unit area is exceeded on the front edge of the base, are matters for separate consideration. The latter will seldom govern with ordinary retaining walls.

$\alpha = 0$; i.e., wall is vertical; also density of wall = $\frac{2}{3}$ that of the earth.

		I. $\zeta = 90°$ $\theta = 90°$			II. $\zeta = 90°$ $\theta = \beta$			III. $\zeta = \beta$ $\theta = \beta$.		
tan β	β	ϕ'	A	d	ϕ'	A	d	ϕ'	A	d
1.0	45°	22½°	.17	.34h	26°	.18	.22h	45°	.71	.33h
1.5	56½°	28°	.29	.44h	33°	.26	.30h	56°	.83	.43h
2.0	63½°	31½°	.38	.51h	38°	.33	.36h	63°	.89	.51h
4.0	76°	38°	.61	.64h	45°	.54	.50h	76°	.97	.65h
Infinity	90°	45°	1.00	.82h	90°	1.00	.82h	90°	1.00	.82h

In Case I of table, since $\alpha = 0$, $\theta = 90°$ and $\zeta = 90°$; $\therefore \delta = 90°$, and hence $C'F'$ of Fig. 499 is $\perp$ to AD, so that

(since the area of $\triangle ABC' = \triangle AC'F'$) ϕ' must $= \frac{1}{2}\beta$. These values, in (5), give

$$P' = \tfrac{1}{2}\gamma h^2 \tan^2 \tfrac{1}{2}\beta; \text{ i.e., } A = \tan^2 \tfrac{1}{2}\beta. \quad . \quad . \quad . \quad (6)$$

In Case II, since $\zeta = 90°$, $\alpha = 0$ and $\theta = \beta$, $\therefore$ $\delta = \beta$; and (5) reduces to

$$P' = \tfrac{1}{2}\gamma h^2 \frac{\sin^2(\beta - \phi')}{\sin \beta \cos^2 \phi'}; \text{ i.e., } A = \frac{\sin^2(\beta - \phi')}{\sin \beta \cos^2 \phi'}. \quad . \quad (7)$$

In Case III, $\zeta = \beta$ and BD will be $\parallel$ to AD, D being at infinity. See Fig. 501. Through B draw $BH \urcorner$ to AD, and BF'' making angle δ with AD. C' is now to be located on BD, so as to make (area of) $\triangle ABC' =$ (area of) $\triangle AC'F'$ (according to § 447), the angle $C'F'A$ being $= \delta = \alpha + \theta$; $= \theta$, in this case, and hence also $= \beta$. Conceive B and F' to be joined.



FIG. 501.

Now $\triangle AC'F' = \triangle ABF'' + \triangle BF'F''$.

But $\triangle ABC' = \triangle BF'F''$ (equal bases and altitudes).

Hence $\triangle ABC'$ *cannot* $= \triangle AC'F'$ *unless* C' *is moved out to infinity;* and then ϕ' becomes $= \beta$, and eq. (5) reduces to

$$P' = \tfrac{1}{2}\gamma h^2 \sin \beta; \quad \text{i.e., } A = \sin \beta. \quad . \quad . \quad . \quad (8)$$

[Increasing α from zero will decrease the thickness d; i.e., inclining the wall inwards will decrease the required thickness, but diminish the frictional stability at the base, unless the latter be $\urcorner$ to AB. The back of the wall is frequently inclined outwards, making the section a trapezoid, to increase the frictional stability at the base when necessary, as with timber walls supporting water.]

452. Practical Considerations. — An examination of the values of A and d in the table of § 451 will show that in supporting quicksand and many kinds of clay which are almost fluid under the influence of water, it is important to know what kind of drainage can be secured, for on that will depend the thickness of the wall. With well compacted material free from water-bearing strata, an assumed natural slope of $1\frac{1}{2}$ to 1 (i.e., $1\frac{1}{2}$ hor. to 1 vert.) will be safe; the actual pressure below the effect of frost and surface water will be that due to a much steeper slope on account of *cohesion* (neglected in this theory).

The thrust from freshly placed material can be reduced by depositing it in layers sloping back from the wall. If it is not so placed, however, the natural slope will seldom be flatter than $1\frac{1}{2}$ to 1 unless reduced by water. In supporting material which contains water-bearing strata sloping toward the wall and overlain by strata which are liable to become semi-fluid and slippery, the thrust may exceed that due to semi-fluid material on account of the surcharge. If these strata are under the wall and cannot be reached by the foundation, or if resistance to sliding cannot be obtained from the material in front by sheet-piling, no amount of masonry can give security.

Water at the back of the wall will, by freezing, cause the material to exert an indefinitely great pressure, besides disintegrating the wall itself. If there is danger of its accumulation, drainage should be provided by a layer of loose stone at the back leading to "weep-holes" through the wall.

A friction-angle at the back of the wall equal to that of the filling should always be realized by making the back rough by steps, or projecting stones or bricks. Its effect on the required thickness is too great to be economically ignored.

The resistance to slipping at the base can be increased, when necessary, by inclining the foundation inwards; by stepping or sloping the back of the wall so as to add to its effective weight or incline the thrust more nearly to the vertical; by sheet-piling in front of the foundation, thus gaining the resistance offered by the piles to lateral motion; by deeper foundations, gaining the resistance of the earth in front of the wall.

The coefficient of friction on the base ranges, according to Trautwine, from 0.20 to 0.30 on wet clay;
" .50 to .66 " dry earth;
" .66 to .75 " sand or gravel;
" .60 on a dry wooden platform; to .75 on a wet one.

If the wall is partially submerged, the buoyant effort should be subtracted from G_1, the weight of wall.

453. Results of Experience.—(Trautwine.) In railroad practice, a vertical wall of rectangular section, sustaining sand, gravel, or earth, level with the top [p. 682 of Civ. Eng. Pocket Book] and loosely deposited, as when dumped from carts, cars, etc., should have a thickness d, as follows:

If of cut stone, or of first-class large ranged rubble, in mortar. . . . $d = .35h$
" good common scabbled mortar-rubble, or brick. . . . . $d = .40h$
" well scabbled dry rubble . . . . . $d = .50h$

Where h includes the total height, or about 3 ft. of foundations.

(*a*) For the best masonry of its class h may be taken from the top of the foundation in front.

(*b*) A mixture of sand or earth, with a large proportion of round boulders or cobbles, will weigh more than the backing assumed above; requiring d to be increased from one eighth to one sixth part.

(*c*) The wall will be stronger by inclining the back inwards, especially if of dry masonry, or if the backing is put in place before the mortar has set.

(*d*) The back of the wall should be left rough to increase friction.

(*e*) Where deep freezing occurs, the back should slope outward for 3 or 4 feet below the top and be left smooth.

(*f*) When a wall is too thin, it will generally fail by bulging outward at about one third the height. The failure is usually gradual and may take years.

(*g*) *Counterforts*, or buttresses at the back of the wall, usually of rectangular section, may be regarded as a waste of masonry, although considerably used in Europe; the bond will

seldom hold them to the wall. Buttresses *in front* add to the strength, but are not common, on account of expense.

(*h*) *Land-ties* of iron or wood, tying the wall to anchors imbedded below the line of natural slope, are sometimes used to increase stability.

(*i*) Walls with curved cross-sections are not recommended.

454. Conclusions of Mr. B. Baker.—("Actual Lateral Pressure of Earthwork.") Experience has shown that $d = 0.25h$, with batter of 1 to 2 inches per foot on face, is sufficient when backing and foundation are both favorable; also that under *no* ordinary conditions of surcharge or heavy backing, with solid foundation, is it necessary for d to be greater than $0.50h$.

Mr. Baker's own rule is to make $d = 0.33h$ at the top of the footings, with a face batter of $1\frac{1}{2}$ inches per foot, in ground of average character; and, if any material is taken out to form a face-panel, three fourths of it is put back in the form of a pilaster. The object of the batter, and of the panel if used, is to distribute the pressure better on the foundation. All the walls of the "District Railway" (London) were designed on this basis, and there has not been a single instance of settlement, of overturning, or of sliding forward.

455. Experiments with Models.—Accounts of experiments with apparatus on a small scale, with sand, etc., may be found in vol. LXXI of Proceedings of Institution of Civil Engineers, London, England (p. 350); also in vol. II of the "Annales des Ponts et Chaussées" for 1885 (p. 788).

The results of these experiments, and the results of experience given in §§ 453 and 454, when compared with the table of p. 581, indicate a fairly close agreement between practice and theory. This agreement is believed to be close enough so that the general method of §§ 447 and 451, with the table of p. 581, can be relied upon in practice. The greatest value of this method will, of course, be for cases of exceptional loading, inclined walls, etc., where the results of experience do not furnish so valuable a guide.

Note.—A recent and valuable book in this connection is *The Design of Walls, Bins, and Grain Elevators*, by Milo S. Ketchum. Published by John Wiley & Sons, New York, 1907.

CHAPTER IV.

HYDROSTATICS (*Continued*)—IMMERSION AND FLOTATION.

456. Rigid Body Immersed in a Liquid. Buoyant Effort.—If any portion of a body of homogeneous liquid at rest be conceived to become rigid without alteration of shape or bulk, it would evidently still remain at rest; i.e., its weight, applied at its centre of gravity, would be balanced by the pressures, on its bounding surfaces, of the contiguous portions of the liquid; hence,

If a rigid body or solid is immersed in a liquid, both being at rest, the resultant action upon it of the surrounding liquid (or fluid) is a vertical upward force called the "buoyant effort," equal in amount to the weight of liquid displaced, and acting through the centre of gravity of the volume (considered as homogeneous) of displacement (now occupied by the solid). This point is called *the centre of buoyancy*, and is sometimes spoken of as *the centre of gravity of the displaced water*. If $V' =$ the volume of displacement, and $\gamma =$ heaviness of the liquid, then the

$$\textit{buoyant effort} = V'\gamma. \quad . \quad . \quad . \quad . \quad . \quad (1)$$

(By "volume of displacement" is meant, of course, the volume of liquid actually displaced when the body is immersed.)

If the weight G' of the solid is not equal to the buoyant effort, or if its centre of gravity does not lie in the same vertical as the centre of buoyancy, the two forces form an unbalanced system and motion begins. But as a consequence of this very motion the action of the liquid is modified in a manner dependent on the shape and kind of motion of the body.

Problems in this chapter are restricted to cases of rest, i.e., balanced forces.

Suppose $G' = V'\gamma$; then,

If the centre of gravity lies in the same vertical line as the centre of buoyancy and *underneath* the latter, the equilibrium is *stable;* i.e., after a slight angular disturbance the body returns to its original position (after several oscillations); while if *above* the latter, the equilibrium is *unstable.* If they *coincide*, as when the solid is homogeneous (but not hollow), and of the same heaviness (§ 7) as the liquid, the equilibrium is *indifferent,* i.e., possible in any position of the body.

The following is interesting in this connection:

In an account of the new British submarine boat "Nautilus," a writer in *Chambers's Journal* remarked [1887]: "At each side of the vessel are four port-holes, into which fit cylinders two feet in diameter. When these cylinders are projected outwards, as they can be by suitable gearing, the displacement of the boat is so much increased that the vessel rises to the surface; but when the cylinders are withdrawn into their sockets, it will sink."

As another case in point, large water-tight canvas "air-bags" have recently been used for raising sunken ships. They are sunk in a collapsed state, attached by divers to the submerged vessel, and then inflated with air from pumps above, which of course largely augments their displacement while adding no appreciable weight.

457. Examples of Immersion.—Fig. 502. At (a) is an example of stable equilibrium, the centre of buoyancy B being above the centre of gravity C, and the buoyant effort $V'\gamma = G' =$ the weight of the solid; at (a'), conversely, we have unstable equilibrium, with $V'\gamma$ still $= G'$. At (b) the buoyant effort $V'\gamma$ is $> G'$, and



FIG. 502.

to preserve equilibrium the body is attached by a cord to the bottom of the vessel. The tension in this cord is

$$S_b = V'\gamma - G'. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

At (c) $V'\gamma$ is $< G'$, and the cord must be attached to a support above, and its tension is

$$S_c = G' - V'\gamma. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

If in eq. (2) [(c) in figure] we call S_c the *apparent weight* of the immersed body, and measure it by a spring- or beam-balance, we may say that

The apparent weight of a solid totally immersed in a liquid equals its real weight diminished by that of the amount of liquid displaced; in other words, *the loss of weight = the weight of displaced liquid.*

EXAMPLE 1.—How great a mass (not hollow) of cast-iron can be supported in water by a wrought-iron cylinder weighing 140 lbs., if the latter contains a vacuous space and displaces 3 cub. feet of water, both bodies being completely immersed? [Ft., lb., sec.]

The buoyant effort on the cylinder is

$$V'\gamma = 3 \times 62.5 = 187.5 \text{ lbs.},$$

leaving a residue of 47.5 lbs. upward force to buoy the cast-iron, whose volume V'' is unknown, while its heaviness (§ 7) is $\gamma'' = 450$ lbs. per cub. foot. The direct buoyant effort of the water on the cast-iron is $V''\gamma = [V'' \times 62.5]$ lbs., and the problem requires that this force $+ 47.5$ lbs. shall $= V''\gamma'' =$ the weight G'' of the cast-iron;

$$\therefore \quad V'' \times 62.5 + 47.5 = V'' \times 450;$$

$\therefore$ $V'' = 0.12$ cub. ft., while $0.12 \times 450 = 54$ lbs. of cast-iron. *Ans.*

EXAMPLE 2.—Required the volume V', and heaviness γ', of a *homogeneous* solid which weighs 6 lbs. out of water and 4 lbs. when immersed (*apparent weight*) (ft., lb., sec).

From eq. (2), $4 = 6 - V' \times 62.5$; $\therefore\ V' = 0.032$ cub. feet;

$$\therefore\ \gamma' = G' \div V' = 6 \div 0.032 = 187.5 \text{ lbs. per cub. ft.},$$

and the ratio of γ' to γ is $187.5 : 62.5 = 3.0$ (abstract number); i.e., the substance of this solid is three times as dense, or three times as heavy, as water. [The buoyant effort of the air has been neglected in giving the true weight as 6 lbs.]

458. Specific Gravity.—By *specific gravity* is meant the ratio of the heaviness of a given homogeneous substance to that of a standard homogeneous substance; in other words, the ratio of the weight of a certain volume of the substance to the weight of an *equal* volume of the standard substance. Distilled water at the temperature of maximum density (4° Centigrade) under a pressure of 14.7 lbs. per sq. inch is sometimes taken as the standard substance, more frequently, however, at 62° Fahrenheit (16°.6 Centigrade). Water, then, being the standard substance, the numerical example last given illustrates a common method of determining experimentally the specific gravity of a homogeneous solid substance, the value there obtained being 3. The symbol σ will be used to denote specific gravity, which is evidently an abstract number. The standard substance should always be mentioned, and its heaviness γ; then the heaviness of a substance whose specific gravity is σ is

$$\gamma' = \sigma\gamma, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

and the weight G' of any volume V' of the substance may be written

$$G' = V'\gamma' = V'\sigma\gamma. \quad . \quad . \quad . \quad . \quad . \quad (2)$$

Evidently a knowledge of the value of γ' dispenses with the use of σ, though when the latter can be introduced into problems involving the buoyant effort of a liquid the criterion as to whether a *homogeneous* solid will sink or rise, when immersed in the *standard* liquid, is more easily applied, thus: Being immersed, the volume V' of the body = that, V, of displaced liquid. Hence,

if G' is $> V'\gamma$, i.e., if $V'\gamma'$ is $> V'\gamma$, or $\sigma > 1$, it sinks;

while if G' is $< V'\gamma$, ... or $\sigma < 1$, it rises;

i.e., according as the weight G' is $>$ or $<$ than the buoyant effort.

Other methods of determining the specific gravity of solids, liquids, and gases are given in works on Physics.

459. Equilibrium of Flotation.—In case the weight G' of an immersed solid is less than the buoyant effort $V'\gamma$ (where V' is the volume of displacement, and γ the heaviness of liquid) the body rises to the surface, and after a series of oscillations comes to rest in such a position, Fig. 503, that its centre of gravity C and the centre of buoyancy B (the new B, belonging to the new volume of displacement, which is limited above by the horizontal plane of the free surface of the liquid) are in the same vertical (called the axis of flotation, or line of support), and that the volume of displacement has diminished to such a new value V, that

$$V\gamma = G'. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

In the figure, V = vol. AND, below the horizontal plane AN, and the slightest motion of the body *will change the form of this volume*, in general (whereas with complete immersion the volume of displacement remains constant). For stable equilibrium it is not essential in every case that C (centre of gravity of body) should be below B (the centre of buoyancy) as with complete immersion, since if the solid is turned, B may change its position in the body, as the form of the volume AND changes.



FIG. 503.

There is now no definite relation between the volume of displacement V and that of the body, V', unless the latter is *homogeneous*, and then for G' we may write $V'\gamma'$, i.e.

$$V'\gamma' = V\gamma \text{ (for a homogeneous solid)}; \quad . \quad . \quad (2)$$

or, *the volumes are inversely proportional to the heavinesses.*

The buoyant effort of the air on the portion ANE may be neglected in most practical cases, as being insignificant.

If the solid is *hollow*, the position of its centre of gravity G may be easily varied (by shifting ballast, e.g.) within certain limits, but that of the centre of buoyancy B depends only on the geometrical form of the volume of displacement AND, below the horizontal plane AN.

EXAMPLE.—(Ft., lb., sec.) Will a solid weighing $G' = 400$ lbs., and having a volume $V' = 8$ cub. feet, without hollows or recesses, float in water? To obtain a buoyant effort of 400 lbs., we need a volume of displacement, see eq. (1), of

$$V = \frac{G'}{\gamma} = \frac{400}{62.5} = \text{only } 6.4 \text{ cub. ft.}$$

Hence the solid will float with $8 - 6.4$, or 1.6, cub. ft. projecting above the water level.

Query: A vessel contains water, reaching to its brim, and also a piece of ice which floats without touching the vessel. When the ice melts will the water overflow?

460. The Hydrometer is a floating instrument for determining the relative heavinesses of liquids. Fig. 504 shows a simple form, consisting of a bulb and a cylindrical stem of glass, so designed and weighted as to float upright in all liquids whose heavinesses it is to compare. Let F denote the uniform sectional area of the stem (a circle), and suppose that when floating in water (whose heaviness $= \gamma$) the water surface marks a point A on the stem; and that when floating in another liquid, say petroleum, whose heaviness, $= \gamma_p$, we wish to determine, it floats at a greater depth, the liquid surface now marking A' on the stem, a height $= x$ above A. G' is the same in both experiments; but while the volume of displacement in water is V, in petroleum it is $V + Fx$. Therefore from eq. (1), § 459;



FIG. 504.

in the water $G' = V\gamma$, ... (1)

and *in the petroleum* $G' = (V + Fx)\gamma_p$; . . (2)

from which, knowing G', F, x, and γ, we find V and γ_p, i.e.,

$$V = \frac{G'}{\gamma} \quad \text{and} \quad \gamma_p = \frac{G'\gamma}{G' + Fx\gamma}. \quad . \ . \ . \quad (3)$$

[N.B.—F is best determined by noting the additional distance, $= l$, through which the instrument sinks in water under an additional load P, *not immersed;* for then

$$G' + P = (V + Fl)\gamma, \text{ or } F = \frac{P}{l\gamma}.]$$

EXAMPLE.—[Using the *inch*, *ounce*, and *second*, in which system $\gamma = 1000 \div 1728 = 0.578$ (§ 409).] With $G' = 3$ ounces, and $F = 0.10$ sq. inch, x being observed, on the graduated stem, to be 5 inches, we have for the petroleum

$$\gamma_p = \frac{3 \times 0.578}{3 + 0.10 \times 5 \times 0.578} = 0.525 \text{ oz. per cubic inch}$$
$$= 56.7 \text{ lbs. per cub. foot.}$$

Temperature influences the heaviness of most liquids to some extent.

In another kind of instrument a scale-pan is fixed to the top of the stem, and the specific gravity computed from the weight necessary to be placed on this pan to cause the hydrometer to sink to the *same* point in *all* liquids for which it is used.

461. Depth of Flotation.—If the weight and external shape of the floating body are known, and the centre of gravity so situated that the position of flotation is known, the *depth of the lowest point below the surface may be determined.*

Case I. *Right prism or cylinder with its axis vertical.*—Fig. 505. (For stability in this position, see § 464*a*.) Let G' = weight of cylinder, F the area of its cross-section (full circle), h' its altitude, and h the unknown depth of flotation (or *draught*); then from eq. (1), § 426,



Fig. 505.

$$G' = Fh\gamma;\ \therefore\ h = \frac{G'}{F\gamma};. \quad (1)$$

in which γ = heaviness of the liquid. If the prism (or cylinder) is *homogeneous* (and then C, at the middle of h', is higher than B) and γ' its heaviness, we then have

$$h = \frac{Fh'\gamma'}{F\gamma} = \frac{\gamma' h'}{\gamma} = \sigma h'; \quad . \ . \ . \ . \quad (2)$$

in which σ = specific gravity of solid referred to the liquid as standard. (See § 458.)

Case II. *Pyramid or cone with axis vertical and vertex down.*—Fig. 506. Let V' = volume of whole pyramid (or cone), and V = volume of displacement. From similar pyramids,



Fig. 506.

$$\frac{V}{V'} = \frac{h^3}{h'^3};\ \therefore\ h = \sqrt[3]{\frac{V}{V'}} \cdot h'.$$

But $G' = V\gamma$; or, $V = \dfrac{G}{\gamma}$; whence

$$h = h' \sqrt[3]{\frac{G'}{V'\gamma}}. \quad . \ . \ . \ . \ . \ . \ . \quad (3)$$

CASE III. *Ditto, but vertex up.*—Fig. 507. Let the notation be as before, for V and V'. The part out of water is a pyramid of volume $= V'' = V' - V$, and is similar to the whole pyramid;



FIG. 507.

$$\therefore\ V' - V : V' :: h''^3 : h'^3.$$

Also, $$V = \frac{G'}{\gamma};$$

$$\therefore\ h'' = h'\sqrt[3]{\frac{V' - V}{V'}} = h'\sqrt[3]{\frac{V'\gamma - G'}{V'\gamma}};$$

$$\therefore, \text{ finally, } h = h'\left[1 - \sqrt[3]{1 - [G' \div V'\gamma]}\right]. \quad . \quad . \quad . \quad (4)$$

CASE IV. *Sphere.*—Fig. 508. The volume immersed is

$$V = \int_{z=0}^{z=h} (\pi x^2)dz = \pi\int_0^h (2rz - z^2)dz = \pi h^2\left[r - \frac{h}{3}\right];$$



FIG. 508.

and hence, since $V\gamma = G' =$ weight of sphere,

$$\pi r h^2 - \frac{\pi h^3}{3} = \frac{G'}{\gamma} \quad . \quad . \quad (5)$$

From which cubic equation h may be obtained by successive trials and approximations.*

[An exact solution of (5) for the unknown h is impossible, as it falls under the irreducible case of Cardan's Rule.]

CASE V. *Right cylinder with axis horizontal.*—Fig. 509.



FIG. 509.

$$\left.\begin{matrix}\text{Vol.}\\ \text{immers.}\end{matrix}\right\} = V = [\text{area of seg. } ADB] \times l$$

$$= (r^2\alpha - \tfrac{1}{2}r^2 \sin 2\alpha)l;$$

hence, since $V = \frac{G'}{\gamma}$,

$$lr^2[\alpha - \tfrac{1}{2}\sin 2\alpha] = \frac{G'}{\gamma}. \quad . \quad . \quad . \quad . \quad . \quad . \quad (6)$$

* See p. 224 of the *Engineering Record* for Feb. 22, 1908, for a diagram to be used in solving this equation.

From this transcendental equation we can obtain α, by trial, in *radians* (see example in § 428), and finally h, since

$$h = r(1 - \cos \alpha). \quad . \quad . \quad . \quad . \quad . \quad . \quad (7)$$

EXAMPLE 1.—A sphere of 40 inches diameter is observed to have a depth of flotation $h = 9$ in. in water. Required its weight G'. From eq. (5) (inch, lb., sec.) we have

$$G' = [62.5 \div 1728]\pi 9^2[20 - \tfrac{1}{3} \times 9] = 156.5 \text{ lbs.}$$

The sphere may be hollow, e.g., of sheet metal loaded with shot; constructed in any way, so long as G' and the volume V of displacement remain unchanged. But if the sphere is *homogeneous, its heaviness* (§ 7) γ' must be

$$= G' \div V' = G' \div \tfrac{4}{3}\pi r^3 = (156.5) \div \tfrac{4}{3}\pi 20^3$$
$$= .00466 \text{ lbs. per cubic inch,}$$

and hence, referred to water, its specific gravity is $\sigma =$ about 0.13.

EXAMPLE 2.—The right cylinder in Fig. 509 is homogeneous and 10 inches in diameter, and has a specific gravity (referred to water) of $\sigma = 0.30$. Required the depth of flotation h.

Its heaviness must be $\gamma' = \sigma\gamma$; hence its weight

$$G' = V'\sigma\gamma = \pi r^2 l \sigma\gamma;$$

hence, from eq. (6),

$$r^2 l[\alpha - \tfrac{1}{2} \sin 2\alpha] = \pi r^2 l\sigma, \ \therefore \ \alpha - \tfrac{1}{2} \sin 2\alpha = \pi\sigma$$

(involving abstract numbers only). Trying $\alpha = 60°$ ($= \frac{1}{3}\pi$ in *radians*), we have

$$\tfrac{1}{3}\pi - \tfrac{1}{2} \sin 120° = 0.614; \text{ whereas } \pi\sigma = .9424$$

For $\alpha = 70°$, $1.2217 - \frac{1}{2} \sin 140° = 0.9003$;
For $\alpha = 71°$, $1.2391 - \frac{1}{2} \sin 142° = 0.9313$;
For $\alpha = 71° 22'$, $1.2455 - \frac{1}{2} \sin 142° 44' = 0.9428$, which may be considered sufficiently close. Now from eq. (7),

$$h = (5 \text{ in.})\ (1 - \cos 71° 22') = 3.40 \text{ in.}—Ans.$$

462. Draught of Ships.—In designing a ship, especially if on a new model, the position of the centre of gravity is found by eq. (3) of § 23 (with weights instead of volumes); i.e., the sum of the products obtained by multiplying the weight of each portion of the hull and cargo by the distance of its centre of gravity from a convenient reference-plane (e.g., the horizontal plane of the keel bottom) is divided by the sum of the weights, and the quotient is the distance of the centre of gravity of the whole from the reference-plane.

Similarly, the distance from another reference-plane is determined. These two co-ordinates and the fact that the centre of gravity lies in the median vertical plane of symmetry of the ship (assuming a symmetrical arrangement of the framework and cargo) fix its location. The total weight, G', equals, of course, the sum of the individual weights just mentioned. The *centre of buoyancy*, for *any assumed draught* and corresponding position of ship, is found by the same method; but more simply, since it is the centre of gravity of the imaginary homogeneous volume between the water-line plane and the *wetted* surface of the hull. This volume (of "displacement") is divided into an even number (say 4 to 8) of horizontal laminæ of *equal thickness*, and Simpson's Rule applied to find the volume (i.e., the V of preceding formulæ), and also (eq. 3, § 23) the height of its centre of gravity above the keel. Similarly, by division into (from 8 to 20) vertical slices, ⊥ to keel (an even number and of *equal thickness*), we find the distance of the centre of gravity from the bow. Thus the centre of buoyancy is fixed, and the corresponding buoyant effort Vw (technically called the *displacement* and usually expressed in tons) computed, for any assumed draught of ship (upright). That position in which the "displacement" $= G' =$ weight of ship is the position of equilibrium of the ship when floating upright in still water, and the corresponding draught is noted. As to whether this equilibrium is stable or unstable, the following will show.

In most ships the centre of gravity G is several feet above the centre of buoyancy, B, and a foot or more below the water line.

After a ship is afloat and its draught actually noted its total weight $G' = V\gamma$, can be computed, the values of V for different draughts having been calculated in advance. In this way the weights of different cargoes can also be measured.

EXAMPLE.—A ship having a displacement of 5000 tons is itself 5000 tons in weight, and displaces a volume of *salt* water $V' = G' \div \gamma = 10{,}000{,}000$ lbs. $\div$ 64 lbs. per cub. ft. $= 156250$ cub. ft.

463. Angular Stability of Ships.—If a vessel floating upright were of the peculiar form and position of Fig. 510 (the water-line section having an area = zero) its tendency to regain that position, or depart from it, when slightly inclined an angle ϕ from the vertical is due to the action of the couple now formed by the equal and parallel forces $V\gamma$ and G', which are no longer directly opposed. This couple is called a *righting couple* if it acts to restore the first position (as in Fig. 511, where C is lower than B), and an upsetting couple if the reverse, C above B. In either case the moment of the couple is



FIG. 510.

$$= V\gamma \cdot \overline{BC} \sin\phi = V\gamma e \sin\phi,$$

and *the centre of buoyancy B does not change its position in the vessel*, since the water-displacing shape remains the same; i.e., no new portions of the vessel are either immersed or raised out of the water.



FIG. 511.

But in a vessel of ordinary form, when turned an angle ϕ from the vertical, Fig. 512 (in which ED is a line which is vertical when the ship is upright), there is a *new* centre of buoyancy, B_1, corresponding to the new shape A_1N_1D of the displacement-volume, and the couple to right the vessel (or the reverse)

consists of the two forces G' at C and $V\gamma$ at B_1, and has a moment (which we may call M, or *moment of stability*) of a value (§ 28)



Fig. 512.

$$M = V\gamma \cdot \overline{mC} \sin \phi. \quad . \quad . \quad (1)$$

Now conceive put in at B (centre of buoyancy of the upright position) two vertical and opposite forces, each $= V\gamma = G'$, calling them P and P_1 (see § 20), Fig. 512. We can now regard the couple $[G', V\gamma]$ as replaced by the two couples $[G', P]$ and $[P_1, V\gamma]$; for evidently

$$V\gamma \cdot \overline{mC} \sin \phi = V\gamma \cdot \overline{BC} \sin \phi + V\gamma \cdot \overline{mB} \sin \phi;$$

(§§ 33 and 34;)

$$\therefore M = V\gamma\, \overline{BC} \sin \phi + V\gamma\, \overline{mB} \sin \phi. \quad . \quad . \quad (2)$$

But the couple $[G', P]$ would be the only one to right the vessel if no new portions of the hull entered the water or emerged from it, in the inclined position; hence the other couple $[P_1, V\gamma]$ owes its existence to the emersion of the wedge AOA_1, and the immersion of the wedge NON_1; i.e., to the loss of a buoyant force $Q = (\text{volume } AOA_1) \times \gamma$ on one side, and the gain of an equal buoyant force on the other; therefore this couple $[P_1, V\gamma]$ is the equivalent of the couple $[Q, Q]$, Fig. 513, formed by putting in at the centre of buoyancy of each of the two wedges a vertical force



Fig. 513.

$$Q = (\text{vol. of wedge}) \times \gamma = V_w \gamma. \quad \text{(See figure.)}$$

If a denotes the arm of this couple, we may write

$$V\gamma \cdot \overline{mB} \sin \phi, \text{ [of eq. (2)]}, = V_w \gamma a ; \quad . \quad . \quad (3)$$

and hence, denoting $\overline{BC}$ by e, we have

$$M = \pm V\gamma e \sin \phi + V_w \gamma a ; \quad . \quad . \quad . \quad . \quad (4)$$

the negative sign in which is to be used when C is above B (as with most ships). O, the intersection of ED and AN, does not necessarily lie on the new water-line plane A_1N_1.

EXAMPLE.—If a ship of ($V\gamma$ =) 3000 tons displacement with C 4 ft. *above* B (i.e., $e = -4$ ft.) is deviated 10° from the vertical, in *salt* water, for which angle the wedges AOA_1 and NON_1 have each a volume of 4000 cubic feet, while the horizontal distance a between their centres of buoyancy is 18 feet, the moment of the acting couple will be, from eq. (4) (ft.-ton-sec. system, in which γ of salt water = 0.032),

$$M = -3000 \times 4 \times 0.1736 + 4000 \times 0.032 \times 18 = 220.8 \text{ ft. tons},$$

which being + indicates a *righting* couple.

464. Remark.—If with a given ship and cargo this moment of stability, M, be computed, by eq. (4), for a number of values of ϕ, and the results plotted as ordinates (to scale) of a curve, ϕ being the abscissa, the curve obtained is indicative of the general stability of the ship. See Fig. 514. For some value of $\phi = OK$ (as well as for $\phi = 0$) the value of M is zero, and for $\phi > OK$, M is negative, indicating an *upsetting couple*. That is, for $\phi = 0$ the equilibrium is stable, but for $\phi = OK$, *unstable*; and $M = 0$ in both positions. From eq. (4) we see why, if C is above B, instability does not necessarily follow.



FIG. 514.

464a. Metacentre of a Ship.—Referring again to Fig. 512, we note that the entire couple [G', $V\gamma$] will be a righting couple, or an upsetting couple, according as the point m (the

intersection of the vertical through B_1, the new centre of buoyancy, with BC prolonged) is above or below the centre of gravity C of the ship. The location of this point m changes with ϕ; but as ϕ becomes very small (and ultimately zero) m *approaches a definite position* on the line DE, though not occupying it exactly till $\phi = 0$. This limiting position of m is called the *metacentre*, and accordingly the following may be stated: *A ship floating upright is in stable equilibrium if its metacentre is above its centre of gravity; and vice versâ.* In other words, for a slight inclination from the vertical a righting, and not an upsetting, couple is called into action, if m is above C. To find the metacentre, by means of the distance $\overline{Bm}$, we have, from eq. (3),

$$\overline{mB} = \frac{V_w \gamma a}{\nabla \gamma \sin \phi}, \quad \ldots \ldots \quad (5)$$

and wish ultimately to make $\phi = 0$. Now the moment $(V_w \gamma)a =$ the sum of the moments about the horizontal fore-and-aft water-line axis OL, Fig. 515, of the buoyant efforts due to the immersion of the separate vertical elementary prisms of the wedge OLN_1N, plus the moments of those lost, from emersion, in the wedge OLA_1A. Let OA_1LN_1 be the new water-line section of the ship when inclined a small angle ϕ from the vertical ($\phi = NO_1N_1$), and $OALN$ the old water-line. Let $z =$ the distance of any elementary area dF of the water-line section from OL (which is the intersection of the two water-line planes). Each dF is the base of an elementary prism, with altitude $= \phi z$, of the wedge N_1OLN (or of wedge A_1OLA when z is negative). The buoyant effort of this prism $=$ (its vol.) $\times \gamma = \gamma z \phi dF$, and its moment about OL is $\phi \gamma z^2 dF$. Hence the total moment, $= Qa$, or $V_w \gamma a$, of Fig. 513,



Fig. 515.

$$= \phi \gamma \int z^2 dF = \gamma \phi \times I_{OL}$$

of water-line section, in which I_{OL} denotes the "moment of inertia" (§ 85) of the plane figure $OALNO$ about the axis OL. Hence from (5), putting $\phi = \sin\phi$ (true when $\phi = 0$), we have $\overline{mB} = I_{OL} \div V$; and therefore the distance $\overline{mC}$ of the metacentre m above C, the centre of gravity of the ship, Fig. 512, is

$$\overline{mC} = h_m = \frac{I_{OL} \text{ (of water-line sec.)}}{V} \pm e, \quad . \quad . \quad . \quad (6)$$

in which $e = BC$ = distance from the centre of gravity to the centre of buoyancy, the negative sign being used when C is above B; while V = whole volume of water displaced by the ship.

We may also write, from eqs. (6) and (1), for *small values of* ϕ,

$$\textit{Mom. of righting couple} = M = V\gamma \sin\phi \left[\frac{I_{OL}}{V} \pm e\right], \quad . \quad (7)$$

or

$$M = \gamma \sin\phi\,[I_{OL} \pm Ve]. \quad . \quad . \quad . \quad . \quad (7)'$$

Eqs. (7) and (7)′ will give close approximations for $\phi < 10°$ or $15°$ with ships of ordinary forms.

EXAMPLE 1. — A homogeneous right parallelopiped, of heaviness γ', floats upright as in Fig. 516. Find the distance $mC = h_m$ for its metacentre in this position, and whether the equilibrium is stable. Here the centre of gravity, C, being the centre of figure, is of course above B, the centre of buoyancy; hence *e is negative*. B is the centre of gravity of the displacement, and is therefore a distance $\frac{1}{2}h$ below the water-line. We here assume that l is greater than b'. From eq. (2), § 461,



FIG. 516.

$$h = \frac{h'\gamma'}{\gamma};$$

and since $CD = \frac{1}{2}h'$, and $BD = \frac{1}{2}h$, $\therefore e = \frac{1}{2}(h' - h)$;

$$\text{i.e., } e = \tfrac{1}{2}h'\left[1 - \frac{\gamma'}{\gamma}\right];$$

while (§ 90) I_{OL}, of the water-line section AN, $= \frac{1}{12}l'b'^3$.

Also,

$$V = b'hl' = b'l'h'\frac{\gamma'}{\gamma};$$

and hence, from eq. (6), we have

$$h_m = \frac{l'b'^3\gamma}{12b'h'l'\gamma'} - \tfrac{1}{2}h'\left[1 - \frac{\gamma'}{\gamma}\right] = \frac{\gamma}{12h'\gamma'}\left[b'^2 - 6h'^2\frac{\gamma'}{\gamma}\left(1 - \frac{\gamma'}{\gamma}\right)\right]$$

Hence if b'^2 is $> 6h'^2\frac{\gamma'}{\gamma}\left(1 - \frac{\gamma'}{\gamma}\right)$, the position in Fig. 516 is one of stable equilibrium, and *vice versâ*. E.g., if $\gamma' = \frac{1}{2}\gamma$, $b' = 12$ inches and $h' = 6$ inches, we have (inch, pound, sec.)

$$h_m = \overline{mC} = \tfrac{1}{36}\left[144 - 6 \times \tfrac{36}{2}(1 - \tfrac{1}{2})\right] = 2.5 \text{ in.}$$

The equilibrium will be unstable if, with $\gamma' = \frac{1}{2}\gamma$, b' is made less than $1.225\ h'$; for, putting $\overline{mC} = 0$, we obtain $b' = 1.225\ h'$.

Example 2.—(Ft., lb., sec.) Let Fig. 517 represent the *half* water-line section of a loaded ship of $G' = V\gamma = 1010$ tons



Fig. 517.

displacement; required the height of the metacentre above the centre of buoyancy, i.e., $\overline{mB} = ?$ (See equation just before eq. (6).) Now the quantity I_{OL}, of the water-line section, may, from symmetry, (see § 93,) be written

$$I_{OL} = 2\int_0^L \tfrac{1}{3}y^3 dx, \quad \ldots\ldots \quad (1)$$

in which $y =$ the ordinate ⊓ to the axis OL at any point; and this, again, by Simpson's Rule for approximate integration, OL being divided into an even number, n, of equal parts, and ordinates erected (see figure), may be written

$$I_{OL} = \frac{2}{3} \cdot \frac{\overline{OL} - 0}{3n} \Big[y_0^3 + 4(y_1^3 + y_3^3 + \ldots + y_{n-1}^3) + 2(y_2^3 + y_4^3 + \ldots + y_{n-2}^3) + y_n^3 \Big].$$

From which, by numerical substitution (see figure for dimensions; $n = 8$),

$$I_{OL} = \frac{2}{3} \cdot \frac{160}{3 \times 8} \Big[(0.5^3 + 4(5^3 + 12^3 + 13^3 + 7^3) + 2(9^3 + 14^3 + 11^3) + 0.5^3 \Big];$$

or,

125	
1728	729
2197	2744
343	1331

$$I_{OL} = \tfrac{40}{9}[0.125 + 4 \times \overline{4393} + 2 \times \overline{4804} + 0.125]$$

$$= 120801 \text{ biquad. ft.}; \quad \therefore \overline{mB} = \frac{I_{OL}}{V} = \frac{120801}{[2020000 \div 64]}$$

$$= 3.8 \text{ feet.}$$

That is, the metacentre is 3.8 feet above the centre of buoyancy, and hence, if $BC = 2$ feet, is 1.90 ft. above the centre of gravity. [See Johnson's Cyclopædia, article *Naval Architecture.*]

465. Metacentre for Longitudinal Stability.—If we consider the stability of a vessel with respect to pitching, in a manner similar to that just pursued for rolling, we derive the position of the metacentre for *pitching* or for longitudinal stability—and this of course occupies a much higher position than that for *rolling*, involving as it does the moment of inertia of the water-line section about a horizontal gravity axis ⊓ to the keel. With this one change, eq. (6) holds for this case also. In large ships the height of this metacentre above the centre of gravity of the ship may be as great as 90 feet.

CHAPTER V.

HYDROSTATICS (*Continued*)—GASEOUS FLUIDS.

466. Thermometers.—The temperature, or "*hotness*," of liquids has, within certain limits, but little influence on their statical behavior, but with gases must always be taken into account, since the three quantities, *tension*, *temperature*, and *volume*, of a given mass of gas are connected by a nearly invariable law, as will be seen.

An *air-thermometer*, Fig. 518, consists of a large glass bulb filled with air, from which projects a fine straight tube of even bore (so that equal lengths represent equal volumes). A small drop of liquid, A, separates the internal from the external air, both of which are at a tension of (say) one atmosphere (14.7 lbs. per sq. inch). When the bulb is placed in melting ice (freezing-point) the drop stands at some point F in the tube; when in boiling water (boiling under a pressure of one atmosphere), the drop is found at B, on account of the expansion of the internal air under the influence of the heat imparted to it. (The glass also expands, but only about $\frac{1}{180}$ as much; this will be neglected.) The distance FB along the tube may now be divided into a convenient number of equal parts called degrees. If into one hundred degrees, it is found that each degree represents a volume equal to the $\frac{367}{100000}$ (.00367) part of the total volume occupied by the air at freezing-point; i.e., the increase of volume from the temperature of freezing-point to that of the boiling-point of water = 0.367 of the volume at freezing, *the pressure being the same*, and even having *any value whatever* (as well as one atmosphere), within ordinary limits, so long as it is the same both at freezing and boil-



FIG. 518.

ing. It must be understood, however, that by *temperature of boiling* is always meant that of water boiling under *one* atmosphere pressure. Another way of stating the above, if one hundred degrees are used between freezing and boiling, is as follows: That for each degree increase of temperature the increase of volume is $\frac{1}{273}$ of the total volume at freezing; 273 being the reciprocal of .00367.

As it is not always practicable to preserve the pressure constant under all circumstances with an air-thermometer, we use the common mercurial thermometer for most practical purposes. In this, the tube is sealed at the outer extremity, with a vacuum above the column of mercury, and its indications agree very closely with those of the air-thermometer. That equal absolute increments of volume should imply equal increments of heat imparted to these thermometric fluids (under constant pressure) could not reasonably be asserted without satisfactory experimental evidence. This, however, is not altogether wanting, so that we are enabled to say that within a moderate range of temperature equal increments of heat produce equal increments of volume in a given mass not only of atmospheric air, but of the so-called "perfect" or "permanent" gases, oxygen, nitrogen, hydrogen, etc. (so named before it was found that they could be liquefied). This is nearly true for mercury also, and for alcohol, *but not for water*. Alcohol freezes at — 200° Fahr., and hence is used instead of mercury as a thermometric substance to measure temperatures below the freezing-point of the latter.

The scale of a mercurial thermometer is fixed; but with an air-thermometer we should have to use a new scale, and in a new position on the tube, for each value of the pressure.

467. Thermometric Scales.—In the *Fahrenheit* scale the tube between freezing and boiling is marked off into 180 equal parts, and the zero placed at 32 of these parts below the freezing-point, which is hence + 32°, and the boiling-point + 212°.

The *Centigrade*, or *Celsius*, scale, which is the one chiefly used in scientific practice, places its zero at freezing, and 100° at boiling-point. Hence to reduce

Fahr. readings to Centigrade, subtract 32° and multiply by $\frac{5}{9}$;
Cent. " " Fahrenheit, multiply by $\frac{9}{5}$ and add 32°.

468. Absolute Temperature.—Experiment also shows that if a mass of air or other perfect gas is confined in a vessel whose volume is but slightly affected by changes of temperature, equal increments of temperature (and therefore equal increments of heat imparted to the gas, according to the preceding paragraph) produce equal increments of tension (i.e., pressure per unit area); or, as to the amount of the increase, that when the temperature is raised by an amount 1° Centigrade, the tension is increased $\frac{1}{273}$ of its value at freezing-point. Hence, theoretically, an ideal barometer (containing a liquid unaffected by changes of temperature) communicating with the confined gas (whose *volume* practically remains constant) would by its indications serve as a thermometer, Fig. 519, and the attached scale could be graduated accordingly. Thus, if the column stood at A when the temperature was freezing, A would be marked 0° on the Centigrade system, and the degree spaces above and below A would each $= \frac{1}{273}$ of the height AB, and therefore the point B (cistern level) to which the column would sink if the gas-tension were zero would be marked — 273° Centigrade.



FIG. 519.

But a zero-pressure, in the *Kinetic Theory of Gases* (§ 408), signifies that the gaseous molecules, no longer impinging against the vessel walls (so that the press. = 0), have become motionless; and this, in the Mechanical Theory of Heat, or *Thermodynamics*, implies that *the gas is totally destitute of heat.* Hence this ideal temperature of — 273° Centigrade, or — 460° Fahrenheit, is called the *Absolute Zero of Temperature*, and by reckoning temperatures from it as a starting-point, our formulæ will be rendered much more simple and compact. Temperature so reckoned is called *absolute temperature*, and will be denoted by the letter T. Hence the following rules for reduction:

Absol. temp. T in Cent. degrees = Ordinary Cent. + 273°;
Absol. temp. T in Fahr. degrees = Ordinary Fahr. + 460°.

For example, for 20° Cent., T = 293° Abs. Cent.

469. Distinction Between Gases and Vapors.—All known gases can be converted into liquids by a sufficient reduction of temperature or increase of pressure, or both; some, however, with great difficulty, such as atmospheric air, oxygen, hydrogen, nitrogen, etc., these having been but recently (1878) reduced to the liquid form. A *vapor* is a gas near the point of liquefaction, and does not show that regularity of behavior under changes of temperature and pressure characteristic of a gas when at a temperature much above the point of liquefaction. All gases treated in this chapter (except steam) are supposed in a condition far removed from this stage. The following will illustrate the properties of vapors. See Fig. 520. Let a quantity of liquid, say water, be introduced into a closed space, previously vacuous, of considerably larger volume than the water, and furnished with a manometer and thermometer. Vapor of water immediately begins to form in the space above the liquid, and continues to do so until its pressure attains a definite value dependent on the temperature, and not on the ratio of the volume of the vessel and the original volume of water; e.g., if the temperature is 70° Fahrenheit, the vapor ceases to form when the tension reaches a value of 0.36 lbs. per sq. inch. If heat be gradually applied to raise the temperature, more vapor will form (with ebullition; i.e., from the body of the liquid, unless the heat is applied very slowly), but the tension *will not rise above a fixed value for each temperature* (independent of size of vessel) *so long as there is any liquid left.* Some of these corresponding values, for water, are as follows: For a



FIG. 520.

Fahr. temp.	= 70°	100°	150°	212°	220°	287°	300°
Tension (lbs. per sq. in.)	= 0.36	0.93	3.69	14.7 = one atm.	17.2	55.0	67.2

At any such stage the vapor is said to be *saturated.*

Finally, at some temperature, dependent on the ratio of the original volume of water to that of the vessel, all of the water will have been converted into vapor (i.e., steam); and if the temperature be still further increased, the tension also increases and *no longer depends on the temperature alone, but also on the heaviness of the vapor when the water disappeared.* The vapor is now said to be *superheated,* and conforms more in its properties to perfect gases.

470. Critical Temperature.—From certain experiments there seems to be reason to believe that at a certain temperature, called the *critical temperature,* different for different liquids, all of the liquid in the vessel (if any remains, and supposing the vessel strong enough to resist the pressure) is converted into vapor, whatever be the size of the vessel. That is, above the critical temperature the substance is necessarily gaseous, in the most exclusive sense, incapable of liquefaction by pressure alone; while below this temperature it is a vapor, and liquefaction will begin if, by compression in a cylinder and consequent increase of pressure, the tension can be raised to a value *corresponding, for a state of saturation, to the temperature* (in such a table as that just given for water). For example, if vapor of water at 220° Fahrenheit and tension of 10 lbs. per sq. inch (this is superheated steam, since 220° is higher than the temperature which for saturation corresponds to $p = 10$ lbs. per sq. inch) is compressed slowly (slowly, to avoid change of temperature) till the tension rises to 17.2 lbs. per sq. in., which (see above table) is the pressure of saturation for a temperature of 220° Fahrenheit for water-vapor, the vapor is saturated, i.e., liquefaction is ready to begin, and during any further slow reduction of volume the pressure remains constant and some of the vapor is liquefied.

By "perfect gases," or gases proper, we may understand, therefore, those which cannot be liquefied by pressure unaccompanied by great reduction of temperature; i.e., whose "critical temperatures" are very low. The critical temperature of N_2O, or nitrous oxide gas, is between $-11°$ and $+8°$ Centigrade, while that of oxygen is said to be at $-118°$ Centi-

grade. [See p. 471, vol. 122 of the *Journal of the Franklin Institute*. For an account of the liquefaction of oxygen, etc., see the same periodical, January to June, 1878.]

471. Law of Charles (and of Gay Lussac).—The mode of graduation of the air-thermometer may be expressed in the following formula, which holds good (for practical purposes) within the ordinary limits of experiment for a given mass of *any perfect gas, the tension remaining constant:*

$$V = V_0 + 0.00367\,V_0 t = V_0(1 + .00367t); \quad . \quad . \quad (1)$$

in which V_0 denotes the volume occupied by the given mass at freezing-point under the given pressure, V its volume at any other temperature t Centigrade under the *same pressure.* Now, 273 being the reciprocal of .00367, we may write

$$V = V_0\frac{(273 + t)}{273}; \text{ i.e., } \frac{V}{V_0} = \frac{T}{T_0} \quad . \quad . \quad \left\{\begin{matrix}\text{press.}\\ \text{const.}\end{matrix}\right\}; \quad (2)$$

(see § 468;) in which T_0 = the *absolute temperature* of freezing-point, = 273° absolute Centigrade, and T the absolute temperature corresponding to t Centigrade. Eq. (2) is also true when T and T_0 are both expressed in Fahrenheit degrees (from absolute zero, of course). Accordingly, we may say that, *the pressure remaining the same, the volume of a given mass of gas varies directly as the absolute temperature.*

Since the weight of the given mass of gas is invariable at a given place on the earth's surface, we may

always use the equation $V\gamma = V_0\gamma_0$, ... (3)

pressure constant or not, and hence (2) may be rewritten

$$\frac{\gamma_0}{\gamma} = \frac{T}{T_0} \quad . \quad . \quad \text{(press. const.)}; \quad . \quad (4)$$

i.e., *if the pressure is constant, the heaviness (and therefore the specific gravity) varies inversely as the absolute temperature.*

Experiment also shows (§ 468) that if the volume [and therefore the heaviness, eq. (3)] remains constant, while the temperature varies, the tension p will change according to the following relation, in which $p_0 =$ the tension when the temperature is freezing:

$$p = p_0 + \tfrac{1}{273} p_0 t = p_0 \frac{273 + t}{273}, \quad . \quad . \quad . \quad (5)$$

t denoting the Centigrade temperature. Hence transforming, as before, we have

$$\frac{p}{p_0} = \frac{T}{T_0}. \quad . \quad \left\{ \begin{matrix} \text{vol., and} \\ \text{heav., const.} \end{matrix} \right\} \therefore \quad . \quad (6)$$

or, *the volume and heaviness remaining constant, the tension of a given mass of gas varies directly as the absolute temperature.* This is called the *Law of Charles* (or of *Gay Lussac*).

472. General Formulæ for any Change of State of a Perfect Gas. —If any two of the three quantities, viz., *volume* (or heaviness), *tension*, and *temperature*, are changed, the new value of the third is determinate from those of the other two, according to a relation proved as follows (remembering that *henceforth the absolute temperature only* will be used, T, § 468): Fig. 521. At A a certain mass of gas at a tension of p_0, one atmosphere, and absolute temperature T_0 (freezing), occupies a volume V_0. Let it now be heated to an absolute temp. $= T'$, without change of tension (expanding behind a piston, for instance). Its volume will increase to a value V which from (2) of § 471 will satisfy the relation



FIG. 521.

$$\frac{V}{V_0} = \frac{T'}{T_0}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (7)$$

(See B in figure.)

Let it now be heated without change of volume to an absolute temperature T (C in figure). Its volume is still V, but

the tension has risen to a value p, such that, on comparing B and C by eq. (6), we have

$$\frac{p}{p_0} = \frac{T}{T'}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (8)$$

Combining (7) and (8), we obtain for *any state* in which the tension is p, volume V, and absolute temperature T, in

$$(General) \quad . \quad . \quad . \quad \frac{pV}{T} = \frac{p_0 V_0}{T_0}; \quad \text{or} \quad \frac{pV}{T} = a\ constant; \quad . \quad (9)$$

or

$$(General) \quad . \quad . \quad . \quad . \quad \frac{p_m V_m}{T_m} = \frac{p_n V_n}{T_n}, \quad . \quad . \quad . \quad . \quad . \quad . \quad (10)$$

which, since

$$(General) \quad . \quad . \quad V\gamma = V_0\gamma_0 = V_m\gamma_m = V_n\gamma_n, \quad . \quad . \quad . \quad (11)$$

is true for any change of state, we may also write

$$(General) \quad . \quad . \quad . \quad . \quad \frac{p}{\gamma T} = \frac{p_0}{\gamma_0 T_0}, \quad . \quad . \quad . \quad . \quad . \quad . \quad (12)$$

or

$$\frac{p_m}{\gamma_m T_m} = \frac{p_n}{\gamma_n T_n}. \quad . \quad . \quad . \quad . \quad . \quad . \quad (13)$$

These equations (9) to (13), inclusive, hold good for any state of a mass of any perfect gas (most accurately for air). The subscript 0 refers to the state of one-atmosphere tension and freezing-point temperature, m and n to any two states whatever (within practical limits); γ is the heaviness, §§ 7 and 409, and T the *absolute temperature*, § 468.

If p, V, and T of equation (9) be treated as variables, and laid off to scale as co-ordinates parallel to three axes in space, respectively, the surface so formed of which (9) is the equation is a hyperbolic paraboloid.

473. Examples.—Example 1.—What cubic space will be occupied by 2 lbs. of hydrogen gas at a tension of two atmospheres and a temperature of 27° Centigrade?

With the *inch-lb.-sec.* system we have $p_0 = 14.7$ lbs. per sq. inch, $\gamma_0 = [.0056 \div 1728]$ lbs.* per cubic inch, and $T_0 = 273°$ absolute Centigrade, when the gas is at freezing-point at one atmosphere (i.e., in *state sub-zero*). In the state mentioned in the problem, we have $p = 2 \times 14.7$ lbs. per sq. in.,

$$T = 273 + 27 = 300° \text{ absolute Centigrade,}$$

while γ is required. Hence, from eq. (12),

$$\frac{2 \times 14.7}{\gamma\ 300} = \frac{14.7}{(.0056 \div 1728)273};$$

$$\therefore \gamma = \frac{.0102}{1728} \text{ lbs. per cub. in.} = .0102 \text{ lbs. per cub. foot;}$$ and if the total weight, $= G$, $= V\gamma$, is to be 2 lbs., we have (ft., lb., sec.) $V = 2 \div 0102 = 196$ cubic feet.—*Ans.*

Example 2.—A mass of air originally at 24° Centigrade and a tension indicated by a barometric column of 40 inches of mercury has been simultaneously reduced to half its former volume and heated to 100° Centigrade; required its tension in this new state, which we call the state n, m being the original state. Use the inch, lb., sec. We have given, therefore, $p_m = \frac{40}{30} \times 14.7$ lbs. per sq. inch, $T_m = 273 + 24 = 297°$ absolute Centigrade, the ratio

$$V_m : V_n = 2 : 1, \text{ and } T_n = 273 + 100 = 373° \text{ Abs. Cent.;}$$

while p_n is the unknown quantity. From eq. (10), hence,

$$p_n = \frac{V_m}{V_n} \cdot \frac{T_n}{T_m} \cdot p_m = 2 \times \frac{373}{297} \cdot \frac{40}{30} \times 14.7 = 49.22 \text{ lbs. per sq. in.,}$$

which an ordinary steam-gauge would indicate as

$$(49.22 - 14.7) = 34.52 \text{ lbs. per sq. inch.}$$

(That is, if the weather barometer indicated exactly 14.7 lbs. per sq. inch.)

* See table on p. 517.

EXAMPLE 3.—A mass of air, Fig. 522, occupies a rigid closed vessel at a temperature of 15° Centigrade (equal to that of surrounding objects) and a tension of four atmospheres [*state m*]. By opening a stop-cock a few seconds, thus allowing a portion of the gas to escape quickly, and then shutting it, the remainder of the air [now in *state n*] is found to have a tension of only 2.5 atmospheres (measured immediately); its temperature cannot be measured immediately (so much time being necessary to affect a thermometer), and is less than before. To compute this temperature, T_n, we allow the air now in the vessel to come again to the same temperature as surrounding objects (15° Centigrade); find then the tension to be 2.92 atmospheres. Call the last state, *state r* (inch, lb., sec.). The problem then stands thus:



FIG. 522.

$p_m = 4 \times 14.7$	$p_n = 2.5 \times 14.7$	$p_r = 2.92 \times 14.7$
$\gamma_m = ?$	$\gamma_n = ?$	$\gamma_r = \gamma_n$ (since $V_r = V_n$)
$T_m = 288°$ Abs. Cent.	$T_n = ?$ { principal unknown	$T_r = T_m = 288°$ Abs. Cent.

In states n and r the heaviness is the same; hence an equation like (6) of § 471 is applicable, whence

$$\frac{p_n}{p_r} = \frac{T_n}{T_r}, \quad \text{or } T_n = \frac{2.5 \times 14.7}{2.92 \times 14.7} \times 288 = 246° \text{ Abs. Cent.}$$

or $-27°$ Centigrade; considerably *below freezing*, as a result of allowing the sudden escape of a portion of the air, and the consequent sudden expansion, and reduction of tension, of the remainder. In this sudden passage from state m to state n, the remainder altered its heaviness (and its volume in inverse ratio) in the ratio (see eqs. (11) and (10) of § 472)

$$\frac{\gamma_n}{\gamma_m} = \frac{V_m}{V_n} = \frac{p_n}{p_m} \cdot \frac{T_m}{T_n} = \frac{2.5 \times 14.7}{4 \times 14.7} \cdot \frac{288}{246} = 0.73.$$

Now the heaviness in state m (see eq. (12), § 472) was

$$\gamma_m = \frac{p_m}{T_m} \cdot \frac{\gamma_0 T_0}{p_0} = \frac{4 \times 14.7}{288} \cdot \frac{.0807}{1728} \cdot \frac{273}{14.7} = \frac{.306}{1728}$$

lbs. per cub. in. = .306 lbs. per cub. ft.

$$\therefore \gamma_n = 0.73 \times \gamma_m = 0.223 \text{ lbs. per cub. ft.,}$$

and also, since $V_m = 0.73\, V_n$, about $\frac{27}{100}$ of the original quantity of air in vessel has escaped.

[NOTE.—By numerous experiments like this, the law of cooling, when a mass of gas is allowed to expand suddenly (as, e.g., behind a piston, doing work) has been determined; and *vice versâ*, the law of heating under sudden compression; see § 487.]

474. The Closed Air-manometer.—If a manometer be formed of a straight tube of glass, of uniform cylindrical bore, which is partially filled with mercury and then inverted in a cistern of mercury, *a quantity of air having been left between the mercury and the upper end of the tube, which is closed*, the tension of this confined air (to be computed from its observed volume and temperature) must be added to that due to the mercury column, in order to obtain the tension p' to be measured. See Fig. 523. The advantage of this kind of instrument is, that to measure great tensions the tube need not be very long. Let the temperature T_1 of whole instrument, and the tension p_1 of the air or gas in the cistern, be known when the mercury in the tube stands at the same level as that in the cistern. The tension of the air in the tube must now be p_1 also, its temperature T_1, and its volume is $V_1 = Fh_1$, F being the sectional area of the bore of the tube; see on left of figure. When the instrument is used, gas of unknown tension p' is admitted to the cistern, the temperature of the whole instrument being noted ($= T$), and the heights h and h'' are observed ($h + h''$ cannot be put $= h_1$



FIG. 523.

unless the cistern is very large). p' is then computed as follows (eq. (2), § 413):

$$p' = h''\gamma_m + p; \quad \ldots \ldots \quad (1)$$

in which p = the tension of the air in the tube, and γ_m the heaviness of mercury. But from eq. (10), § 472, putting $V_1 = Fh_1$ and $V = Fh$,

$$p = p_1 \frac{V_1}{V} \cdot \frac{T}{T_1} = \frac{h_1}{h} \frac{T}{T_1} p_1. \quad \ldots \ldots \quad (2)$$

Hence finally, from (1) and (2),

$$p' = h''\gamma_m + \frac{h_1}{h} \cdot \frac{T}{T_1} p_1. \quad \ldots \ldots \quad (3)$$

Since T_1, p_1, and h_1 are fixed constants for each instrument, we may, from (3), compute p' for any observed values of h and T (N.B. T and T_1 are *absolute temperatures*), and construct a series of tables each of which shall give values of p' for a range of values of h, and one special value of T.

Example.—Supposing the fixed constants of a closed air manometer to be (in inch-lb.-sec. system) $p_1 = 14.7$ (or one atmosphere), $T_1 = 285°$ Abs. Cent. (i.e., 12° Centigrade), and $h_1 = 3'\ 4'' = 40$ inches; required the tension in the cistern indicated by $h'' = 25$ inches and $h = 15$ inches, when the temperature is $-3°$ Centigrade, or $T = 270°$ Abs. Cent.

For mercury, $\gamma_m = [848.7 \div 1728]$ (§ 409) (though strictly it should be specially computed for the temperature, since it varies about .00002 of itself for each Centigrade degree). Hence, eq. (3),

$$p' = \frac{25 \times 848.7}{1728} + \frac{40}{15} \cdot \frac{270}{285} \times 14.7 = 12.26 + 37.13 = 49.39$$

lbs. per sq. inch, or nearly $3\frac{1}{2}$ atmospheres [steam-gauge would read 34.7 lbs. per sq. in.].

475. Mariotte's Law, (or Boyle's,) Temperature Constant; i.e., Isothermal Change.—If a mass of gas be compressed, or al-

lowed to expand, *isothermally*, i.e., without change of temperature (practically this cannot be done unless the walls of the vessel are conductors of heat, and then the motion must be slow), eq. (10) of § 472 now becomes (since $T_m = T_n$)

$$\left\{\begin{matrix}\textit{Mariotte's Law,}\\ \textit{Temp. constant}\end{matrix}\right\} \quad . \quad V_m p_m = V_n p_n, \quad \text{or} \quad \frac{p_m}{p_n} = \frac{V_n}{V_m}; \qquad (1)$$

i.e., *the temperature remaining unchanged, the tensions are inversely proportional to the volumes, of a given mass of a perfect gas*; or, *the product of volume by tension is a constant quantity*. Again, since $V_m \gamma_m = V_n \gamma_n$ for any change of state,

$$\left\{\begin{matrix}\textit{Mariotte's Law,}\\ \textit{Temp. constant}\end{matrix}\right\} \quad . \quad \frac{p_m}{p_n} = \frac{\gamma_m}{\gamma_n}, \quad \text{or} \quad \frac{p_m}{\gamma_m} = \frac{p_n}{\gamma_n}; \qquad (2)$$

i.e., *the pressures* (*or tensions are directly proportional to the* (*first power of the*) *heavinesses, if the temperature is the same.*

This law, which is very closely followed by all the perfect gases, was discovered by Boyle in England and Mariotte in France more than two hundred years ago, but of course is only a particular case of the general formula, for any change of state, in § 472. It may be verified experimentally in several ways. E.g., in Fig. 524, the tube OM being closed at the top, while PN is open, let mercury be poured in at P until it reaches the level $A'B'$. The air in OA' is now at a tension of one atmosphere. Let more mercury be slowly poured in at P, until the air confined in O has been compressed to a volume $OA'' = \frac{1}{2}$ of OA', and the height $B''E''$ then measured; it will be found to be 30 inches; i.e., the tension of the air in O is now *two atmospheres* (corresponding to 60 inches of mercury) Again, compress the air in O to $\frac{1}{3}$ its original volume (when at one atmosphere), i.e., to volume $OA''' = \frac{1}{3}OA'$, and the mercury height $B'''E'''$ will be 60 inches, showing a tension of three atmospheres in the confined air at O (90



FIG. 524.

inches of mercury in a barometer). It is understood that the temperature is the same, i.e., that time is given the compressed air to acquire the temperature of surrounding objects after being heated by the compression, if sudden.

[NOTE.—The law of decrease of steam-pressure in a steam-engine cylinder, after the piston has passed the point of "cut off" and the confined steam is expanding, does not materially differ from Mariotte's law, which is often applied to the case of expanding steam; see § 479.]

While Mariotte's law may be considered exact for practical purposes, it is only approximately true, the amount of the deviations being different at different temperatures. Thus, for decreasing temperatures the product Vp of volume by tension becomes smaller, with most gases.

EXAMPLE 1.—If a mass of compressed air expands in a cylinder behind a piston, having a tension of 60 lbs. per sq. inch (45.3 by steam-gauge) at the beginning of the expansion, which is supposed slow (that the temperature may not fall); then when it has doubled in volume its tension will be only 30 lbs. per sq. inch; when it has tripled in volume its tension will be only 20 lbs. per sq. inch, and so on.

EXAMPLE 2. *Diving-bell.*—Fig. 525. If the cylindrical diving-bell AB is 10 ft. in height, in what depth, $h = ?$, of *salt water*, can it be let down to the bottom, without allowing the water to rise in the bell more than a distance $a = 4$ ft.? Call the horizontal sectional area, F. The mass of air in the bell is constant, at a constant temperature. *First, algebraically;* at the surface this mass of air occupied a volume $V_m = Fh''$ at a tension $p_m = 14.7 \times 144$ lbs. per sq. ft., while at the depth mentioned it is compressed to a volume $V_n = F(h'' - a)$, and is at a tension $p_n = p_m + (h - a)\gamma_w$, in which γ_w = heaviness of salt water. Hence, from eq. (1),



FIG. 525.

$$p_m Fh'' = [p_m + (h - a)\gamma_w]F(h'' - a); \quad . \quad . \quad (3)$$

$$\therefore h = a\left[1 + \frac{p_m}{(h'' - a)\gamma_w}\right]; \quad . \quad . \quad . \quad . \quad . \quad (4)$$

hence, *numerically*, (ft., lb., sec.,)

$$h = 4 \times \left[1 + \frac{14.7 \times 144}{(10 - 4) \times 64}\right] = 26.05 \text{ feet.}$$

476. Mixture of Gases.—It is sometimes stated that if a vessel is occupied by a mixture of gases (between which there is no chemical action), the tension of the mixture is equal to the sum of the pressures of each of the component gases present; or, more definitely, is equal to the sum of the pressures which the separate masses of gas would exert on the vessel if each in turn occupied it alone at the same temperature.

This is a direct consequence of Mariotte's law, and may be demonstrated as follows:

Let the actual tension be p, and the capacity of the vessel V. Also let V_1, V_2, etc., be the volumes actually occupied by the separate masses of gas, so that

$$V_1 + V_2 + \ldots = V; \quad . \quad . \quad . \quad . \quad . \quad (1)$$

and p_1, p_2, etc., the pressures they would individually exert when occupying the volume V alone at the same temperature. Then, by Mariotte's law,

$$Vp_1 = V_1 p; \quad Vp_2 = V_2 p; \quad \text{etc.}; \quad . \quad . \quad . \quad (2)$$

whence, by addition, we have

$$V(p_1 + p_2 + \ldots) = (V_1 + V_2 + \ldots)p;$$

$$\text{i.e.,} \quad p = p_1 + p_2 + \ldots \quad . \quad . \quad . \quad . \quad . \quad (3)$$

Of course, the same statement applies to any number of separate parts into which we may imagine a mass of homogeneous gas to be divided.

For numerical examples and practical questions in the solution of which this principle is useful, see p. 239, etc., Rankine's Steam-engine. (Rankine uses 0.365, where 0.367 has been used here.)

477. Barometric Levelling.—By measuring with a barometer the tension of the atmosphere at two different levels, simultaneously, and on a still day, the two localities not being widely separated horizontally, we may compute their vertical distance apart if the temperature of the stratum of air between them is known, being the same, or nearly so, at both stations. Since the heaviness of the air is different in different layers of the vertical column between the two elevations N and M, Fig. 526, we cannot immediately regard the whole of such a column as a free body (as was done with a liquid, § 412), but must consider a horizontal thin lamina, L, of thickness $= dz$ and at a distance $= z$ (variable) below M, the level of the upper station, N being the lower level at a distance, h, from M.



Fig. 526.

The tension, p, must increase from M downwards, since the lower laminæ have to support a greater weight than the upper; and the heaviness γ must also increase, proportionally to p, since we assume that all parts of the column are at the same temperature, thus being able to apply Mariotte's law. Let the tension and heaviness of the air at the upper base of the elementary lamina, L, be p and γ respectively. At the lower base, a distance dz below the upper, the tension is $p + dp$. Let the area of the base of lamina be F; then the vertical forces acting on the lamina are Fp, downward; its weight γFdz downward; and $F(p + dp)$ upward. For its equilibrium Σ(vert. compons.) must $= 0$;

$$\therefore F(p + dp) - Fp - F\gamma dz = 0;$$

$$\text{i.e., } dp = \gamma dz, \quad \ldots\ldots \quad (1)$$

which contains three variables. But from Mariotte's law, § 475, eq. (2), if p_n and γ_n refer to the air at N, we may substitute $\gamma = \frac{\gamma_n}{p_n} p$ and obtain, after dividing by p, to separate the variables p and z,

$$\frac{p_n}{\gamma_n} \cdot \frac{dp}{p} = dz. \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

Summing equations like (2), one for each lamina between M (where $p = p_m$ and $z = 0$) and N (where $p = p_n$ and $z = h$), we have

$$\frac{p_n}{\gamma_n} \cdot \int_{p_m}^{p_n} \frac{dp}{p} = \int_0^h dz;$$

$$\text{i.e., } h = \frac{p_n}{\gamma_n} \cdot \log_{\epsilon} \left[\frac{p_n}{p_m}\right], \quad . \quad . \quad . \quad . \quad . \quad (3)$$

which gives h, the difference of level, or altitude, between M and N, in terms of the observed tensions p_n and p_m, and of γ_n, the heaviness of the air at N, which may be computed from eq. (12), § 472, substituting from which we have finally

$$h = \frac{p_0}{\gamma_0} \cdot \frac{T_n}{T_0} \cdot \log_{\epsilon} \left[\frac{p_n}{p_m}\right], \quad . \quad . \quad . \quad . \quad (4)$$

in which the subscript 0 refers to freezing-point and one atmosphere tension; T_n and T_0 are absolute temperatures. For the ratio $p_n : p_m$ we may put the equal ratio $h_n : h_m$ of the actual barometric heights which measure the tensions. The log. $_{\epsilon}$ (or Naperian, or natural, or hyperbolic, log.) = (common log. to base 10) $\times$ 2.30258. From § 409, γ_0 of air = 0.08076 lbs. per cub. ft., and $p_0 = 14.701$ lbs. per sq. inch; $T_0 = 273°$ Abs. Cent.

If the temperatures of the two stations (both in the *shade*) are not equal, a mean temp. $= \frac{1}{2}(T_m + T_n)$ may be used for T_n in eq. (4), for approximate results. Eq. (4) may then be written

$$h \text{ (in feet)} = 26213 \frac{T_n}{T_0} \cdot \log_{\epsilon} \left[\frac{p_n}{p_m}\right]. \quad . \quad . \quad . \quad (5)$$

The quantity $\frac{p_0}{\gamma_0} = 26213$ ft., just substituted, is called the *height of the homogeneous atmosphere*, i.e., the ideal height which the atmosphere would have, if incompressible and non-

expansive like a liquid, in order to exert a pressure of 14.701 lbs. per sq. inch upon its base, being throughout of a constant heaviness = .08076 lbs. per cub. foot.

By inversion of eq. (4) we may also write

$$p_m e^{\frac{\gamma_0}{p_0} \cdot \frac{T_0}{T_n} \cdot h} = p_n, \quad \ldots \ldots \quad (6)$$

where $e = 2.71828$ = the Naperian Base, which is to be raised to the power whose index is the abstract number $\frac{\gamma_0}{p_0} \cdot \frac{T_0}{T_n} \cdot h$, and the result multiplied by p_m to obtain p_n.

Example.—Having observed as follows (simultaneously):

At lower station N, $h_n = 30.05$ in. mercury; temp. $= 77.6°$ F.;
" upper " M, $h_m = 23.66$ " " " $= 70.4°$ F.;

required the altitude h. From these figures we have a mean absolute temperature of $460° + \frac{1}{2}(77.6 + 70.4) = 534°$ Abs. Fahr.; hence, from (5),

$$h = 26213 \times \tfrac{534}{492} \times 2.30258 \times \log._{10} \left[\frac{30.05}{23.66}\right] = 6787.9 \text{ ft.}$$

(Mt. Guanaxuato, in Mexico, by Baron von Humboldt.) Strictly, we should take into account the latitude of the place, since γ_0 varies with g (see § 76), and also the decrease in the intensity of gravitation as we proceed farther from the earth's centre, for the mercury in the barometer weighs less per cubic inch at the upper station than at the lower.

Tables for use in barometric levelling can be found in Trautwine's Pocket-book, and in Searles's Field-book for Railroad Engineers, as also tables of boiling-points of water under different atmospheric pressures, forming the basis of another method of determining heights.

478. Adiabatic Change—Poisson's Law.—By an *adiabatic* change of state, on the part of a gas, is meant a compression or expansion in which work is done *upon* the gas (in compress-

ing it) or *by* the gas (in expanding against a resistance) when there is *no transmission of heat* between the gas and enclosing vessel, or surrounding objects, by conduction or radiation. This occurs when the volume changes in a vessel of non-conducting material, or when the compression or expansion takes place *so quickly* that there is no time for transmission of heat to or from the gas.

The experimental facts are, that if a mass of gas in a cylinder be suddenly compressed to a smaller volume its temperature is raised, and its tension increased more than the change of volume would call for by Mariotte's law; and *vice versâ*, if a gas at high tension is allowed to expand in a cylinder and drive a piston against a resistance, its temperature falls, and its tension diminishes more rapidly than by Mariotte's law.

Again (see Example 3, § 473), if $\frac{27}{100}$ of the gas in a rigid vessel, originally at 4 atmos. tension and temperature of 15° Cent., is allowed to escape suddenly through a stop-cock into the outer air, the remainder, while increasing its volume in the ratio 100 : 73, is found to have cooled to — 27° Cent., and its tension to have fallen to 2.5 atmospheres; whereas, by Mariotte's law, if the temperature had been kept at 288° Abs. Cent., the tension would have been lowered to $\frac{73}{100}$ of 4, i.e., to 2.92 atmospheres only.

The reason for this cooling during sudden expansion is, according to the *Kinetic Theory of Gases*, that since the "sensible heat" (i.e., that perceived by the thermometer), or "*hotness*" of a gas depends on the velocity of its incessantly moving molecules, and that each molecule after impact with a *receding* piston has a less velocity than before, the temperature necessarily falls; and *vice versâ*, when an advancing piston compresses the gas into a smaller volume.

If, however, a mass of gas expands *without doing work*, as when, in a vessel of two chambers, one a vacuum, the other full of gas, communication is opened between them, and the gas allowed to fill both chambers, *no cooling* is noted in the mass as a whole (though parts may have been cooled temporarily).

By experiments similar to that in Example 3, § 473, it has

been found that for air and the "perfect gases," in an adiabatic change of volume [and therefore of heaviness], the tension varies inversely with the 1.41th power of the volume. This is called *Poisson's Law*. That is to say,

$$\left.\begin{matrix}\textit{Adiabat.}\\ \textit{Change}\end{matrix}\right\} \quad \frac{p_m}{p_n}=\left(\frac{\gamma_m}{\gamma_n}\right)^{1.41} \text{ or } \frac{p_m}{p_n}=\left(\frac{V_n}{V_m}\right)^{1.41}; \quad (1)$$

and combining this relation with the general eqs. (10) and (13), § 472, we have also

$$\left.\begin{matrix}\textit{Adiabat.}\\ \textit{Change}\end{matrix}\right\} \quad \frac{p_m}{p_n}=\left(\frac{T_m}{T_n}\right)^{3.44} \text{ or } \frac{T_m}{T_n}=\left(\frac{p_m}{p_n}\right)^{0.29}, \quad (2)$$

i.e., the tension varies directly as the 3.44th power of the absolute temperature; also,

$$\left.\begin{matrix}\textit{Adiabat.}\\ \textit{Change}\end{matrix}\right\} \quad \left(\frac{V_m}{V_n}\right)=\left(\frac{T_n}{T_m}\right)^{2.44} \text{ or } \frac{\gamma_n}{\gamma_m}=\left(\frac{T_n}{T_m}\right)^{2.44}. \quad (3)$$

i.e., the volume is inversely, and the heaviness directly, as the 2.44th power of the absolute temperature.

Here m and n refer to any two adiabatically related states. T is the *absolute temperature*.

Example 1.—Air in a cylinder at 20° Cent. is *suddenly* compressed to $\frac{1}{6}$ its original volume (and therefore is six times as dense, i.e., has six times the heaviness, as before). To what temperature is it heated? Let m be the initial state, and n the final. From eq. (3) we have

$$\frac{T_n}{293}=\left(\frac{6}{1}\right)^{0.41}; \quad \therefore \; T_n=611° \text{ Abs. Cent.},$$

or nearly double the absolute temperature of boiling water.

Example 2.—After the air in Example 1 has been given time to cool again to 20° Cent. (temperature of surrounding objects) it is allowed to resume, suddenly, its first volume, i.e.,

to increase its volume sixfold by expanding behind a piston. To what temperature has it cooled? Here $T_m = 293°$ Abs. Cent., the ratio $V_m : V_n = \frac{1}{6}$, and T_n is required. Hence, from (3),

$$\frac{T_n}{293} = \left(\frac{1}{6}\right)^{0.41}; \quad \therefore T_n = 293 \times 0.4796 = 140.5° \text{ Abs. Cent.},$$

or $= -132.5°$ Cent., indicating extreme cold.

From these two examples the principle of one kind of ice-making apparatus is very evident. As to the work necessary to compress the air in Example 1, see § 483. It is also evident why motors using compressed air expansively have to encounter the difficulty of frozen watery vapor (present in the air to some extent).

EXAMPLE 3.—What is the tension of the air in Example 1 (suddenly compressed to $\frac{1}{6}$ its original volume) immediately after the compression, if the original tension was one atmosphere? That is, with $V_n : V_m = 1 : 6$, and $p_m = 14.7$ lbs. per sq. inch, $p_n = ?$ From eq. (1), (in., lb., sec.,)

$$p_n = 14.7 \times (6)^{1.41} = 14.7 \times 12.52 = 184$$

lbs. per sq. inch; whereas, if, after compression and without change of volume, it cools again to 20° Cent., the tension is only $14.7 \times 6 = 88.2$ lbs. per sq. inch (now using Mariotte's law).

479. Work of Expanding Steam following Mariotte's Law.—Although gases do not in general follow Mariotte's law in expanding behind a piston (without special provision for supplying heat), it is found that the tension of saturated steam (i.e., saturated at the beginning of the expansion) in a steam engine cylinder, when left to expand after the piston has passed the point of "*cut-off*," diminishes very nearly in accordance with Mariotte's law, which may therefore be applied in this case to find the work done per stroke, and thence the power. In Fig. 527 a horizontal steam-cylinder is

shown in which the piston is making its left-to-right stroke. The "back-pressure" is constant and $= Fq$, F being the area of the piston and q the *intensity* (i.e., per unit area) of the back or exhaust pressure on the right side of the piston, while the forward pressure on the left face of the piston $= Fp$, in which p is the steam-pressure per unit area, and is different at different points of the stroke. While the piston is passing from O'' to D'', p is constant, being $= p_b =$ the boiler-pressure, since the steam-port is still open. Between D'' and C'', however, the steam being *cut off* (i.e., the steam-port is closed) at D'', a distance a from O'', p decreases with Mariotte's law (nearly), and its value is $(Fa \div Fx)p_b$ at any point on $C''D''$, x being the distance of the point from O''.



FIG. 527.

Above the cylinder, conceive to be drawn a diagram in which an axis OX is $\parallel$ to the cylinder-axis, OY an axis $\perp$ to the same, while O is vertically above the left-hand end of the cylinder. As the piston moves, let the value of p corresponding to each of its positions be laid off, to scale, in the vertical immediately above the piston, as an ordinate from the axis X. Make $OD' = q$ by the same scale, and draw the horizontal $D'C'$. Then the effective work done on the piston-rod while it moves through any small distance dx is

$$dW = \text{force} \times \text{distance} = F(p - q)dx,$$

and is proportional to the area of the strip RS, whose width is dx and length $= p - q$; so that the effective work of one stroke is

$$\left[{}^{C''}_{O''}W = \int_{x=0}^{x=l} dW = F\int_{x=0}^{x=l}(p - q)dx, \quad \ldots \quad (1)\right.$$

and is represented graphically by the area $A'ARBC''D'A'$. From O'' to D'' p is constant and $= p_b$ (while q is constant at all points), and x varies from 0 to a;

$$\therefore \left[\begin{matrix} D'' \\ W \\ O'' \end{matrix}\right. = F(p_b - q)\int_0^a dx = F(p_b - q)a, \quad . \quad . \quad (2)$$

which may be called the *work of entrance*, and is represented by the area of the rectangle $A'ADD'$.

From D'' to C'' p is variable and, by Mariotte's law, $= \frac{a}{x}p_b$;

$$\therefore \left[\begin{matrix} C'' \\ W \\ D'' \end{matrix}\right. = F\int_a^l (p - q)dx = F\left[ap_b\int_a^l \frac{dx}{x} - q\int_a^l dx\right];$$

i.e.,

$$\left[\begin{matrix} C'' \\ W \\ D'' \end{matrix}\right. = F\left[ap_b \log_e\left(\frac{l}{a}\right) - q(l - a)\right] \quad . \quad . \quad . \quad (3)$$

= the *work of expansion*, adding which to that of entrance, we have for the *total effective work of one stroke*

$$W = Fp_b a\left[1 + \log_e\left(\frac{l}{a}\right)\right] - Fql. \quad . \quad . \quad . \quad (4)$$

By effective work we mean that done upon the piston-rod and thus transmitted to outside machinery. Suppose the engine to be "double-acting"; then at the end of the stroke a communication is made, by motion of the proper valves, between the space on the left of the piston and the condenser of the engine; and also between the right of the piston and the boiler (that to the condenser now being closed). On the return stroke, therefore, the conditions are the same as in the forward stroke, except that the two sides of the piston have changed places as regards the pressures acting on them, and thus the same amount of effective work is done as before.

If n revolutions of the fly-wheel are made per unit of time (two strokes to each revolution), the effective work done per unit of time, i.e., the *power* of the engine, is

$$L = 2n\,W = 2nF\left[ap_b\left[1 + \log_e\left(\frac{l}{a}\right)\right] - ql\right]. \quad (5)$$

For simplicity the above theory has omitted the consideration of "*clearance*," that is, the fact that at the point of "cut-off" the mass of steam which is to expand occupies not only the cylindrical volume Fa, but also the "clearance" or small space in the steam-passages between the valve and the entrance of the cylinder, the space between piston and valve which is never encroached upon by the piston. "Wire-drawing" has also been disregarded, i.e., the fact that during communication with the boiler the steam-pressure on the piston is a little less than boiler-pressure. For these the student should consult special works, and also for the consideration of water mixed with the steam, etc. Again, a strict analysis should take into account the difference in the areas which receive fluid-pressure on the two sides of the piston.

Example 1.—A reciprocating steam-engine makes 120 revolutions per minute, the boiler-pressure is 40 lbs. by the gauge (i.e., $p_b = 40 + 14.7 = 54.7$ lbs. per sq. inch), the piston area is $F = 120$ sq. in., the length of stroke $l = 16$ in., the steam being "cut off" at $\frac{1}{4}$ stroke ($\therefore a = 4$ in., and $l : a = 4.00$), and the exhaust pressure corresponds to a "vacuum of 25 inches" (by which is meant that the pressure of the exhaust steam will balance 5 inches of mercury), whence $q = \frac{5}{30}$ of $14.7 = 2.45$ lbs. per sq. inch. Required the work per stroke, W, and the corresponding power L.

Since $l : a = 4$, we have $\log_e 4 = 2.302 \times .60206 = 1.386$, and from eq. (4), (*foot*, lb., sec.,)

$$W = \tfrac{120}{44}(54.7 \times 144) \cdot \tfrac{1}{3} \cdot [2.386] - \tfrac{120}{144}(2.45 \times 144) \cdot \tfrac{4}{3}$$

$$= 5165.86 - 392.0 = 4773.868 \text{ ft. lbs. of work per stroke,}$$

and therefore the power at 2 rev. per sec. (eq. 5) is

$$L = 2 \times 2 \times 4773.87 = 19095.5 \text{ ft. lbs. per second.}$$

Hence in horse-powers, which, in ft.,-lb.-sec. system, $= L \div 550$

$$Power = 19095.5 \div 550 = 34.7 \text{ H. P.}$$

Example 2.—Required the weight of steam consumed per

second by the above engine with given data; assuming with Weisbach that the heaviness of saturated steam at a definite pressure (and a *corresponding temperature*, § 469) is about $\frac{5}{8}$ of that of air at the same pressure and temperature.

The heaviness of air at 54.7 lbs. per sq. in. tension and temperature 287° Fahr. (see table, § 469) would be, from eq. (12) of § 472 (see also § 409),

$$\gamma = \frac{\gamma_0 T_0}{T} \cdot \frac{p}{p_0} = \frac{.0807 \times 492}{460 + 287} \cdot \frac{54.7}{14.7} = 0.198$$

lbs. per cub. foot, $\frac{5}{8}$ of which is 0.1237 lbs. per cub. ft. Now the volume* of steam, of this heaviness, admitted from the boiler at each stroke is $V = Fa = \frac{120}{144} \cdot \frac{1}{3} = 0.2777$ cub. ft., and therefore the weight of steam used per second is

$$4 \times .2777 \times 0.1237 = 0.1374 \text{ lbs.}$$

Hence, per hour, $0.1374 \times 3600 = 494.6$ lbs. of feed-water are needed for the boiler.

If, with this same engine, the steam is used at full boiler pressure throughout the whole stroke, the power will be greater, viz. $= 2nFl(p_b - q) = 33440$ ft. lbs. per sec., but the consumption* of steam will be four times as great; and hence in economy of operation it will be only 0.44 as efficient (nearly).

480. Graphic Representation of any Change of State of a Confined Mass of Gas.—The curve of expansion AB in Fig. 527 is an equilateral hyperbola, the axes X and Y being its asymptotes. If compressed air were used instead of steam its expansion curve would also be an equilateral hyperbola if its temperature could be kept from falling during the expansion (by injecting hot-water spray, e.g.), and then, following Mariotte's law, we would have, as for steam, (§ 475,) $pV =$ constant, i.e., $pFx =$ constant, and therefore $px =$ constant, which is the equation of a hyperbola, p being the ordinate and x the abscissa. This curve (dealing with a perfect gas) is also called an *isothermal*, the x and y co-ordinates of its points being pro-

* We here neglect the practical fact that a portion of the fresh steam entering the cylinder is condensed prematurely, so that the actual consumption is somewhat greater than as here derived.

portional to the volume and tension, respectively, of a mass of air (or perfect gas) whose temperature is maintained constant.

Hence, *in general*, if a mass of gas be confined in a rigid cylinder of cross-section F (area), provided with an air-tight piston, Fig. 528, its volume, Fx, is proportional to the distance $OD = x$ (of the piston from the closed end of the cylinder) taken as an abscissa, while its tension p at the same instant may be laid off as an ordinate from D.



FIG 528.

Thus a point A is fixed. Describe an equilateral hyperbola through A, asymptotic to X and Y, and mark it with the observed temperature (absolute) of the air at this instant. In a similar way the diagram can be filled up with a great number of equilateral hyperbolas, or *isothermal curves*, each for its own temperature. Any point whatever (i.e., above the critical temperature) in the plane angular space YOX will indicate by its co-ordinates a volume and a tension, while the corresponding absolute temperature T will be shown by the hyperbola passing through the point, since these three variables always satisfy the relation (§ 472)

$$\frac{pV}{T} = \text{const.}; \text{ i.e., } \frac{pFx}{T} = \frac{p_0 V_0}{T_0}. \quad . \ . \ . \quad (1)'$$

Any change of state of the gas in the cylinder may now be represented by a line in the diagram connecting the two points corresponding to its initial and final states. Thus, a point moving along the line AB, a portion of the isothermal marked 293° Abs. Cent., represents a motion of the piston from D to E, and a consequent increase of volume, accompanied by just sufficient absorption of heat by the gas (from other bodies) to maintain its temperature at that figure (viz., its temperature at

A). If the piston move from D to E, *without transmission of heat*, i.e., *adiabatically* (§ 478), the tension falls more rapidly, and a point moving along the line AB' represents the corresponding continuous change of state. AB' is a portion of an *adiabatic curve*, whose equation, from § 478, is

$$\frac{p}{p_K}=\left[\frac{Fx_K}{Fx}\right]^{1.41} \quad \text{or} \quad px^{1.41}=p_Kx_K^{1.41}=\text{const.}; \quad . \quad (1)$$

in which p_K and x_K refer to the point K where this particular adiabatic curve cuts the isothermal of freezing-point. Evidently an adiabatic may be passed through any point of the diagram. The mass of gas in the cylinder may change its state from A to B' by an infinite number of routes, or lines on the diagram, the adiabatic route, however, being that most likely to occur for a rapid motion of the piston. For example, we may cool it without allowing the piston to move (and hence without altering its volume nor the abscissa x) until the pressure falls to a value $p_{B'} = DL = EB'$, and this change is represented by the vertical path from A to L; and then allow it to expand, and push the piston from D to E (i.e., do external work), during which expansion heat is to be supplied at just such a rate as to keep the tension constant, $= p_{B'} = p_L$, this latter change corresponding to the horizontal path LB' from L to B'.

It is further noticeable that the *work done* by the expanding gas upon the *near face* of the piston (or done *upon* the gas when compressed) when the space dx is described by the piston, is $= Fpdx$, and therefore is proportional to the area pdx of the small vertical strip lying between the axis X and the line or route showing the change of state; whence the total work done on the near piston-face, being $= F\int pdx$, is represented by the area $\int pdx$ of the plane figure between the initial and final ordinates, the axis X and the particular *route* followed between the initial and final states (N.B. We take no account here of the pressure on the other side of the piston, the latter depending on the style of engine). For example, the work done on the near face of the piston during adiabatic expansion

from D to E is represented by the plane figure $AB'EDA$, and is measured by its area.

The mathematical relations between the quantities of heat imparted or rejected by conduction and radiation, and transformed into work, in the various changes of which the confined gas is capable, belong to the subject of *Thermodynamics*, which cannot be entered upon here.

It is now evident how the cycle of changes which a definite mass of air or gas experiences when used in a hot-air engine, compressed-air engine, or air-compressor, is rendered more intelligible by the aid of such a diagram as Fig. 528; but it must be remembered that during the entrance into, or exit from, the cylinder, of the mass of gas used in one stroke, the distance x does not represent its volume, and hence the locus of the points in the diagram determined by the co-ordinates p and x during entrance and exit does not indicate changes of state in the way just explained for the mass when confined in the cylinder. However, the *work done* by or upon the gas during entrance and exit will still be represented by the plane figure included by that locus (usually a straight horizontal line, pressure constant) and the axis of X and the terminal ordinates.

481. Adiabatic Expansion in an Engine using Compressed Air. —Fig. 529. Let the compressed air at a tension p_m and an absolute temperature T_m be supplied from a reservoir (in which the loss is continually made good by an air-compressor). Neglecting the resistance of the port, its tension and temperature when behind the piston are still p_m and T_m. Let x_n = length of stroke, and let the cut-off (or closing of communication with the reservoir) be made at some point D where $x = x_m$, the position of D being so chosen (i.e., the ratio $x_m : x_n$ so computed) that after adiabatic expansion from D to E the pressure shall have fallen from p_m at M (*state m*) to a value $p_n = p_a$



FIG. 529.

= one atmosphere at N(*state n*), at the end of stroke; so that when the piston returns the air will be expelled ("exhausted") at a tension equal to that of the external atmosphere (though at a low temperature). Hence the back-pressure at all points either way will be $= p_n$ per unit area of piston, and hence the total back-pressure $= Fp_n$, F being the piston area.

From O to D the forward pressure is constant and $= Fp_m$, and the effective work, therefore, or work on piston-rod from O to D, is

$$\textit{Work of entrance} = \Big[_O^D W = F[p_m - p_n]x_m, \quad . \ . \quad (1)$$

represented by the rectangle $M'MLN'$. The cut-off being made at D, the volume of gas now in the cylinder, viz., $V_m = Fx_m$, is left to expand. Assuming no device adopted (such as injecting hot-water spray) for preventing the cooling and rapid decrease of tension during expansion, the latter is *adiabatic*, and hence the tension at any point P between M and N will be

$$p = p_m\left(\frac{x_m}{x}\right)^{1.41} . \ . \ [\text{see } \S 478;\ V = Fx]; \ . \ . \ (a)$$

$\therefore$ *Work of expansion*

$$= \Big[_D^E W = \int_{x_m}^{x_n} F(p - p_n)dx = F\int_{x_m}^{x_n} pdx - Fp_n(x_n - x_m), \quad (2)$$

and is represented by the area $MPNL$.

But $$\int_m^n pdx = p\ x_m^{1.41}\int_{x_m}^{x_n} x^{-1.41}dx$$

$$= -2.44p_m x_m^{1.41}\left[\left(\frac{1}{x_n}\right)^{0.41} - \left(\frac{1}{x_m}\right)^{0.41}\right];$$

i.e., $$F\int_m^n pdx = 2.44Fp_m x_m\left[1 - \left(\frac{x_m}{x_n}\right)^{0.41}\right]. \quad . \ . \ . \quad (3)$$

Now substitute (3) in (2) and then add (2) to (1), noting that

$$F(p_m - p_n)x_m - Fp_n(x_n - x_m) = Fp_m x_m\left[1 - \frac{x_n p_n}{x_m p_m}\right],$$

which furthermore, since n and m are adiabatically related [see (a)], can be reduced to

$$Fp_m x_m\left[1 - \left(\frac{x_m}{x_n}\right)^{0.41}\right],$$

and we have finally:

$$\left.\begin{array}{l}\textit{Total work on piston-}\\ \textit{rod per stroke}\end{array}\right\} = W = 3.44Fx_m p_m\left[1 - \left(\frac{x_m}{x_n}\right)^{0.41}\right]. \quad (4)$$

But $Fx_m = V_m$, and the adiabatic relation holds good,

$$\left(\frac{V_m}{V_n}\right)^{1.41} = \left(\frac{p_n}{p_m}\right); \quad \text{i.e.,} \quad \left(\frac{x_m}{x_n}\right)^{0.41} = \left(\frac{p_n}{p_m}\right)^{0.29};$$

therefore we may also write

$$W = 3.44V_m p_m\left[1 - \left(\frac{p_n}{p_m}\right)^{0.29}\right]; \quad \ldots \quad (5)$$

in which V_m = the volume which the mass of air used per stroke occupies in the *state* m, i.e., in the reservoir, where the tension is p_m and the absolute temperature $= T_m$.

To find the *work done per pound of air used* (or other unit of weight), we must divide W by the weight $G = V_m\gamma_m$ of the air used per stroke, remembering (eq. (13), § 472) that

$$V_m\gamma_m = [V_m p_m \gamma_0 T_0] \div (T_m p_0).$$

$$\left.\begin{array}{l}\textit{Work per unit of weight of}\\ \textit{air used in adiabatic working}\end{array}\right\} = 3.44T_m\frac{p_0}{\gamma_0 T_0}\left[1 - \left(\frac{p_n}{p_m}\right)^{0.29}\right]. \quad (6)$$

The back-pressure $p_n = p_a$ = one atmosphere.

In (6), $\gamma_0 = 0.0807$ lbs. per cub. ft., $p_0 = (14.7 \times 144)$ lbs. per sq. ft., and $T_0 = 273°$ Abs. Cent., or $492°$ Abs. Fahr.

It is noticeable in (6) that for given tensions p_m and p_n, the work per unit of weight of air used is *proportional to the absolute temperature T_m of the reservoir*. The temperature T_n to which the air has cooled at the end of the stroke is obtained as in Example 2, § 478, and may be far below freezing-point unless T_m is very high or the ratio of expansion, $x_m : x_n$, large.

EXAMPLE.—Let the cylinder of a compressed-air engine have a section of $F = 108$ sq. in. and a stroke $x_n = 15$ inches. The compressed air entering the cylinder is at a tension of 2 atmos. (i.e., $p_m = 29.4$ lbs. per sq. in., and $p_n \div p_m = \frac{1}{2}$), and at a temperature of 27° Cent. (i.e., $T_m = 300°$ Abs. Cent.). Required the proper point of cut-off, or $x_m = ?$, in order that the tension may fall to one atmosphere at the end of the stroke; also the work per stroke, and the work per pound of air. Use the *foot*, *pound*, and *second*.

From eq. (*a*), above, we have

$$x_m = x_n\left(\frac{p_n}{p_m}\right)^{.71} = 1.25(\tfrac{1}{2})^{0.71} = 1.25 \times .6112 = 0.764 \text{ ft.},$$

and hence the volume of air in state m, used per stroke [eq. (5)] is

$$V_m = Fx_m = \tfrac{108}{144} \times 0.764 = 0.573 \text{ cubic feet;}$$

while the work per stroke is

$$W = 3.44 \times 0.573 \times 29.4 \times 144 \times [1 - (\tfrac{1}{2})^{.29}] = 1519 \text{ ft. lbs.},$$

and the work obtained from each pound of air, eq. (6),

$$= 3.44 \times 300 \times \frac{14.7 \times 144}{0.0807 \times 273} \times [1 - (\tfrac{1}{2})^{0.29}] = 18040$$

ft. lbs. per pound of air used.

The temperature to which the air has cooled at the end of stroke [eq. (2), § 478] is

$$T_n = T_m\left(\frac{p_n}{p_m}\right)^{0.29} = 300\times(\tfrac{1}{2})^{.29} = 300\times.818 = 245^\circ \text{ Abs. C.};$$

i.e., -28° Centigrade.

482. Remarks on the Preceding.—This low temperature is objectionable, causing, as it does, the formation and gradual accumulation of snow, from the watery vapor usually found in small quantities in the air, and the ultimate blocking of the ports. By giving a high value to T_m, however, i.e., by heating the reservoir, T_n will be correspondingly higher, and also *the work per pound of air*, eq. (6). If the cylinder be encased in a "jacket" of hot water, or if spray of hot water be injected behind the piston during expansion, the temperature may be maintained nearly constant, in which event Mariotte's law will hold for the expansion, and more work will be obtained per pound of air; but the point of cut-off must be differently placed. Thus if, in eq. (4), § 479, we make the back-pressure, q, equal to the value $(Fa \div Fl)p_b$, to which the air pressure has fallen at the end of the stroke by Mariotte's law, we have

$$\left.\begin{array}{l}\textit{Work per stroke with}\\ \textit{isotherm. expans.}\end{array}\right\} = Fap_b \log_{.\epsilon}\left(\frac{l}{a}\right) = V_b p_b \log_{.\epsilon}\left(\frac{l}{a}\right), \quad (1)$$

and hence

$$\left.\begin{array}{l}\textit{Work per unit of weight of air,}\\ \textit{with isothermal expansion}\end{array}\right\} = T_m \frac{p_0}{\gamma_0 T_0} \log_{.\epsilon}\left(\frac{l}{a}\right). \quad . \quad (2)$$

Applying these equations to the data of the example, we obtain

$$\left.\begin{array}{l}\text{Work per unit of weight of air with } \textit{iso-}\\ \textit{thermal expansion}\end{array}\right\} = 0.69\, T_m \frac{p_0}{\gamma_0 T_0};$$

$$\left.\begin{array}{l}\text{whereas, with } \textit{adiabatic expansion}\text{, work}\\ \text{per unit of weight of air is only}\end{array}\right\} = 0.63\, T_m \frac{p_0}{\gamma_0 T_0}.$$

483. Double-acting Air-compressor, with Adiabatic Compression.—This is the converse of § 481. In Fig. 530 we have the piston moving from right to left, compressing a mass of air which at the beginning of the stroke fills the cylinder. This is brought about by means of an external motor (steam-engine or turbine, e.g.) which exerts a thrust or pull along the piston-rod, enabling it with the help of the atmospheric pressure of the fresh supply of air flowing in behind it, to first *compress* a cylinder-full of air to the tension of the compressed air in the reservoir, and then, the port or valve opening at this stage, to force or *deliver* it into the reservoir. Let the temperature and tension of the cylinder-full of fresh air be T_{n_1} and p_{n_1}, and the tension in the reservoir be p_{m_1}. Suppose the compression adiabatic. As the piston passes from E toward the left, the air on the left has no escape and is compressed, its tension and temperature increasing adiabatically until it reaches a value p_{m_1} = that in reservoir, at which instant, the piston being at some point D, a valve opens and the further progress of the piston simply transfers the compressed air into the reservoir without further increasing its tension. Throughout the whole stroke the piston-rod has the help of one atmosphere pressure on the right face, since a new supply of air is entering on the right to be compressed in its turn on the return stroke. The work done from E to D may be called the *work of compression;* that from D to O, the *work of delivery.*



FIG. 530.

[Since, here, dx and dW (or increment of work) have contrary signs, we introduce the negative sign as shown.]

$$\textit{The work of compression} = -\int_E^D F(p - p_{n_1})dx. \quad . \quad . \quad . \quad (1c)$$

$$\textit{The work of delivery} \quad = -\int_D^O F(p_{m_1} - p_{n_1})dx. \quad . \quad . \quad (1d)$$

In these equations only p and x are variables. In the summation indicated in (1*c*) p changes adiabatically; in (1*d*) p is constant $= p_{m_1}$ as now written.

In the adiabatic compression the air passes from the state n_1 to the state m_1 (see N_1 and M_1 in figure).

The summations in these equations being of the same form as those in equations (1) and (2) of § 481, but with limits inverted, we may write immediately,

$$\text{Work per stroke} = W = 3.44 V_{m_1} p_{m_1} \left[1 - \left(\frac{p_{n_1}}{p_{m_1}}\right)^{0.29}\right], \quad (2)$$

and

$$\left.\begin{matrix}\text{Work per unit of weight} \\ \text{of air compressed}\end{matrix}\right\} = 3.44 T_{m_1} \frac{p_0}{\gamma_0 T_0}\left[1 - \left(\frac{p_{n_1}}{p_{m_1}}\right)^{0.29}\right]. \quad (3)$$

The value of T_{m_1}, at the immediate end of the sudden compression, by eq. (2) of § (478), is

$$T_{m_1} = T_{n_1}\left(\frac{p_{m_1}}{p_{n_1}}\right)^{0.29}. \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

The temperature of the reservoir being T_m, as in § 481 (usually much less than T_{m_1}), the compressed air entering it cools down gradually to that temperature, T_m, contracting in volume correspondingly since it remains at the same tension p_{m_1}. The mechanical equivalent of this heat is lost.

Let us now inquire what is the *efficiency of the combination* of air-compressor and compressed-air engine, the former supplying air for the latter, both working adiabatically, assuming that no tension is lost by the compressed air in passing along the reservoir between, i.e., that $p_{m_1} = p_m$. Also assume (as already implied, in fact) that $p_{n_1} = p_n =$ one atmos.; and that the temperature, T_{n_1}, of the air entering the compressor cylinder is equal to that, T_m, of the reservoir and transmission-pipe.

To do this we need only find the ratio of the amount of work obtained from one pound (or other unit of weight) in the compressed-air engine to the amount spent in compressing one pound of air in the compressor. Calling this ratio η, the

efficiency, and dividing eq. (6) of § 481 by eq. (3) of this paragraph, we have, with substitutions just mentioned,

$$\eta = \frac{T_m}{T_{m_1}} = \frac{\textit{Abs. temp. of outer free air}}{\left\{\begin{array}{l}\textit{Abs. temp. of air at end}\\ \textit{of sudden compression,}\end{array}\right.}; \quad . \quad . \quad (5)$$

or, substituting from eq. (4), and remembering that $T_{n_1} = T_m$, we have also

$$\eta = \left(\frac{p_n}{p_m}\right)^{0.29}; \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (6)$$

also, since

$$\left(\frac{p_n}{p_m}\right)^{0.29} = \frac{T_n}{T_m},$$

we may write

$$\eta = \frac{T_n}{T_m} = \frac{\text{Ab. tem. air leaving eng. cyl.}}{\text{Ab. tem. outer free air.}}. \quad . \quad (7)$$

For practical details of the construction and working of engines and compressors, and the actual efficiency realized, the student may consult special works, as they lie somewhat beyond the scope of the present work.

Example 1.—In the example of p. 634, the ratio of p_m to p_n was $= \frac{1}{2}$. Hence, if compressed air is supplied to the reservoir under above conditions, the efficiency of the system is, from eq. (6), $\eta = (\frac{1}{2})^{0.29} = 0.816$, about 82 per cent.

Example 2.—If the ratio of the tensions is as small as $\frac{p_n}{p_m} = \frac{1}{6}$, the efficiency would be only $(\frac{1}{6})^{0.29} = 0.59$; i.e., 40 per cent of the energy spent in the compressor is lost in heat.

Example 3.—What horse-power is required in a blowing engine to furnish 10 lbs. of air per minute at a pressure of 4 atmos., with adiabatic compression, the air being received by the compressor at one atmosphere tension and 27° Cent. (ft.-lb.-sec. system). Since 27° C. = 300° Abs. C. = T_{n_1}, we have, from eq. (4),

$$T_{m_1} = 300(\tfrac{4}{1})^{0.29} = 448.5° \text{ Abs. Cent.};$$

and hence, eq. (3),

$$\left.\begin{matrix}\textit{The work per}\\ \textit{pound of air}\end{matrix}\right\} = 3.44 \times 448.5 \frac{14.7 \times 144}{.0807 \times 273}\left[1 - \left(\frac{1}{4}\right)^{0.29}\right]$$

$= 49060$ ft. lbs. per pound of air. Hence 10 lbs. of air will require 490600 ft. lbs. of work; and if this is done every minute we have the req. H.P. $= \frac{490600}{33000} = 14.8$ H.P.

NOTE.—If the compression could be made *isothermal*, an approximation to which is obtained by injecting a spray of cold water, we should have, from eqs. (1) and (2) of § 482:

$$\left.\begin{matrix}\textit{Work per}\\ \textit{lb. air}\end{matrix}\right\} = T_{n_1} \frac{p_0}{\gamma_0 T_0} \log_e\left(\frac{p_{m_1}}{p_{n_1}}\right) = \frac{300 \times 14.7 \times 144}{.0807 \times 273} \times 1.386$$

$= 39950$ ft. lbs. per lb., and the corresponding H. P. $= 12.1$; a saving of about 25 per cent, compared with the former. The difference was employed in heating the air in the air-compressor with adiabatic compression, and was lost when that extra heat was dissipated in the reservoir as the air cooled again. This difference is easily shown graphically by comparing in the same diagram the areas representing the work done in the two cases.*

484. Hot-air Engines.—Since we have seen that the tension of air and other gases can be increased by heating, if the volume be kept the same, a mass of air thus treated can afterwards be allowed to expand in a working cylinder, and thus become a means of converting heat into work. In *Stirling's* hot-air engine a definite confined mass of air is used indefinitely without loss (except that occasional small supplies are needed to make up for leakage), and is alternately heated and cooled. A displacement-plunger, or piston, fitting loosely in a bell-like chamber, is so connected with the piston of the working cylinder and the fly-wheel, that its forward stroke is made while the other piston waits at the beginning of its stroke. In this motion the plunger causes the confined air to pass in a thin sheet over the top and sides of the furnace dome, thus greatly increasing its tension. The air then expands behind the working piston with falling tension and temperature, and,

* See *Eng. News*, pp. 234 and 297, Oct. and Nov. 1897, for an account of a "four-stage" compressor and test of same.

while that piston pauses at the end of its forward stroke, is again shifted in position, though without change of volume, by the return stroke of the plunger, in such a way as to pass through a coil of pipes in which cold water is flowing. This reduces both its temperature and tension, and hence its resistance to the piston on the return stroke is at first less than atmospheric, but is gradually increased by the compression. This cycle of changes is repeated indefinitely, and is easily traced on a diagram like that in Fig. 528, and computations made accordingly.

A special invention of Stirling's is the "*regenerator*" or box filled with numerous sheets of wire gauze, in its passage through which the working air, after expansion, deposits some of its heat, which it *re-absorbs* to some extent when, after further cooling in the "refrigerator" or pipe coil and compression by the return stroke of the piston, it is made to pass backward through the regenerator to be further heated by the furnace in readiness for a forward stroke. This feature, however, has not realized all the expectations of its inventor and improvers, as to economy of heat and fuel.

In *Ericsson's* hot-air engine, of more recent date, the displacement-plunger fits its cylinder air-tight, but valves can be opened through its edges when moving in one direction, thus causing it to act temporarily as a loose plunger, or shifter. The two pistons move simultaneously in the same direction in the same cylinder, but through different lengths of stroke, so that the space between them is alternately enlarged and contracted. The working piston also has valves opening through it for receiving a fresh supply of air into the space between the two pistons. During the forward stroke a fresh instalment from the outer air enters through the working piston into the space between it and the other, whose valves are now closed and which is now expelling from its further face, through proper valves, the air used in the preceding stroke; no work is done in this stroke. On the return stroke this fresh supply of air is free to expand behind the now retreating working piston, while its tension is greatly increased by its being shifted (at least a large portion of it) over the furnace

dome through the valve (now open) of the plunger piston, by the motion of the latter, which now acts as a loose plunger The engine is therefore only single-acting, no work being done in each forward stroke.

During the last thirty years (1878 to 1908) numerous small hot-air engines have been used for domestic pumping of water, many of them being of the Stirling type, (though some of these have borne the Ericsson name, commercially).

485. Internal-Combustion Engines.—In the case of the Stirling and Ericsson hot-air engines, the heat was derived from a source outside of the working cylinder. Another class is called "*internal-combustion*" engines, from the fact that the air used is heated by the combustion of inflammable gas, or of oil spray or vapor, *within the working cylinder itself*. These motors are "gas-engines" and "oil-engines."

486. Gas-engines.—If a mixture of atmospheric air and illuminating gas (from bituminous coal) or "producer gas" (made by passing steam over incandescent anthracite coal) in the proportion of about ten parts of air to one of gas, is introduced into the working cylinder and ignited at the beginning of a stroke, a very sudden rise of temperature and of pressure occurs; after which the fluid expands, with diminishing pressure, behind the moving piston, thus doing work on the latter. On the return stroke the nitrogen and products of combustion are expelled (more or less completely) from the cylinder, but no work is done. With most gas-engines the inflammable charge of air and gas is *compressed* before ignition; since in that way more power is obtained from a given size of cylinder, and less heat is lost to the cylinder walls (which are of necessity kept cool by a "water-jacket," to avoid decomposition of lubricants). The ignition is also rendered more certain; an electric spark being frequently used for this purpose.

In the "Otto Silent Gas-engine" the explosion occurs only every fourth stroke, and one side of the piston is always open to the air. The action on the other side of the piston is as follows: (1) In the forward stroke a fresh supply of explosive mixture is drawn into the cylinder at one atmosphere tension. (2) The next (backward) stroke compresses the mixture into

about one-fourth of its original bulk, this operation occurring at the expense of the kinetic energy of the fly-wheel. (3) The mixture is ignited, the pressure rises to 8 or 10 atmospheres, and work is done on the piston through the next (forward) stroke, the tension of the products of combustion having fallen to about two atmospheres at the end of the stroke. (4) In the next (backward) stroke the products of combustion are expelled and no work is done.

The "Atkinson Cycle Gas-engine" [no longer manufactured (1908); see London Engineer, May, 1887, pp. 361 and 380] also made an explosion every fourth stroke, but the link work connecting the piston and fly-wheel was of such design that the latter made but one revolution during the four strokes. Also the length of the expansion or working stroke was greater than that of the compression stroke and the products of combustion were completely expelled.

486a. Oil-engines.—The Priestman engine is a prominent one of this class. The "oils" which may be used are petroleum, kerosene, gasoline, alcohol, etc.; gasoline being among the cheapest, but the most dangerous in storage. For use in each cycle of four strokes a small quantity of the oil is first converted into spray, and then into vapor in the "vaporizer," a chamber heated sufficiently for vaporizing, but not so hot as to produce premature ignition. Air charged with this vapor is drawn into the cylinder during the first stroke of the cycle and is compressed on the return stroke; while at the beginning of the third, or working stroke, the vapor is ignited by an electric spark (or otherwise), and by its combustion produces a high temperature and pressure in the air within the cylinder; the remaining action being as with the Otto gas-engine just mentioned.

In the Diesel oil-engine, which also has a four-stroke cycle, a cylinderful of air is compressed in the second stroke to a pressure of some 500 lbs./in.^{2}, its temperature being then so high (*from adiabatic compression*) that upon the injection of a small quantity of oil spray the latter is immediately ignited. This engine has a very high thermal efficiency. The Hornsby-Akroyd oil-engine is somewhat similar to the Diesel. (See *Internal combustion Engines* by Profs. Carpenter

and Diederichs; also Robinson's *Gas and Petroleum Engines.*

487. Thermal Efficiency of Heat-engines.—According to the mechanical theory of heat, the combustion of one pound of good coal, producing as it does some 14,000 heat-units (British Thermal Units, or "B.T.U.;" see § 149) should furnish ($14{,}000 \times 778 =$) 1,089,200 ft.-lbs. of work, if entirely converted into work.

The triple and quadruple expansion steam-engines, and the more recent steam-turbines of Atlantic steamships, consume in their furnaces about 1.50 lbs. of coal per hour for each horse-power of effective work done on their pistons (or other moving part); (1.3 lbs. of coal per H.P. hour in exceptional instances). The work equivalent of 1.5 lbs. of coal per hour is $1.5 \times 14{,}000 \times 778 = 16{,}340{,}000$ ft.-lbs. per hour, while the actual work per hour implied in "one H.P. per hour" is $33{,}000 \times 60 = 1{,}980{,}000$ ft.-lbs. per hour.

That is, even these engines utilize only about *one-eighth* of the heat of combustion of the fuel.

In the case of the gas-engine, the water jacket (a necessary evil) is a source of much loss of heat and work. Nevertheless, the Atkinson gas-engine was found capable of turning into work one-fifth of the heat of combustion of the gas used; that is, it developed a thermal efficiency of 20 per cent. Small gas-engines are about as economical in this respect as large steam-engines.

The highest record in this connection is held by the Diesel oil-engine. In 1902, at Harrogate, England, a commercial test of a 35 H.P. Diesel engine, using crude petroleum of 19,000 B.T.U. heat of combustion per lb., showed a heat efficiency of 36 per cent for the power developed in the cylinder, and 29 per cent for power obtained on the friction brake. (See p. 885, Robinson's *Gas and Petroleum Engines*).

488. "Duty" of Large Steam Pumping-engines.—Previous to 1891 the form of expressing the degree of economy attained in the use of fuel by the combined furnace, boiler, and engine, of a steam-pumping engine, was to state the number of ft.-lbs. of work done in the cylinders for each 100 lbs. of coal used under the boiler; this performance being called the "*duty*" of the engine. For example, if

the duty was 120,000,000, it meant that from each 100 lbs. of coal 120,000,000 ft.-lbs. of work was done in the cylinders, or 1,200,000 ft.-lbs. of work was obtained from one pound of coal. This would imply a fuel consumption at the rate of 1.65 lbs. of coal per hour for each horse-power (since $33{,}000 \times 60 \div 1{,}200{,}000 = 1.65$); or a thermal efficiency of 1/9, i.e., 11.1 per cent.

But since there is much variation in the heating quality of coal, the Am. Soc. of Mech. Engr's established a new definition in 1891 for "duty," viz., the number of ft.-lbs. of work obtained for *each million heat-units* furnished by the boiler to the engine. In this way, also, the performance of the engine is separated from that of the boiler and furnace.

The new unit coincides with the old in case each 100 lbs. of the coal used imparts 10,000 heat-units to the boiler (which is quite attainable in the case of good anthracite).

In the *Engineering News* of Jan. 10, 1907, p. 50, are given the results of a "duty trial" of a "Snow" high-duty pumping-engine at Mahanoy City, Pa. The duty attained was 141,400,000; i.e., a thermal efficiency of about 16 per cent.

489. Buoyant Effort of the Atmosphere.—In the case of a body of large bulk but of small specific gravity the buoyant effort of the air (due to the same cause as that of water, see § 456) becomes quite appreciable, and may sometimes be greater than the weight of the body. This buoyant effort is equal to the weight of air displaced, i.e., $= V\gamma$, where V is the volume of air displaced, and γ its heaviness.

If G_1 = total weight of the body producing the displacement, the resultant vertical force is

$$P = G_1 - V\gamma, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

and for equilibrium, or *suspension in the air*, we must have $P = 0$, i.e.,

$$G_1 = V\gamma. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

We may therefore find approximately the elevation where a given balloon will cease to ascend, by determining the heaviness γ of the air at that elevation from eq. (2); then, knowing approximately the temperature of the air at that elevation,

we may compute its tension p [eq. (13), § 472], and finally, from eqs. (3), (4), or (5) of § 477, obtain the altitude required.

EXAMPLE.—The car and other solid parts of a balloon weigh 400 lbs., and the bag contains 12,000 cub. feet of illuminating gas weighing 0.030 lb. per cub. foot at a tension of one atmosphere and temperature of 15° Cent., so that its total weight $= 12{,}000 \times 0.030 = 360$ lbs.

Hence $G_1 = 760$ lbs. We may also write with sufficient accuracy: Whole volume of displacement $= V = 12{,}000$ cub. ft.

As the balloon ascends the exterior pressure diminishes, and the confined gas tends to expand and so increase the volume of displacement V; but this we shall suppose prevented by the strength of the envelope. At the surface of the ground (station n of Fig. 531; see also Fig. 526) let the barometer read 29.6 inches and the temperature be 15° Cent. Then $T_n = 288°$ Abs. Cent., and the heaviness of the air at n is



FIG. 531.

$$\gamma_n = \frac{.0807 \times 273}{14.7} \cdot \frac{\frac{29.6}{30} \times 14.7}{288}$$

$$\left(= \frac{\gamma_0 T_0 p_n}{p_0 T_n}\right) = .0807 \times \frac{273}{288} \cdot \frac{29.6}{30} = .0754 \text{ lbs. per cub. ft.}$$

At the unknown height h, where the balloon is to come to rest, i.e., at M, G_1 must $= V\gamma$ [eq. (2)]; therefore

$$\gamma_m = \frac{G_1}{V} = \frac{760 \text{ lbs.}}{12{,}000 \text{ cub. ft.}} = .0633 \text{ lbs. per cub. ft.};$$

and if the temperature at M be estimated to be 5° Cent. (or $T_m = 278°$ Abs. Cent.) (on a calm day the temperature decreases about 1° Cent. for each 500 ft. of ascent), we shall have, from $\frac{p_m}{\gamma_m T_m} = \frac{p_n}{\gamma_n T_n}$,

$$\frac{p_n}{p_m} = \frac{\gamma_n T_n}{\gamma_m T_m} = \frac{.0754}{.0633} \cdot \frac{288}{278} = 1.206;$$

and hence, from eq. (5), § 477, with $\frac{1}{2}(T_m + T_n)$ put for T_n,

$$h = 26213 \times \tfrac{283}{273} \times 2.30258 \times \log_{10} 1.206 = 5088 \text{ ft.}$$

CHAPTER VI.

HYDROKINETICS BEGUN—STEADY FLOW OF LIQUIDS THROUGH PIPES AND ORIFICES.

489a. The subject of **Water in Motion** presents one of the most unsatisfactory branches of Applied Mechanics, from a mathematical stand-point. The internal eddies, cross-currents, and general intricacy of motion of the particles among each other, occurring in a pipe transmitting a fluid, are almost entirely defiant of mathematical expression, though the flow of water through a circular orifice in a thin plate into the air presents a simpler case, where the conception of "stream lines" is probably quite close to the truth. In most practical cases we are forced to adopt as a basis for mathematical investigation the simple assumption that the particles move side by side in such a way that those which at any instant form a lamina or thin sheet, ⊓ to the axis of the pipe or orifice, remain together as a lamina during the further stages of the flow. This is the Hypothesis of Flow in Plane Layers, or Laminated Flow. Experiment is then relied on to make good the discrepancies between the indications of the formulæ resulting from this theory and the actual results of practice; so that the science of Hydrokinetics is largely one of coefficients determined by experiment.

490. Experimental Phenomena of a "Steady Flow."—As preliminary to the analysis on which the formulæ of this chapter are based, and to acquire familiarity with the quantities involved, it will be advantageous to study the phenomena of the apparatus represented in Fig. 532. A large tank or reservoir BC is connected with another, DE, at a lower level, by means of a rigid pipe opening under the water-level in each tank. This

pipe has no sharp curves or bends, is of various sectional areas at different parts, the changes of section being very gradual, and the highest point N_2 not being more than 30 ft. higher than BC, the surface-level of the upper tank. Let both tanks



FIG. 532.

be filled with water (or other liquid), which will also rise to H and to K in the pipe. Stop the ends L and N_4 of the pipe, and through M, a stop-cock in the highest curve, pour in water to fill the remainder of the pipe; then, closing M, unstop L and N_4.

The water in the pipe will now begin to acquire movement from L toward N_4, with an accelerating velocity at every section, but in a very short time the velocity at any section (mean velocity) will have reached a *maximum value, at which it remains practically constant*, if the reservoir BC is kept full by a suitable continual influx at A. A "**Steady Flow**" is now said to have set in, or a "*state of permanency*" is said to exist; that is, the circumstances of the flow at each section of the pipe are *permanent*, or *steady*.

Even without influx at A, if reservoir BC is very large compared with the capacity of the pipe the flow will be essentially steady after the preliminary short period of acceleration; (see foot-note on next page).

By measuring the volume, V, of water discharged at E in a time t, we obtain the *volume of flow per unit of time*, viz.,

$$Q = \frac{V}{t}, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

while the *weight of flow* per unit of time is

$$G = Q\gamma, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

where γ = heaviness (§ 7) of the liquid concerned.

Water being incompressible and the pipe rigid, it follows that the same volume of water per unit of time must be passing at each cross-section of the pipe. But this is equal to the volume of a prism of water having F, the area of the section, as a base, and, as an altitude, the mean velocity $= v$ with which the liquid particles pass through the section. Hence for any section we have

$$Q = Fv = \text{constant} = F_1v_1 = F_2v_2, \text{ etc.} \left\{ \begin{matrix} \textit{Equat. of} \\ \textit{continuity} \end{matrix} \right\}, \quad . \quad (3)$$

in which the subscripts refer to different sections. If the flow were *unsteady*, e.g., if the level BC were sinking, this would be true for a definite instant of time; but when *steady*, we see that it is permanently true; e.g., F_1v_1 at any instant $= F_2v_2$ at the same or *any other* instant, subsequent or previous. In other words, *in a steady flow the velocity at a given section remains unchanged with lapse of time.**

[N.B. We here assume for simplicity that the different particles of water passing simultaneously through a given section (i.e., abreast of each other) have equal velocities, viz., the velocity which all other particles will assume on reaching this section. Strictly, however, the particles at the sides are somewhat retarded by friction on the surface of the pipe. This assumption is called the *Assumption of Parallel Flow*, or *Flow in Plane Layers*, or *Laminated Flow*.]

Let us suppose Q to have been found as already prescribed. We may then, knowing the internal sectional areas at different parts of the pipe, N_1, N_2, etc., compute the velocities

* The flow of water in the drive-pipe of a hydraulic ram is a familiar instance of an *unsteady* flow. The water in this pipe is permitted to flow with an accelerated motion for a short time and then suddenly brought to rest; this operation being repeated indefinitely.

$$v_1 = Q \div F_1, \quad v_2 = Q \div F_2, \quad \text{etc.},$$

which the water must have in passing those sections, respectively. It is thus seen that the velocity at any section has no direct connection with the height or depth of the section from the plane, BC, of the upper reservoir surface. The fraction $\frac{v^2}{2g}$ will be called the *height due to the velocity*, v, or simply the *velocity-head*, for convenience.

Next, as to the value of the internal fluid pressure, p, per unit-area (in the water itself and against the side or wall of pipe) at different sections of the pipe. If the end N_4 of the pipe were stopped, the problem would be one in Hydrostatics, and the pressure against the side of the pipe at N_1 (also at N_3 on same level) would be simply

$$p_1 = p_a + h_1\gamma,$$

measured by a water column of height

$$\frac{p_1}{\gamma} = \frac{p_a}{\gamma} + h_1 = b + h_1,$$

in which p_a = one atmosphere, and b = 34 ft. = height of an ideal water barometer, and γ = 62.5 lbs. per cubic foot; and this would be shown experimentally by screwing into the side of the pipe at N_1 a small tube open at both ends; the water would rise in it to the level BC. That is, a column of water of height = h_1 would be sustained in it, which indicates that the internal pressure at N_1 corresponds to an ideal water column of a height

$$= \frac{p_1}{\gamma} = b + h_1.$$

But when a steady flow is proceeding, the case being now one of Hydrokinetics, we find the column of water sustained at rest in the small tube (called an *open piezometer*) N_1S has a height y_1, *less* than h_1, and hence the internal fluid pressure is

less than it was when there was no flow.* This pressure being called p_1, the ideal water column measuring it has a height

$$\frac{p_1}{\gamma} = b + y_1 \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

at N_1, and will be called the *pressure-head* at the section referred to. We also find experimentally that while the flow is steady the piezometer-height y (and therefore the pressure-head $b + y$) at any section remains unchanged with lapse of time, as a characteristic of a steady flow.

[For correct indications, the extremity of the piezometer should have its edges flush with the inner face of the pipe wall, where it is inserted.]

At N_3, although at the same level as N_1, we find, on inserting an open piezometer, W, that with $F_3 = F_1$ (and therefore with $v_3 = v_1$) y_3 is a little less than y_1; while if $F_3 < F_1$ (so that $v_3 > v_1$), y_3 is not only less than y_1, but the difference is greater than before. We have therefore found experimentally that, in a general way, when water is flowing in a pipe it presses less against the side of the pipe than it did before the flow was permitted, or (what amounts to the same thing) the pressure between the transverse laminæ is less than the hydrostatic pressure would be.

In the portion HN_2O of the pipe we find the pressure less than one atmosphere, and consequently a manometer registering pressures from zero upward (and not simply the excess over one atmosphere, like the Bourdon steam-gauge and the open piezometer just mentioned) must be employed. At N_2, e.g., we find the pressure

$$= \tfrac{1}{2} \text{ atmos., i.e., } \frac{p_2}{\gamma} = 17 \text{ ft.}$$

Even below the level BC, by making the sections quite narrow (and consequently the velocities great) the pressure may be made less than one atmosphere. At the surface BC the pressure is of course just one atmosphere, while that in the jet at N_4, entering the right-hand tank under water, is necessarily

$p_4 = 1$ atmos. + press. due to col. h' of water practically at rest;

* N_4 being stopped and L open.

$$\text{i.e., } \frac{p_4}{\gamma} = \text{pressure-head at } N_4 = b + h';$$

(whereas if N_4 were stopped by a diaphragm, the pressure-head just on the right of the diaphragm would be $b + h'$, and that on the left $b + h_4$.)

Similarly, when a jet enters the atmosphere in parallel filaments its particles are under a pressure of one atmosphere, i.e., their pressure-head $= b = 34$ ft. (for water); for the air immediately around the jet may be considered as a pipe between which and the water is exerted a pressure of one atmosphere.

491. Recapitulation and Examples.—We have found experimentally, then, that in a steady flow of liquid through a rigid pipe there is at each section of the pipe a definite velocity and pressure which all the liquid particles assume on reaching that section; in other words, at each section of the pipe the liquid velocity and pressure remain constant with progress of time.

Example 1.—If in Fig. 532, the flow having become steady, the volume of water flowing in 3 minutes is found on measurement to be 134 cub. feet, the volume per second is, from eq. (1), § 490,

$$Q = \tfrac{134}{180} = 0.744 \text{ cub. ft. per second.}$$

Example 2.—If the flow in 2 min. 20 sec. is 386.4 lbs., the volume of flow per second is [ft., lb., sec.; eqs. (1) and (2)]

$$Q = \frac{V}{t} = \frac{G}{\gamma} \div t = \frac{386.4}{62.5} \cdot \frac{1}{140} = 0.0441 \text{ cub. ft. per sec.}$$

Example 3.—In Fig. 532 the height of the open piezometer at N_1 is $y_1 = 9$ feet; what is the internal fluid pressure? [Use the inch, lb., and sec.] The internal pressure is

$$p_1 = p_a + y_1\gamma = 14.7 + 108 \times \tfrac{62.5}{1728} = 18.6 \text{ lbs. per sq. inch.}$$

The pressure on the outside of the pipe is, of course, one atmosphere, so that the resultant bursting pressure at that point (N_1) is 3.9 lbs. per sq. in.

Example 4.—The volume of flow per second being .0441

cub. ft. per sec., as in Example 1, required the velocity at a section of the (circular) pipe where the diameter is 2 inches. [Use ft., lb., and sec.]

$$v = \frac{Q}{F} = \frac{0.0441}{\frac{1}{4}\pi(\frac{2}{12})^2} = 2.02 \text{ ft. per sec.};$$

while at another section of the pipe where the diameter is four inches (double the former) and the sectional area, F, is therefore four times as great, the velocity is $\frac{1}{4}$ of $2.02 = 0.505$ ft. per sec.

492. Bernoulli's Theorem for Steady Flow; without Friction.— If the pipe is comparatively short, without sudden bends, elbows, or abrupt changes of cross-section, the effect of friction of the liquid particles against the sides of the pipe and against each other (as when eddies are produced, disturbing the parallelism of flow) is small, and will be neglected in the present analysis, whose chief object is to establish a formula for steady flow through a short pipe and through orifices.

An assumption, now to be made, of *flow in plane layers*, or *laminated flow*, i.e., flow in laminæ ⌐ to the axis of the pipe at every point, may be thus stated: (see Fig. 533, which shows a steady flow proceeding, through a pipe CD of indefinite extent.) All the liquid particles which at any instant form a small lamina, or sheet, as AB, ⌐ to axis of pipe, *keep company as a lamina throughout the whole flow.* The thickness, ds', of this lamina remains constant so long as the pipe is of constant cross-section, but shortens up (as at C) on passing through a larger section, and lengthens out (as at D) in a part of the pipe where the section is smaller (i.e., the sectional area, F, is smaller). The mass of such a lamina is $Fds'\gamma \div g$ [§ 55], its velocity at any section will be called v (pertaining to that point of the pipe's axis), the pressure of the lamina just behind it is Fp, upon the rear face, while the resistance (at the same instant) offered by its neighbor just ahead is $F(p + dp)$ on the front face; also



FIG. 533.

its weight is the vertical force $Fds'\gamma$. Fig. 534 shows, as a free body, the lamina which at any instant is passing a point A of the pipe's axis, where the velocity is v and pressure p.



FIG. 534.

Note well the forces acting; the pressures of the pipe wall on the edges of the lamina have no components in the direction of v, for the wall is considered smooth, i.e., those pressures are ⊥ to wall; in other words, no friction is considered. To this free body apply eq. (7) of § 74, for any instant of any curvilinear motion of a material point

$$vdv = (tang.\ acceleration) \times ds, \quad . \quad . \quad . \quad . \quad (1)$$

in which ds = a small portion of the path, and is described in the time dt. Now the tang. accel. = Σ(tang. compons. of the acting forces) ÷ mass of lamina, i.e.,

$$tang.\ acc. = \frac{Fp - F(p+dp) + F\gamma ds' \cos\phi}{F\gamma ds' \div g}. \quad . \quad (2)$$

Now, Fig. 535, at a *definite instant of time*, conceive the volume of water in the pipe to be subdivided into a great number of laminæ of *equal mass* (which implies equal volumes



FIG. 535.

in the case of a liquid, but not with gaseous fluids), and let the ds just mentioned for any one lamina be the distance from its centre to that of the one next ahead; this mode of subdivision

makes the ds of any one lamina identical in value with its thickness ds', i.e.,

$$ds = ds'. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

We have also

$$ds \cos \phi = -dz, \quad \text{or} \quad ds' \cos \phi = -dz; \quad . \quad . \quad (4)$$

z being the height of the centre of a lamina above any convenient horizontal datum plane. Substituting from (2), (3), and (4) in (1), we derive finally

$$\frac{1}{g} v dv + \frac{1}{\gamma} dp + dz = 0. \quad . \quad . \quad . \quad . \quad . \quad (5)$$

The flow being steady, and the subdivision into laminæ being of the nature just stated, each lamina in some small time dt moves into the position which at the beginning of dt was filled by the lamina next ahead, *and acquires the same velocity, the same pressures on its faces, and the same value of* z, *that the front lamina had at the beginning of* dt.

Hence, considering the simultaneous advance made by all the laminæ in this same dt, we may write out an equation like (5) for each of the laminæ between any two cross-sections n and m of the pipe, thus obtaining an infinite number of equations, from which by adding corresponding terms, i.e., *by integration*, we obtain

$$\frac{1}{g} \int_{v_n}^{v_m} v dv + \frac{1}{\gamma} \int_{p_n}^{p_m} dp + \int_{z_u}^{z_m} dz = 0; \quad . \quad . \quad . \quad (6)$$

whence, performing the integrations and transposing,

$$\frac{v_m^2}{2g} + \frac{p_m}{\gamma} + z_m = \frac{v_n^2}{2g} + \frac{p_n}{\gamma} + z_n \quad . \quad . \quad \left\{ \begin{matrix} \textit{Bernoulli's} \\ \textit{Theorem} \end{matrix} \right\} \quad . \quad . \quad (7)$$

Denoting by *Potential Head* the vertical height of any section of the pipe above a convenient datum level, we may state Bernoulli's Theorem as follows:

In steady flow without friction, the sum of the velocity-head, pressure-head, and potential head at any section of the pipe is a constant quantity, being equal to the sum of the corresponding heads at any other section.

It is noticeable that in eq. (7) each of the terms is a linear quantity, viz., a height, or head, either actual, such as z_n and z_m, or ideal (all the others), and does not bring into account the absolute size of the pipe, nor even its relative dimensions (v_m and v_n, however, are connected by the equation of continuity $F_m v_m = F_n v_n$), and contains no reference to the volume of water flowing per unit of time [Q] or the shape of the pipe's axis. When the pipe is of considerable length compared with its diameter the friction of the water on the sides of the pipe cannot be neglected (§ 512).

It must be remembered that Bernoulli's Theorem does not hold unless the flow is *steady*, i.e., unless each lamina, in coming into the *position* just vacated by the one next ahead (of equal mass), comes also into the exact conditions of velocity and pressure in which the other was when in that position.

[N.B. This theorem can also be proved by applying to all the water particles between n and m, as a collection of small *rigid* bodies (water being incompressible) the theorem of Work and Energy for a collection of Rigid Bodies in § 142, eq. (xvi), taking the respective paths which they describe simultaneously in a single dt.]

493. First Application of Bernoulli's Theorem without Friction. —Fig. 536 shows a large tank from which a vertical pipe of uniform section leads to another tank and dips below the surface of the water in the latter. Both surfaces are open to the air. The vessels and pipe being filled with water, and the lower end m of the pipe unstopped, a steady flow is established almost immediately, the surface BC being very large compared with F, the area of the (*uniform*) section of the pipe.



FIG. 536.

Given F, and the heights h_0 and h, required the velocity v_m of the jet at m and also the pressure, p_n, at n (in pipe near entrance of same). m is in the jet, just clear of the pipe, and practically in the water-level, AD. The velocity v_m is unknown, but the pressure p_m is practically $= p_a =$ one atmosphere, since

the pressure on the sides of the jet is necessarily the hydrostatic pressure due to a slight depth below the surface AD.

$$\therefore \textit{Press.-head at } m \textit{ is } \frac{p_m}{\gamma} = \frac{p_a}{\gamma} = b = 34 \text{ feet.} \quad . \quad . \quad (\S\ 423)$$

Now apply Bernoulli's Theorem to sections m and n, taking a horizontal plane through m as a datum plane for potential heads, so that $z_n = h$ and $z_m = 0$, and we have

$$\frac{v_m^2}{2g} + b + 0 = \frac{v_n^2}{2g} + \frac{p_n}{\gamma} + h. \quad . \quad . \quad . \quad . \quad (1)$$

But, *assuming that the section of the pipe is filled at every point*, we must have

$$v_m = v_n;$$

for, in the equation of continuity

$$F_m v_m = F_n v_n,$$

if we put $F_m = F_n$, the pipe being of uniform section, we obtain $v_m = v_n$. Hence eq. (1) reduces to

$$\frac{p_n}{\gamma} = b - h = 34 \text{ ft.} - h. \quad . \quad . \quad . \quad . \quad . \quad (2)$$

Hence the pressure at n is *less than one atmosphere*, and if a small tube communicating with an air-tight receiver full of air were screwed into a small hole at n, the air in the receiver would gradually be drawn off until its tension had fallen to a value p_n. [This is the principle of *Sprengel's air-pump*, mercury, however, being used instead of water, as for this heavy liquid b = only 30 inches.]



FIG. 537.

If h is made $> b$ for water, i.e. > 34 feet (or > 30 inches for mercury), p_n would be negative from eq. (2), which is impossible, showing that the assumption of full pipe-sections is not borne out. In this case, $h > b$, only a portion, mn', (in length somewhat less than b,) of the tube will be kept full

during the flow (Fig. 537); while in the part Kn' vapor of water, of low tension corresponding to the temperature (§ 469), will surround an internal jet which does not fill the pipe. As for the value of v_m, Bernoulli's Theorem, applied to BC and m, in Fig. 536, gives finally $v_m = \sqrt{2gh_0}$.

EXAMPLE.—If $h = 20$ feet, Fig. 536, and the liquid is water, the pressure-head at n is (ft., lb., sec.)

$$\frac{p_n}{\gamma} = b - h = 34' - 20' = 14 \text{ ft.},$$

and therefore

$$p_n = 14 \times 62.5 = 875 \text{ lbs. per sq. ft.} = 6.07 \text{ lbs. per sq. in.}$$

494. Second Application of Bernoulli's Theorem without Friction.—Knowing by actual measurement the open piezometer height y_n at the section n in Fig. 538 (so that the pressure-head, $\frac{p_n}{\gamma} = b + y_n$, at n is known); knowing also the vertical distance h_n from n to m, and the respective cross-sections F_n and F_m (F_m being the sectional area of the jet, flowing into the air, so that $\frac{p_m}{\gamma} = b$), required the volume of flow per sec.; i.e., required Q, which



FIG. 538.

$$= F_n v_n = F_m v_m. \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

The pipe is short, with smooth curves, if any, and friction will therefore be neglected. From Bernoulli's Theorem [eq. (7), § 492], taking m as a datum plane for potential heads, we have

$$\frac{v_m^2}{2g} + b + 0 = \frac{v_n^2}{2g} + (y_n + b) + h_n. \quad . \quad . \quad . \quad (2)$$

But from (1) we have

$$v_n = [F_m \div F_n] v_m;$$

substituting which in (2) we obtain, solving for v_m,

$$v_m = \frac{\sqrt{2g(y_n + h_n)}}{\sqrt{1 - \left(\frac{F_m}{F_n}\right)^2}}, \quad \ldots\ldots \quad (3)$$

and hence the volume per unit of time becomes known, viz.,

$$Q = F_m v_m. \quad \ldots\ldots \quad (4)$$

NOTE.—If the cross-section F_m of the nozzle, or jet, is $> F_n$, v_m becomes imaginary (unless y_n is *negative* (i.e., $p_n <$ one atmos.), and numerically $> h_n$); in other words, the assigned cross-sections are *not filled by the flow.*

EXAMPLE.—If $y_n = 17$ ft. (thus showing the internal fluid pressure at n to be $p_n = \gamma(y_n + b) = 1\frac{1}{2}$ atmos.), $h_n = 10$ ft., and the (round) pipe is 4 inches in diameter at n and 3 inches at the nozzle m, we have from (3) (using ft.-lb.-sec. system of units in which $g = 32.2$)

$$v_m = \frac{\sqrt{2 \times 32.2(17 + 10)}}{\sqrt{1 - \left[\frac{\frac{1}{4}\pi 3^2}{\frac{1}{4}\pi 4^2}\right]^2}} = 50.4 \text{ ft. per sec.}$$

[N.B. Since $F_m \div F_n$ is a ratio and therefore an abstract number, the use of the inch in the ratio will give the same result as that of the foot.]

Hence, from (4),

$$Q = F_m v_m = \tfrac{1}{4}\pi(\tfrac{3}{12})^2 \times 50.4 = 2.474 \text{ cub. ft. per sec.}$$

495. Orifices in Thin Plate.—Fig. 539. When efflux takes place through an orifice in a thin plate, i.e., a *sharp-edged* orifice in the plane wall of a tank, a contracted vein (or "vena

contracta") is formed, the filaments of water not becoming parallel until reaching a plane, m, parallel to the plane of vessel wall, which for circular orifices is at a distance from the interior plane of vessel wall equal to the radius of the circular aperture; and not until reaching this plane does the internal fluid pressure become equal to that of the surrounding medium (atmosphere, here), i.e., surrounding the jet. We assume that the width of the orifice is small compared with h, unless the vessel wall is horizontal.



FIG. 539.

The area of the cross-section of the jet at m, called the *contracted section*, is found on measurement to be from .60 to .64 of the area of the aperture with most orifices of ordinary shapes, even with widely different values of the area of aperture and of the height, or head, h, producing the flow. Calling this abstract number [.60 to .64] the *Coefficient of Contraction*, and denoting it by C, we may write

$$F_m = CF,$$

in which F = area of the orifice, and F_m = that of the contracted section. C ranges from .60 to .64 with circular orifices, but may have lower values with some rectangular forms. (See table in § 503.)

A lamina of particles of water is under atmospheric pressure at n (the free surface of the water in tank or reservoir), while its velocity at n is practically zero, i.e. $v_n = 0$ (the surface at B being very large compared with the area of orifice). It experiences increasing pressure as it slowly descends until in the immediate neighborhood of the orifice, when its velocity is rapidly accelerated and pressure decreased, in accordance with Bernoulli's Theorem, and its shape lengthened out, until finally at m it forms a portion of a filament of a jet, its pressure is one atmosphere, and its velocity, $= v_m$, we wish to determine. The course of this lamina we call a

"*stream-line*," and Bernoulli's Theorem is applicable to it, just as it it were enclosed in a frictionless pipe of the same form. Taking then a datum plane through the centre of m, we have

$$\frac{p_m}{\gamma} = b, \quad z_m = 0, \quad \text{and} \quad v_m = ?;$$

while

$$\frac{p_n}{\gamma} \text{ also } = b, \quad z_n = h, \quad \text{and} \quad v_n = 0.$$

Hence Bernoulli's Theorem gives

$$\frac{v_m^2}{2g} + b + 0 = 0 + b + h;$$

$$\therefore \frac{v_m^2}{2g} = h, \quad \ldots\ldots\ldots \quad (1)$$

and

$$v_m = \sqrt{2gh}.$$

That is, *the velocity of the jet at m is theoretically the same as that acquired by a body falling freely in vacuo through a height* $= h =$ the "head of water." We should therefore expect that if the jet were directed vertically upward, as at m, Fig. 540,



FIG. 540.

$$\text{a height } \frac{v_m^2}{2g}$$

would be actually attained. [See §§ 52 and 53.] Experiment shows that the height of the jet (at m) does not materially differ from h if h is not > 6 or 8 feet. For $h > 8$ ft., however, the actual height reached is $< h$, the difference being not only absolutely but relatively greater as h is taken greater, since the resistance of the air is then more and more effective in depressing and breaking up the stream. (See § 578.)

At m', Fig. 540, we have a jet, under a head $= h'$, directed

at an angle α_0 with the horizontal. Its form is a parabola (§ 81), and the theoretical height reached is $h'' = h' \sin^2 \alpha_0$ (§ 80).

The jet from an orifice in thin plate is very limpid and clear.

From eq. (1), we have theoretically

$$v_m = \sqrt{2gh}$$

(an equation we shall always use for efflux *into the air* through *orifices* and *short pipes* in the plane wall of a large tank whose water-surface is very large compared with the orifice, and is open to the air), but experiment shows that for an "*orifice in thin plate*" this value is reduced about 3% by friction at the edges, so that for ordinary practical purposes we may write

$$v_m = \phi \sqrt{2gh} = 0.97 \sqrt{2gh}, \quad . \quad . \quad . \quad . \quad (2)$$

in which ϕ is called the *coefficient of velocity.**

Hence the volume of flow, Q, per time-unit will be

$$Q = F_m v_m = CF\phi \sqrt{2gh}, \text{ on the average} = 0.62F\sqrt{2gh}. \quad (3)$$

It is to be understood that the flow is steady, and that the reservoir surface (very large) and the jet are *both under atmospheric pressure.* ϕC is called the *coefficient of efflux.*

EXAMPLE 1.—Fig. 539. Required the velocity of efflux, v_m, at m, and the volume of the flow per second, Q, into the air, if $h = 21$ ft. 6 inches, the *circular* orifice being 2 in. in diam.; take $C = 0.64$. [Ft., lb., and sec.]

From eq. (2),

$$v_m = 0.97 \sqrt{2 \times 32.3 \times 21.5} = 36.1 \text{ ft. per sec.};$$

hence the discharge is

$$Q = F_m v_m = 0.64 \times \frac{\pi}{4}\left(\frac{2}{12}\right)^2 \times 36.1 = 0.504 \text{ cub. ft. per second.}$$

EXAMPLE 2.—[Weisbach.] Under a head of 3.396 metres the velocity v_m in the contracted section is found by measure-

* See *Engineering News* for Sept. 27, 1906, p. 326, for an account of extensive experiments on flow through orifices. Values of ϕ as high as 0.99 were obtained.

ments of the jet-curve to be 7.98 metres per sec., and the discharge proves to be 0.01825 cub. metres per sec. Required the coefficient of velocity (ϕ) and that of contraction (C), if the area of the orifice is 36.3 sq. centimetres.

Use the *metre-kilogram-second* system of units, in which $g = 9.81$ met. per sq. second.

From eq. (2),

$$\phi = \frac{v_m}{\sqrt{2gh}} = \frac{7.98}{\sqrt{2 \times 9.81 \times 3.396}} = 0.978;$$

while from (3) we have

$$C = \frac{Q}{F\phi\sqrt{2gh}} = \frac{Q}{Fv_m} = \frac{.01825}{\frac{36.3}{10000} \times 7.98} = 0.631.$$

ϕ and C, being abstract numbers, are independent of the system of concrete units adopted.

NOTE.—To find the velocity v_m of the jet at the orifice by measurements of the jet-curve, as mentioned in Example 2, we may proceed as follows: Since we cannot very readily assure ourselves that the direction of the jet at the orifice is horizontal, we consider the angle α_0 of the parabola (see Fig. 93 and § 80) as unknown, and therefore have two unknowns to deal with, and obtain the necessary two equations by measuring the x and y (see page 84) of two points of the jet, remembering that if we use the equation (3) of page 84 in its present form points of the jet below the orifice will have negative y's. The substitution of these values x_1, x_2, y_1, and y_2 in equation (3) furnishes two equations between constants, in which only α_0 and h are unknown. To eliminate α_0, for $\frac{1}{\cos^2 \alpha_0}$ we write $1 + \tan^2 \alpha_0$, and taking $x_2 = 2x_1$ for convenience, we finally obtain

$$h = \frac{1}{8} \cdot \frac{x_2^2 + (4y_1 - y_2)^2}{y_2 - 2y_1}, \quad \text{and} \quad \therefore v_m = \sqrt{\frac{g[x_2^2 + (4y_1 - y_2)^2]}{4(y_2 - 2y_1)}},$$

in which y_1 and y_2 are the vertical distances of the two points

chosen *below* the orifice; that is, we have already made them negative in eq. (3) of page 84. The h of the preceding equation simply denotes $v_m^2 \div 2g$, and must not be confused with that of the last two figures. For accuracy the second point should be as far from the orifice along the jet as possible.

496. Orifice with Rounded Approach.*—Fig. 541 shows the general form and proportions of an orifice or mouth-piece in the use of which contraction does not take place beyond the edges, the inner surface being one "of revolution," and so shaped that the liquid filaments are parallel on passing the outer edge m; hence the pressure-head at m is $= b$ (= 34 ft. for water and 30 inches for mercury) in Bernoulli's Theorem, if efflux takes place *into the air*. We have also the sectional area $F_m = F =$ that of final edge of orifice, i.e., the coefficient of contraction, or C, = unity = 1.00, so that the discharge per time-unit has a volume



FIG. 541.

$$Q = F_m v_m = F v_m.$$

The tank being large, as in Fig. 540, Bernoulli's Theorem applied to m and n will give, as before,

$$v_m = \sqrt{2gh}$$

as a theoretical result, while practically we write

$$v_m = \phi \sqrt{2gh}, \quad . \ . \ . \ . \ . \ . \ . \ . \ (1)$$

and

$$Q = F\phi \sqrt{2gh}. \quad . \ . \ . \ . \ . \ . \ . \ . \ (2)$$

As an average ϕ is found to differ little from 0.97 with this orifice, the same value as for an orifice in thin plate (§ 495).

497. Problems in Efflux Solved by Applying Bernoulli's Theorem.—In the two preceding paragraphs the pressure-heads at sections m and n were each $= p_a \div \gamma =$ height of

* Smooth conical nozzles for fire-streams give $\phi = .97$ with $h =$ press.-head + veloc.-head at base of play-pipe; see p. 833.

the liquid barometer $= b$; but in the following problems this will not be the case necessarily. However, efflux is to take place through a simple orifice in the side of a large reservoir, whose upper surface (n) is very large, so that v_n may be put $=$ zero.

Problem I.—Fig. 542. What is the velocity of efflux, v_m, at the orifice m (i.e., at the contracted section, if it is an orifice in thin plate) of a jet of water from a steam-boiler, if the free surface at n is at a height $= h$ above m, and the pressure of the steam over the water is p_n, the discharge taking place into the air?



FIG. 542.

Applying Bernoulli's Theorem to section m at the orifice [where the pressure-head is b and velocity-head $v_m^2 \div 2g$ (unknown)] and to section n at water-surface (where velocity-head $= 0$ and pressure-head $= p_n \div \gamma$), we have, taking m as a datum for potential heads so that $z_m = 0$ and $z_n = h$,

$$\frac{v_m^2}{2g} + b + 0 = 0 + \frac{p_n}{\gamma} + h;$$

$$\therefore v_m = \sqrt{2g\left[\frac{p_n}{\gamma} - b + h\right]}. \quad . \quad . \quad . \quad . \quad (1)$$

EXAMPLE.—Let the steam-gauge read 40 lbs. (and hence $p_n = 54.7$ lbs. per sq. inch) and $h = 2$ ft. 4 in.; required v_m.

Also if $F = \frac{1}{2}$ sq. in., in "thin plate," required the rate of discharge (volume). The temperature of saturated steam of the given tension must be 286° Fahr. [see foot of page 607]. The water is practically at the same temperature and hence of a heaviness, γ, of 57.7 lbs. per cubic ft. (p. 518).

From eq. (1) above, then, with ft. lb. and sec., noting that for this case $b = [(14.7 \times 144) \div 57.7]$ feet,

$$v_m = \sqrt{2 \times 32.2\left[\frac{54.7 \times 144}{57.7} - \frac{14.7 \times 144}{57.7} + \frac{28}{12}\right]}$$

$= 81.1$ ft. per sec., theoretically; but * practically

* Another practical matter in this case is that some of the hot water will "flash" into steam on relief from the higher pressure.

$$v_m = 0.97 \times 81.1 = 78.6 \text{ ft. per sec.};$$

so that the discharge begins at the rate of

$$Q = 0.64\, Fv_m = 0.64 \times \tfrac{1}{2} \cdot \tfrac{1}{144} \times 78.6 = 0.174 \text{ cub. ft. p. sec.}$$

Problem II.—Fig. 543. With what velocity, v_m, will water flow into the condenser C of a steam-engine where the tension of the vapor is p_m, < one atmosphere, if h = the head of water, and the flow takes place through an orifice in thin plate? Taking position m in the contracted section where the filaments are parallel, and the pressure therefore equal to that of the surrounding vapor, viz., p_m, and position n in the (wide) free surface of the water in the tank, where (at surface) the pressure is one atmosphere [and $\therefore \frac{p_n}{\gamma} = b = 34$ ft.] and velocity practically zero; we have, applying Bernoulli's Theorem to n and m, taking m as a datum level for potential heads (so that $z_n = h$ and $z_m = 0$),



FIG. 543.

$$\frac{v_m^2}{2g} + \frac{p_m}{\gamma} + 0 = 0 + b + h,$$

$\therefore$

$$v_m = \sqrt{2g\left[h + b - \frac{p_m}{\gamma}\right]}, \quad \ldots \quad (1)$$

and

$$Q = F_m v_m, \quad \ldots \quad (2)$$

as theoretical results. But practically we must write

$$v_m = 0.97\sqrt{2g\left[h + b - \frac{p_m}{\gamma}\right]}, \quad \ldots \quad (3)$$

and

$$Q = F_m v_m = CFv_m, \quad \ldots \quad (4)$$

in which F = area of orifice in thin plate, and C = coefficient of contraction = about 0.62 approximately [see § 495].

EXAMPLE.—If in the condenser there is a "vacuum" of $27\frac{1}{2}$ inches (meaning that the tension of the vapor would support $2\frac{1}{2}$ inches of mercury, in a barometer), so that

$$p_m = [\tfrac{2.5}{30} \times 14.7] \text{ lbs. per sq. inch, and } h = 12 \text{ feet,}$$

while the orifice is $\frac{1}{2}$ inch in diameter; we have, using the ft., lb., and sec.,

$$v_m = 0.97\sqrt{2 \times 32.2\left[12 + 34 - \frac{\frac{5}{60} \times 14.7 \times 144}{62.5}\right]}$$

$$= 51.1 \text{ ft. per sec.}$$

(We might also have written, for brevity,

$$\frac{p_m}{\gamma} = [2\tfrac{1}{2} : 30] \times 34 = 2.833,$$

since the pressure-head for one atmos. = 34 feet, for water. Hence, for a circular orifice in thin plate, we have the volume discharged per unit of time,

$$Q = CFv = 0.62 \times \frac{\pi}{4}\left(\frac{\frac{1}{2}}{12}\right)^2 \times 51.1 = 0.0431 \text{ cub. ft. per sec.}$$

497a. Efflux through an Orifice in Terms of the Internal and External Pressures.—Fig. 544. Let efflux take place through a small orifice from the plane side of a large tank, in which at the level of the orifice the *hydrostatic pressure* was $= p'$ before the opening of the orifice, that of the medium surrounding the jet being $= p''$. When a steady flow is established, after opening the orifice, the pressure in the water on a level with the orifice will not be materially changed, *except in the immediate neighborhood of the orifice* [see § 495]; hence, applying Bernoulli's Theorem to m in the jet, where the filaments are parallel, and a point n, in the body of the liquid and at the same level as m, and *where the particles are practically at rest* [i.e., $v_n = 0$] (hence not too near the



FIG. 544.

orifice), we shall have, cancelling out the potential heads which are equal,

$$\frac{v_m^2}{2g} + \frac{p''}{\gamma} = \frac{0^2}{2g} + \frac{p'}{\gamma},$$

$$\therefore\ v_m = 0.97\sqrt{2g\left[\frac{p' - p''}{\gamma}\right]}. \quad . \quad . \quad . \quad (1)$$

(In Fig. 544 p' would be equal to $p_a + h\gamma$.) Eq. (1) is conveniently applied to the jet produced by a *force-pump*, supposing, for simplicity, the orifice to be *in the head of the pump-cylinder*, as shown in Fig. 545. Let the thrust (force) exerted along the piston-rod be $= P$, and the area of the piston be $= F'$. Then the intensity of internal pressure produced in the chamber AB (when the piston moves uniformly) is



Fig. 545.

$$p' = \frac{P + F'p_a}{F'},$$

while the external pressure in the air around the jet is simply p_a (one atmos.).

$$\therefore\ v_m = 0.97\sqrt{2g \cdot \frac{P}{F'\gamma}}. \quad . \quad . \quad . \quad . \quad (1)'$$

(N.B. Of course, at points near the orifice the internal pressure is $< p'$; read § 495.)

Example.—Let the force, or thrust, P, [due to steam-pressure on a piston not shown in figure,] be 2000 lbs., and the diameter of pump-cylinder be $d = 9$ inches. the liquid being *salt water* (so that $\gamma = 64$ lbs. per cubic foot).

Then

$$F' = \tfrac{1}{4}\pi\left(\tfrac{9}{12}\right)^2 = 0.442 \text{ sq. ft.},$$

and [ft., lb., sec.]

$$v_m = 0.97\sqrt{2 \times 32.2 \times \frac{2000}{0.442 \times 64}} = 65.4 \text{ ft. per sec.}$$

If the orifice is well rounded, with a diameter of one inch, the volume discharged per second is

$$Q = F_m v_m = F v_m = \frac{\pi}{4}\left(\frac{1}{12}\right)^2 \times 65.4 = 0.353 \text{ cub. ft. per sec.}$$

To maintain steadily this rate of discharge, the piston must move at the rate [veloc. $= v'$] of

$$v' = Q \div F' = .353 \div \left[\frac{\pi}{4}\left(\frac{9}{12}\right)^2\right] = 0.800 \text{ ft. per sec.,}$$

and the force P must exert a *power* (§ 130) of

$$L = Pv' = 2000 \times 0.800 = 1600 \text{ ft. lbs. per sec.}$$
$$= \text{about 3 horse-power (or 3 H. P.).}$$

If the water must be forced from the cylinder through a pipe or hose before passing out of a nozzle into the air, the velocity of efflux will be smaller, on account of "*fluid friction*" in the hose, for the same P; such a problem will be treated later [§ 513]. Of course, in a pumping-engine, by the use of several pump-cylinders, and of air-chambers, a practically steady flow is kept up, notwithstanding the fact that the motion of each piston is not uniform, and must be reversed at the end of each stroke.

498. Influence of Density on the Velocity of Efflux in the Last Problem.—From the equation

$$v_m = \sqrt{2g\frac{p' - p''}{\gamma}}$$

of the preceding paragraph, where p'' is the external pressure around the jet, and p' the internal pressure at the same level as the orifice but well back of it, *where the liquid is sensibly*

at rest, we notice that for the same *difference* of pressure $[p' - p'']$ *the velocity of efflux is inversely proportional to the square root of the heaviness of the liquid.* Hence, *for the same* $(p' - p'')$, mercury would flow out of the orifice with a velocity only 0.272 of that of water; for

$$\sqrt{\frac{62.5}{848}} = \sqrt{\frac{1}{13.5}} = \frac{272}{1000}.$$

Again, assuming that the equation holds good for the flow of gases (as it does approximately when p' does not greatly exceed p''; e.g., by 6 or 8 per cent), the velocity of efflux of atmospheric air, when at a heaviness of 0.807 lbs. per cub. foot, would be

$$\sqrt{\frac{62.5}{.0807}} = \sqrt{775.3} = 27.8$$

times as great as for water, with the same $p' - p''$. (See § 548, etc.)

499. Efflux under Water. Simple Orifice.—Fig. 546. Let h_1 and h_2 be the depths of the (small) orifice below the levels of the "head" and "tail" waters respectively. Then, using the formula of § 497*a*, we have for the pressure at n (at same level as m, the jet)

$$p' = (h_1 + b)\gamma,$$



FIG. 546.

and for the external pressure, around the jet at m,

$$p'' = (h_2 + b)\gamma;$$

whence, theoretically,

$$v_m = \sqrt{2g\frac{p' - p''}{\gamma}} = \sqrt{2g(h_1 - h_2)} = \sqrt{2gh}, \quad . \quad (1)$$

where $h =$ *difference of level between the surfaces of the two bodies of water.*

Practically, $v_m = \phi\sqrt{2gh}$; . . . . . (2)

but the value of ϕ for efflux under water is somewhat uncertain; as also that of C, the coefficient of contraction. Weisbach says that $\mu, = \phi C$, is $\frac{1}{75}$ part less than for efflux into the air; others, that there is no difference (Trautwine). See also p. 389 of vol. 6, Jour. of Engin. Associations, where it is stated that with a circular mouth-piece of 0.37 in. diam., and of "nearly the form of the *vena contracta*," μ was found to be .952 for discharge into the air, and .945 for submerged discharge.

500. Efflux from a Small Orifice in a Vessel in Motion.

Case I. *When the motion is a vertical translation and uniformly accelerated.*—Fig. 547. Suppose the vessel to move upward with a constant acceleration $\bar{p}$. (See § 49a.) Taking m and n as in the two preceding paragraphs, we know that $p_m = p'' =$ external pressure $=$ one atmos. $= p_a$ (and $\therefore \frac{p_m}{\gamma} = b$). As to the internal pressure at n (same level as m, but well back of orifice), p_n, this is not equal to $(b+h)\gamma$, because of the accelerated motion, but we may determine it by considering free the vertical column or prism On of liquid, of cross-section $= dF$, the vertical forces acting on which are $p_a dF$, downward at O, $p_n dF$ upward at n, and its weight, downward, $hdF\gamma$. All other pressures are horizontal. For a vertical upward acceleration $= \bar{p}$, the algebraic sum of the vertical components of all the forces must $=$ *mass* $\times$ *vert. accel.*,



Fig. 547.

i.e., $$dF(p_n - p_a - h\gamma) = \frac{h\gamma dF}{g} \cdot \bar{p};$$

whence

$$p_n = p_a + h\gamma\left[1 + \frac{\bar{p}}{g}\right]. \quad . \quad . \quad . \quad . \quad . \quad (1)$$

Putting p_n and p_a equal to the p' and p'', respectively, of the equation, we have

$$v_m = \sqrt{2g\left[\frac{p_n - p_m}{\gamma}\right]}$$

of § 497,

$$v_m = \sqrt{2(g+\bar{p})h}. \quad . \quad . \quad . \quad . \quad . \quad (2)$$

It must be remembered that v_m is the velocity of the jet *relatively to the orifice*, which is itself in motion with a variable velocity. The absolute velocity w_m of the particles of the jet is found by the construction in § 83, being represented graphically by the diagonal of a parallelogram one of whose sides is v_m, and the other the velocity c with which the orifice itself is moving at the instant, as part of the vessel. The jet may make any angle with the side of the vessel.

On account of the flow the internal pressures of the water against the vessel are no longer balanced horizontally, and the latter will swing out of the vertical unless properly constrained.

If $\bar{p} = g =$ acc. of gravity, $v_m = \sqrt{2}\sqrt{2gh}$. If $\bar{p}$ is *negative* and $= g$, $v_m = 0$; i.e., there is no flow, but both the vessel and its contents fall freely, without mutual action.

Case II. *When the liquid and the vessel both have a uniform rotary motion* about a vertical axis with an angular velocity $= \omega$ (§ 110). *Orifice small*, so that we may consider the liquid inside (except near the orifice) to be in relative equilibrium. Suppose the jet horizontal at m, Fig. 548, and the radial distance of the orifice from the axis to be $= x$. The external pressure $p_m = p_a$, and the internal [see § 428, eqs. (3) and (4)] is



Fig. 548.

$$p_n = p_a + (h_0 + z)\gamma = p_a + h_0\gamma + \frac{\omega^2 x^2}{2g}\gamma;$$

hence the velocity of the jet, relatively to the orifice, is (from § 497, since p_n and p_m correspond to the p' and p'' of that article),

$$v_m = \sqrt{2g\frac{(p_n - p_m)}{\gamma}} = \sqrt{2gh_0 + (\omega x)^2},$$

i.e., $$v_m = \sqrt{2gh_0 + w^2}; \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

in which w, $= \omega x$, = the (constant) linear velocity of the orifice in its circular path. The *absolute velocity* w_m *of the particles in the jet* close to the orifice is the diagonal formed on w and v_m (§ 83). Hence by properly placing the orifice in the casing, w_m may be made small or large, and thus the kinetic energy carried away in the effluent water be regulated, within certain limits. Equation (3) will be utilized subsequently in the theory of Barker's Mill.*

EXAMPLE.—Let the casing make 100 revol. per min. (whence $\omega = [2\pi 100 \div 60]$ *radians* per sec.), $h_0 = 12$ feet, and $x = 2$ ft.; then (ft., lb., sec.)

$$v_m = \sqrt{2 \times 32.2 \times 12 + \left(\frac{2\pi 100 \times 2}{60}\right)^2} = 34.8 \text{ ft. per sec.}$$

(while, if the casing is not revolving, $v_m = \sqrt{2gh_0} =$ only 27.8 ft. per sec.).

If the jet is now directed horizontally and backward, and also tangentially to the circular path of the centre of the orifice, its *absolute velocity* (i.e., relatively to the earth) is

$$w_m = v_m - \omega x = 34.8 - 20.9 = 13.9 \text{ ft. per sec.},$$

and is also horizontal and backwards. If the volume of flow is $Q = 0.25$ cub. feet per sec., the *kinetic energy carried away with the water per second* (§ 133) is

$$= \tfrac{1}{2} M w_m^2 = \frac{Q\gamma}{g} \cdot \frac{w_m^2}{2} = \frac{\frac{1}{4} \times 62.5}{32.2} \frac{(13.9)^2}{2} = 46.8$$

ft. lbs. per second = 0.085 horse-power.

501. Theoretical Efflux through Rectangular Orifices of Considerable Vertical Depth, in a Vertical Plate.—If the orifice is so large vertically that the velocities of the different filaments in a vertical plane of the stream are theoretically different, having different "heads of water," we proceed as follows, taking into account, also, *the velocity of approach*, c, or mean velocity

* See p. 84 of the author's "Hydraulic Motors" (New York, 1905, John Wiley and Sons).

(if any appreciable), of the water in the channel approaching the orifice.

Fig. 549 gives a section of the side of the tank and orifice. Let b = width of the rectangle, the sills of the latter being *horizontal*, and $a = h_2 - h_1$, its height. Disregarding contraction for the present, the theoretical volume of discharge per unit of time is equal to the sum of the volumes like $v_m dF$ ($= v_m b dx$), in which v_m = the velocity of any filament, as m, in the jet, and bdx = cross-section of the small prism which passes through any horizontal strip of the area of orifice, in a unit of time, its altitude being v_m. For each strip there is a different x or "head of water," and hence a different velocity. Now the *theoretical* discharge (volume) per unit of time is



FIG. 549.

$$Q = \textit{sum of the volumes of the elem. prisms} = \int_{x=h_1}^{x=h_2} v_m dF;$$

i.e.,
$$Q = b\int_{h_1}^{h_2} v_m dx. \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)'$$

But from Bernoulli's Theorem, if $k = c^2 \div 2g$ = the velocity-head at n, the surface of the *channel of approach* nC, b being the pressure-head of n, and x its potential head referred to m as datum (N.B. This $b = 34$ ft. for water, and must not be confused with the width b of orifice), we have [see § 492, eq. (7)]

$$\frac{v_m^2}{2g} + b + 0 = \frac{c^2}{2g}(\text{or } k) + b + x;$$

$$\therefore\ v_m = \sqrt{2g}\sqrt{x+k}; \quad . \quad . \quad . \quad . \quad . \quad (2)'$$

and since $dx = d(x+k)$, k being a constant, we have, from (1)' and (2)',

$$\textit{Theoret. } Q = b\sqrt{2g}\int_{h_1+k}^{h_2+k} (x+k)^{\frac{1}{2}} d(x+k),$$

or

$$Theoret.\ Q = \tfrac{2}{3} b \sqrt{2g}\left[(h_2 + k)^{\frac{3}{2}} - (h_1 + k)^{\frac{3}{2}}\right]. \quad . \quad (1)$$

(b now denotes the width of orifice.) If c is small, the channel of approach being large, we have

$$Theoret.\ Q = \tfrac{2}{3} b \sqrt{2g}\,(h_2^{\frac{3}{2}} - h_1^{\frac{3}{2}}) \quad . \quad . \quad . \quad . \quad (2)$$

(c being $= Q \div$ area of section of nC).

If $h_1 = 0$, i.e., if the orifice becomes a *notch in the side*, or an *overfall* [see Fig 550, which shows the contraction which actually occurs in all these cases], we have for an *overfall* *

$$Theoret.\ Q = \tfrac{2}{3} b \sqrt{2g}\left[(h_2 + k)^{\frac{3}{2}} - k^{\frac{3}{2}}\right]. \quad . \quad . \quad . \quad . \quad (3)$$

NOTE.—Both in (1) and (2) h_1 and h_2 are the vertical depths of the respective sills of the orifice from the *surface of the water three or four feet back of the plane of the orifice*, where the surface is comparatively level. This must be specially attended to in deriving the actual discharge from the theoretical (see § 503).



FIG. 550.

If Q were the unknown quantity in eqs. (1) and (3) it would be necessary to proceed by successive assumptions and approximations, since Q is really involved in k; for

$$k = \frac{c^2}{2g} \quad \text{and} \quad F_0 c = Q$$

(where F_0 is the sectional area of the channel of approach nC).

With $k = 0$ (or c very small, i.e., F_0 very large), eq. (3) reduces (for an *overfall*) to

$$Theoret.\ Q = \tfrac{2}{3} b h_2 \sqrt{2g h_2}, \quad . \quad . \quad . \quad . \quad (3\tfrac{1}{2})$$

or $\frac{2}{3}$ as much as if all parts of the orifice had the same head of water $= h_2$ (as for instance if the orifice were in the horizontal bottom of a tank in which the water was h_2 deep, the orifice having a width $= b$ and length $= h_2$).

* The most satisfactory mathematical treatment of the flow over an overfall weir is that of Flamant (see p. 96 of his *Hydraulique*, Paris, 1900, 2d edition). Its resulting formula is in remarkable accord with experiment, but is not convenient for practical use.

502. Theoretical Efflux through a Triangular Orifice in a Thin Vertical Plate or Wall. Base Horizontal.—Fig. 551. Let the channel of approach be so large that the velocity of approach may be neglected. h_1 and h_2 = depths of sill and vertex, which is downward. The analysis differs from that of the preceding article only in having $k = 0$ and the length u, of a horizontal strip of the orifice, variable; b being the length of the base of the triangle. From similar triangles we have

$$\frac{u}{b} = \frac{h_2 - x}{h_2 - h_1}; \quad \text{i.e.,} \quad u = \frac{b}{h_2 - h_1}(h_2 - x).$$

$$\therefore \textit{Theoret. } Q = \int v_m dF = \int v_m u dx = \frac{b}{h_2 - h_1}\int_{h_1}^{h_2} v_m (h_2 - x) dx;$$

and finally, substituting from eq. (2)′ of § 501, with $k = 0$,



FIG. 551.



FIG. 552.

$$\textit{Theoret. } Q = \frac{b\sqrt{2g}}{h_2 - h_1}\int_{h_1}^{h_2} (h_2 - x)x^{\frac{1}{2}} dx$$

$$= \frac{2}{15}\frac{b\sqrt{2g}}{h_2 - h_1}\left[2h_2^{\frac{5}{2}} - 5h_2 h_1^{\frac{3}{2}} + 3h_1^{\frac{5}{2}}\right]. \quad . \quad . \quad . \quad (4)$$

For a *triangular notch* as in Fig. 552, this reduces to

$$\textit{Theoret. } Q = \frac{4}{15} b h_2 \sqrt{2gh_2} = \frac{8}{15}\frac{bh_2}{2}\sqrt{2gh_2}; \quad . \quad . \quad . \quad . \quad . \quad (5)$$

i.e., $\frac{8}{15}$ of the volume that would be discharged per unit of

time if the triangular orifice with base b and altitude h_2 were cut in the horizontal bottom of a tank under a head of h_2. The measurements of h_2 and b are made with reference to the *level surface* back of the orifice (see figure); for the water-surface in the plane of the orifice is curved below the level surface in the tank.

Prof. Thomson has found by experiment that with $b = 2h_2$, the actual discharge = theoret. disch. $\times$ 0.595; and with $b = 4h_2$, actual = theoret. disch. $\times$ 0.620.

503. Actual Discharge through Sharp-edged Rectangular Orifices (sills horizontal) *in the vertical side of a tank or reservoir.*

Case I. *Complete and Perfect Contraction.*—The actual volume of water discharged per unit of time is much less than the theoretical values derived in § 501, chiefly on account of contraction. By *complete contraction* we mean that no edge of the orifice is flush with the side or bottom of the reservoir; and by *perfect contraction*, that the channel of approach, to whose surface the heads h_1 and h_2 are measured, is so large that the contraction is practically the same if the channel were of infinite extent sideways and downward from the orifice.



Fig. 553.

For this case (h_1 not zero) it is found most convenient to use the following practical formula (b = width):

$$Actual\ Q = \mu_0 ab\sqrt{2g\left[h_1 + \frac{a}{2}\right]}, \quad . \quad . \quad . \quad (6)$$

in which (see Fig. 553) a = the height of orifice, h_1 = the vertical depth of the upper edge of the orifice below the level of the reservoir surface, *measured a few feet back of the plane of the orifice*, and μ_0 is a *coefficient of efflux* (an abstract number), dependent on experiment.

With $\mu_0 = 0.62$ approximate results (within 3 or 4 per cent) may be obtained from eq. (6) with openings not more than

18 inches, or less than 1 inch, high; and not less than 1 inch wide; with heads $\left(h_1 + \frac{a}{2}\right)$ from 1 ft. to 20 or 30 feet.

EXAMPLE.—What is the actual discharge (volume) per minute through the orifice in Fig. 553, 14 inches wide and 1 foot high, the upper sill being 8 ft. 6 in. below the surface of still water? Use eq. (6) with the ft., lb., and sec. as units, and $\mu_0 = 0.62$.

Solution:

$$Q = 0.62 \times 1 \times 1\tfrac{1}{6} \times \sqrt{2 \times 32.2[8\tfrac{1}{2} + \tfrac{1}{2}]} = 17.41 \text{ cub. ft. per. sec.}$$

while the *flow of weight* is

$$G = Q\gamma = 17.41 \times 62.5 = 1088 \text{ lbs. per second.}$$

Poncelet and Lesbros' Experiments.—For comparatively accurate results, values of μ_0 taken from the following table (computed from the careful experiments of Poncelet and Lesbros) may be used for the sizes there given, and, where practicable, for other sizes by interpolation. To use the table, the values of h_1, a, and b must be reduced to metres, which can be done by the reduction-table below; but in substituting in eq. (6), if the metre-kilogram-second system of units be used g must be put = 9.81 metres per square second (see § 51), and Q will be obtained in cubic metres per second.

Since μ_0 is an abstract number, once obtained as indicated above, it does not necessitate any particular system of units in making substitutions in eq. (6). The ft., lb., and sec. will be used in subsequent examples.

TABLE FOR REDUCING FEET AND INCHES TO METRES.

1 foot	= 0.30479 metre.	1 inch	= 0.0253 metre.
2 feet	= 0.60959 "	2 inches	= 0.0507 "
3 "	= 0.91438 "	3 "	= 0.0761 "
4 "	= 1.21918 metres.	4 "	= 0.1015 "
5 "	= 1.52397 "	5 "	= 0.1268 "
6 "	= 1.82877 "	6 "	= 0.1522 "
7 "	= 2.13356 "	7 "	= 0.1776 "
8 "	= 2.43836 "	8 "	= 0.2030 "
9 "	= 2.74315 "	9 "	= 0.2283 "
10 "	= 3.04794 "	10 "	= 0.2536 "
		11 "	= 0.2790 "

TABLE, FROM PONCELET AND LESBROS.

VALUES OF μ_0, FOR EQ (6), FOR RECTANGULAR ORIFICES IN THIN PLATE.

(Complete and perfect contraction.)

Value of h_1, Fig. 553 (in metres).	$b = .20^m$. $a = .20^m$.	$b = .20^m$. $a = .10^m$.	$b = .20^m$. $a = .05^m$.	$b = .20^m$. $a = .03^m$.	$b = .20^m$. $a = .02^m$.	$b = .20^m$. $a = .01^m$.	$b = .60^m$. $a = .20^m$.	$b = .60^m$. $a = .02^m$.
	μ_0	μ_0	μ_0	μ_0	μ_0	μ_0	μ_0	μ_0
0.005						0.705		
.010			0.607	0.630	0.660	.701		0.644
.015		0.593	.612	.632	.660	.697		.644
.020	0.572	.596	.615	.634	.659	.694		.643
.030	.578	.600	.620	.638	.659	.688	0.593	.642
.040	.582	.603	.623	.640	.658	.683	.595	.642
.050	.585	.605	.625	.640	.658	.679	.597	.641
.060	.587	.607	.627	.640	.657	.676	.599	.641
.070	.588	.609	.628	.639	.656	.673	.600	.640
.080	.589	.610	.629	.638	.656	.670	.601	.640
.090	.591	.610	.629	.637	.655	.668	.601	.639
.100	.592	.611	.630	.637	.654	.666	.602	.639
.120	.593	.612	.630	.636	.653	.663	.603	.638
.140	.595	.613	.630	.635	.651	.660	.603	.637
.160	.596	.614	.631	.634	.650	.658	.604	.637
.180	.597	.615	.630	.634	.649	.657	.605	.636
.200	.598	.615	.630	.633	.648	.655	.605	.635
.250	.599	.616	.630	.632	.646	.653	.606	.634
.300	.600	.616	.629	.632	.644	.650	.607	.633
.400	.602	.617	.628	.631	.642	.647	.607	.631
.500	.603	.617	.628	.630	.640	.644	.607	.630
.600	.604	.617	.627	.630	.638	.642	.607	.629
.700	.604	.616	.627	.629	.637	.640	.607	.628
.800	.605	.616	.627	.629	.636	.637	.606	.628
.900	.605	.615	.626	.628	.634	.635	.606	.627
1.000	.605	.615	.626	.628	.633	.632	.605	.626
1.100	.604	.614	.625	.627	.631	.629	.604	.626
1.200	.604	.614	.624	.626	.628	.626	.604	.625
1.300	.603	.613	.622	.624	.625	.622	.603	.624
1.400	.603	.612	.621	.622	.622	.618	.603	.624
1.500	.602	.611	.620	.620	.619	.615	.602	.623
1.600	.602	.611	.618	.618	.617	.613	.602	.623
1.700	.602	.610	.617	.616	.615	.612	.602	.622
1.800	.601	.609	.615	.615	.614	.612	.602	.621
1.900	.601	.608	.614	.613	.612	.611	.602	.621
2.000	.601	.607	.613	.612	.612	.611	.602	.620
3.000	.601	.603	.606	.608	.610	.609	.601	.615

EXAMPLE. — With $h_1 = 4$ in. [$= 0.10$ met.], $a = 8$ in. [$= 0.20$ met.], $b = 1$ ft. 8 in. [$= 0\ 51$ met.], required the (actual) volume discharged per second. See Fig. 553.

From the foregoing table,

for $h_1 = 0.10^{m.}$, $b = 0.60^{m.}$ and $a = 0.20^{m.}$, we find $\mu_0 = .602$
" $h_1 = 0.10^{m.}$, $b = 0.20^{m.}$ " $a = 0.20^{m.}$, " $\mu_0 = .592$
diff. $= .010$

Hence, by interpolation,

for $h_1 = 0.10^{m.}$ $b = 0.51^{m.}$, and $a = 0.20^{m.}$, we have

$$\mu_0 = 0.602 - \tfrac{9}{40}\,[0.602 - 0.592] = 0.600.$$

Hence [ft., lb., sec.], remembering that μ_0 is an abstract number, from eq. (6),

$$Q = 0.600 \times \tfrac{8}{12} \times \tfrac{20}{12}\sqrt{2 \times 32.2\left(\tfrac{4}{12} + \tfrac{1}{2} \cdot \tfrac{8}{12}\right)} = 4.36$$

cub. ft. per second.

Case II. *Incomplete Contraction.*—This name is given to the cases, like those shown in Fig. 554, where one or more sides of the orifice have an interior border flush with the sides or bottom of the (square-cornered) tank.

Not only is the general direction of the stream altered, but the discharge is *greater*, on account of the larger size of the contracted section, since contraction is prevented on those sides which have a border. It is assumed that the contraction which *does* occur (on the other edges) is *perfect;* i.e., the cross-section of the tank is large compared with the orifice. According to the experiments of Bidone and Weisbach with Poncelet's orifices (i.e., orifices in thin plate mentioned in the preceding table), the actual volume discharged per unit of time is

$$Q = \mu ab\sqrt{2g\left(h_1 + \frac{a}{2}\right)} \quad . \quad (7)$$



Fig. 554.

(differing from eq. (6) only in the coefficient of efflux μ), in which the abstract number μ is found thus: Determine a coefficient of efflux μ_0 as if eq. (6) were to be used in Case I; i.e., as if contraction were complete and perfect; then write

$$\mu = \mu_0[1 + 0.155\,n], \quad . \quad . \quad . \quad . \quad . \quad (7)'$$

where n = the ratio of the length of periphery of the orifice with a border to the whole periphery.

E.g., if the lower sill, only, has a border,

$$n = b \div [2(a + b)];$$

while if the lower sill and both sides have a border,

$$n = (2a + b) \div [2(a + b)].$$

EXAMPLE.—If $h_1 = 8$ ft. $(= 2.43^{m.})$, $b = 2$ ft. $(= 0.60^{m.})$, $a = 4$ in. $(= 0.10^{m.})$, and one side is even with the side of the tank, and the lower sill even with the bottom, required the volume discharged per second. (Sharp-edged orifice, in vertical plane, etc.)

Here for complete and perfect contraction we have, from Poncelet's tables (Case I), $\mu_0 = 0.608$. Now $n = \frac{1}{2}$; hence, from eq. (7)',

$$\mu = 0.608\,[1 + 0.155 \times \tfrac{1}{2}] = 0.6551;$$

hence, eq. (7),

$$Q = 0.655 \times 2 \times \tfrac{4}{12}\sqrt{2 \times 32.2\,(8 + \tfrac{1}{2} \cdot \tfrac{2}{12})}$$

$$= 10.23 \text{ cub. ft. per sec.}$$

CASE III. *Imperfect Contraction.*—If there is a submerged channel of approach, symmetrically placed as regards the orifice, and of an area (cross-section), $= G$, not much larger than that, $= F$, of the orifice (see Fig. 555), the contraction is less than in Case I, and is called *imperfect contraction.* Upon his experiments with Poncelet's orifices, with imperfect contraction, Weisbach bases the following formula for the discharge (volume) per unit of time, viz.,



FIG. 555.

$$Q = \mu a b_1 \sqrt{2g\left(h_1 + \frac{a}{2}\right)} \quad . \quad . \quad . \quad . \quad . \quad (8)$$

(see Fig. 553 for notation), with the understanding that the coefficient

$$\mu = \mu_0(1+\beta), \quad \ldots\ldots\ldots \quad (8)'$$

where μ_0 is the coefficient obtained from the tables of Case I (as if the contraction were perfect and complete), and β an abstract number depending on the ratio $F : G = m$, as follows:

$$\beta = 0.0760\,[9^m - 1.00]. \quad \ldots\ldots \quad (8)''$$

To shorten computation Weisbach gives the following table for β:

TABLE A.

m.	β.	m.	β.
.05	.009	.55	.178
.10	.019	.60	.208
.15	.030	.65	.241
.20	.042	.70	.278
.25	.056	.75	.319
.30	.071	.80	.365
.35	.088	.85	.416
.40	.107	.90	.473
.45	.128	.95	.537
.50	.152	1.00	.608

EXAMPLE.—Let $h_1 = 4'\,9\frac{1}{2}''$ (= 1.46 met.), the dimensions of the orifice being—

width $= b = 8$ in. (= 0.20m.);

height $= a = 5$ in. (= 0.126m.);

while the channel of approach (*CD*, Fig. 555) is one foot square. From Case I, we have, for the given dimensions and head,

$$\mu_0 = 0.610;$$

$$\frac{F}{G} = \frac{40 \text{ sq. in.}}{144 \text{ sq. in.}} = 0.27.$$

We find [Table A]

$$\beta = 0.062;$$

and hence $\mu = \mu_0\,(1.062)$, from eq. (8)'. Therefore, from eq. (8), with ft., lb., and sec.,

$$Q = 0.610 \times 1.062 \times \tfrac{5}{12} \cdot \tfrac{8}{12} \sqrt{2 \times 32.2 \times 5}$$

$$= 3.22 \text{ cub. ft. per sec.}$$

CASE IV. *Head measured in Moving Water.*—See Fig. 556. If the head h_1, of the upper sill, cannot be measured to the level of still water, but must be taken to the surface of a channel of approach, where the velocity of approach is quite

appreciable, not only is the contraction imperfect, but strictly we should use eq. (1) of § 501, in which the velocity of approach is considered. Let F = area of orifice, and G that of the cross-section of the channel of approach; then the velocity of approach is $c = Q \div G$, and k (of above eq.) $= c^2 \div 2g = Q^2 \div 2gG^2$; but Q itself being unknown, a substitutionof k in terms of Q in eq. (1), § 501, leads to an equation of high degree with respect to Q.



Fig. 556.

Practically, therefore, it is better to write

$$Q = \mu ab\sqrt{2g\left(h_1 + \frac{a}{2}\right)}, \quad . \quad . \quad . \quad (9)$$

and determine μ by experiment for different values of the ratio $F \div G$. Accordingly, Weisbach found, for Poncelet's orifices, that if μ_0 is the coefficient for complete and perfect contraction from Case I, we have

$$\mu = \mu_0(1 + \beta'), \quad \text{where} \quad \beta' = 0.641(F \div G)^2 \quad . \quad . \quad (9')$$

h_1 was measured to the surface one metre back of the plane of the orifice, and $F:G$ did not exceed 0.50.

504. Actual Discharge of Sharp-edged Overfalls (Overfall-weirs; or Rectangular Notches in a Thin Vertical Plate).

Case I. *Complete and Perfect Contraction* (*the normal case*), Fig. 557; i.e., no edge is flush with the side or bottom of the reservoir, whose sectional area is very large compared with that, bh_2, of the notch. By depth, h_2, of the notch, we are to understand the *depth of the sill below the surface a few feet back of the notch where it is level.* In the plane of the notch the vertical thickness of the stream is only from $\frac{3}{4}$ to $\frac{9}{10}$ of h_2. Putting, therefore, the velocity of approach = zero, and hence $k = 0$, in eq. (3) of § 501, we have for the



Fig. 557.

$$\textit{Actual } Q = \mu_0 \tfrac{2}{3} b h_2 \sqrt{2gh_2}, \quad . \quad . \quad . \quad . \quad (10)$$

(b = width of notch,) where μ_0 is a *coefficient of efflux* to be determined by experiment.

Experiments with overfalls do not agree as well as might be desired. Those of Poncelet and Lesbros gave the results in Table C.

EXAMPLE 1.—With

$h_2 = 1$ ft. 4 in. ($= .405^{m.}$),

$b = 2$ ft. ($= 0.60^{m.}$),

we have, from Table C, $\mu_0 = .586$, and (ft., lb., sec.)

$$\therefore Q = .586 \times \tfrac{2}{3} \times 2 \times \tfrac{4}{3} \sqrt{2 \times 32.2 \times \tfrac{4}{3}}$$

$$= 9.54 \text{ cub. ft. per sec.}$$

TABLE C.

For $b = 0.20^{m.}$		For $b = 0.60^{m.}$	
metres.		metres.	
h_2	μ_0	h_2	μ_0
.01	.636	.06	.618
.02	.620	.08	.613
.03	.618	.10	.609
.04	.610	.12	.605
.06	.601	.15	.600
.08	.595	.20	.592
.10	.592	.30	.586
.15	.589	.40	.586
.20	585	.50	.586
.22	.577	.60	.585
For approx. results $\mu_0 = .60$			

EXAMPLE 2. — What width, b, must be given to a rectangular notch, for which $h_2 = 10$ in. ($= 0.25^{m.}$), that the discharge may be $Q = 6$ cub. feet per sec.?

Since b is unknown, we cannot use the table immediately, but take $\mu_0 = .600$ for a first approximation; whence, eq. (10), (ft., lb., sec.,)

$$b = \frac{6}{0.6 \times \frac{2}{3} \times \frac{10}{12} \sqrt{2 \times 32.2 \times \frac{10}{12}}} = 2.46 \text{ ft.}$$

Then, since this width does not much exceed 0.60 metre, we may take, in Table C, for $h_2 = 0.25$ met., $\mu_0 = .589$;

$$\therefore \quad b = \frac{6}{.589 \times \frac{2}{3} \times \frac{10}{12} \sqrt{2 \times 32.2 \times \frac{10}{12}}} = 2.50 \text{ ft.}$$

CASE II. *Incomplete Contraction; i.e., both ends are flush with the sides of the tank, these being ⅂ to the plane of the notch.* According to Weisbach, we may write

$$Q = \tfrac{2}{3} \mu b h_2 \sqrt{2gh_2}, \quad . \quad . \quad . \quad . \quad . \quad . \quad (11)$$

in which $\mu = 1.041 \mu_0$, μ_0 being obtained from Table C for the normal case, i.e., Case I. The section of channel of approach is large compared with that of the notch; if not, see Case IV.

CASE III. *Imperfect Contraction; i.e., the velocity of approach is appreciable;* the sectional area G of the channel of approach not being much larger than that, $F, = bh_2 =$ area of notch. Fig. 558. $b =$ width, and $h_2 =$ depth of notch (see Case I). Here, instead of using a formula involving



FIG. 558.

$$k = c^2 \div 2g = [Q \div G]^2 \div 2g$$

(see eq. (3), § 501), it is more convenient to put

$$Q = \tfrac{2}{3}\mu b h_2 \sqrt{2gh_2}, \quad \ldots \quad (12)$$

as before, with

$$\mu = \mu_0(1 + \beta), \quad \ldots \quad (12)'$$

in which μ_0 is for the normal case [Case I]; and β, according to Weisbach's experiments, may be obtained from the empirical formula

$$\beta = 1.718\left(\frac{F}{G}\right)^4. \quad \ldots \quad (12)''$$

[Table D is computed from (12)''.]

(The contraction is *complete* in this case; i.e., the ends are not flush with the sides of the tank.)

EXAMPLE.—If the water in the channel of approach has a vertical transverse section of $G = 9$ sq. feet, while the notch is 2 feet wide (i.e., $b = 2'$) and 1 foot deep ($h_2 = 1'$) (to level of surface of water 3 or 4 ft. back of notch), we have, from Table C, with $b = .60$ met. and $h_2 = 0.30$ met.,

$$\mu_0 = 0.586;$$

while from Table D, with $F : G = 0.222$ (or $\frac{2}{9}$),

$$\beta = .005;$$

TABLE D.

$\frac{F}{G}$	β.
0.05	.000
.10	.000
.15	.001
.20	.003
.25	.007
.30	.014
.35	.026
.40	.044
.45	.070
.50	.107

hence (ft.-lb.-sec. system of units), from eq. (12),

$$Q = \tfrac{2}{3} \times 0.586 \times 1.005 \times 2 \times 1 \times \sqrt{64.4 \times 1.0}$$

$$= 6.30 \text{ cub. ft. per second.}$$

CASE IV. Fig. 559. *Imperfect and incomplete contraction together;* both end-contractions being "suppressed" (by making the ends flush with the sides of the reservoir, these sides being vertical and ⊓ to the plane of the notch), and the channel of approach not being very deep, i.e., having a sectional area G but little larger than that, F, of notch. $F = bh_2$ as before.

Again we write

$$Q = \tfrac{2}{3}\mu b h_2 \sqrt{2gh_2}, \quad \ldots\ldots \quad (13)$$

with μ computed from

$$\mu = \mu_0 (1 + \beta), \quad \ldots\ldots \quad (13)'$$

μ_0 being obtained from Table C; while

$$\beta = 0.041 + 0.3693 \left(\frac{F}{G}\right)^2, \quad \ldots\ldots \quad (13)''$$

an empirical formula based by Weisbach on his own experiments. To save computation, β may be found from Table E, founded on eq. (13)''.

TABLE E.

$\frac{F}{G}$ =	.00	.05	.10	.15	.20	.25	.30	.35	.40	.45	.50
β =	.041	.042	.045	.049	.056	.064	.074	.086	.100	.116	.133



FIG. 559.

EXAMPLE.—Fig. 559. With

$$b = 2 \text{ ft. } (= 0.60 \text{ met.})$$

and

$$h_2 = 1 \text{ ft. } (= 0.30 \text{ met.}),$$

we have, from Table C, $\mu_0 = 0.586$. But, the ends being flush with the sides of the reservoir or channel, and G being $= 6$ sq. ft. (see figure), which is not excessively large compared with $F = bh_2 = 2$ sq. ft., we have from Table E, with $F : G = 0.333$, $\beta = .081$; and hence [eq. (13) and (13)'], μ_0 being .586 as in last example,

$$Q = \tfrac{2}{3} \times 0.586 \times (1 + .081) \times 2 \times 1 \times \sqrt{64.4 \times 1.6}$$

$$= 6.78 \text{ cub. ft. per sec.}$$

505. Francis' Formula for Overfalls (i.e., rectangular notches).—From extensive experiments at Lowell, Mass., in 1851, with rectangular overfall-weirs, Mr. J. B. Francis deduced the following formula for the volume, Q, of flow per second over such weirs 10 feet in width, and with h_2 varying from 0.6 to 1.6 feet (from sill of notch to level surface of water a few feet back):

$$Q = \tfrac{2}{3} \times 0.622 h_2 (b - \tfrac{1}{10} n h_2) \sqrt{2 g h_2}, \quad . \quad . \quad (14)$$

in which b = width.

This provides for incomplete contraction, as well as for complete and perfect contraction, by making

$n = 2$ for perfect and complete contraction (Fig. 557);

$n = 1$ when one end only is flush with side of channel;

$n = 0$ when both ends are flush with sides of channel.

The contraction was considered complete and perfect when the channel of approach was made as wide as practicable, = 13.96 feet, the depth being about 5 feet.

Mr. Francis also experimented with submerged or "drowned" weirs in 1883; such a weir being one in which the sill is below the level of the tail-water (i.e., of receiving channel).

505a. The Cippolletti, or Trapezoidal, Weir.—It is evident that in the rectangular notch of Fig. 559, where the ends are flush with the vertical walls of the channel of approach (so that the end-contractions are "suppressed"), the discharge, Q, is proportional to the length, b, of the sill (or "crest") of the weir; for a given h_2. To secure a similar simplicity of relation for a notch *not* filling the whole width of channel, the Italian engineer, Cippolletti, proposed and used a symmetrical trapezoidal sharp-edged notch in a vertical plate, as shown in Fig. 559*a*; with such an inclination of side edges that $\overline{ae}$ and $\overline{rd}$ were each equal to 1/4 of $\overline{es}$. The theoretical basis of such a slope is as follows:



FIG. 559*a*.

Writing μ for the 0.622 of the Francis formula, eq. (14), we have for a rectangular notch with perfect and complete contraction (Fig. 557),

$$Q = \tfrac{2}{3}\mu h_2\sqrt{2gh_2}(b - \tfrac{2}{10}h_2); \quad . \quad . \quad . \quad . \quad (14a)$$

whereas for the case of end contractions suppressed (Fig. 559) and deep channel of approach, this becomes

$$Q_0 = \tfrac{2}{3}\mu b h_2\sqrt{2gh_2}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (14b)$$

It is therefore evident that the *additional* discharge obtained in the latter case is,

$$Q'' = \tfrac{2}{15}\mu h_2^2\sqrt{2gh_2}. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (14c)$$

Now the discharge through the trapezoidal notch in Fig. 559*a* is made up of that (Q_0) through the rectangle *edts*, considered as taking place without end contractions, and that (Q'), through the two triangles *aes* and *rtd*, which may be considered as equivalent to that through a single triangular notch of width b', $= \overline{ae} + \overline{rd}$, for which [see Fig. 552, and eq. (5) on p. 675] we have a discharge

$$Q' = \tfrac{4}{15}\mu b' h_2\sqrt{2gh_2}. \quad . \quad . \quad . \quad . \quad . \quad . \quad (14d)$$

Hence, equating Q' and Q'', we derive $b' = \frac{1}{2}h_2$, i.e., $\overline{ae}, = \overline{rd}, = \frac{1}{4} \cdot \overline{es}$ as a proper relation such that the discharge of trapezoidal weir shall be

$$Q = \tfrac{2}{3}\ bh_2\sqrt{2gh_2}, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (14e)$$

that is, that its discharge shall be *proportional to the length, b, of sill.* (It is understood that in Fig. 559*a* that $\overline{es} = h_2$, *ar* being in the horizontal plane of the surface of quiet water somewhat back from the weir.)

With the foot and second as units, and the value $\mu = .622$ of the Francis formula [eq. (14)], we find $\frac{2}{3}\mu\sqrt{2g} = 3.33$; but the careful experiments of Messrs. Flinn and Dyer, at Holyoke, Mass., in April, 1893 (*Transac. Amer. Soc. Civil Engineers*, vol. xxxii, p. 9) led them to conclude that the equation

$$Q = (3.366)bh^{\frac{3}{2}} \quad . \quad . \quad . \quad . \quad (14f)$$

(*for foot and second*), (which is the formula proposed by Cippolletti himself), gives results within one per cent of the truth.

In these experiments the length b of sill ranged from 3 ft. to 9 ft., and the head h_2 from 0.30 ft. on a 3-ft. sill to 1.25 ft. on a 9-ft. sill. The channel of approach was 20 ft. wide and about 8 ft. deep below the sill of each weir. The contraction was therefore "complete" and "perfect."

Since 1881 the Cippolletti weir has been much used in Italy in measuring water for irrigation, and is now used to some extent in the Western part of the United States for the same purpose.

506. Fteley and Stearns's Experiments at Boston, Mass., in 1877 and 1880.—These may be found in the Transactions of the American Society of Civil Engineers, vol. XII, and gave rise to formulæ differing slightly from those of Mr. Francis in some particulars. In the case of *suppressed end-contractions*, like that in Fig. 559, they propose formulæ as follows:

When depth of notch is not large,

$$Q \text{ (in cub. ft. per sec.)} = 3.31\, bh_2^{\frac{3}{2}} + 0.007b \quad . \quad (15)$$

(*b and h_2 both in feet*),

"h_2, the depth on the weir, should be measured from the surface of the water above the curvature of the sheet."

"Air should have free access to the space under the sheet." The crest must be horizontal. The formula does not apply to depths on the weir less than 0.07 feet.

When the depth of notch is quite large, a correction must be made for velocity of approach, c, thus:

$$Q \text{ (in cub. ft. per sec.)} = 3.31b\left[h_2 + 1.5\frac{c^2}{2g}\right]^{\frac{3}{2}} + 0.007b \quad (16)$$

(b, h_2, and $c^2 \div 2g$, *in feet*).

The channel should be of uniform rectangular section for about 20 ft. or more from the weir, to make this correction properly. If G = the cross-section, in sq. ft., of the channel of approach, c is found approximately by dividing an approximate value of Q by G; and so on for closer results.

The weir may be of any length, b, from 5 to 19 feet.

506a. Recent Experiments on Overfall-weirs in France.*—In the *Annales des Ponts et Chaussées* for October 1888 is an account of extensive and careful experiments conducted in 1886 and 1887 by M. Bazin on the flow over sharp-edged overfall-weirs with end-contractions suppressed; i.e., like that shown in Fig. 559. The widths of the weirs ranged from 0.50 to 2.00 metres, and the depths on the weirs (h_2) from 0.05 to 0.60 metre. With p indicating the height of the sill of the weir from the bottom of the channel of approach, M. Bazin, as a practical result of the experiments, recommends the following formula as giving a reasonably accurate value for the volume of discharge per unit of time:

$$Q = \tfrac{2}{3}\mu'\left[1 + 0.55\left(\frac{h_2}{p + h_2}\right)^2\right]bh_2\sqrt{2gh_2}, \quad . \quad . \quad (17)$$

where the coefficient μ' has a value

$$\mu' = 0.6075 + \frac{0.0148}{h_2 \text{ (in ft.)}} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (18)$$

Eq. (17) is homogeneous, i.e., admits of any system of units.

* A valuable résumé of "Weir Experiments, Coefficients, and Formulas," by Robert E. Horton, appeared as "*Water-supply and Irrigation Paper*," No. 150, issued by the U. S. Geological Survey in 1906.

Provision was made in these experiments for the free entrance of air under the sheet (a point of great importance), while the walls of the channel of approach were continued down-stream, beyond the plane of the weir, to prevent any lateral expansion of the sheet. The value of p ranged from 0.20 to 2.00 metres.*

507. Efflux through Short Cylindrical Tubes.—When efflux takes place through a short cylindrical tube, or "short pipe," at least $2\frac{1}{2}$ times as long as wide, inserted at right angles in the plane side of a large reservoir, the inner corners *not rounded* (see Fig. 560), the jet issues from the tube in parallel filaments and with a sectional area, F_m, equal to that, F, of interior of tube.



FIG. 560.

To attain this result, however, the tube must be full of water before the outer end is unstopped, and must not be oily; nor must the head, h, be greater than about 40 ft. for efflux into the air. Since at m the filaments are parallel and the pressure-head therefore equal to b (= 34 ft. of water, nearly), = that of surrounding medium, = head due to one atmosphere in this instance; an application of Bernoulli's Theorem [eq. (7), § 492] to positions m and n would give (precisely as in §§ 454 and 455)

$$v_m = \text{veloc. at } m = \sqrt{2gh}$$

as a theoretical result; but experiment shows that the actual value of v_m in this case is

$$v_m = \phi_0 \sqrt{2gh} = 0.815 \sqrt{2gh}, \quad . \quad . \quad . \quad . \quad (1)$$

0.815 being an average value for ϕ_0, the *coefficient of velocity*, for ordinary purposes. It increases slightly as the head decreases,

* Mr. Rafter's paper, in Vol. 44 (p. 220) of the Trans. Am. Soc. C. E., gives an account of Bazin's experiments with weirs of irregular forms; as also of similar experiments made at the Hydraulic Laboratory of the College of Civil Engineering at Cornell University.

and is evidently much less than the value 0.97 for an orifice in a thin plate, § 495, or for a rounded mouth-piece as in § 496.

But as the sectional area of the stream where the filaments are parallel, at m, where $v_m = 0.815\sqrt{2gh}$, is also equal to that, *F, of the tube*, the coefficient of efflux, μ_o, in the formula

$$Q = \mu_o F\sqrt{2gh},$$

is equal to ϕ_o; i.e., there is no contraction, or the coefficient of contraction, C, in this case $= 1.00$.

Hence, for the volume of discharge per unit of time, we have practically

$$Q = \phi_o F\sqrt{2gh} = 0.815\, F\sqrt{2gh}. \quad . \quad . \quad . \quad (2)$$

The discharge is therefore about $\frac{1}{5}$ greater than through an orifice of the same diameter in a thin plate under the same head [compare eq. (3), § 495]; for although at m the velocity is less in the present case, the *sectional area of the stream is greater*, there being no contraction.

This difference in velocity is due principally to the fact that the entrance of the tube has square edges, so that the stream contracts (at m', Fig. 561) to a section smaller than that of the tube, and then *re-expands* to the full section, F, of tube. The eddying and accompanying internal friction caused by this re-expansion (or "sudden enlargement" of the stream) is the principal *resistance* which diminishes the velocity. It is noticeable, also, in this case that the jet is not limpid and clear, as from thin plate, but troubled and only translucent (like ground-glass). The internal pressure in the stream at m' is found to be *less than one atmosphere*, i.e. less than that at m, as shown experimentally by the sucking in of air when a small aperture is made in the tube op



FIG. 561.


FIG. 562.

posite m'. If the tube itself were so formed internally as to fit this contracted vein, as in Fig. 562, the eddying would be diminished and the velocity at m increased, and hence the volume Q of efflux increased in the same proportion. (See § 509a.)

If the tube is less than $2\frac{1}{2}$ times as long as wide, or if the interior is *not wet by the water* (as when greasy), or if the head is over 40 or 50 ft. (about), the efflux takes place as if the tube were not there, Fig. 563, and we have



Fig. 563.

$$v_m = 0.97\sqrt{2gh}, \text{ as in § 495.}$$

Example.—The discharge through a short pipe 3 inches in diameter, like that in Fig. 560, is 30 cub. ft. per minute, under a head of 2′ 6″, reservoir large. Required the coefficient of efflux μ_0, $= \phi_0$, in this case. For variety use the *inch-pound-minute* system of units, in which $g = 32.2 \times 12 \times 3600$ (see Note, § 51). μ_0, being an abstract number, will be the same numerically in any system of units.

From eq. (2),

$$\phi_0 = \mu_0 = \frac{Q}{F\sqrt{2gh}} = \frac{30 \times 1728}{\frac{\pi}{4} \times 3^2 \sqrt{2 \times 32.2 \times 12 \times 60^2 \times 30}}$$

$$= 0.803.$$

508. Inclined Short Tubes (Cylindrical).—Fig. 564. If the short tube is inclined at some angle $\alpha < 90°$ to the interior plane of the reservoir wall, the efflux is smaller than when the angle is 90°, as in § 507.



Fig. 564.

We still use the form of equation

$$Q = \mu F\sqrt{2gh} = \phi F\sqrt{2gh}; \quad . \quad (3)$$

but from Weisbach's experiments μ should be taken from the following table:

TABLE F, COEFFICIENT OF EFFLUX (INCLINED TUBE).

For $\alpha =$	90°	80°	70°	60°	50°	40°	30°
take $\mu = \phi =$	.815	.799	.782	.764	.747	.731	.719

EXAMPLE.—With $h = 12$ ft., $d =$ diam. of tube $= 4$ ins. and $\alpha = 46°$, we have for the volume discharged per sec. (ft., lb., and sec.)

$$Q = [0.731 + \tfrac{6}{10}(.016)]\frac{\pi}{4}\left(\frac{1}{3}\right)^2\sqrt{64.4 \times 12} = 1.79 \text{ cub.ft.per sec.}$$

The tube must be at least 3 times as long as wide, to be filled.

509. Conical Diverging, and Converging, Short Tubes.—With *conical convergent tubes*, as at A, Fig. 565, with inner edges not rounded, D'Aubuisson and Castel found by experiment values of the coefficient of velocity, ϕ, and of that of efflux, μ, [from which the coefficient of contraction, $C = \mu \div \phi$, may be



FIG. 565.

computed,] for tubes 1.55 centimeters wide at the narrow end, and 4.0 centimeters long, under a head of $h = 3$ metres, and with different angles of convergence. By angle of convergence is meant the angle between the sides CE and DB, Fig. 565. In the following table will be found some values of μ and ϕ founded on these experiments, for use in the formulæ

$$v_m = \phi\sqrt{2gh} \quad \text{and} \quad Q = \mu F\sqrt{2gh};$$

in which F denotes the area of the outlet orifice EB.

TABLE G (CONICAL CONVERGING TUBES).

Angle of convergence	= 3° 10′	8°	10° 20′	13° 30′	19° 30′	30°	49°
	μ = .895	.930	.938	.946	.924	.895	.847
	ϕ = .894	.932	.951	.963	.970	.975	.984

Evidently μ is a maximum for $13\frac{1}{2}°$.

With a conically divergent tube as at MN, having the internal diameter $MO = .025$ metre, the internal diam. $NP = .032$ metre, and the angle between MN and $PO = 4° 50'$, Weisbach found that in the equation $Q = \mu F\sqrt{2gh}$ (where F = area of *outlet* section NP) μ should be $= 0.553$; the great loss of velocity as compared with $\sqrt{2gh}$ being due to the eddying in the re-expansion from the contracted section at M (corners *not rounded*), as occurs also in Fig. 549. The jet was much troubled and pulsated violently.

When the angle of divergence is too great, or the head h too large, or if the tube is *not wet* by the water, efflux with the tube filled cannot be maintained, the flow then taking place as in Fig. 563.

Venturi and Eytelwein experimented with a conically divergent tube (called now "*Venturi's tube*"), with rounded entrance to conform to the shape of the contracted vein, as in Fig. 566, having a diameter of one inch at m' (narrowest part), where the sectional area $= F'$ $= 0.7854$ sq. in., and of 1.80 inches at m (outlet), where area $= F$; the length being 8 ins., and the angle of convergence 5° 9′.



FIG. 566.

With $Q = \mu F\sqrt{2gh}$ they found $\mu = 0.483$.

Hence $2\frac{1}{2}$ times as much water was discharged as would have flowed out under the same head through an orifice in thin plate with area $= F' =$ the *smallest* section of the divergent tube, and 1.9 times as much as through a short pipe of section $= F'$. A similar calculation shows that the velocity at m' must have been $v_{m'} = 1.55\sqrt{2gh}$, and hence that the pressure at m' was much less than one atmosphere.

Mr. J. B. Francis also experimented with Venturi's tube (see "Lowell Hydraulic Experiments"). See also p. 389 of vol. 6 of the Journal of Engineering Societies, for experiments with diverging short tubes discharging under water. The highest coefficient (μ) obtained by Mr. Francis was 0.782.

509a. New Forms of the Venturi Tube.—The statement made in § 507, in connection with Fig. 562, was based on purely theoretic grounds, but has recently (Dec. 1888) been completely verified by experiments* conducted in the hydraulic laboratory of the College of Civil Engineering at Cornell University. Three short tubes of circular section, each 3 in. in length and 1 in. in internal diameter at *both* ends, were experimented with, under heads of 2 ft. and 4 ft.† Call them A, B, and C. A was an ordinary straight tube as in Fig. 561; the longitudinal section of B was like that in Fig. 562, the narrowest diameter being 0.80 in. [see § 495; $(0.8)^2 = 0.64$]; while C was somewhat like that in Fig. 566, being formed like B up to the narrowest part (diameter 0.80 in.), and then made conically divergent to the discharging end. The results of the experiments are given in the following table:

Name of Tube.	Head.	Number of Experiments.	Range of Values of μ.	Average Values of μ.
A	$h = 2$ ft.	4	From 0.804 to 0.823	0.814
A	$h = 4$ ft.	3	" 0.819 to 0.823	0.821
B	$h = 2$ ft.	5	" 0.875 to 0.886	0.882
B	$h = 4$ ft.	4	" 0.881 to 0.902	0.892
C	$h = 2$ ft.	5	" 0.890 to 0.919	0.901
C	$h = 4$ ft.	4	" 0.902 to 0.923	0.914

The fact that B discharges more than A is very noticeable, while the superiority of C to B, though evident, is not nearly so great as that of B to A, showing that in order to increase the discharge of an (originally) straight tube (by *encroaching* on the passage-way) it is of more importance to fill up with solid substance the space around the contracted vein than to make the transition from the narrow section to the discharging end very gradual.

* See Journal of the Franklin Inst., for April, 1889.

† Practically the same co-efficients were obtained later, by Mr. E. M. Holbrook, with higher heads; up to 18 ft.

510. "Fluid Friction."—By experimenting with the flow of water in glass pipes inserted in the side of a tank, Prof. Reynolds of England has found that the flow goes on in parallel filaments for only a few feet from the entrance of the tube, and that then the liquid particles begin to intermingle and cross each other's paths in the most intricate manner. To render this phenomenon visible, he injected a fine stream of colored liquid at the inlet of the pipe and observed its further motion, and found that the greater the velocity the nearer to the inlet was the point where the breaking up of the parallelism of flow began. The hypothesis of laminated flow is, nevertheless, the simplest theoretical basis for establishing practical formulæ, and the resistance offered by pipes to the flow of liquids in them will therefore be attributed to the friction of the edges of the laminæ against the inner surface of the pipe.*

The amount of this resistance (often called *skin-friction*) for a given extent of rubbing surface is by experiment found—

1. To be *independent of the pressure* between the liquid and the solid;
2. To vary nearly with the *square of the relative velocity;*
3. To vary directly with the *amount of rubbing surface;*
4. To vary directly with the *heaviness* [γ, § 409] of the liquid.

Hence for a given velocity v, a given rubbing surface of area $= S$, and a liquid of heaviness γ, we may write

$$\text{Amount of friction (force)} = fS\gamma\frac{v^2}{2g}, \quad \ldots\ldots (1)$$

in which f is an abstract number called the *coefficient of fluid friction*, to be determined by experiment. For a given liquid, given character (roughness) of surface, and small range of velocities it is approximately constant. The object of introducing the $2g$ is not only because $\frac{v^2}{2g}$ is a familiar and useful function of v, but that $v^2 \div 2g$ is a *height*, or distance, and therefore the product of S (an area) by $v^2 \div 2g$ is a *volume*, and this volume multiplied by γ gives the *weight* of an ideal prism of

* The resistance is really due both to the friction of the water on the sides of the pipe and to the friction of the water particles on each other. The assumption that it is due to the former action alone simply affects the mathematical form of our expressions, without invalidating their accuracy, since the value of f is in any case dependent on experiment. See *Engineering News*, July–Dec. 1901, pp. 332 and 476.

the liquid; hence $S\frac{v^2}{2g}\gamma$ is a *force* and f must be *an abstract number* and therefore the same in all systems of units, in any given case or experiment.*

In his experiments at Torquay, England, the late Mr. Froude found the following values for f, the liquid being salt water, while the rigid surfaces were the two sides of a thin straight wooden board $\frac{3}{16}$ of an inch thick and 19 inches high, coated or prepared in various ways, and drawn edgewise through the water at a constant velocity, the total resistance being measured by a dynamometer.

511. Mr. Froude's Results.—(Condensed.) [The velocity was the same = 10 ft. per sec. in each of the following cases. For other velocities the resistance was found to vary nearly as the square of the velocity, the index of the power varying from 1.8 to 2.16.]

TABLE H.

Character of Surface.	Value of f [from eq. (1), § 510].			
	When the board was			
	2 ft. long.	8 ft. long.	20 ft. long.	50 ft. long.
Varnish.....f =	0.0041	0.0032	0.0028	0.0025
Paraffine..... "	.0038	.0031	.0027	.....
Tinfoil.....	.0030	.0028	.0026	.0025
Calico.....	.0087	.0063	.0053	.0047
Fine Sand.....	.0081	.0058	.0048	.0040
Medium Sand.....	.0090	.0062	.0053	.0049
Coarse Sand.....	.0110	.0071	.0059	.....

N.B. These numbers multiplied by 100 also give the mean frictional resistance in lbs. per sq. foot of area of surface in each case (v = 10' per sec.), considering the heaviness of sea water, 64 lbs. per cubic foot, to cancel the $2g$ = 64.4 ft. per sq. sec. of eq. (1) of the preceding paragraph.

For use in formulæ bearing on flow in pipes, f is best determined directly by experiments of that very nature, the results of which will be given as soon as the proper formulæ have been established.

512. Bernoulli's Theorem for Steady Flow, with Friction.—[The student will now re-read the first part of § 492, as far as eq. (1).] Considering free any lamina of fluid, Fig. 567, (according to the subdivision of the stream agreed upon in § 492 referred

* For very low velocities, below the range of ordinary engineering practice, the friction varies more nearly as the *first power* of the velocity, instead of the square. See p. 42, etc., of Blaine's *Hydraulic Machinery*.

to,) the frictions on the edges are the only additional forces as compared with the system in Fig. 534. Let w denote the length of the *wetted perimeter* of the base of this lamina (in case of a pipe running full, as we here postulate, the wetted perimeter is of course the *whole perimeter*, but in the case of an open channel or canal, w is only a portion of the whole perimeter of the cross-section). Then, since the area of rubbing surface at the edge is $S = wds'$, the total friction for the lamina is [by eq. (1), § 510] $= fw\gamma(v^2 \div 2g)ds'$. Hence from $vdv =$ (tan. accel.) $\times ds$, and from (tan. accel.) $=$ [Σ(tang. compons. of acting forces)] $\div$ (mass of lamina), we have



FIG. 567.

$$vdv = \frac{Fp - F(p+dp) + F\gamma ds' \cos\phi - fw\gamma \frac{v^2}{2g} ds'}{F\gamma ds' \div g} \cdot ds \ldots (a)$$

As in § 492, so here, considering the simultaneous advance of all the laminæ lying between any two sections m and n during the small time dt, putting $ds' = ds$, and $ds' \cos\phi = -dz$ (see Fig. 568), we have, for any one lamina,

$$\frac{1}{g} vdv + \frac{1}{\gamma} dp + dz = -f \frac{w}{F} \cdot \frac{v^2}{2g} ds. \quad . \quad . \quad . \quad (1)$$

Now conceive an infinite number of equations to be formed like eq. (1), one for each lamina between n and m, for *the same* dt, viz., a dt of such length that each lamina at the end of dt will occupy the same position, and acquire the same values of v, z, and p, that the lamina next in front had at the beginning of the dt (this is the characteristic of a *steady flow*). Adding up



FIG. 568.

the corresponding terms of all these equations, we have (remembering that for a liquid γ is the same in all laminæ),

$$\frac{1}{g}\int_n^m v dv + \frac{1}{\gamma}\int_n^m dp + \int_n^m dz = -\frac{f}{2g}\cdot\int_n^m \frac{w}{F} v^2 ds\,; \quad . \quad (2)$$

i.e., after transposition and writing R for $F \div w$, for brevity,

$$\frac{v_m^2}{2g} + \frac{p_m}{\gamma} + z_m = \frac{v_n^2}{2g} + \frac{p_n}{\gamma} + z_n - \frac{f}{2g}\int_n^m \frac{v^2 ds}{R} \quad . \quad (3)$$

This is *Bernoulli's Theorem for steady flow of a liquid in a pipe of slightly varying sectional area F, and internal perimeter w*, taking into account no resistances or friction, except the "skin-friction," or "fluid-friction," of the liquid and sides of the pipe.

Resistances due to the internal friction of eddying occasioned by sudden enlargements of the cross-section of the pipe, by elbows, sharp curves, valve-gates, etc., will be mentioned later. The negative term on the right in (3) is of course a *height* or *head* (one dimension of length), as all the other terms are such, and since it is the amount by which the sum of the three heads (viz., *velocity-head*, *pressure-head*, and *potential head*) at m, the down-stream position, *lacks* of being equal to the sum of the corresponding heads at n, the up-stream position or section, we may call it the "**Loss of Head**" due to skin-friction between n and m; also called *friction-head*, or *resistance-head*, or *height of resistance*.

The quantity $R = F \div w$ = sectional-area ÷ wetted-perimeter, is an imaginary distance or length called the *Hydraulic Mean Radius*, or *Hydraulic Mean Depth*, or simply *hydraulic radius* of the section. For a circular pipe of diameter $= d$,

$$R = \tfrac{1}{4}\pi d^2 \div \pi d = \tfrac{1}{4}d;$$

while for a pipe of rectangular section,

$$R = \frac{ab}{2(a+b)}.$$

a and b are lengths of sides of rectangle.

513. Problems involving Friction-heads; and Examples of Bernoulli's Theorem with Friction.

PROBLEM I.—Let the portion of pipe between n and m be level, and of uniform circular section and diameter $= d$. The jet at m discharges into the air, and has the same sectional area, $F = \frac{1}{4}\pi d^2$, as the pipe; then the pressure-head at m is $\frac{p_m}{\gamma} = b = 34$ feet (for water), and the velocity-head at m is $=$ that at n, since $v_m = v_n$. The height of the water column in the open piezometer at n is noted, and $= y_n$ (so that the pressure-head at n is $\frac{p_n}{\gamma} = y_n + b$); while the length of pipe from n to m is $= l$.



FIG. 569.

Knowing l, d, y_n, and having measured the volume Q, of flow, per unit of time, it is required to find the form of the friction-head and the value of f. From

$$F_m v_m = Q, \quad \text{or} \quad \tfrac{1}{4}\pi d^2 v_m = Q, \quad . \quad . \quad . \quad . \quad (1)$$

v_m becomes known. Also, v_m is known to be $= v_n$, and the velocity at each ds is $v = v_m$, since F (sectional area) is constant along the pipe, and $Fv = Q$. The hydraulic radius is

$$R = \tfrac{1}{4}d; \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

the same for all the ds's between n and m.

Substituting in eq. (3) of § 512, with the horizontal axis of the pipe as a datum for potential heads, we have

$$\frac{v_m^2}{2g} + b + 0 = \frac{v_n^2}{2g} + y_n + b + 0 - \frac{f}{\frac{1}{4}d} \cdot \frac{v_m^2}{2g} \int_n^m ds; \quad . \quad (3)$$

i.e., since $\int_n^m ds = l =$ length of pipe from n to m, *the friction-head for a pipe of length $= l$, and uniform circular section of diameter $= d$, reduces to the form*

$$Friction\text{-}head = 4f\frac{l}{d}\cdot\frac{v^2}{2g}; \quad . \quad . \quad . \quad . \quad (4)$$

where v = velocity of water *in the pipe*, being in this case also $= v_m$ and $= v_n$. Hence this friction-head *varies directly as the length and as the square of the velocity, and inversely as the diameter; also directly as the coefficient f.*

From (3), then, we derive (for this particular problem)

$$Piezometer\text{-}height\ at\ n = y_n = 4f\frac{l}{d}\cdot\frac{v^2}{2g}; \quad . \quad . \quad (5)$$

i.e., the open piezometer-height at n is equal to the loss of head (all of which is friction-head here) sustained between n and the mouth of the pipe. (Pipe horizontal.)

EXAMPLE.—Required the value of f, knowing that $d = 3$ in., y_n (by observation) $= 10.4$ ft., and $Q = 0.1960$ cub. ft. per sec., while $l = 400$ ft. (n to m). From eq. (1) we find, in ft.-lb.-sec. system, the velocity in the pipe to be

$$v = \frac{4Q}{\pi d^2} = \frac{4 \times 0.1960}{\pi \frac{1}{16}} = 4.0 \text{ ft. per sec.};$$

then, using eq. (5), we determine f to be

$$f = \frac{2gy_n d}{4lv^2} = \frac{2 \times 32.2 \times \frac{1}{4} \times 10.4}{4 \times 400 \times 4^2} = 0.0065.$$

PROBLEM II. *Hydraulic Accumulator.*—Fig. 570. Let the area F_n of the piston on the left be quite large compared with



FIG. 570.

that of the pipes and nozzle. The cylinder contains a friction-

less weighted piston, producing (so long as its downward *slow* motion is uniform) a fluid pressure on its lower face of an intensity $p_n = [G + F_n p_a] \div F_n$ per unit area (p_a = one atmos.).

Hence the pressure-head at n is

$$\frac{p_n}{\gamma} = \frac{G}{F_n \gamma} + b, \quad \ldots\ldots \quad (6)$$

where G = load on piston.

The jet has a section at $m = F_m$ = that of the small straight nozzle (no contraction). The junctions of the pipes with each other, and with the cylinder and nozzle, are all smoothly rounded; hence the only losses of head in steady flow between n and m are the friction-heads in the two long pipes, neglecting that in the short nozzle. These friction-heads will be of the form in eq. (4), and will involve the velocities v_1 and v_2 respectively in these pipes (*supposed* running full). v_1 and v_2 may be unknown at the outset, as here.

Knowing G and all dimensions and heights, we are required to find the velocity v_m of the jet, flowing into the air, and the volume of flow, Q, per unit of time, assuming f to be known and to be the same in both pipes (not strictly true).

Let the lengths and diameters be denoted as in Fig. 570, their sectional areas F_1 and F_2, the unknown velocities in them v_1 and v_2.

From the *equation of continuity* [eq. (3), § 490], we have

$$v_1 = \frac{F_m v_m}{F_1} \quad \text{and} \quad v_2 = \frac{F_m v_m}{F_2}. \quad \ldots \quad (7)$$

To find v_m, we apply Bernoulli's Theorem (with friction), eq. (3), § 512, taking the down-stream position m in the jet close to the nozzle, and the up-stream position n just under the piston in the cylinder where the velocity v_n is practically nothing. Then with m as datum plane we have

$$\frac{v_m^2}{2g} + b + 0 = 0 + \frac{p_n}{\gamma} + h - 4f\frac{l_1}{d_1} \cdot \frac{v_1^2}{2g} - 4f\frac{l_2}{d_2} \cdot \frac{v_2^2}{2g}. \quad (8)$$

Apparently (8) contains three unknown quantities, v_m, v_1, and v_2; but from eqs. (7) v_1 and v_2 can be expressed in terms of v_m, whence [see also eq. (6)]

$$\frac{v_m^2}{2g}\left[1+4f\frac{l_1}{d_1}\left(\frac{F_m}{F_1}\right)^2+4f\frac{l_2}{d_2}\left(\frac{F_m}{F_2}\right)^2\right]=h+\frac{G}{F_n\gamma}; \quad (9)$$

or, finally,

$$v_m=\frac{\sqrt{2g\left(h+\frac{G}{F_n\gamma}\right)}}{\sqrt{1+4f\frac{l_1}{d_1}\left(\frac{F_m}{F_1}\right)^2+4f\frac{l_2}{d_2}\left(\frac{F_m}{F_2}\right)^2}}; \quad (10)$$

and hence we have also

$$Q=F_m v_m. \quad (11)$$

EXAMPLE.—If we replace the force G of this problem by the thrust P exerted along the pump-pist n of a steam fire-engine, we may treat the foregoing as a close approximation to the practical problem of such an apparatus, the pipes being consecutive straight lengths of hose, in which (for the probable character of the internal surface) we shall take $f=.0075$ (see Mr. Freeman's experiments on p. 832). (Strictly, f varies somewhat with the velocity; see § 517.) Let $P=12000$ lbs., and the piston-area at $n=F_n=72$ sq. in.$=\frac{1}{2}$ sq. ft. Also, let $h=20$ ft., and the dimensions of the hose be as follows:

$$d_1=3 \text{ in.} \quad d_2=2 \text{ in.}, \quad d_n(\text{of nozzle})=1 \text{ in.};$$

$$l_1=400 \text{ ft.}, \quad l_2=500 \text{ ft.}$$

With the foot-pound-second system of units, we now have [eq. (10)]

$$v_m=\sqrt{\frac{2\times 32.2\left[20+\frac{12000}{\frac{1}{2}\times 62.5}\right]}{1+4\times .0075\left[\frac{400}{\frac{1}{4}}\left(\frac{1}{9}\right)^2+\frac{500}{\frac{1}{8}}\left(\frac{1}{4}\right)^2\right]}}$$

$$= \sqrt{\frac{2 \times 32.2 \times 404}{1 + 0.59 + 5.62}};$$

i.e., $v_m = 60.0$ ft. per sec. If this jet were directed vertically upward it should theoretically attain a height $= \frac{v_m^2}{2g} =$ nearly 56 feet, but the resistance of the air would reduce this to about 40 or 45 ft.

We have further, from eq. (1),

$$Q = F_m v_m = \frac{\pi}{4}\left(\frac{1}{12}\right)^2 \times 60.0 = 3.27 \text{ cub. ft. per sec.}$$

If there were no resistance in the hose we should have, from § 497*a*,

$$v_m = \sqrt{2g\left[\frac{P}{F_n\gamma} + h\right]} = \sqrt{2 \times 32.2 \times 404} = 161.3 \text{ ft. per sec.}$$

513a. **Influence of Changes of Temperature.**—Poiseuille and Hagen found that with glass tubes of very small diameters the flow of water was increased threefold by a rise of temperature from 0° to 45° Cent.; but with ordinary pipes the diminution of resistance with increase of temperature is much smaller. Mr. J. G. Mair found the following differences in the coefficient f, in flow through a brass pipe 25 ft. long and 1½ in. in diameter:

At velocities, in ft. per sec., of		At temperatures *Fahr.* of 56°	90°	160°
6.5	f =	.0047	.0042	.0035
4.5	f =	.0052	.0044	.0038

With about the same range of temperature, Mr. Mair found that with a round orifice in thin plate 2½ in. in diameter and also with a rounded mouth-piece 1½ in. in diameter, each under a head of 1.75 ft., the maximum effect of rise of temperature in increasing the flow was only 2 per cent for the latter, and practically nothing for the former. See pp. 92, 202, 219, of Prof. Unwin's *Hydraulics* (1907).

514. Loss of Head in Orifices and Short Pipes.—So long as the steady flow between two localities n and m takes place in a pipe having *no abrupt* enlargement or diminution of section, nor sharp curves, bends, or elbows, the loss of head may be ascribed solely to the surface * action (or "skin-friction") between water and pipe; but the introduction of any of the above-mentioned features occasions eddying and internal disturbance, and friction (and consequent heat): thereby causing further

† See foot-note on p. 695.

deviations from Bernoulli's Theorem; i.e., additional *losses of head*, or *heights of resistance.*

From the analogy of the form of a friction-head in a long pipe [eq. (4), § 513], we may assume that any of the above heights of resistance is proportional to the square of the velocity, and may therefore always be written in the form

$$\left\{\begin{matrix}\textit{Loss of Head due to any}\\ \textit{cause except skin-friction}\end{matrix}\right\} = \zeta \frac{v^2}{2g}, \quad \ldots\ldots (1)$$

in which v is the velocity of the water in the pipe at the section where the resistance occurs; or if, on account of an abrupt enlargement of the stream-section, there is a corresponding diminution of velocity, then v is *always to denote this diminished velocity* (i.e., in the down-stream section). This velocity v is often an unknown at the outset.

ζ, corresponding to the abstract factor $4f\frac{l}{d}$ in the height of resistance due to skin-friction [eq. (4), § 513], is an abstract number called the **Coefficient of Resistance**, to be determined experimentally; or computed theoretically, where possible. Roughly speaking, it is independent of the velocity, for a given fitting, casing, pipe-joint, elbow, bend, valve-gate at a definite opening, etc., etc.

515. Heights of Resistance (or Losses of Head) Occasioned by Short Cylindrical Tubes.—When dealing with short tubes discharging into the air, in § 507, deviations from Bernoulli's Theorem were made good by using a *coefficient of velocity* ϕ, dependent on experiment. This device answered every purpose for the simple circumstances of the case, as well as for simple orifices. But the great variety of possible designs of a compound pipe (with skin-friction, bends, sudden changes of cross-section, etc.) renders it almost impossible, in such a pipe, to provide for deviations from Bernoulli's Theorem by a single coefficient of velocity (velocity of jet, that is) for the pipe *as a whole*, since new experiments would be needed for each new design of pipe. Hence the great utility of the conception of "loss of head," one for each source of resistance.

If a long pipe issues from the plane side of a reservoir and the corners of the junction are not rounded [see Fig. 571], we shall need an expression for the loss of head at the entrance, E, as well as that

$$\left[= 4f\frac{l}{d}\cdot\frac{v^2}{2g}\right]$$



FIG. 571.

due to the skin-friction in the pipe. But, whatever the velocity, v, in the pipe proves to be, influenced as it is both by the entrance loss of head and the skin-friction head (in applying Bernoulli's Theorem), the loss of head at E, viz., $\zeta_E \frac{v^2}{2g}$, will be just the same as if efflux took place through enough of the pipe at E to constitute a "short pipe," discharging into the air, under *some* head h different from h' of Fig. 571) sufficient to produce the same velocity v. But in that case we should have

$$v = \phi\sqrt{2gh}, \quad \text{or} \quad \frac{v^2}{2g} = \phi^2 h. \quad . \quad . \quad . \quad . \quad (1)$$

(See §§ 507 and 508, ϕ being the "coefficient of velocity," and h the head, in the cases mentioned in those articles.)

We therefore apply Bernoulli's Theorem to the cases of those articles (see Figs. 560 and 564) in order to determine the loss of head due to the short pipe and obtain (with m as datum level for potential heads)

$$\frac{v_m^2}{2g} + b + 0 = 0 + b + h - \zeta_E\frac{v^2}{2g}. \quad . \quad . \quad . \quad (2)$$

Now the v of eq. (2) is equal to the v_m of the figures referred to, and ζ_E is a *coefficient of resistance* for the short pipe, and we now desire its value. Substituting for

$$\frac{v^2}{2g}\left[= \frac{v_m^2}{2g}\right]$$

its value $\phi^2 h$ from eq. (1), we have

$$\zeta_E = \frac{1}{\phi^2} - 1. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

Hence when $\alpha = 90°$ (i.e., the pipe is ⊓ to the inner reservoir surface), we derive

$$\zeta_E = \frac{1}{\phi_0^2} - 1 = \frac{1}{(0.815)^2} - 1 = 0.505; \quad . \quad . \quad [\alpha = 90°;] \quad . \quad . \quad (4)$$

and similarly, for other values of α (taking ϕ from the table, § 508), we compute the following values of ζ_E (corners not rounded) for use in the expression for "loss of head," $\zeta_E \frac{v^2}{2g}$:

For $\alpha =$	90°	80°	70°	60°	50°	40°	30°
$\zeta_E =$	.505	.565	.635	.713	.794	.870	.987

From eq. (4) we see that the loss of head at the entrance of the pipe, corners not rounded, with $\alpha = 90°$, is about one half (.505) of the height due to the velocity v in that part of the pipe (v being the same all along the pipe if cylindrical).* The value of v itself, Fig. 571, depends on *all* the features of the design from reservoir to nozzle. See § 518.

If the corners at E are properly rounded, the entrance loss of head may practically be done away with; still, if v is quite small (as it may frequently be, from large losses of head farther down-stream), the saving thus secured, while helping to increase v slightly (and thus the saving itself), is insignificant.

516. General Form of Bernoulli's Theorem, considering all Losses of Head.

In view of preceding explanations and assumptions, we may write in a general and final form Bernoulli's Theorem for a steady flow from an up-stream position n to a down-stream position m, as follows:

$$\frac{v_m^2}{2g} + \frac{p_m}{\gamma} + z_m = \frac{v_n^2}{2g} + \frac{p_n}{\gamma} + z_n - \left\{ \begin{array}{c} \textit{all losses of head} \\ \textit{occurring between} \\ n \textit{ and } m \end{array} \right\} . \quad (B_f)$$

* If the entrance of the pipe has well-rounded corners (see Fig. 541 on p. 663), the value of ζ_E is very small; viz., about 0.05.

Each loss of head (or height of resistance) will be of the form $\zeta \frac{v^2}{2g}$ (except skin-friction head in long pipes, viz., $4f \frac{l}{d} \frac{v^2}{2g}$), the v in each case being the velocity, known or unknown, in that part of the pipe where the resistance occurs (and hence is not necessarily equal to v_m or v_n).

517. The Co-efficient, f, for Friction of Water in Pipes.—(See eq. (1), § 510).—Experiments have been made by Weisbach, Bossut, Prony, Darcy, Lampe, Stearns, Hamilton Smith, Fanning, Herschel, Williams (with Hubbell and Fenkell), Marx (with Hoskins and Wing), Saph, Schoder, and others, to determine f in cylindrical pipes of various materials (wood, tin, glass, zinc, lead, brass, cast and wrought iron), of diameters from $\frac{1}{2}$ inch to 72 in. In general, the following conclusions have been reached:

1st. f decreases when the velocity increases; e.g., in one case with the

same pipe f was $= .0070$ for $v = 2'$ per sec.,
while f was $= .0056$ for $v = 20'$ per sec.

2dly. f decreases slightly as the diameter increases (other things being equal);

e.g., in one experiment f was $= .0069$ in a 3-in. pipe,
while for the same velocity f was $= .0064$ in a 6-in. pipe.

3dly. The condition of the interior surface of the pipe affects the value of f, which is larger with increased roughness of pipe.

Thus, Darcy found, with a *foul* iron pipe with $d = 10$ in. and veloc. $= 3.67$ ft. per sec.. the value .0113 for f; whereas Fanning (see p. 238 of his "Water-supply Engineering"), with a cement-lined pipe and velocity of 3.74 ft. per sec. and $d =$ 20 inches, obtained $f = .0052$.

The Hazen-Williams formula for *new cast iron* pipes, presented by its authors as embodying fairly well the results of experiment, implies the relation

$$f = (.00590) \div (d^{.166} v^{.15}), \quad . \quad . \quad . \quad . \quad . \quad (1)$$

where d and v denote diameter and mean velocity, respectively, and the *foot* and *second* are used as units; while for all fairly smooth pipes, including small brass pipes, Drs. Saph and Schoder have derived

$$f = (.00606) \div (d^{.25} v^{.14}). \quad . \quad . \quad . \quad . \quad . \quad (2)$$

For use with *new cast iron* pipes Prof. Unwin recommends the formula $f = (.00538) \div (d^{.168} v^{.05})$; . . . . . (3) and values computed from this will be found to differ but little from those given herewith on p. 709, which (by permission) is condensed from a more extensive table in Mr. Fanning's *Water Supply Engineering*.

Let a general expression for f now be written of the form

$$f = f_0 \div (d^m v^n) \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

where the factor f_0 and the exponents m and n are constant for a given character of pipe surface. According to Prof. Unwin's conclusions, from a study of the available experiments, the following average values of these quantities may be used:

Kind of Pipe.	f_0	m	n
Tin plate	.00662	.10	.18
Wrought iron	.00565	.21	.25
Asphalted iron	.00635	.127	.15
Riveted wrought iron	.00650	.390	.13
New cast iron	.00538	.168	.05
Cleaned cast iron	.00608	.168	.00
Incrusted cast iron	.01100	.16	.00

Note.—For *riveted steel pipe of 3 ft. diameter and over*, f is probably much larger than as indicated for riveted wrought-iron pipe above. See *Engineering News*, Dec. 1895, p. 415; also in Jan., etc., 1896, pp. 59, 74, 193, and 393. In some experiments by Mr. Herschel on new riveted steel pipe, from 36 to 48 in. diameter, values of f were found about double those of above table for riveted wrought iron. After four years' use some of these pipes were found to be discharging considerably less than when new, probably on account of incrustation and deposits.

EXAMPLE.—Fig. 572. In the steady pumping of crude petroleum weighing $\gamma = 55$ lbs. per cubic foot, through a six-inch pipe 30 miles long, to a station 700 ft. *higher* than the pump, it is found that the pressure in the pump cylinder at n, necessary to keep up a velocity of 4.4 ft. per sec. in the pipe, is 1000 lbs. per sq. inch. Required the coefficient f in the pipe. As all losses except the friction-head in the pipe are insignificant, the latter only will be considered. The velocity-head at n may

FIG. 572.

TABLE OF THE COEFFICIENT, *f*, FOR FRICTION OF WATER IN *CLEAN* IRON PIPES.

[Abridged from Fanning.]

Vel. in ft. per sec.	diam. = ½ in. = .0417ft.	diam. = 1 in. = .0834ft.	diam. = 2 in. = .1667ft.	diam. = 3 in. = .25 ft.	diam. = 4 in. = .333 ft.	diam. = 6 in. = .50 ft.	diam. = 8 in. = .667 ft.	diam. = 10 in. = .833 ft.	diam. = 12 in. = 1.00ft.	diam. = 16 in. = 1.333ft.	diam. = 20 in. = 1.667ft.	diam. = 30 in. = 2.50 ft.	diam. = 40 in. = 3.333ft.	diam. = 60 in. = 5. ft.
0.1	.0150	.0119	.00870	.00800	.00763	.00730	.00704	.00684	.00669	.00623				
0.3	.0137	.0113	850	784	750	720	693	673	657	614	.00578			
0.6	.0124	.0104	822	767	732	702	677	659	642	603	567	.00504	.00434	.00357
1.0	.0110	.00950	790	743	712	684	659	643	624	588	555	492	428	353
1.5	.00959	.00868	.00757	.00720	.00693	.00662	.00640	.00625	.00607	.00572	.00542	.00482	.00421	.00349
2.0	.00862	810	731	700	678	648	624	609	593	559	529	470	416	346
2.5	795	768	710	683	662	634	611	596	581	548	518	460	410	342
3.0	.00753	.00734	.00692	.00670	.00650	.00623	.00600	.00584	.00570	.00538	.00509	.00452	.00407	00339
4.0	722	702	671	651	631	607	586	568	553	524	498	441	400	333
6.0	689	670	640	622	605	582	562	548	534	507	482	430	391	324
8.0	663	646	618	600	587	562	544	532	520	491	470	422	384	320
12.0	630	614	590	582	560	540	522	512	500	478	457	412	377	.00313
16.0	.00618	.00600	.00581	.00570	.00552	.00530	.00513	.00502	.00491	.00470	.00450	.00406	.00370	
20.0	615	598	579	566	549	525	508	498	485					

N.B. See notes at foot of pp. 711 and 712.

be put = 0; the jet at m being of the same size as the pipe, the velocity in the pipe is $= v_m$, and therefore $v_m = 4.4$ ft. per sec. Notice that m, the *down-stream* section, is at a *higher* level than n.

From Bernoulli's Theorem, § 516, we have, with n as a datum level,

$$\frac{v_m^2}{2g} + b + h = 0 + \frac{p_n}{\gamma} + 0 - 4f\frac{l}{d}\frac{v^2}{2g}. \quad . \quad . \quad (1)$$

Using the ft., lb., and sec., we have

$$h = 700 \text{ ft.}, \quad v_m^2 \div 2g = 0.30 \text{ ft.},$$

while

$$b = \frac{14.7 \times 144}{55} = 38.47 \text{ ft., and } \frac{p_n}{\gamma} = \frac{1000 \times 144}{55} = 2618 \text{ ft.}$$

Hence, in eq. (1),

$$0.30 + 38.5 + 700 = 2618 - 4f \cdot \frac{30 \times 5280}{\frac{1}{2}} \cdot \frac{(4.4)^2}{64.4}.$$

Solving for f, we have $f = .00485$ (whereas for water, with $v = 4.4$ ft. per sec. and $d = \frac{1}{2}$ ft., the table, p. 709, gives $f = .00601$.

If the γ of the petroleum had been 50 lbs. per cubic foot, instead of 55, we should have obtained $\frac{p_n}{\gamma} = 2880$ feet and $f = .0056$.

518. Flow through a Long Straight Cylindrical Pipe, including both friction-head and entrance loss of head (corners not rounded); reservoir large. Fig. 573. The jet issues directly from the end of the pipe, in parallel filaments, into the air, and therefore has same section as pipe; hence, also, v_m of the jet $= v$ in the pipe (which is assumed to be running full), and is



FIG. 573.

therefore the velocity to be used in the loss of head $\zeta_E \frac{v^2}{2g}$ at the entrance E (§ 515).

Taking m and n as in figure and applying Bernoulli's Theorem (§ 474), with m as datum level for the potential heads z_m and z_n, we have

$$\frac{v_m^2}{2g} + b + 0 = 0 + b + h - \zeta_E \frac{v^2}{2g} - 4f \frac{l}{d} \frac{v^2}{2g}. \quad . \quad (1)$$

Three different problems may now be solved:

First, required the head h to keep up a flow of given volume $= Q$ per unit of time in a pipe of given length l and diameter $= d$.

From the equation of continuity we have

$$Q = F_m v_m = \tfrac{1}{4}\pi d^2 v_m;$$

$$\therefore \textit{ veloc. of jet, which } = \textit{veloc. in pipe, } = v_m = \frac{4Q}{\pi d^2}. \quad . \quad . \quad . \quad (2)$$

Having found $v_m = v$, from (2), we obtain from (1) the required h, thus:

$$h = \frac{v^2}{2g}\left[1 + \zeta_E + 4f \frac{l}{d}\right]. \quad . \quad . \quad . \quad . \quad (3)$$

Now $\zeta_E = 0.505$ if $\alpha = 90°$ (see § 515), while f may be taken from the table, § 517, for the given diameter and computed velocity [$v_m = v$, found in (2)], if the pipe is *clean;* if not clean, see end of § 517, for *slightly tuberculated* and for *foul* pipes.*

Secondly. Given the head h, and the length l and diameter d of pipe, required the velocity in the pipe, viz., v, $= v_m$, that of jet; also the volume delivered per unit of time, Q. Solving eq. (1) for v_m, we have

$$v_m = \sqrt{\frac{1}{1 + \zeta_E + 4f \frac{l}{d}}}\sqrt{2gh}; \quad . \quad . \quad . \quad (4)$$

* "*Hydraulic Tables,*" for friction-head of water in pipes, by Prof. G. S. Williams and Mr. Allen Hazen (New York, 1905, John Wiley & Sons), cover the cases of pipes in various states of tuberculation, etc.

whence Q becomes known, since

$$Q = \tfrac{1}{4}\pi d^2 v_m. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

[NOTE.—The first radical in (4) might for brevity be called a *coefficient of velocity*, ϕ, for this case. Since the jet has the same diameter as the pipe, this radical may also be called a *coefficient of efflux*.]

Since in (4) f depends on the unknown v as well as on the known d, we must first put $f = .006$ for a first approximation for v_m; then take a corresponding value for f and substitute again; and so on.

Thirdly, knowing the length of pipe and the head h, we wish to find the proper diameter d for the pipe to deliver a given volume Q of water per unit of time. Now

$$v_1 = v_m = \frac{Q}{\tfrac{1}{4}\pi d^2}, \quad . \quad . \quad . \quad . \quad . \quad . \quad (6)$$

which substituted in (1) gives

$$2gh = \left(\frac{4Q}{\pi}\right)^2 \frac{1}{d^4}\left[1 + \zeta_E + 4f\frac{l}{d}\right] = \left(\frac{4Q}{\pi}\right)^2 \left[\frac{1+\zeta_E}{d^4} + \frac{4fl}{d^5}\right];$$

that is,

$$2ghd^5 = \left(\frac{4Q}{\pi}\right)^2 [(1+\zeta_E)d + 4fl];$$

$$\therefore\ d = \sqrt[5]{\frac{(1+\zeta_E)d + 4fl}{2gh} \cdot \left(\frac{4Q}{\pi}\right)^2}. \quad . \quad . \quad . \quad (7)$$

As the radical contains d, we first assume a value for d, with $f = .006$, and substitute in (7). With the approximate value of d thus obtained, we substitute again with a new value for f based on an approximate v from eq. (6) (with $d =$ its first approximation), and thus a still closer value for d is derived; and so on. (Trautwine's Pocket-book contains a table of fifth roots and powers.) If l is quite large, we may put $d = 0$ for a first approximation. In connection with these examples, see last figure.*

* In Chap. VIII (p. 188) of the Author's "Hydraulic Motors" will be found additional matter on flow in pipes. In that work are also given friction-head diagrams, the use of which saves much computation in solving problems like those of pp. 713, 714, 731–734 of the present work.

EXAMPLE 1.—What head h is necessary to deliver 120 cub. ft. of water per minute through a clean straight iron pipe 140 ft. long and 6 in. in diameter?

From eq. (2), with ft., lb., and sec., we have

$$v = v_m = [4 \times \tfrac{120}{60}] \div \pi(\tfrac{1}{2})^2 = 10.18 \text{ ft. per sec.}$$

Now for $v = 10$ ft. per sec. and $d = \frac{1}{2}$ ft., we find (in table, § 517) $f = .00549$; and hence, from eq. (3),

$$h = \frac{(10.18)^2}{2 \times 32.2}\left[1 + .505 + \frac{4 \times .00549 \times 140}{\frac{1}{2}}\right] = 12.23 \text{ ft.},$$

of which total head, as we may call it, 1.60 ft. is used in producing the velocity 10.18 ft. per sec. (i.e., $v_m^2 \div 2g = 1.60$ ft.), while 0.808 ft. $\left(= \zeta_E \frac{v_m^2}{2g}\right)$ is lost at the entrance E (with $\alpha = 90°$), and 9.82 ft. (friction-head) is lost in skin-friction.

EXAMPLE 2.—[Data from Weisbach.] Required the delivery, Q, through a straight clean iron pipe 48 ft. long and 2 in. in diameter, with 5 ft. head ($= h$). $v_m = v_m$, being unknown, we first take $f = .006$ and obtain [eq. (4)]

$$v_m = \sqrt{\frac{1}{1 + .505 + \frac{4 \times .006 \times 48}{\frac{1}{6}}}}\sqrt{2 \times 32.2 \times 5}$$

$$= 6.18 \text{ ft. per sec.}$$

From the table, § 517, for $v = 6.2$ ft. per sec. and $d = 2$ in., $f = .00638$, whence

$$v_m = \sqrt{\frac{1}{1 + .505 + \frac{4 \times .00638 \times 48}{\frac{1}{6}}}}\sqrt{2 \times 32.2 \times 5}$$

$$= 6.04 \text{ ft. per sec.},$$

which is sufficiently close. Then, for the volume per second,

$$Q = \frac{\pi}{4} d^2 v_m = \tfrac{1}{4}\pi(\tfrac{1}{6})^2 6.04 = 0.1307 \text{ cub. ft. per sec.}$$

[Weisbach's results in this example are

$$v_m = 6.52 \text{ ft. per sec.}$$

and $$Q = 0.1420 \text{ cub. ft. per sec.},$$

but his values for f are slightly different.]

EXAMPLE 3.—[Data from Weisbach.] What must be the diameter of a straight clean iron pipe 100 ft. in length, which is to deliver $Q = \frac{1}{2}$ of a cubic foot of water per second under 5 ft. head ($= h$)?

With $f = .006$ (approximately), we have from eq. (7), putting $d = 0$ under the radical for a first trial (ft., lb., sec.),

$$d = \sqrt[5]{\frac{4 \times .006 \times 100}{2 \times 32.2 \times 5} \cdot \left(\frac{\frac{4}{2}}{\pi}\right)^2} = \text{about } 0.30 \text{ ft.};$$

whence $$v = \frac{4Q}{\pi d^2} = 7 \text{ ft. per sec.}$$

For $d = 3.6$ in. and $v = 7$ ft. per sec., we find $f = .00601$; whence, again,

$$d = \sqrt[5]{\frac{1.505 \times .30 + 4 \times .00601 \times 100}{2 \times 32.2 \times 5} \cdot \left(\frac{4 \times \frac{1}{2}}{\pi}\right)^2} = 0.324 \text{ ft.};$$

and the corresponding $v = 6.06$ ft.

For this d and v we find $f = .00609$, whence, finally,

$$d = \sqrt[5]{\frac{1.505 \times .30 + 4 \times .00609 \times 100}{2 \times 32.2 \times 5} \left(\frac{2}{\pi}\right)^2} = 0.326 \text{ ft.}$$

[Weisbach's result is $d = .318$ ft.]

519. Chézy's Formula.—If, in the problem of the preceding paragraph, the pipe is *so long*, and therefore $l : d$ *so great*, that $4fl \div d$ in eq. (3) is very large compared with $1 + \zeta_E$, we may neglect the latter term without appreciable error; whence eq. (3) reduces to

$$h = 4f \frac{l}{d} \cdot \frac{v_m^2}{2g} \quad . \quad . \quad (\textit{pipe very long;} \text{ Fig. 573}), \quad . \quad . \quad (8)$$

which is known as *Chézy's Formula.* For example, if $l = 1000$ ft. and $d = 2$ in. $= \frac{1}{6}$ ft., and f approx. $= .006$, we have $4f\frac{l}{d} = 144$, while $1 + \zeta_E$ for square corners $= 1.505$ only.

If in (8) we substitute

$$v_m = \frac{Q}{F_m} = Q \div \tfrac{1}{4}\pi d^2,$$

(8) reduces to

$$h = \frac{64}{\pi^2} \cdot f \frac{l}{d^5} \cdot \frac{Q^2}{2g} \quad . \quad . \quad . \quad (\textit{very long pipe}); \quad . \quad . \quad . \quad . \quad (9)$$

so that for a very long pipe, considering f as approximately constant, we may say that to deliver a volume $= Q$ per unit of time through a pipe of *given length* $= l$, the necessary head, h, is *inversely proportional to the fifth power of the diameter.*

And again, solving (9) for Q, we find that the volume conveyed per unit of time is directly proportional to the *fifth power of the square root of the diameter;* directly proportional to the *square root of the head;* and *inversely proportional to the square root of the length.* (Not true for short pipe; see above example.)

520. The Hydraulic Grade-line.—The pipe of Fig. 573 is repeated in Fig. 573*a*. It has *no nozzle* and hence the velocity vm of the jet at m is equal to that, v, in the pipe. If we conceive of the insertion of a great number of open piezometers, such as PS, along this pipe,



FIG. 573*a*.



FIG. 573*b*.

the summits of the respective stationary water columns maintained in them will lie in the straight line Bm. For a *very long pipe* the point B is practically in the plane of reservoir surface and vertically over the entrance E. This line Bm is called the "**Hydraulic Grade-line**" or "**Hydraulic Gradient.**" From eq. (3), p. 711, we note that the total head h is made up of three parts, viz.: $v_m^2 \div 2g$, or velocity head in jet; $\zeta_E(v^2 \div 2g)$, or loss of head at entrance; and the friction-head. h_F, in pipe, $= (4fl \div d)(v^2 \div 2g)$, which for a very long pipe is practically equal to h itself (in this case of no nozzle). Evidently the vertical drop

$AB=(1+\zeta_E)(v^2\div 2g)$. For instance, in example 1 of p. 713, we note that the vertical distance from A to B is 1.41 ft., while $h_F=9.82$ ft.

Let us now consider that a conical nozzle is attached to the end of a long horizontal pipe whose length is 1200 ft. and diameter 6 in., with a head of 78 ft., the diameter of the tip of the nozzle (so formed as not to produce contraction) being 2 in. See Fig. 573*b*. After a steady flow has set in, the velocity of the jet is v_m ft./sec. and that of the water in the pipe is v, only 1/9 of v_m; since $Q=\frac{\pi}{4}\left(\frac{1}{6}\right)^2 v_m=\frac{\pi}{4}\left(\frac{1}{2}\right)^2 v$. The loss of head in the nozzle may be written $=1/20$ of $v_m^2\div 2g$. Application of Bernoulli's Theorem between points n and m gives rise to

$$b+h+0=b+\frac{v_m^2}{2g}+\frac{1}{20}\cdot\frac{v_m^2}{2g}+4f\frac{l}{d}\cdot\frac{v^2}{2g}+\zeta_E\frac{v^2}{2g}. \quad . \quad . \quad . \quad (10)$$

With f written $=.006$ at first, and corrected later, we finally derive $v=6$ ft./sec. and $v_m=54$ ft./sec. Hence $Q=1.17$ cub. ft./sec. Fig. 573*b* shows the hydraulic grade-line, BD, for the 6-in. pipe in this problem. The vertical drop $AB=1.505(v^2\div 2g)=0.85$ ft., while $h_F=30$ ft. The height of the piezometer column at E', at the base of the conical nozzle, is 47.1 ft. The velocity of the jet being 54 ft./sec. with $Q=1.17$ cub. ft./sec., the "*kinetic power*" of the jet (i.e., kinetic energy of the mass of water passing *per second*) is $\frac{1}{2}(Q\gamma\div g)v_m^2$, $=3308$ ft.-lbs. per second, $=6.01$ H.P.; so that a "jet motor," or impulse wheel, utilizing 80 per cent of this power would develop 4.8 H.P. (See *Hydraulic Motors* by the present writer.) The *slope* of the hydraulic grade-line in Fig. 573*b* is $h_F\div l$, i.e., $30\div 1200$ or $1/40$; that is, it drops one foot in each 40 ft. of length of pipe.

If a steady flow is proceeding in a pipe of *uniform section* it may easily be shown, by Bernoulli's Theorem, that the vertical distance between the summits of the open piezometers inserted at any two points is equal to the *loss of head* occurring between those two points. Even if the pipe is not of uniform section between the two points the foregoing is still true if the *sectional areas at the two points themselves are equal.*

If any part of the pipe, flowing full, projects *above* the hydraulic grade-line, the internal pressure in that part is less than atmospheric, and air previously dissolved in the water may collect after a time, and air may also enter through imperfect joints, thus causing the pipe to be only partly full at such points and seriously altering the conditions of flow. For example, the pipe shown in Fig. 573*c* discharges into the air at m and the portion *acb* rises above the hydraulic grade-line *Babm*. Air may collect in the summit c to such a degree that finally only the part *Eac* of the pipe flows full, while in the portion *cbm* water flows through only the lower part of each cross-section, with air above. In such a case the hydraulic grade-line for *Ec* would rise to position *Bc*.



FIG. 573*c*.

521. Bernoulli's Theorem as an Expression of the Conservation of Energy for the Liquid Particles.—In any kind of flow *without friction, steady or not*, in *rigid immovable vessels*, the aggregate potential and kinetic energy of the whole mass of liquid concerned is necessarily a constant quantity (see §§ 148 and 149), but *individual particles* (as the particles in the sinking free surface of water in a vessel which is rapidly being emptied) may be continually losing potential energy, i.e., reaching lower and lower levels, without any compensating increase of kinetic energy or of any other kind; but in a *steady flow without friction in rigid motionless vessels*, we may state that the stock of energy of a given particle, or small collection of particles, is *constant* during the flow, provided we recognize a third kind of energy which may be called **Pressure-energy**, or capacity for doing work by virtue of internal fluid pressure; as may be thus explained:

In Fig. 574 let water, with a very slow motion and under a pressure p (due to the reservoir-head + atmosphere-head behind it), be admitted behind a piston the space beyond which is *vacuous*. Let s = length of stroke, and F = the area of piston. At the end of the stroke, by motion of proper valves, communication with the reservoir is cut off on the left of the piston and opened on the right, while the water in the cylinder now on the left of the piston is put in communication with the vacuous exhaust-chamber. As a consequence the internal pressure of this water falls to zero (height of cylinder small), and on the return stroke is simply conveyed out of the cylinder, neither helping nor hindering the motion. That is, in doing the work of one stroke, viz.,



FIG. 574.

$$W = \text{force} \times \text{distance} = Fp \times s = Fps,$$

a volume of water $V = Fs$, weighing $Fs\gamma$ (lbs. or other unit), has been used, and, in passing through the motor, has experienced no appreciable change in velocity (motion slow), and

therefore no change in kinetic energy, nor any change of level, and hence no change in potential energy, *but it has given up all its pressure.* (See § 409 for γ.)

Now W, the work obtained by the consumption of a weight $= G = V\gamma$ of water, may be written

$$W = Fps = Fsp = Vp = V\gamma\frac{p}{\gamma} = G\frac{p}{\gamma}. \quad . \quad . \quad (1)$$

Hence a weight of water $= G$ *is capable of doing the work* $G \times \frac{p}{\gamma} = G \times$ *head due to pressure* p, i.e., $= G \times$ *pressure-head, in giving up all its pressure* p; or otherwise, while still having a pressure p, a weight G of water possesses an *amount of energy*, which we may call *pressure-energy*, of an amount $= G \cdot \frac{p}{\gamma}$, where $\gamma =$ the heaviness (§ 7) of water, and $\frac{p}{\gamma} =$ a height, or head, measuring the pressure p; i.e., it equals the pressure-head.

We may now state Bernoulli's Theorem without friction in a new form, as follows: Multiplying each term of eq. (7), § 451, by $Q\gamma$, the weight of water flowing per second (or other time-unit) in the steady flow, we have

$$Q\gamma\frac{v_m^2}{2g} + Q\gamma\frac{p_m}{\gamma} + Q\gamma z_m = Q\gamma\frac{v_n^2}{2g} + Q\gamma\frac{p_n}{\gamma} + Q\gamma z_n. \quad (2)$$

But $Q\gamma\frac{v_m^2}{2g} = \frac{1}{2}\frac{Q\gamma}{g}v_m^2 = \frac{1}{2} \times$ *mass* flowing per time-unit $\times$ square of the velocity $=$ the *kinetic energy* inherent in the volume Q of water on passing the section m, due to the velocity at m. Also, $Q\gamma\frac{p_m}{\gamma} =$ the *pressure-energy* * of the volume Q at m, due to the pressure at m; while $Q\gamma z_m =$ the *potential energy* of the volume Q at m due to its height z_m above the arbitrary datum plane. Corresponding statements may be made for the terms on the right-hand side of (2) referring to the other section, n, of the pipe. Hence (2) may be thus read: *The aggregate amount of energy* (of the three kinds mentioned) *resident in the particles of liquid when passing section* m *is*

* This idea of "pressure energy" in connection with water is artificial, but is of great convenience in dealing with questions of water power; it is of use only when the *flow is steady.* See p. 8 of the Author's "Hydraulic Motors," and p. 66 of Blaine's "Hydraulic Machinery."

equal to that when passing any other section, as n; in steady flow without friction in rigid motionless vessels; that is, the store of energy is constant.

522. Bernoulli's Theorem with Friction, from the Standpoint of Energy.—Multiply each term in the equation of § 516 by $Q\gamma$, as before, and denote a loss of head or height of resistance due to any cause by h_r, and we have

$$Q\gamma\frac{v_m^2}{2g}+Q\gamma\frac{p_m}{\gamma}+Q\gamma z_m$$

$$=Q\gamma\frac{v_n^2}{2g}+Q\gamma\frac{p_n}{\gamma}+Q\gamma z_n-\Sigma_n^m Q\gamma h_r. \quad . \quad . \quad (3)$$

Each term $Q\gamma h_r$ (e.g., $Q\gamma\, 4f\,\frac{l}{d}\frac{v^2}{2g}$ due to skin-friction in a long pipe, and $Q\gamma\,\zeta_E\frac{v^2}{2g}$ due to loss of head at the reservoir entrance of a pipe) represents a *loss of energy*, occurring between any position n and any other position m down-stream from n, but is really still in existence in the form of heat generated by the friction of the liquid particles against each other or the sides of the pipes.

As illustrative of several points in this connection, consider two short lengths of pipe in Fig. 575, A and B, one offering a gradual, the other a sudden, enlargement of section, but *otherwise identical in dimensions.* We suppose them to occupy places in separate lines of pipe in each of which a steady flow with full cross-sections is proceeding, and so regulated that the velocity and internal pressure at n, in A, are equal respectively to those at n in B. Hence, if *vacuum* piezometers be inserted at n, the



FIG. 575.

smaller section, the water columns maintained in them by the internal pressure will be of the same height, $\frac{p_n}{\gamma}$, for both A and B. Since at m, the larger section, the sectional area is the same for both A and B, and since F_n in $A = F_n$ in B, so that $Q_A = Q_B$, hence v_m in $A = v_m$ in B and is less than v_n.

Now in B a loss of head occurs (and hence a loss of energy) between n and m, but *none* in A (except slight friction-head); hence in A we should find as much energy present at m as at n, only differently distributed among the three kinds, while at m in B the aggregate energy is less than that at n in B.

As regards kinetic energy, there has been a loss between n and m in both A and B (and equal losses), for v_m is less than v_n. As to potential energy, there is no change between n and m either in A or B, since n and m are on a level. Hence if the loss of kinetic energy in B is not compensated for by an equal gain of pressure-energy (as it *is* in A), the pressure-head $\left(\frac{p_m}{\gamma}\right)_B$ at m in B should be less than that $\left(\frac{p_m}{\gamma}\right)_A$ at m in A. Experiment shows this to be true, the loss of head being due to the internal friction in the eddy occasioned by the sudden enlargement; the water column at m in B is found to be of a less height than that at m in A, whereas at n they are equal. (See p. 467 of article "Hydromechanics" in the *Ency. Britannica* for Mr. Froude's experiments.)

In brief, in A the loss of kinetic energy has been made up in pressure-energy, with no change of potential energy, but in B there is an actual absolute loss of energy $= Q\gamma h_r$, or $= Q\gamma\zeta\frac{v_m^2}{2g}$, suffered by the weight $Q\gamma$ of liquid. The value of ζ in this case and others will be considered in subsequent paragraphs.

Similarly, losses of head, and therefore losses of energy, occur at elbows, sharp bends, and obstructions, causing eddies and internal friction, the amount of each loss for a given weight, G, of water being $= Gh_r = G\zeta\frac{v^2}{2g}$; $h_r = \zeta\frac{v^2}{2g}$ being the loss of head occasioned by the obstruction (p. 704). It is

therefore very important in transmitting water through pipes for purposes of *power* to use all possible means of preventing disturbance and eddying among the liquid particles. E.g., sharp corners, turns, elbows, abrupt changes of section, should be avoided in the design of the supply-pipe. The amount of the losses of head, or heights of resistance, due to these various causes will now be considered (except skin-friction, already treated). Each such loss of head will be written in the form $\zeta \frac{v^2}{2g}$, and we are principally concerned with the value of the abstract number ζ, or *coefficient of resistance*, in each case. The velocity v is the velocity, known or unknown, *where the resistance occurs;* or if the section of pipe changes at this place, then v = velocity on the *down-stream section*. The late Professor Weisbach, of the mining-school of Freiberg, Saxony, was one of the most noted experimenters in this respect, and will be frequently quoted.

523. Loss of Head Due to Sudden (i.e., Square-edged) Enlargement. Borda's Formula.—Fig. 576. An eddy is formed in the angle with consequent loss of energy. Since each particle of water of weight $= G_1$, arriving with the velocity v_1 in the small pipe, may be considered to have an *impact* against the base of the infinitely great and more slowly moving column of water in the large pipe, and, after the impact, moves on with the same velocity, v_2, as that column, just as occurs in *inelastic direct central impact* (§ 60), we may find the energy lost by this particle on account of the impact by eq. (1) of § 138, in which, putting $M_1 = G_1 \div g$, and $M_2 = G_2 \div g$ = mass of infinitely great body of water in the large pipe, so that $M_2 = \infty$, we have

FIG. 576.

$$\text{Energy lost by particle} = G_1 \frac{(v_1 - v_2)^2}{2g}, \quad . \quad . \quad (1)$$

and the corresponding

$$\textit{Loss of head} = \frac{(v_1 - v_2)^2}{2g},$$

which, since $F_1 v_1 = F_2 v_2$, may be written

$$\textit{Loss of head in sudden enlargement} = \left[\frac{F_2}{F_1} - 1\right]^2 \frac{v_2^2}{2g}. \quad . \quad (2)$$

That is, the coefficient ζ for a sudden enlargement is

$$\zeta = \left(\frac{F_2}{F_1} - 1\right)^2. \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

F_1 and F_2 are the respective sectional areas of the pipes. Eq. (2) is *Borda's Formula.*

NOTE.—Practically, the flow cannot always be maintained with full sections. In any case, if we *assume* the pipes to be running full (once started so), and on that assumption compute the internal pressure at F_1, and find it to be zero or negative, the assumption is incorrect. That is, unless there is some pressure at F_1 the water will not swell out laterally to fill the large pipe.

EXAMPLE.—Fig. 577. In the short tube AB containing a sudden enlargement, we have given $F_2 = F_m = 6$ sq. inches, $F_1 = 4$ sq. inches, and $h = 9$ feet. Required the velocity of the jet at m (in the air, so that $p_m \div \gamma = b = 34$ ft.), if the only loss of head considered is that due to the sudden enlargement (skin-friction neglected, as the tube is short; the reservoir entrance has *rounded corners*). Applying Bernoulli's Theorem to m as down-stream section, and n in reservoir surface as up-stream position (datum level at m), we have



FIG. 577.

$$\frac{v_m^2}{2g} + b + 0 = 0 + b + h - \zeta\frac{v_2^2}{2g}. \quad . \quad . \quad . \quad (4)$$

But, here, $v_2 = v_m$;

$$\therefore (1 + \zeta)\frac{v_m^2}{2g} = h. \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

From eq. (3) we have

$$\zeta = (\tfrac{4}{6} - 1)^2 = 0.25,$$

and finally (ft., lb., sec.)

$$v_m = \sqrt{\frac{1}{1.25}}\sqrt{2 \times 32.2 \times 9} = 0.895\sqrt{2 \times 32.2 \times 9}$$

$$= 21.55 \text{ ft. per sec.}$$

(The factor 0.895 might be called a *coefficient of velocity* for this case.) Hence the volume of flow per second is

$$Q = F_m v_m = \tfrac{6}{144} \times 21.55 = 0.898 \text{ cub. ft. per sec.}$$

We have so far assumed that the water fills both parts of the tube, i.e., that the pressure p_1, at F_1, is greater than zero (see foregoing note). To verify this assumption, we compute p_1 by applying Bernoulli's Theorem to the centre of F_1 as down-stream position and datum plane, and n as up-stream position, with no loss of head between, and obtain

$$\frac{v_1^2}{2g} + \frac{p_1}{\gamma} + 0 = 0 + b + h - 0. \quad \ldots \quad (6)$$

But since $F_1 v_1 = F_2 v_2$, we have

$$v_1^2 = (\tfrac{6}{4})^2 v_2^2 = (\tfrac{6}{4})^2 v_m^2,$$

and hence the pressure-head at F_1 (substituting from equations above) is

$$\frac{p_1}{\gamma} = b + h - (\tfrac{6}{4})^2 \cdot \frac{h}{1+\zeta} = 34 + 9 - \frac{9}{4} \cdot \frac{9}{1+.25} = 27 \text{ feet,}$$

and $\therefore p_1 = \frac{27}{34}$ of $14.7 = 11.6$ lbs. per sq. inch, which is greater than zero; hence efflux with the tube full in both parts can be maintained under 9 ft. head.

If, with F_1 and F_2 as before (and $\therefore \zeta$), we put $p_1 = 0$, and solve for h, we obtain $h = 42.5$ ft. as the maximum head under which efflux with the large portion full can be secured.

524. Short Pipe, Square-edged Internally.—This case, already

treated in §§ 507 and 515 (see Fig. 578; a repetition of 560), presents a loss of head due to the sudden enlargement from the contracted section at m' (whose sectional area may be put $= CF$, C being an unknown coefficient, or ratio, of contraction) to the full section F of the pipe. From § 515 we know that the loss of head due to the short pipe is $h_r = \zeta_E \frac{v_m^2}{2g}$ (for $\alpha = 90°$), in which $\zeta_E = 0.505$; while from Borda's Formula, § 523, we have also $\zeta_E = \left[\frac{F}{CF} - 1\right]^2$. Equating these, we find the coefficient of internal contraction at m' to be



Fig. 578.

$$C = \frac{1}{1 + \sqrt{\zeta_E}} = \frac{1}{1 + \sqrt{.505}} = 0.584,$$

or about 0.60 (compare with $C = .64$ for thin-plate contraction, § 495). It is probably somewhat larger than this (.584), since a small part of the loss of head, h_r, is due to friction at the corners and against the sides of the pipe.

By a method similar to that pursued in the example of § 523, we may show that unless h is less than 40 feet, about, the tube cannot be kept full, the discharge being as in Fig. 551. If the efflux takes place into a "partial vacuum," this limiting value of h is still smaller. Weisbach's experiments confirm these statements (but those in the C. U. Hyd. Lab. seem to indicate that the limiting value for h in the first case is about 50 ft.).

525. Diaphragm in a Cylindrical Pipe.—Fig. 579. The diaphragm being of "thin plate," let the circular opening in it (concentric with the pipe) have an area $= F$, while the sectional area of pipe $= F_2$. Beyond F, the stream contracts to a section of area $= CF = F_1$, *in enlarging*



Fig. 579.



FIG. 580*c*.—Chart, showing rates of flow during twenty-four hours. The ordinates are gallons per hour.



FIG. 580*b*.—Chart Recorder; an attachment to Register. It records the rate of flow upon a sheet of paper. (See above, in Fig. 580*c*.)



FIG. 580*a*.—The complete meter; consisting of a Venturi Tube and a Register. They are connected by two pressure-pipes, and the Register is driven by weights. The narrowest part of Tube is the "Throat."



FIG. 580*d*.—Manometer; which may replace the Register.

THE VENTURI METER.

[*To face page* 724.



FIG. 580e.—A 60-inch Venturi Meter Tube; made by *Builders Iron Foundry*, Providence, R. I. The diameter at narrowest part ("throat") is $22\frac{1}{2}$ inches. The flow of the water would be from left to right. [*To face page* 725.

from which to fill the section F_2, of pipe, a loss of head occurs which by Borda's Formula, § 523, is

$$h_r = \zeta \frac{v_2^2}{2g} = \left(\frac{F_2}{F_1} - 1\right)^2 \frac{v_2^2}{2g},$$

where v_2 is the velocity in the pipe (*supposed full*). Of course F_1 (or CF) depends on F; but since experiments are necessary in any event, it is just as well to give the values of ζ itself, as determined by Weisbach's experiments, viz.:

For $\frac{F}{F_2} = .10$	.20	.30	.40	.50	.60	.70	.80	.90	1.00
$\zeta = 226.$	48.	17.5	7.8	3.7	1.8	.8	.3	.06	0.00

By internal lateral filling, Fig. 580, the change of section may be made gradual and eddying prevented; and then but little loss of head (and therefore little loss of energy) occurs, besides the slight amount due to skin-friction along this small surface. On p. 467 of the article *Hydromechanics* in the *Encyclopædia Britannica* may be found an account of experiments by Mr. Froude, illustrating this fact.



FIG. 580.

526. "The Venturi Water-meter."—The invention* bearing this name was made by Mr. Clemens Herschel (see *Trans. Am. Soc. Civ. Engineers*, for November 1887), and may be described as a portion of pipe in which a gradual narrowing of section is immediately succeeded by a more gradual enlargement, as in Fig. 580; but the dimensions are more extreme. During the flow the piezometer-heights are observed at the three positions r, n, and m (see below), and the rate of discharge may be computed as follows: Referring to Fig. 580, let us denote by r the (up-stream) position where the narrowing of the pipe begins, and by m that where the enlargement ends, while n refers to the narrowest section. $F_m = F_r$.

Applying Bernoulli's Theorem to sections r and n, assuming

* See illustration on opp. page of a 60-inch Venturi Meter tube.

no loss of head between, we have, as the principle of the apparatus,

$$\frac{p_r}{\gamma}+\frac{v_r^2}{2g}=\frac{p_n}{\gamma}+\frac{v_n^2}{2g}; \quad \ldots\ldots \quad (1)$$

whence, since $F_r v_r = F_n v_n$,

$$v_n=\sqrt{\frac{1}{1-\left(\frac{F_n}{F_r}\right)^2}}\cdot\sqrt{2g\left(\frac{p_r}{\gamma}-\frac{p_n}{\gamma}\right)}=\phi\sqrt{2g\left(\frac{p_r}{\gamma}-\frac{p_n}{\gamma}\right)}, \quad (2)$$

in which ϕ represents the first radical factor. ϕ should differ but little from unity with $\frac{F_n}{F_r}$ small (and such was found to be the case by experiment). Its theoretical value is constant and greater than unity. In the actual use of the instrument the $\frac{p_r}{\gamma}$ and $\frac{p_n}{\gamma}$ are inferred from the observed piezometer-heights y_r and y_n (since $\frac{p_r}{\gamma}=y_r+b$, and $\frac{p_n}{\gamma}=y_n+b$, b being $=34$ ft.), and then the quantity flowing per time-unit computed, from $Q=F_n v_n$, v_n having been obtained from eq. (2). This process gives a value of Q about four per cent in excess of the truth, according to the second set of experiments mentioned below, if $v_n=35$ ft. per sec.; but only one per cent excess with $v_n=5$ or 6 ft. per sec.

Experiments were made by Mr. Herschel on two meters of this kind, in each of which F_n was only one ninth of F_r, a ratio so extreme that the loss of head due to passage through the instrument is considerable. E.g., with the smaller apparatus, in which the diameter at n was 4 in., the loss of head between r and m was 10 or 11 ft., when the velocity through n was 50 ft. per sec., those at other velocities being roughly proportional to the square of the velocity. In the larger instrument d_n was 3 ft., and the loss of head between r and m was much more nearly proportional to the square of the velocity than in the smaller. (E.g., with $v_n=34.56$ ft. per sec. the loss of head was 2.07 ft., while with $v_n=16.96$ ft. per sec. it

was 0.49 ft.) The angle of divergence was much smaller in these meters than that in Fig. 580.

527. Sudden Diminution of Cross-section, Square Edges.—Fig. 581. Here, again, the resistance is due to the sudden enlargement from the contracted section to the full section F_2 of the small pipe, so that in the loss of head, by Borda's formula,



FIG. 581.

$$h_r = \zeta \frac{v_2^2}{2g} = \left[\frac{F_2}{F_1} - 1\right]^2 \frac{v_2^2}{2g}, \quad . \quad . \quad . \quad . \quad (1)$$

the coefficient

$$\zeta = \left(\frac{F_2}{F_1} - 1\right)^2 = \left(\frac{F_2}{CF_2} - 1\right)^2 = \left(\frac{1}{C} - 1\right)^2 . \quad . \quad . \quad (2)$$

depends on the coefficient of contraction C; but this latter is influenced by the ratio of F_2 to F_0, the sectional area of the larger pipe, C being about .60 when F_0 is very large (i.e., when the small pipe issues directly from a large reservoir so that $F_2 : F_0$ practically $= 0$). For other values of this ratio Weisbach gives the following table for C, from his own experiments:

For $F_2 : F_0 =$	.10	.20	.30	.40	.50	.60	.70	.80	.90	1.00
$C =$	.624	.632	.643	.659	.681	.712	.755	.813	.892	1.00

C being found, we compute ζ from eq. (2) for use in eq. (1).

528. Elbows.—The internal disturbance caused by an elbow, Fig. 582 (pipe full, both sides of elbow), occasions a loss of head



FIG. 582.

$$h_r = \zeta \frac{v^2}{2g}, \quad . \quad . \quad . \quad . \quad (1)$$

in which, according to Weisbach's experiments with tubes 3 centims., i.e. 1.2 in., in diameter, we may put

For $\alpha =$ 20°	40°	60°	80°	90°	100°	110°	120°	130°	140°
$\zeta =$ .046	.139	.364	.740	.984	1.26	1.556	1.86	2.16	2.43

computed from the empirical formula;

$$\zeta = .9457 \sin^2 \tfrac{1}{2}\alpha + 2.047 \sin^4 \tfrac{1}{2}\alpha;$$

v is the velocity in pipe; α as in figure. For larger pipes ζ would probably be somewhat smaller; and *vice versâ*.

If the elbow is immediately succeeded by another in the same plane and turning the same way, Fig. 583, the loss of head is not materially increased, since the eddying takes place chiefly in the further branch of the second elbow; but if it turns in the reverse direction, Fig. 584, but still in the same plane, the total loss of head is double that of one elbow; while if the plane of the second is ⊥ to that of the first, the total loss of head is $1\frac{1}{2}$ times that of one alone. (Weisbach.)



Fig. 583.

Fig. 584.

529. Bends in Pipes of Circular Section.—Fig. 585. Weisbach bases the following empirical formula for ζ, the coefficient of resistance of a quadrant bend in a pipe of circular section, on his own experiments and some of Dubuat's, viz.:



Fig. 585.

$$\zeta = 0.131 + 1.847 \left(\frac{a}{r}\right)^{\frac{7}{2}}, \quad \ldots\ldots \quad (1)$$

for use in

$$h_r = \zeta \frac{v^2}{2g}, \quad \ldots\ldots \quad (2)$$

where $a =$ radius of pipe, $r =$ radius of bend (to centre of pipe), and $v =$ velocity in pipe; $h_r =$ loss of head due to bend.

It is understood that the portion BC of the pipe is kept full by the flow; which, however, may not be practicable unless

BC is more than three or four times as long as wide, and is full at the outset. A semicircular bend occasions about the same loss of head as a quadrant bend, but two quadrants forming a reverse curve in the same plane, Fig. 586, occasion a double loss. By enlarging the pipe at the bend, or providing internal thin partitions parallel to the sides, the loss of head may be considerably diminished. Weisbach gives the following table computed from eq. (1), but does not state the absolute size of the pipes.

FIG. 586.

For $\frac{a}{r} = .10$	.20	.30	.40	.50	.60	.70	.80	.90	1.0
$\zeta = .131$	.138	.158	.206	.294	.440	.661	.977	1.40	1.98

5 ?a. Resistance of Bends in Larger Pipes.—In Vol. xlvii (April, 1902, p. 183) of the *Transac. Am. Soc. Civ. Engs.* is an account of experiments made by Prof. G. S. Williams and Messrs. Hubbell and Fenkell, at Detroit, Mich., on the loss of head in 90° bends in pipes of diameters of 12, 16, and 30 in. In each case the loss of head was measured between two points, of which one was 100 ft. up-stream and the other 100 ft. down-stream, from the mid-point of the bend; so as to include the straight parts adjoining the bend, the disturbance due to which was found to be felt for some distance down-stream from the bend itself. From the loss of head so measured was deducted the loss that would occur in a 200 ft. length of straight pipe for the same velocity; this excess being the loss due to curvature alone. In the case of the 30 in. pipe it was found that when the radius of the bend (i.e., r of Fig. 585) was 60 ft. the excess loss was equal to that under normal conditions in a straight pipe (of same diameter) 180.4 ft. in length. For values of this radius equal to 40, 25, 15, and 10 ft., the results for the excess loss were equal to those in straight pipes 123, 105.4, 83, and 34.6 ft., respectively, in length; showing that in this instance the loss of head *diminished* with increasing sharpness of curvature (the direct contrary of Weisbach's results with small pipes).

Mr. A. W. Brightmore's experiments on 90° bends in 3-inch and 4-inch pipes are described in the *Proc. Civ. Engineers*, vol. 169 (1907), p. 323. The radii of the 3-inch bends were equal to 2, 4, 6, 8, 10, 12, and 14 diameters, while those in the 4-inch pipe were 2, 4, 6, 8, and 10 diameters. "It was found that most of the loss of head due to the bend does not take place in the bend itself but in the straight pipe following the bend. Consequently, in measuring the loss of head, a length of straight pipe sufficient for the flow to become normal again (6.7 ft. for the 3-inch pipe and 6 ft. for the 4-inch) was included with the bend, and the normal resistance in a straight pipe equal in length to the bend was subtracted" to obtain the excess loss due to curvature. The range of velocity was from 3 to 11 ft./sec.

The conclusions reached were: that the excess loss of head due to curvature for bends of these diameters is a minimum when the radius is 4 diameters, regardless of the velocity; that it rises to a maximum for a radius of 6 or 7 diameters and falls again for greater radii; that the minimum loss referred to is independent of the size of the pipe, but depends only on velocity and state of internal surface of pipe; and that the excess loss is very nearly proportional to the square of the velocity. Putting excess loss of head $= \zeta(v^2 \div 2g)$, there was found:

With r (*in diams.*) =	2	4	6	8	10	14
For 3-inch bends, $\zeta =$	.400	.311	.377	.355	.191	.146
For 4-inch bends, $\zeta =$	.422	.311	.337	.302	.235	

529b. Common Pipe-elbows.—Capt. L. F. Bellinger, C.E., of U. S. Navy Yard, Brooklyn, N. Y., made a set of experiments in 1887, when a student at Cornell, on the loss of head occasioned by a common elbow (for wrought-iron pipe), whose longitudinal section is shown in Fig. 586a. The elbow served to connect at right angles two wrought-iron pipes having an internal diameter of 0.482 in.



FIG. 586a.

The internal diameter of the short bend or elbow was $\frac{5}{8}$ in., and the radius of its curved circular axis (a quadrant) was $\frac{3}{4}$ in. Its internal surface was that of an ordinary rough casting.

The following values for the coefficient ζ were obtained; (the velocity v is in feet per sec.):

$v =$	2	4	6	8	10	12	14	16	18	20
$\zeta =$	.633	.649	.670	.697	.734	.782	.845	.929	1.039	1.185

530. Valve-gates and Throttle-valves in Cylindrical Pipes.—Adopting, as usual, the form

$$h_r = \zeta \frac{v^2}{2g}, \quad \ldots\ldots\ldots \quad (1)$$

for the loss of head due to a *valve-gate*, Fig. 587, or for a



FIG. 587.

FIG. 588.

throttle-valve, Fig. 588, each in a definite position, Weisbach's

experiments furnish us with a range of values of ζ in the case of these obstacles in a cylindrical pipe 1.6 inches in diameter, as follows (for meaning of s, d, and α, see figures. v is the velocity in the full section of pipe, running *full* on *both* sides.)

Valve-gate.		Throttle-valve.	
$\frac{s}{d}$	ζ	α	ζ
		5°	.24
1.0	.00	10°	.52
		15°	.90
$\frac{7}{8}$	.07	20°	1.54
		25°	2.51
$\frac{6}{8}$	.26	30°	3.91
		35°	6.22
$\frac{5}{8}$	.81	40°	10.8
		45°	18.7
$\frac{4}{8}$	2.06	50°	32.6
		55°	58.8
$\frac{3}{8}$	5.52	60°	118.0
		65°	256.0
$\frac{2}{8}$	17.00	70°	751.
$\frac{1}{8}$	97.8		

Mr. Kuichling's experiments on a 24-inch valve-gate are described in the *Transac. Am. Soc. Civ. Engs.* for May, 1892 (p. 439); (also *Eng. News*, Aug., 1892, p. 117). Mr. Kuichling's values for ζ are somewhat different from Weisbach's, probably from the greater size of pipe, and are given in the following table (from Unwin):

For $s \div d =$	0.66	0.60	0.50	0.37	0.25	0.18
$\zeta =$	0.8	1.6	3.3	8.6	22.7	41.2

531. Examples involving Divers Losses of Head.—We here suppose, as before, that the pipes are full during the flow. Practically, provision must be made for the escape of the air which collects at the high points. If this air is at a tension greater than one atmosphere, automatic air-valves will serve to provide for its escape; if less than one atmosphere, an air-pump can be used, as in the case of a siphon used at the Kansas City Water Works. (See p. 346 of the *Engineering News* for November 1887.)



FIG. 589.

EXAMPLE 1.—Fig. 589. What head, $= h$, will be required to deliver $\frac{1}{2}$ U. S. gallon (i.e. 231 cubic inches) per second

through the continuous line of pipe in the figure, containing two sizes of cylindrical pipe ($d_0 = 3$ in., and $d_2 = 1$ in.), and two 90° elbows in the larger. The flow is into the air at m, the jet being 1 in. in diameter, like the pipe. At E, $\alpha = 90°$, and the corners are not rounded; at K, also, corners not rounded. Use the ft.-lb.-sec. system of units in which $g = 32.2$.

Since $Q = \frac{1}{2}$ gal. $= \frac{1}{2} \cdot \frac{231}{1728} = .0668$ cub. ft. per sec., and therefore the velocity of the jet

$$v_m = v_2 = Q \div \tfrac{1}{4}\pi(\tfrac{1}{12})^2 = 12.25 \text{ ft. per sec.};$$

hence the velocity in the large pipe is to be $v_0 = (\frac{1}{3})^2 v_2 = 1.36$ ft. per sec. From Bernoulli's Theorem, we have, with m as datum plane,

$$\frac{v_m^2}{2g} + b + 0 = 0 + b + h - \zeta_E \frac{v_0^2}{2g} - 4f_0 \frac{l_0}{d_0} \cdot \frac{v_0^2}{2g}$$
$$- 2\zeta_{el.} \cdot \frac{v_0^2}{2g} - \zeta_K \frac{v_2^2}{2g} - 4f_2 \frac{l_2}{d_2} \cdot \frac{v_2^2}{2g},$$

involving six separate losses of head, for each of which there is no difficulty in finding the proper ζ or f, since the velocities and dimensions are all known, by consulting preceding paragraphs. (Clean iron pipe.)

From § 515, table, for $\alpha = 90°$ we have . . . $\zeta_E = 0.505$
" § 517, for $d_0 = 3$ in., and $v_0 = 1.36$ ft. per sec., $f_0 = .00725$
" " " $d_2 = 1$ in., and $v_2 = 12.25$ " " $f_2 = .00613$
" § 528 (elbows), for $\alpha = 90°$ . . . . $\zeta_{el.} = 0.984$
" § 527, for sudden diminution at K we have
[since $F_2 \div F_0 = 1^2 \div 3^2 = 0.111$, $\therefore C = 0.625$]

$$\zeta_K = \left(\frac{1}{.625} - 1\right)^2 = 0.360.$$

Solving the above equation for h, then, and substituting above numerical values (in ft.-lb.-sec.-system), we have (noting that $v_m = v_2$, and $v_0 = \frac{1}{9}v_2$)

$$h = \frac{(12.25)^2}{64.4}\left[1 + (\tfrac{1}{9})^2\left(.505 + \frac{4 \times .00725 \times 50}{\frac{1}{4}} + 2 \times .984\right)\right.$$
$$\left. + .360 + \frac{4 \times .00613 \times 20}{\frac{1}{12}}\right];$$

i.e.,

$$h = \frac{(12.25)^2}{64.4}\left[1+(.00623+.07160+.0243)+(.360+5.8848\right];$$

$$\therefore\ h = 2.323 \times 7.3469 = 17.09 \text{ ft.}—\textit{Ans.}$$

It is here noticeable how small are the losses of head in the large pipe, the principal reason of this being that the *velocity* in it is so small (v_0 = only 1.36 ft. per sec.), and that in general losses of head depend on the *square* of the velocity (nearly).

In other words, the large pipe approximates to being a reservoir in itself.

With no resistances a head $h = v_m^2 \div 2g = 2.32$ ft. would be sufficient.

Example 2.—Fig. 590. With the valve-gate V half raised (i.e., $s = \frac{1}{2}d$ in Fig. 587), required the volume delivered per second through the *clean* pipe here shown. The jet issues



Fig. 590.

from a short straight pipe, or nozzle (of diameter $d_2 = 1\frac{1}{2}$ in.) inserted in the end of the larger pipe, with the inner corners *not rounded*. Dimensions as in figure. Radius of each bend $= r = 2$ in. The velocity v_m of the jet in the air = velocity v_2 in the small pipe; hence the loss of head at K is

$$\zeta_K \frac{v_2^2}{2g}, \quad = \zeta_K \frac{v_m^2}{2g}.$$

Now v_m is unknown, as yet; but v_0, the velocity in the large pipe, is $= v_m\left[\frac{(\frac{3}{2})^2}{2^2}\right]$; i.e., $v_0 = \frac{9}{16}v_m$. From Bernoulli's The-

orem (m as datum level) we obtain, after transposition,

$$h = \frac{v_m^2}{2g} + \zeta_E \frac{v_0^2}{2g} + \zeta_V \frac{v_0^2}{2g} + 2\zeta_B \frac{v_0^2}{2g} + 4f_0 \frac{l_0}{d_0} \frac{v_0^2}{2g} + \zeta_K \frac{v_m^2}{2g}. \quad (1)$$

Of the coefficients concerned, f_0 alone depends on the unknown velocity v_0. For the present [first approximation], put . . . . . $f_0 = .006$
From § 515, with $\alpha = 90°$, ... $\zeta_E = .505$
From § 517, valve-gate with $s = \frac{4}{8}d$, ... $\zeta_V = 2.06$
From § 529, with $a : r = 0.5$, ... $\zeta_B = 0.294$
While at K, from § 527, having

$$(F_2 : F_0) = (\tfrac{3}{4})^2 : 2^2 = \tfrac{9}{16} = 0.562;$$

we find from table, ... $C = 0.700$

and $\therefore \zeta_K = \left(\frac{1}{.700} - 1\right)^2 = (0.428)^2$. . . . i.e., $\zeta_K = 0.183$

Substituting in eq. (1) above, with $v_c^2 = (\frac{9}{16})^2 v_m^2$, we have

$$v_m = \sqrt{\frac{1}{1 + \frac{81}{256}\left[\zeta_E + \zeta_V + 2\zeta_B + 4f_0 \frac{l_0}{d_0}\right] + \zeta_K}}\ \sqrt{2gh}, \quad (2)$$

in which the first radical, an abstract number, might be called a *coefficient of velocity*, ϕ, for the whole delivery pipe; and also, since in this case $Q, = F_m v_m = F_2 v_2$, may be written $Q = \mu F_2 \sqrt{2gh}$, it may be named a *coefficient of efflux*, μ.

Hence

$$v_m = \sqrt{\frac{1}{1 + \frac{81}{256}\left[.505 + 2.06 + 2 \times .294 + \frac{4 \times .006 \times 80}{\frac{1}{6}}\right] + .183}}\ \sqrt{2 \times 32.2 \times 25};$$

$\therefore v_m = 0.421 \sqrt{2gh} = 0.421 \sqrt{2 \times 32.2 \times 25} = 16.89$ ft. per sec.

(The .421 might be called a coefficient of velocity.) The volume delivered per second is

$$Q = \tfrac{1}{4}\pi d_2^2 v_m = \tfrac{1}{4}\pi(\tfrac{3}{4})^2 16.89 = .207 \text{ cub. ft. per sec.}$$

(As the section of the jet $F_m = F_2$, that of the short pipe or nozzle, we might also say that $.421 = \mu =$ *coefficient of efflux*, for we may write $Q = \mu F_2 \sqrt{2gh}$, whence $\mu = .421$.)

532. Siphons.—In Fig. 590*a* the part HN_2O of the pipe is above the level, BC, of the surface of the water in the head reservoir BL, and yet under proper conditions a steady flow can be maintained with all parts of the pipe full of water, including HN_2O. If the atmosphere exerted no pressure, this would be impossible; but its average tension of 14.7 lbs. per sq. inch is equivalent to an additional depth of nearly 34 feet of water placed upon BC. With no flow, or a very small velocity, the pipe may be kept full if N_2 is not more than 33 or 34 feet above BC; but the greater v_2, the velocity of flow at N_2, and the greater and more numerous the losses of head between L and N_2, the less must be the height of N_2 above BC for a steady flow.

The analytical criterion as to whether a flow can be maintained or not, supposing the pipe completely filled at the outset, is that the internal pressure must be > 0 at all parts of the pipe. If on the supposition of a flow through a pipe of given design the pressure p is found < 0, i.e. negative, at any point [N_2 being the important section for test] the supposition is inadmissible, and the design must be altered.

For example, Fig. 590*a*, suppose LN_2N_4 to be a long pipe of uniform section (diameter $= d$, and length $= l$), and that under the assumption of filled sections we have computed v_4, the velocity of the jet at N_4; i.e., $v_4 =$

$$\frac{1}{\sqrt{1+\zeta_L+4f\frac{l}{d}}}\sqrt{2gh}.$$



FIG. 590 a.

To test the supposition, apply Bernoulli's Theorem to the surface BC and the point N_2 where the pressure is p_2, velocity $v_2 (= v_4$, since we have supposed a uniform section for whole pipe), and height above $BC = h_2$. Also, let length of pipe $LN_1HN_2 = l_2$. Whence we have

$$\frac{v_2^2}{2g}+\frac{p_2}{\gamma}+h_2 = 0+\frac{p_a}{\gamma}(=b)+0-\zeta_L\frac{v_2^2}{2g}-4f\frac{l_2}{d}\frac{v_2^2}{2g}. \quad (2)$$

[BC being datum plane.]

Solving for $\frac{p_2}{\gamma}$, we have

$$\frac{p_2}{\gamma} = 34 \text{ feet} - \left[h_2 + \frac{v_2^2}{2g}\left(1 + \zeta_L + 4f\frac{l_2}{d}\right)\right]. \quad . \quad . \quad (3)$$

We note, then, that for p_2 to be > 0,

$$h_2 \textit{ must be} < \left[34 \textit{ feet} - \frac{v_2^2}{2g} - \zeta_L\frac{v_2^2}{2g} - 4f\frac{l}{d}\frac{v_2^2}{2g}\right]. \quad . \quad (4)$$

In the practical working of a siphon it is found that atmospheric air, previously dissolved in the water, gradually collects at N_2, the highest point, during the flow and finally, if not removed, causes the latter to cease. See reference below.

One device for removing the air consists in first allowing it to collect in a chamber in communication with the pipe beneath. This communication is closed by a stop-cock after the water in it has been completely displaced by air. Another stop-cock, above, being now opened, water is poured in to replace the air, which now escapes. Then the upper stop-cock is shut and the lower one opened. The same operation is again necessary, after some hours.

In *Engineering News* of Nov. 12, 1887, p. 346, is an account of a siphon used in connection with the water-works at Kansas City. It is 1350 ft. long and transmits water from the river to the artificial "well" from which the pumping engines draw their supply. At the highest point, which is 16 ft. above low-water level of the river, is placed a "vacuum chamber" in which the air collects under a low tension corresponding to the height, and a pump is kept constantly at work to remove the air and prevent the "breaking" of the (partial) vacuum. The diameter of the pipe is 24 in., and the extremity in the "well" dips 5 ft. below the level of low water. See p. 63 of vol. lix (Dec., 1907) of the *Transac. Am. Soc. Civil Engineers*, for Mr. Anthony's paper on air in siphons.



FIG. 590 b.

532a. Branching Pipes.*—If the flow of water in a pipe is caused to divide and pass into two others having a common

* Problems of this kind are best solved by tables or diagrams. See pp. 197, etc., of the writer's *Hydraulic Motors*.

junction with the first, or *vice versâ*; or if lateral pipes lead out of a main pipe, the problem presented may be very complicated. As a comparatively simple instance, let us suppose that a pipe of diameter d and length l leads out of a reservoir, and at its extremity is joined to two others of diameters d_1 and d_2 and lengths l_1 and l_2 respectively, and that the further extremities of the latter discharge into the air without nozzles under heads h_1 and h_2 below the reservoir surface. Call these two pipes Nos. 1 and 2. See Fig. 590*b*.

Assuming that all entrances and junctions are smoothly rounded, so that all loss of head is due to skin-friction, it is required to find the three velocities of flow, v, v_1, and v_2, in the respective pipes. First applying Bernoulli's Theorem to a stream-line from the reservoir surface through the main pipe to the jet at the discharging end of pipe No. 1, we have

$$\frac{v_1^2}{2g} = h_1 - 4f\frac{l}{d}\cdot\frac{v^2}{2g} - 4f\frac{l_1}{d_1}\cdot\frac{v_1^2}{2g}; \quad . \quad . \quad . \quad (1)$$

and similarly, dealing with a stream-line through the main pipe and No. 2,

$$\frac{v_2^2}{2g} = h_2 - 4f\frac{l}{d}\cdot\frac{v^2}{2g} - 4f\frac{l_2}{d_2}\cdot\frac{v_2^2}{2g}; \quad . \quad . \quad . \quad (2)$$

while the equation of continuity for this case is

$$\tfrac{1}{4}\pi d^2 v = \tfrac{1}{4}\pi d_1^2 v_1 + \tfrac{1}{4}\pi d_2^2 v_2. \quad . \quad . \quad . \quad . \quad (3)$$

From these three equations, assuming f the same in all pipes as a first approximation, we can find the three velocities (best by numerical trial, perhaps); and then the volume of discharge of the system per unit of time

$$Q = \tfrac{1}{4}\pi d^2 v. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

533. Time of Emptying Vertical Prismatic Vessels (or Inclined Prisms if Bottom is Horizontal) under Variable Head.

Case I. *Through an orifice or short pipe in the bottom and opening into the air.*—Fig. 591. As the upper free surface,

of area $= F'$, sinks, F' *remains constant.* Let $z =$ head of water at any stage of the emptying; it $= z_0$ at the outset, and $= 0$ when the vessel is empty. At any instant, Q, the *rate of discharge* (= volume per time-unit) depends on z and is



FIG. 591.

$$Q = \mu F \sqrt{2gz}, \quad . \quad . \quad . \quad (1)$$

where $\mu =$ *coefficient of efflux* $= \phi C =$ *coefficient of velocity* $\times$ *coefficient of contraction* [see § 495, eq. (3)]. We here suppose F' so large compared with F, the area of the orifice, that the free surface of the water in the vessel does not acquire any notable velocity at any stage, and that hence the rate of efflux is the same at any instant, as for a steady flow with head $= z$ and a zero velocity in the free surface. μ is considered constant. From (1) we have

$$dV = (\text{vol. discharged in time } dt) = Qdt = \mu F \sqrt{2g} z^{\frac{1}{2}} dt. \quad . \quad (2$$

But this is also equal to the volume of the horizontal lamina, $F'dz$, through which the free surface has sunk in the same time dt.

$$\therefore \; -F'dz = \mu F \sqrt{2g}\, z^{\frac{1}{2}} dt; \;\; \therefore \; dt = \frac{-F'}{\mu F \sqrt{2g}} z^{-\frac{1}{2}} dz. \quad . \quad (3)$$

We have written *minus* $F'dz$ because, dt being an increment, dz is a decrement. To reduce the depth from z_0 (at the start, time $= t =$ zero) to z_n, demands a time

$$\Big[_0^n t = -\frac{F'}{\mu F \sqrt{2g}} \int_{z_0}^{z_n} z^{-\frac{1}{2}} dz = \frac{2F'}{\mu F \sqrt{2g}} [z_0^{\frac{1}{2}} - z_n^{\frac{1}{2}}]; \quad (4)$$

whence, by putting $z_n = 0$, we have the time necessary to empty the whole prism

$$\Big[_0^n t = \frac{2F' z_0^{\frac{1}{2}}}{\mu F \sqrt{2g}} = \frac{2F' z_0}{\mu F \sqrt{2gz_0}} = \frac{2 \times \text{volume of vessel}}{\text{initial rate of discharge}}; \quad (5)$$

that is, to empty the vessel requires *double the time* of discharging the same amount of water if the vessel had been kept full (at constant head $= z_0 =$ altitude of prism).

To *fill* the same vessel through an orifice in the bottom, the flow through which is supplied from a body of water of infinite extent horizontally, as with the (single) canal lock of Fig. 592, will obviously require the same time as given in eq. (5) above, since the effective head z diminishes from z_0 to 0, according to the same law.



FIG. 592.

EXAMPLE.—What time will be needed to empty a parallelopipedical tank (Fig. 591) 4 ft. by 5 ft. in horizontal section and 6 ft. deep, through a stop-cock in the bottom whose coefficient of efflux when fully open is known to be $\mu = 0.640$, and whose section of discharge is a circle of diameter $= \frac{1}{2}$ in.? From given dimensions $F' = 4 \times 5 = 20$ sq. ft., while $z_0 = 6$ ft. Hence from eq. (5) (ft.-lb.-sec.)

$$\left.\begin{matrix}\text{time of}\\ \text{emptying}\end{matrix}\right\} = \frac{2 \times 20 \times \sqrt{6}}{0.64 \times \frac{1}{4}\pi(\frac{1}{24})^2 \sqrt{2 \times 32.2}} = \left\{\begin{matrix}13980 \text{ seconds}\\ = 3^{\text{hours}}\, 53^{\text{min.}}\, 0^{\text{sec.}}\end{matrix}\right.$$

CASE II. *Two communicating prismatic vessels. Required the time* for the water to come to a common level ON, Fig. 593, efflux taking place through a small orifice, of area $= F$, under water. At any instant the *rate of discharge* is



FIG. 593.

$$Q = \mu F \sqrt{2gz},$$

as before. $z =$ difference of level. Now if F' and F'' are the horizontal sectional areas of the two prismatic vessels (axes vertical) we have $F'x = F''y$, and hence z, which $= x + y$, $= x + (F' \div F'')x$;

$$\therefore x = \frac{z}{1 + \frac{F'}{F''}}, \quad \text{and} \quad dx = \frac{dz}{1 + \frac{F'}{F''}}.$$

As before, we have

$$-F'dx = \mu F\sqrt{2g}\,z^{\frac{1}{2}}dt, \quad \text{or} \quad dt = -\frac{F'F''}{F'+F''}\frac{z^{-\frac{1}{2}}dz}{\mu F\sqrt{2g}}.$$

Hence, integrating, the time for the *difference* of level to change from z_0 to z_n

$$= \frac{2F'F''}{F'+F''}\cdot\frac{z_0^{\frac{1}{2}} - z_n^{\frac{1}{2}}}{\mu F\sqrt{2g}}, \quad . \quad . \quad . \quad . \quad (6)$$

and by making $z_n = 0$ in (6), we have the

$$\textit{time of coming to a common level} = \frac{2F'F''}{F'+F''}\cdot\frac{1}{\mu F}\sqrt{\frac{z_0}{2g}}. \quad (7)$$

Algebraic Example.—In the double lock in Fig. 594, let L' be full, while in L'' the water stands at a level MN the same as that of the tail-water. F' and F'' are the horizontal sectional areas of the prismatic locks. Let the orifice, O, between them, be at a depth $= h_1$ below the initial level KE of L', and a height $= h_2$ *above* that, MN, of L''.



Fig. 594.

The orifice at O, area $= F$, being opened, efflux from L' begins *into the air*, and the level of L'' is gradually raised from MN to OD, while that of L' sinks from KE to AB a distance $= a$, computed from the relation vol. $F'a =$ vol. $F''h_2$, and the time occupied is [eq. (4)]

$$t_1 = \frac{2F'}{\mu F\sqrt{2g}}\left[\sqrt{h_1} - \sqrt{h_1 - a}\right]. \quad . \quad . \quad . \quad . \quad (8)$$

As soon as O is submerged, efflux takes place under water, and we have an instance of Case II. Hence the time of reaching a common level (after submersion of O) (see eq. 7) is

$$t_2 = \frac{2F'F''}{\mu F(F'+F'')}\sqrt{\frac{h_1 - a}{2g}}, \quad . \quad . \quad . \quad . \quad (9)$$

and the total time is $= t_1 + t_2$, with $a = F''h_2 \div F'$.

CASE III. *Emptying a vertical prismatic vessel through a rectangular "notch" in the side, or overfall.*—Fig. 595. As before, let even the initial area ($= z_0 b$) of the notch be small compared with the horizontal area F' of tank. Let z = depth of lower sill of notch below level of tank surface at any instant, and b = width of notch. Then, at any instant (see eq. 10, § 504),



FIG. 595.

$$\textit{Rate of disch. (vol.)} = Q = \tfrac{2}{3}\mu_0 bz\sqrt{2gz} = \tfrac{2}{3}\mu b\sqrt{2g}\,z^{\frac{3}{2}}.$$

$$\therefore \text{ vol. of disch. in } dt = \tfrac{2}{3}\mu b\sqrt{2g}\,z^{\frac{3}{2}}dt,$$

and putting this $= -F'dz$ = vol. of water lost by the tank in time dt, we have

$$dt = -\frac{3}{2}\frac{F'}{\mu b\sqrt{2g}}z^{-\frac{1}{2}}dz;$$

whence

$$\Big]_0^n t = -\frac{3}{2}\frac{F'}{\mu b\sqrt{2g}}\int_{z_0}^{z_n} z^{-\frac{1}{2}}dz = -\frac{3}{2}\frac{F'}{\mu b\sqrt{2g}}\Big]_0^n \frac{z^{-\frac{1}{2}}}{-\frac{1}{2}};$$

i.e.,

$$\Big]_0^n t = \frac{3F'}{\mu b\sqrt{2g}}\left[\frac{1}{\sqrt{z_n}} - \frac{1}{\sqrt{z_0}}\right], \quad . \quad . \quad . \quad . \quad (10)$$

as the time in which the tank surface sinks from a height z_0 above sill to a height z_n above sill. If we inquire the time t' for the water to sink to the level *of the sill of the notch* we put z_n = zero, whence $t' = \textit{infinity}$. As explanatory of this result, note that as z diminishes not only does the velocity of flow diminish, but the available area of efflux ($= zb$) also grows less, whereas in Cases I and II the orifice of efflux remained of constant area $= F$.

Eq. (10) is applicable to the waste-weir of a large reservoir or pond.

534. Time of Emptying Vessels of Variable Horizontal Sections.—Considering regular geometrical forms first, let us take

CASE I. *Wedge-shaped vessel, edge horizontal and underneath, orifice F in the edge*, so that z, the variable head, is always the altitude of a triangle similar to the section ABC of the body of water when efflux begins. At any instant during the efflux the area, S, of the free surface, *variable here*, takes the place of F' in eq. (3) of § 533, whence we have,



FIG. 596.

$$\textit{for any case of variable free surface, } dt = \frac{-Sz^{-\frac{1}{2}}dz}{\mu F\sqrt{2g}}. \quad . \quad (11)$$

In the present case $S = ul$, and from similar triangles

$$u : z :: b : z_0;$$

whence

$$S = blz \div z_0,$$

and

$$dt = \frac{-blz^{\frac{1}{2}}dz}{\mu F z_0\sqrt{2g}};$$

$$\therefore \left[{}_0^n t = \frac{bl}{\mu F z_0\sqrt{2g}}\int_{z_n}^{z_0} z^{\frac{1}{2}}dz = \frac{\frac{2}{3}bl}{\mu F z_0\sqrt{2g}}\left[z_0^{\frac{3}{2}} - z_n^{\frac{3}{2}}\right], \quad . \quad (12)\right.$$

and hence the time of emptying the whole *wedge*, putting $z_n = 0$, is

$$t_0 = \frac{4}{3}\cdot\frac{\frac{1}{2}blz_0}{\mu F\sqrt{2gz_0}} = \frac{4}{3}\cdot\frac{\textit{Vol. of wedge.}}{\textit{initial rate of discharge}}; \quad . \quad (13)$$

i.e., $\frac{4}{3}$ as long as to discharge the same volume of water under a constant head $= z_0$. This is equally true if the ends of the wedge are *oblique*, so long as they are parallel.

CASE II. *Right segment of paraboloid of revolution.*—Fig. 597. Axis vertical. Orifice at vertex. Here the variable free surface has at any instant an area, $= S, = \pi u^2$, u being the radius of the circle and variable. From a property of the parabola

$$u^2 : b^2 :: z : z_0; \quad \therefore \quad S = \pi b^2 z \div z_0,$$



FIG. 597.

and hence, from eq. (11),

$$dt = \frac{-\pi b^2 z^{\frac{1}{2}} dz}{\mu F z_0 \sqrt{2g}};$$

$$\therefore \int_0^n t = \frac{\pi b^2}{\mu F z_0 \sqrt{2g}} \int_{z_n}^{z_0} z^{\frac{1}{2}} dz = \frac{2}{3} \frac{\pi b^2}{\mu F z_0 \sqrt{2g}} [z_0^{\frac{3}{2}} - z_n^{\frac{3}{2}}];$$

whence, putting $z_n = 0$, we have the time of emptying the whole vessel

$$t_0 = \frac{4}{3} \frac{\pi b^2 \frac{1}{2} z_0}{\mu F \sqrt{2g z_0}} = \frac{4}{3} \cdot \frac{\textit{total vol.}}{\textit{initial rate of disch.}}, \quad . \quad (14)$$

same result as for the wedge, in Case I; in fact, it applies to any vessel in which the *areas of horizontal sections vary directly with their heights above the orifice.*

Case III. *Any pyramid or cone; vertex down; small orifice in vertex.*—Fig. 598. Let area of the base $= S_0$, at upper edge of vessel. At any stage of the flow S = area of base of pyramid of water. From similar pyramids



Fig. 598.

$$S_0 : S :: z_0^2 : z^2; \quad \therefore \quad S = \frac{S_0}{z_0^2} z^2,$$

and [eq. (11)]

$$dt = -\frac{S_0}{z_0^2} \frac{1}{\mu F \sqrt{2g}} z^{\frac{1}{2}} dz,$$

whence ($z_n = 0$) the time of emptying the whole vessel is

$$t_0 = \frac{S_0}{\mu F z_0^2 \sqrt{2g}} \int_0^{z_0} z^{\frac{1}{2}} dz = \frac{2}{5} \frac{S_0 z_0^{\frac{1}{2}}}{\mu F z_0^2 \sqrt{2g}};$$

or,
$$t_0 = \frac{6}{5} \cdot \frac{\textit{Total volume}}{\textit{initial rate of disch.}} \quad . \quad . \quad . \quad . \quad . \quad (15)$$

Case IV. *Sphere.*—Similarly, we may show that to empty

a sphere, of radius $= r$, through a small orifice, of area $= F$, in lowest part, the necessary time is

$$t_0 = \frac{16}{15} \cdot \frac{\pi r^2}{\mu F \sqrt{gr}} = \frac{8}{5} \cdot \frac{Vol.}{init.\ rate\ of\ disch.}$$

535. Time of Emptying an Obelisk-shaped Vessel.—(An obelisk may be defined as a solid of six plane faces, two of which are rectangles in parallel planes and with sides respectively parallel, the others trapezoids; a frustum of a pyramid is a particular case.)

A volume of this shape is of common occurrence; see Fig. 599. Let the altitude $= h$, the two rectangular faces being horizontal, with dimensions as in figure. By drawing through F, G, and H right lines parallel to EC, to cut the upper base, we form a rectangle $KLMC$ equal to the lower base. Produce ML to P and KL to N, and join PG and NG. We have now subdivided the solid into a parallelopiped $KLMC\text{-}EHGF$, a pyramid $PBNL\text{-}G$, and two wedges, viz. $APLK\text{-}HG$ and $LNDM\text{-}FG$, with their edges horizontal; and may obtain the time necessary to empty the whole obelisk-volume by adding the times which would be necessary to empty the individual component volumes, separately, through the same orifice or pipe in the bottom plane EG. These have been already determined in the preceding paragraphs. The dimensions of each component volume may be expressed in terms of those of the obelisk, and all have a common altitude $= h$.



FIG. 599.

Assuming the orifice to be in the bottom, or else that the discharging end of the pipe, if such is used, is *in the plane of the bottom* EG, we have as follows, F being the area of discharge:

Time to empty the parallelopiped separately would be (Case I, § 533) . . $t_1 = \frac{2b_1l_1}{\mu F\sqrt{2g}}\sqrt{h}.$ (1)

Time to empty the two wedges separately (Case I, § 534) $t_2 = \frac{2}{3}\cdot\frac{b_1(l-l_1)+l_1(b-b_1)}{\mu F\sqrt{2g}}\sqrt{h}.$. (2)

For the pyramid (Case III, § 534) . . . $t_3 = \frac{2}{5}\cdot\frac{(l-l_1)(b-b_1)}{\mu F\sqrt{2g}}\sqrt{h}.$ . . (3)

Hence to empty the whole reservoir we have

$$t = t_1 + t_2 + t_3;$$

i.e.,

$$t = [3bl + 8b_1l_1 + 2bl_1 + 2b_1l]\frac{2\sqrt{h}}{15\mu F\sqrt{2g}}. \quad . \quad . \quad (4)$$

Example.—Let a reservoir of above form, and with $b = 50$ ft., $l = 60$ ft., $b_1 = 10$ ft., $l_1 = 20$ ft., and depth of water $h = 16$ ft., be emptied through a straight iron pipe, horizontal, and leaving the side of the reservoir *close to the bottom*, at an angle $\alpha = 36°$ with the inner plane of side. The pipe is 80 ft. long and 4 inches in internal diameter; and of clean surface. The jet issues directly from this pipe into the air, and hence $F = \frac{1}{4}\pi(\frac{1}{3})^2$ sq. feet. To find μ, the "coefficient of efflux" ($= \phi$, the coefficient of velocity in this case, since there is no contraction at discharge orifice), we use eq. (4) (the first radical) of § 518, with f approx. $= .006$, and obtain

$$\mu = \phi = \sqrt{\frac{1}{1+\zeta_E+4f\frac{l}{d}}} = \sqrt{\frac{1}{1+.896+\frac{4\times.006\times80}{\frac{1}{3}}}} = 0.361.$$

(N.B. Since the velocity in the pipe diminishes from a value

$$v = .361\sqrt{2g\times16} = 11.6 \text{ ft. per sec.}$$

at the beginning of the flow to $v =$ zero at the close, $f = .006$ is a reasonably approximate average with which to compute the average ϕ above; see § 517.

Hence from eq. (4) of this paragraph (ft.-lb.-sec. system)

$$t = \frac{[3 \times 50 \times 60 + 8 \times 10 \times 20 + 2(50 \times 20 + 10 \times 60)]2\sqrt{16}}{15 \times 0.361 \times \frac{\pi}{4}\left(\frac{1}{3}\right)^2 \sqrt{2 \times 32.2}}$$

$= 29110$ sec. $= 8$ hrs. 5 min. { Probably within 2 or 3% of the truth.

536. Time of Emptying Reservoirs of Irregular Shape. Simpson's Rule.—From eq. (11), § 534, we have, for the time in which the free surface of water in a vessel of any shape whatever sinks through a vertical distance $= dz$,

$$dt = \frac{-Sz^{-\frac{1}{2}}dz}{\mu F\sqrt{2g}}, \text{ whence } \left[\begin{matrix} z=z_n \\ time \\ z=z_0 \end{matrix}\right. = \frac{1}{\mu F\sqrt{2g}} \int_{z_n}^{z_0} Sz^{-\frac{1}{2}}dz, \quad . \quad . \quad (1)$$

where S is the variable area of the free surface at any instant, and z the head of water at the same instant, efflux proceeding through a small orifice (or extremity of pipe) of area $= F$. If S can be expressed in terms of z, we can integrate eq. (1) (i.e., provided that $Sz^{-\frac{1}{2}}$ has a known anti-derivative); but if not, the vessel or reservoir being irregular in form, as in Fig. 600 (which shows a pond whose bottom has been accurately surveyed, so that we know the value of S for any stage of the emptying), we can still get an approximate solution by using Simpson's Rule for approximate integration. Accordingly, if we inquire the time in which the surface will sink from 0 to the entrance E of the pipe in Fig. 600 (any point n; at E, or short of that), we divide the *vertical distance* from 0 to n (4 in this figure) into an even number of equal parts, and from the known form of the pond compute the area S corresponding to each point of division, calling them S_0, S_1, etc. Then the required time is approximately



FIG. 600.

$$\left[_0^n t = \frac{z_0 - z_n}{3\mu F\sqrt{2g}\,n}\left[\frac{S_0}{z_0^{\frac{1}{2}}} + 4\left(\frac{S_1}{z_1^{\frac{1}{2}}} + \frac{S_3}{z_3^{\frac{1}{2}}} + \cdots \frac{S_{n-1}}{z_{n-1}^{\frac{1}{2}}}\right)\right.\right.$$

$$\left.\left. + 2\left(\frac{S_2}{z_2^{\frac{1}{2}}} + \frac{S_4}{z_4^{\frac{1}{2}}} + \cdots \frac{S_{n-2}}{z_{n-2}^{\frac{1}{2}}}\right) + \frac{S_n}{z_n^{\frac{1}{2}}}\right].$$

Example.—Fig. 600. Suppose we have a pipe En of the same design as in the example of § 535, and an initial head of $z_0 = 16$ ft., so that the same value of μ, $= .361$, may be used. Let $z_n - z_0 = 8$ feet, and divide this interval (of 8 ft.) into four equal vertical spaces of 2 ft. each. If at the respective points of division we find from a previous survey that $S_0 = 400000$ sq. ft., $S_1 = 320000$ sq. ft., $S_2 = 270000$ sq. ft., $S_3 = 210000$ sq. ft., and $S_4 = 180000$ sq. ft.; while $n = 4$, $\mu = .361$, and the area $F = \frac{1}{4}\pi(\frac{1}{3})^2 = .0873$ sq. ft., we obtain (ft., lb., sec.)

$$\left[_0^4 t = \frac{16 - 8}{0.361 \times .0873\sqrt{2 \times 32.2} \times 3 \times 4}\left[\frac{400000}{\sqrt{16}} + \frac{4 \times 320000}{\sqrt{14}}\right.\right.$$

$$\left.\left. + \frac{2 \times 270000}{\sqrt{12}} + \frac{4 \times 210000}{\sqrt{10}} + \frac{180000}{\sqrt{8}}\right] = 2444000 \text{ sec.}\right.$$
$$= 28^{\text{d.}}\ 6^{\text{h.}}\ 53^{\text{m.}}\ 20^{\text{s.}}$$

The volume discharged, V, may also be found by Simpson's Rule, thus: Since each infinitely small horizontal lamina has a volume

$$dV = -Sdz, \quad \therefore \quad \left[_0^n V = \int_n^0 Sdz,\right.$$

or, approximately,

$$\left[_0^n V = \frac{z_0 - z_n}{3n}\left[S_0 + 4S_1 + 2S_2 + 4S_3 + \ldots + S_n\right]\right.\cdot$$

Hence with $n = 4$ we have (ft., lb., sec.)

$$\left[_0^n V = \frac{16 - 8}{3 \times 4}\left[400000 + 4\left\{\begin{matrix}320000\\+210000\end{matrix}\right\} + 2 \times 270000\right.\right.$$

$$\left.\left. + 180000\right] = 2{,}160{,}000 \text{ cub. ft.}\right.$$

537. Volume of Irregular Reservoir Determined by Observing Progress of Emptying.—Transforming eq. (11), § 534, we have

$$Sdz = -\mu F\sqrt{2g}\, z^{\frac{1}{2}}dt.$$

But Sdz is the infinitely small volume dV of water lost by the reservoir in the time dt, so that the volume of the reservoir between the initial and final (0 and n) positions of the horizontal free surface (at beginning and end of the time t_n) may be written

$$\Big[_0^n V = \mu F\sqrt{2g}\int_0^{t_n} z^{\frac{1}{2}}dt. \quad . \quad . \quad . \quad . \quad . \quad (1)$$

This can be integrated approximately by Simpson's Rule, if the whole *time of emptying*, $= t_n$, be divided into an even number of equal parts, and the values z_0, z_1, z_2, etc., of the head of water noted at these *equal intervals of time* (not of vertical height). The corresponding surface planes will not be equidistant, in general. Whence for the particular case when $n = 4$ (see Fig. 601)



FIG. 601.

$$\Big[_0^4 V = \frac{\mu F\sqrt{2g}\,(t_n - 0)}{3 \times 4}\left[z_0^{\frac{1}{2}} + 4\left(z_1^{\frac{1}{2}} + z_3^{\frac{1}{2}}\right) + 2z_2^{\frac{1}{2}} + z_4^{\frac{1}{2}}\right]. \quad . \quad . \quad (2)$$

537a. Time of Change of Surface-level of Reservoir when Inflow Exists as well as Outflow.—Solutions of problems of this nature involve somewhat more extended mathematics than the foregoing. Results and formulæ applicable to a number of such cases will be found on pp. 147–155 of Mr. Horton's monograph mentioned in the foot-note of p. 688. Cases of both constant and variable inflow are treated in that paper. See also *Engineering News* of Nov. 14, 1901, pp. 362, 363; and Dec. 5, 1901, p. 431.

CHAPTER VII.

HYDROKINETICS (*Continued*)—STEADY FLOW OF WATER IN OPEN CHANNELS.

538. Nomenclature.—Fig. 602. When water flows in an open channel, as in rivers, canals, mill-races, water-courses, ditches, etc., the bed and banks being rigid, the upper surface is free to conform in shape to the dynamic conditions of each case, which therefore regulate to that extent the shape of the cross-section.



FIG. 602.

In the vertical transverse section AC in figure, the line AC is called the *air-profile* (usually to be considered horizontal and straight), while the line ABC, or profile of the bed and banks, is called the *wetted perimeter*. It is evident that the ratio of the wetted perimeter to the whole perimeter, though never $< \frac{1}{2}$, varies with the form of the transverse section.

In a longitudinal section of the stream, $EFGH$, the angle made by a surface filament EF with the horizontal is called the *slope*, and is measured by the ratio $s = h : l$, where l is the length of a portion of the filament and $h =$ the *fall*, or *vertical* distance between the two ends of that length. The angle between the horizontal and the line HG along the bottom is not necessarily equal to that of the surface, unless the portion of the stream forms a prism; i.e., the slope of the bed does not necessarily $= s =$ that of surface.

EXAMPLES.—The old Croton Aqueduct has a slope of 1.10 ft. per mile; i.e., $s = .000208$. The new aqueduct (for New

York) has a slope $s = .000132$, with a larger transverse section. For large sluggish rivers s is much smaller.

539. Velocity Measurements. — Various instruments and methods may be employed for this object, some of which are the following:

Surface-floats are small balls, or pieces of wood, etc., so colored and weighted as to be readily seen, and still but little affected by the wind. These are allowed to float with the current in different parts of the width of the stream, and the surface velocity c in each experiment computed from $c = l \div t$, where l is the distance described between parallel transverse alignments (or actual ropes where possible), whose distance apart is measured on the bank, and $t =$ the time occupied.

Double-floats. Two balls (or small kegs) of same bulk and condition of surface, one lighter, the other heavier than water, are united by a slender chain, their weights being so adjusted that the light ball, without projecting notably above the surface, buoys the other ball at any assigned depth. Fig. 603. It is assumed that the combination moves with a velocity c', equal to the arithmetic mean of the surface velocity c_0 of the stream and that, c, of the water filaments at the depth of the lower ball, which latter, c, is generally less than c_0. That is, we have



FIG. 603.

$$c' = \tfrac{1}{2}(c_0 + c) \quad \text{and} \quad \therefore \; c = 2c' - c_0 \; . \; . \; . \; . \; (1)$$

Hence, c_0 having been previously obtained, eq. (1) gives the velocity c at any depth of the lower ball, c' being observed.

The *floating staff* is a hollow cylindrical rod, of adjustable length, weighted to float upright with the top just visible. Its observed velocity is assumed to be an average of the velocities of all the filaments lying between the ends of the rod.

Woltmann's Mill; or *Tachometer;* or *Current-meter*, Fig. 604, consists of a small wheel with inclined floats (or of a small



FIG. 604*a*.—The *Buff and Buff* Current Meter. Held at the end of a pole. 5-inch wheel.

[*To face page* 750.



FIG. 604*b*.— { *Price* Current Meter. / *Haskell* Hand Current Meter. } *Ritchie-Haskell* Direction-current Meter (length 41¾ in.). Repeater (for direction). Velocity Register.

[*To face page* 751.

"screw-propeller" wheel S) held with its plane ⊥ to the current, which causes it to revolve at a speed nearly proportional to the velocity, c, of the water passing it. By a screw-gearing W on the shaft, connection is made with a counting apparatus to record the number of revolutions. Sometimes a vane B is attached, to compel the wheel to face the current. It is either held at the extremity of a pole; or suspended by a weighted cable, for work in deep water. In some types the counting device is actuated by electric connection with the revolving wheel, and hence may be placed in a boat or on shore. With the screw-gearing, a cord and spring are used for throwing in and out of gear.



FIG. 604.

On the opposite sheet are shown four varieties of current meter: the Buff and Buff meter, for attachment to a pole; the Haskell meter; the Ritchie-Haskell *direction-current* meter (see below); and the Price meter. This last resembles the anemometer of p. 824.

A special form of this instrument has been recently invented, called the *Ritchie-Haskell Direction-current Meter*, possessing the following special features: "This meter registers electrically on dials in boat from which used, the *direction* and *velocity*, simultaneously, of any current. Can be used in river, harbor, or ocean currents."



FIG. 605.

*Pitot's Tube** consists in principle of a vertical tube open above, while its lower end, also open, is bent horizontally up-stream; see A in figure. After the oscillations have ceased, the water in the

* A description of Mr. W. M. White's extensive experiments with this instrument will be found in the Journal of the Assoc. of Engineering Societies for Aug. 1901, p. 35 (Vol. xxvii. No. 2).

tube remains stationary with its free surface a height, h', above that of the stream, on account of the continuous impact of the current against the lower end of the column. By the addition of another vertical tube (see B in figure) with the face of its lower (open) end parallel to the current (so that the water-level in it is the same as that of the current), both tubes being provided with stop-cocks, we may, after closing the stop-cocks, lift the apparatus into a boat and read off the height h' at leisure. We may also cause both columns of water to mount, through flexible tubes, into convenient tubes in the boat by putting the upper ends of both tubes in communication with a receiver of rarefied air, and thus watch the oscillations and obtain a more accurate value of h'. As to a theoretical relation between the velocity c, of the current and the height h', we have, [from eq. (7a), p. 804], writing k' for $1 \div \sqrt{k}$, (k' to be found by experiment)

$$c = k'\sqrt{2gh'} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

The form and position of the "static opening," m, may be such as to cause (by "suction") the water level in the corresponding tube to stand lower than that of the outside surface; thus affecting the observed h'. This opening is frequently made in the side of the tube, or of a thin casing. Hence each instrument requires a separate rating, for k'.

Mr. W. M. White's experiments show, in case the "impact tube" is used alone (see A, Fig. 605) that so long as it is a *solid of revolution with its axis exactly on a line of the current*, the form of the "impact opening," or point, is immaterial, and that the value of k' is practically 1.00, (with c ranging from 3 to 15 ft. per sec.); but that when the "static tube" is used (B, Fig. 605) k' may be considerably less than 1.00. (See also the experiments of Profs. Boyd and Judd, *Engineering News*, Mar., 1904, p. 318.)

The Pitot tube is also used for measuring the velocity of water in free jets, and flowing under pressure in pipes (see p. 833). In closed pipes conditions are more complicated than in an open channel, and the instrument itself forms more of an obstruction.

Rating of current meters.—The relation between the velocity c in ft. per second, of the current, and the revolutions per second, n, made by the wheel, is usually taken as $c = c_0 + b.n$, where c_0 is the value of c below which the wheel (through friction) does not turn at all, and b is another constant. The determination of these two constants by experiments is called the "rating" of the meter and is usually accomplished by moving it uniformly through still water; the instrument being supported from the bow of a boat which is towed over the course, or from the overhanging arm of a truck moved along the edge of a canal. The total time t, total distance s, and total number of revolutions N, made by the wheel, are recorded. Then $c = s \div t$ and $n = N \div t$.

If a number of such experiments or "runs" have been made, covering a fair range of velocities, the most probable values of the two constants, c_0 and b, may be found (according to the theory of "least squares") by the following formulæ, where m denotes the number of "runs:"

$$b = \frac{m\Sigma(nc) - \Sigma(n)\Sigma(c)}{m\Sigma(n^2) - [\Sigma(n)]^2}; \quad \text{and} \quad c_0 = \frac{\Sigma(c)\Sigma(n^2) - \Sigma(n)\Sigma(nc)}{m\Sigma(n^2) - [\Sigma(n)]^2}.$$

Example.—In the table below are placed the data of a set of eight test runs for a current meter, over a course of 200 ft. length; and also the other quantities needed for computing b and c_0 from the above formulæ.

No.	N Total Revs.	t = Total time (sec.)	c ft./sec.	n revs./sec.	nc	n^2
1	118	396.25	0.505	0.298	0.150	0.088
2	158	214.75	0.931	0.736	0.685	0.542
3	170	143.75	1.391	1.183	1.645	1.399
4	177	79.00	2.532	2.241	5.672	5.022
5	180	58.00	3.448	3.104	10.702	9.635
6	184	41.50	4.819	4.434	21.367	19.660
7	187	33.00	6.061	5.667	34.343	32.115
8	187	27.50	7.273	6.800	49.455	46.240
Sums.	.....	.....	26.960	24.463	124.019	114.701

Also $[\Sigma(n)]^2 = 598.41$

$$\therefore\ b = \frac{8 \times 124.019 - 24.463 \times 26.960}{8 \times 114.701 - 598.41} = \frac{332.35}{319.21} = 1.042,$$

and $$c_0 = \frac{26.960 \times 114.701 - 24.463 \times 124.019}{8 \times 114.701 - 598.41} = \frac{58.40}{319.2} = 0.183$$

For this meter, therefore, we have $c = 0.183 + 1.042n$ for the interpretation of its indications when in actual service; and it is seen that the wheel makes about one revolution for each foot of current movement.

540. Velocities in Different Parts of a Transverse Section.—The results of velocity-measurements made by many experimenters do not agree in supporting any very definite relation between the greatest surface velocity ($c_{0\ \max.}$) of a transverse

section and the velocities at other points of the section, but establish a few general propositions:

1st. In any vertical line the velocity is a maximum quite near the surface, and diminishes from that point both toward the bottom and toward the surface.

2d. In any transverse horizontal line the velocity is a maximum near the middle of the stream, diminishing toward the banks.

3d. The *mean velocity* $= v$, of the whole transverse section, i.e., the velocity which must be multiplied by the area, F, of the section, to obtain the volume delivered per unit of time,

$$Q = Fv, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

is about 83 per cent of the maximum surface velocity (c_0 max.) observed when the air is still, for fairly smooth channels of regular forms, i.e.

$$v = 0.83 \times (c_0 \text{ max.}); \quad . \quad . \quad . \quad . \quad . \quad (2)$$

but the ratio diminishes with increasing roughness and greater irregularity of shape. According to Wagner we may use the following for rivers, as a means of rough gauging,

$$v = 0.705 \times (c_0 \text{ max.}) + 0.003 \times (c_0 \text{ max.})^2. \quad . \quad (2a)$$

In the survey of the Mississippi River by Humphreys and Abbot, 1861, it was found that the law of variation of the velocity in any given vertical line could be fairly well represented by the ordinates of a parabola (Fig. 607) with its axis horizontal and its vertex at a distance d_1 below the surface according to the following relation, f'' being a number dependent on the force of the wind (from 0 for no wind to 10 for a hurricane):

Fig. 607.

$$d_1 = [0.317 \pm 0.06 f'']d; \quad . \quad . \quad (3)$$

where d is the total depth, and the double sign is to be taken + for an up stream, − for a down-stream, wind. The following relations were also based on the results of the survey:

(putting, for brevity, $B = 1.69 \div \sqrt{d + 1.5}$,) . (4)

$$c = c_{d_1} - \sqrt{Bv}\left(\frac{z - d_1}{d}\right)^2, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

$$c_m = \tfrac{2}{3}c_{d_1} + \tfrac{1}{3}c_d + \frac{d_1}{d}(\tfrac{1}{3}c_0 - \tfrac{1}{3}c_d), \quad . \quad . \quad . \quad . \quad (6)$$

and

$$c_{\frac{1}{2}d} = c_m + \tfrac{1}{12}\sqrt{Bv}. \quad . \quad . \quad . \quad . \quad . \quad (7)$$

(*These equations are not of homogeneous form*, but call for the *foot* and *second* as units.)

In (5), (6), and (7),

c = velocity at any depth z below the surface;
c_m = mean velocity in the vertical curve;
c_{d_1} = max. " " " "
$c_{\frac{1}{2}d}$ = " at mid-depth;
c_d = velocity at bottom;
v = mean velocity of the whole transverse section.

Flow under Ice.—In current observations made for the U. S. Government in 1897 by Assistant Engineer E. E. Haskell, C.E., (now Director of the College of Civil Engineering at Cornell University) on a section of the St. Mary's River (near Sault Ste. Marie, Michigan) when *frozen over*, it was found that in the mean vertical curve of the whole section (mean of 22 curves; involving 220 separate velocity-observations) the maximum velocity was 1.250 (occurring at 0.4 the depth from surface) and the mean, v, 1.087, ft./sec. The velocity at mid-depth, $c_{0.5}$, in this mean curve was 1.232 ft./sec., and the ratio $v \div c_{0.5}$ was 0.882. The *friction due to the ice* was found to be very nearly 31 per cent of that due to the bottom. (See report of the Chief of Engineers of U. S. Army for 1897, Part 6, p. 4100.)

541. Gauging a Stream or River.*—Where the relation (eq. (2), § 540) $v = .83\ (c_{0\ \max.})$ is not considered accurate enough for substitution in $Q = Fv$ to obtain the volume of discharge (or delivery) Q of a stream per time-unit, the transverse section may be divided into a number of subdivisions as in Fig. 608, of widths a_1, a_2, etc., and mean depths d_1, d_2, etc., and the respective mean velocities, c_1, c_2, etc., computed from measurements with current-meters; whence we may write



FIG. 608.

$$Q = a_1d_1c_1 + a_2d_2c_2 + a_3d_3c_3 + \text{etc.} \quad . \quad . \quad . \quad (7)$$

* A valuable book in this connection is *River Discharge*, by J. C. Hoyt and N. C. Grover, (John Wiley & Sons, New York, 1907); as also *Water Supply Paper*, No. 56, of the U. S. Geol. Surv., Washington, D. C.

With a small stream or ditch, however, we may erect a vertical boarding, and allow the water to flow through a rectangular notch or overfall, Fig. 609, and after the head surface has become permanent, measure h_2 (depth of sill below the *level* surface somewhat back of boards), and b (width) and use the formulæ of § 504; see examples in that article.



FIG. 609.

542. Uniform Motion in an Open Channel.—We shall now consider a straight stream of indefinite length in which *the flow is steady*, i.e., a *state of permanency exists*, as distinguished from a freshet or a wave. That is, the flow is steady when the water assumes fixed values of mean velocity v, and sectional area F, on passing a given point of the bed or bank; and the

$$Eq.\ of\ continuity\ .\ .\ Q = Fv = F_0v_0 = F_1v_1 = \text{constant}\ .\ .\ (1)$$

holds good whether those sections are equal or not.

By *uniform motion* is meant that (the section of the bed and banks being of constant size and shape) the slope of the bed, the quantity of water (volume $= Q$) flowing per time-unit, and the extent of the wetted perimeter, are so adjusted to each other that the mean velocity of flow is the same in all transverse sections, and consequently the area and shape of the transverse section is the same at all points; and *the slope of the surface = that of the bed*. We may therefore consider, for simplicity, that we have to deal with a prism of water of indefinite length sliding down an inclined rough bed of constant slope and moving with *uniform* velocity (viz., the mean velocity v common to all the sections); that is, there is *no acceleration*. Let Fig. 610 show, free, a portion of this prism, of length $= l$, and having its bases ⊓ to the bed and surface.

The hydrostatic pressures at the two ends balance each other from the identity of conditions. The only other forces having



FIG. 610.

components parallel to the bed and surface are the *weight* $G = Fl\gamma$ of the prism (where γ = heaviness of water) making an angle $= s$ (= slope) with a normal to the surface, and the *friction* between the water and the bed which is parallel to the surface. The amount of this friction for the prism in question may be expressed as in § 510, viz.:

$$P = fric. = fS\gamma \frac{v^2}{2g} = fwl\gamma \frac{v^2}{2g}, \quad . \quad . \quad . \quad (2)$$

in which $S = wl$ = rubbing surface (area) = wetted perimeter, w, $\times$ length (see § 538), and f an abstract number. Since the mass of water in Fig. 610 is supposed to be in relative equilibrium, we may apply to it the laws of motion of a rigid body, and since the motion is a *uniform translation* (§ 109) the components, parallel to the surface, of all the forces must balance.

$$\therefore G \sin s \text{ must} = P = fric.; \quad \therefore Fl\gamma \frac{h}{l} = fwl\gamma \frac{v^2}{2g};$$

whence

$$h = f \frac{wl}{F} \cdot \frac{v^2}{2g}, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)'$$

or

$$h = f \frac{l}{R} \cdot \frac{v^2}{2g}, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

in which $F \div w$ is called R, the *hydraulic mean depth*, or *hydraulic radius*. (3) is sometimes expressed by saying that

the whole fall, or head, h, is (in uniform motion) absorbed in friction-head. Also, since the slope $s = h \div l$, we have

$$v = \sqrt{\frac{2g}{f}}\sqrt{Rs}; \text{ or, } v = A\sqrt{Rs}, \quad . \quad . \quad . \quad (4)$$

which is of the same form as Chézy's formula in § 519 for a very long straight pipe (the slope s of the actual surface in this case corresponding to the slope along piezometer-summits in that of a closed pipe). In (4) the coefficient $A = \sqrt{2g \div f}$ is not, like f, an abstract number, but its numerical value depends on the system of units employed.*

542a. Experiments on the Flow of Water in Open Channels.— Those of Darcy and Bazin, begun in 1855 and published in 1865 ("Recherches Hydrauliques"), were very carefully conducted with open conduits of a variety of shapes, sizes, slopes, and character of surface. In most of these a uniform flow was secured before the taking of measurements. The velocities ranged between from about 0.5 to 8 or 10 ft. per second, the hydraulic radii from 0.03 to 3.0 ft., with deliveries as high as 182 cub. ft. per second. For example, the following results were obtained in the canals of Marseilles and Craponne, the quantity A being for the foot and second. The sections were nearly all rectangular. See eq. (4) above.

No.	Q. (cub. ft. per sec.)	R. (ft.)	s. abs. numb.	v. (ft. per sec.)	A. (foot and sec.)	Character of the masonry surface.
1	182.73	1.504	.0037	10.26	137.1	Very smooth.
2	143.74	1.774	.00084	5.55	125.	Quite "
3	43.93	.708	.029	11.23	78.4	
4	43.93	.615	.060	13.93	72.5	Hammered stone.
5	43.93	.881	.0121	7.58	73.5	Rather rough.
6	43.93	.835	.014	8.36	77.3	
7	167.68	2.871	.00043	2.54	72.2	Mud and vegetation.

[In Experiment No. 7 the flow had not fully reached a state of permanency.]

Fteley and Stearns's experiments on the Sudbury conduit at Boston, Mass. (*Trans. A. S. C. E.*, '83), from 1878 to 1880, are also valuable. This open channel was of brick masonry with

* Values of this coefficient A, for the English foot and second as units, may be obtained from diagrams in the Appendix of the Author's "Hydraulic Motors." They are based on Kutter's Formula (see next paragraph).

good mortar joints, and about 9 ft. wide; the depths of water ranging from 1.5 to 4.5 ft. With plaster of pure cement on the bed in one of the experiments the high value of $A = 153.6$ was reached (foot and second), with $v = 2.805$ ft. per second, $R = 2.111$ ft., $s = .0001580$, and $Q = 87.17$ cu. ft. per second.

Captain Cunningham, in his experiments on the Ganges Canal at Roorkee, India, in 1881, found A to range from 48 to 130 (foot and second).

Humphreys and Abbot's experiments on the Mississippi River and branches (see § 540), with values of $R =$ from 2 or 3 ft. to 72 ft., furnish values of $A =$ from 53 to 167 (foot and second).

542b. Kutter's Formula.—The experiments upon which Weisbach based his deductions for f, the coefficient of fluid friction, were scanty and on too small a scale to warrant general conclusions. That author considered that f depended only on the velocity, disregarding altogether the degree of roughness of the bed, and gave a table of values in accordance with that view, these values ranging from .0075 for 15 ft. per sec. to .0109 for 0.4 ft. per sec.; but in 1869 Messrs. Kutter and Ganguillet, having a much wider range of experimental data at command, including those of Darcy and Bazin, and those obtained on the Mississippi River, evolved a formula, known as *Kutter's Formula*, for the uniform motion of water in open channels, which is claimed to harmonize in a fairly satisfactory manner the chief results of the best experiments in that direction. They make the coefficient A in eq. (4) (or rather the factor $\frac{1}{\sqrt{f}}$ contained in A) a function of R, s, and also n an abstract number, or *coefficient of roughness*, depending on the nature of the surface of the bed and banks; viz.,

$$\left.\begin{array}{l} v \text{ in} \\ \text{ft.} \\ \text{per} \\ \text{sec.} \end{array}\right\} = \left[\frac{41.6 + \frac{1.811}{n} + \frac{.00281}{s}}{1 + \left(41.6 + \frac{.00281}{s}\right)\frac{n}{\sqrt{R(\text{in feet})}}}\right] \sqrt{R(\text{in ft.}) \times s}, \quad . . (5)$$

which is *Kutter's Formula.** The bracket is the A of (4).

* A book of "*Diagrams of Mean Velocity based on Kutter's Formula*," by the present writer (New York, J. Wiley & Sons, 1902), obviates the necessity of numerical substitution in Kutter's formula for all practical purposes

That is, comparing (5) with (4), we have f a function of n, R, and s, as follows:

$$f = \left[\frac{1 + \left[41.6 + \frac{.00281}{s} \right] \frac{n}{\sqrt{R \text{ in ft.}}}}{5.184 + \frac{.2256}{n} + \frac{.00035}{s}} \right]^2 \quad . \quad . \quad . \quad (6)$$

From (6) it appears that f decreases with an increasing R, as has been also noted in the case of closed pipes (§ 517); that it increases with increasing roughness of surface; and that it is somewhat dependent on the slope. Values of n may be taken as follows:

.009 for well planed timber evenly laid;
.010; plaster in pure cement; glazed surfaces in good order;
.011; plaster in cement with one-third sand; iron and cement pipes in good order and well laid;
.012; unplaned timber, evenly laid and continuous.
.013; ashlar masonry and well laid brick work;* also the above categories when not in good condition nor well laid;
.015; "canvas lining on frames"; brick-work of rough surface; foul iron pipes; badly jointed cement pipes;
.017; rubble in plaster or cement in good order; inferior brick-work; tuberculated iron pipes; very fine and rammed gravel;
.020; canals in very firm gravel; rubble in inferior condition; earth of even surface;
.025; canals and rivers in perfect order and regimen and perfectly free from stones and weeds;†
.030; canals and rivers in earth in moderately good order and regimen, having stones and weeds occasionally;
.035; canals and rivers in bad order and regimen, overgrown with vegetation, and strewn with stones and detritus.

Kutter's formula finds wide acceptance among engineers. To save computation, values of A (for the *English foot and second*) may be taken from the following table. The slopes .010, .001, .0004, .0002, and .00005 are indicated as 10, 1, .4, .2, and .05, ($=1000s$); and may be read "*fall of* 10 *ft. per thousand ft.*," etc. Ordinary rules of interpolation apply; but *it must be remembered* that *for any slope greater than* .010 *the value of A is practically the same as for that slope* ($s = .010$; or 10 ft. per thousand ft.)

* For ordinary brick sewers Mr. R. F. Hartford claims that $n = .014$ gives good results. See Jour. Eng. Societies for '84–'85, p. 220.

† See *Engineering News* for Feb. 1, 1906, p. 122, for experiments with an open channel; giving $n = 0.025$.

TABLE * OF KUTTER'S COEFFICIENT A. [See eqs. (4) and (5).]

R in ft.	1000s	Values of n									
		.009	.010	.011	.012	.013	.015	.017	.020	.025	.030
0.2	10	129	114	100	90	81	67	57	46	33	27
	1	128	113	99	88	80	66	56	45	33	27
	.4	125	110	97	87	78	64	54	43	32	26
	.2	120	105	93	83	74	61	52	42	30	25
	.05	100	87	78	68	62	52	43	35	26	22
0.3	10	143	126	111	99	90	76	64	52	39	32
	1	142	124	110	98	89	75	63	51	38	31
	.4	138	121	107	96	87	73	62	50	37	30
	.2	133	116	103	92	83	69	59	48	36	28
	.05	113	98	88	78	71	58	51	41	31	25
0.6	10	163	144	129	116	105	89	77	63	49	39
	1	162	142	128	115	104	88	76	62	48	38
	.4	158	140	125	113	102	87	75	61	47	37
	.2	154	137	123	110	100	84	73	59	45	36
	.05	139	122	110	98	89	76	65	53	41	33
1.0	10	176	156	141	128	117	99	86	72	56	45
	1	175	155	140	127	116	99	86	71	56	45
	.4	173	154	138	125	115	98	84	70	55	44
	.2	170	151	136	123	112	96	83	68	53	43
	.05	157	140	126	113	104	89	77	63	48	39
2.0	10	192	172	155	142	130	113	99	83	66	54
	1	190	172	155	142	130	112	98	83	66	54
	.4	189	170	154	141	129	111	97	83	65	53
	.2	188	169	153	139	128	110	96	82	64	53
	.05	183	164	148	135	124	107	93	79	62	51
4.0	10	204	184	167	153	142	123	109	93	75	63
	1	204	184	168	153	142	123	109	93	75	63
	.4	204	184	168	154	143	124	110	94	76	63
	.2	205	185	169	154	143	124	110	94	76	64
	.05	208	187	171	157	145	126	112	95	77	64
6.0	10	210	190	173	159	148	129	115	98	81	67
	1	211	190	174	160	148	129	115	98	82	67
	.4	212	192	175	161	149	130	116	99	82	68
	.2	213	193	176	162	151	132	117	100	83	69
	.05	220	200	183	168	156	138	122	105	86	72
8.0	10	215	194	178	163	151	133	118	102	83	71
	1	216	195	178	164	152	133	119	103	84	72
	.4	217	196	179	165	153	134	120	104	85	73
	.2	218	198	181	167	155	136	122	105	86	74
	.05	228	206	190	175	164	145	129	112	92	78
12.	10	220	198	183	168	156	137	123	107	88	76
	1	220	199	183	169	157	138	124	108	89	77
	.4	222	201	185	171	158	139	126	109	90	78
	.2	225	204	188	173	161	143	128	111	92	80
	.05	240	217	200	185	174	154	139	121	100	86

* See also foot-notes, pp. 758 and 759.

EXAMPLE 1.—A canal 1000 ft. long of the trapezoidal section in Fig. 611 is required to deliver 300 cubic ft. of water per second with the water 8 ft. deep at all sections (i.e., with uniform motion), the slope of the bank being such that for a depth of 8 ft. the width of the water surface (or length of air-profile) will be 20 ft.; and the coefficient for roughness being $n = .020$. What is the necessary slope to be given to the bed (slope of bed = that of surface, here) (ft., lb., sec.)?



FIG. 611.

The mean velocity

$$v = Q \div F = 300 \div \tfrac{1}{2}(20 + 8)\,8 = 2.67 \text{ ft. per sec.}$$

[So that the surface velocity of mid-channel in any section would probably be $(c_{0\,\max.}) = v \div 0.83 = 3.21$ ft. per sec. (eq. (2), § 540).]

The wetted perimeter

$$w = 8 + 2\sqrt{8^2 + 6^2} = 28 \text{ ft.},$$

and therefore the mean hydraulic depth

$$= R = F \div w = 112 \div 28 = 4 \text{ ft.}$$

Although the slope is unknown we see from the table that A must be about 94. From eq. (4), $s = v^2 \div (A^2 R)$; i.e.,

$$s = \frac{(2.67)^2}{(94)^2 \times 4} = 0.000201;$$

or 0.2 *ft. fall per thousand ft. length.* This result needs no revision, since the table gives $A = 94$ for $s = 0.0002$.

EXAMPLE 2.—Find the radius, r, of an open channel of semi-circular section (diameter horizontal) running full, which shall carry, with uniform motion, 80 cub. ft. of water per sec.; having a fall of 0.5 ft. in each 1000 ft. of length and lined with well-laid brickwork ($n = .013$).

Here we find $R = (\frac{1}{2}\pi r^2) \div (\pi r) = \frac{1}{2}r$, and $v, = Q \div F$, $= 80 \div (\frac{1}{2}\pi r^2) = (50.92) \div r^2$; substituting which in $v = A\sqrt{Rs}$, we have, after squaring,

$$r^5 = 10{,}372{,}000 \div A^2 \quad . \quad . \quad . \quad . \quad . \quad . \quad (7)$$

Now, A (which depends on R, $=\frac{1}{2}r$, but in such a complicated way that it is *best to solve by trial*) probably lies between 50 and 150. Take the round number, 100, for the first trial. With $A=100$, $r^5=1{,}037.2$; or $r=4.01$, and $R=2.0$ ft.

For $R=2.0$ ft. and slope of .0005, with $n=.013$, we find from the table, $A=129$; and hence, for a second approximation, may write, from eq. (7), $r^5=10{,}372{,}000\div(129)^2$, which $=623.0$; i.e., $r=3.62$, and $R=1.81$, ft. With this second R the table shows 126 for A, which in eq. (7) gives, finally, $r=3.66$ ft.; and this is sufficiently close, since further revision produces no practical change.

EXAMPLE 3.—If the bed of a creek falls 20 inches every 1500 ft. of length, what volume of water must be flowing to maintain a uniform mean depth of $4\frac{1}{2}$ ft., the corresponding surface-width being 40 ft., and wetted perimeter 46 ft.? The bed is "in moderately good order and regimen;" use Kutter's Formula, putting $n = 0.030$ (ft. and sec.).

First we have

$$\sqrt{Rs}=\sqrt{(40\times 4\tfrac{1}{2})\div\left(46\times\frac{1500}{\frac{20}{12}}\right)}=.066,$$

while $\sqrt{R\,(\text{ft.})}=1.98$, and the slope $=s=\frac{20}{12}\div 1500=.00111$; hence

$$v=\frac{\left[41.6+\dfrac{1.811}{.030}+\dfrac{.00281}{.00111}\right]\times 0.066}{1+\left[41.6+\dfrac{.00281}{.00111}\right]\dfrac{0.030}{1.98}}=\frac{104.43\times .066}{1.6685},$$

or

$$v=4.13 \text{ ft. per sec.}$$

Hence, also,

$$Q=Fv=40\times 4\tfrac{1}{2}\times 4.13=743.4 \text{ cub. ft. per sec.}$$

Or, *using the table* on p. 761, we find (for $R=3.92$ ft., $s=.00111$, and $n=.030$) the value 63 for A; whence v, $=A\sqrt{Rs}$, $=4.15$ ft./sec.; and this, of course, is a much more rapid procedure than the above.

EXAMPLE 3.—The desired transverse water-section of a canal is given in Fig. 612. The slope is to be 3 ft. in 1600; i.e., $s = 3 \div 1600$; or, for $l = 1600$ ft., $h = 3$ ft. What must be the velocity (mean) of each section, for a *uniform motion;* the corresponding volume delivered per sec., $Q, = Fv, = ?$; assuming that the character of the surface warrants the value $n = .030$?

FIG. 612.

Knowing the slope $s, = 3 \div 1600$; and the hydraulic radius $R, = F \div w, = 79.28$ sq. ft. $\div$ 24.67 ft., $= 3.215$ feet; with $n = .030$ we substitute directly in eq. (5), obtaining $v = 4.67$ ft. per sec.; whence $Q = Fv = 370$ cub. ft. per sec.

More briefly, we find by interpolation in the table of p. 761, $A = 59.4$; and hence, by eq. (4), $v = 4.61$ ft./sec. (By the use of the diagrams mentioned at foot of p. 759 the value of v is obtained by simple inspection of a diagram; R and s being the "arguments.")

543. Hydraulic Mean Depth for a Minimum Frictional Resistance.—We note, from eq. (3), § 542, that if an open channel of given length l and sectional area F is to deliver a given volume, Q, per time-unit with uniform motion, so that the common mean velocity v of all sections ($= Q \div F$) is also a given quantity, the necessary fall $= h$, or slope $s = h \div l$, is seen to be inversely proportional to R, the hydraulic mean depth of the section, $= (F \div w)$, = sectional area $\div$ wetted perimeter.

For h to be as small as possible, we may design the form of transverse section, so as to make R as large as possible; i.e., to make the wetted perimeter a minimum for a given F; for in this way a minimum of frictional contact, or area of rubbing surface, is obtained for a prism of water of given sectional area F and given length l.

In a closed pipe running full the wetted perimeter is the whole perimeter; and if the given sectional area is shaped in the form of a *circle*, the wetted perimeter, $= w$, is a minimum (and R a maximum). If the full pipe must have a polygonal shape of n sides, then the *regular* polygon of n sides will provide a minimum w.

Whence it follows that if the pipe or channel is running

half full, and thus becomes an *open channel*, the semicircle, of all curvilinear water profiles, gives a minimum w. Also, of all trapezoidal profiles with banks at 60° with the horizontal the half of a regular hexagon gives a minimum w. Among all rectangular sections the half square gives a minimum w; and of all half octagons the half of a regular octagon gives a minimum w (and max. R) for a given F. See Fig. 613 for all these.



FIG. 613.

The egg-shaped outline, Fig. 614, small end down, is frequently given to sewers in which it is important that the different velocities of the water at different stages (depths) of flow (depending on the volume of liquid passing per unit-time) should not vary widely from each other. The lower portion ABC, providing for the lowest stage of flow AB, is nearly semicircular, and thus induces a velocity of flow (the slope being constant at all stages) which does not differ extremely from that occurring when the water flows at its highest stage DE, although this latter velocity is the greater; the reason being that ABC from its advantageous form has a hydraulic radius, R, larger in proportion to its sectional area, F, than DCE.



FIG. 614.

That is, $F \div w$ for ABC is more nearly equal to $F \div w$ for DEC than if DEC were a semicircle, and the velocity at the lowest stage may still be sufficiently great to prevent the deposit of sediment. See § 575.

544. Trapezoid of Fixed Side-slope.—For large artificial watercourses and canals the trapezoid, or three-sided water-profile (symmetrical), is customary, and the inclination of the bank,

or angle θ with the horizontal, Fig. 615, is often determined by the nature of the material composing it, to guard against washouts, caving in, etc. We are therefore concerned with the following problem: *Given the area, F, of the transverse section, and the angle θ, required the value of the depth x* (or of upper width z, or of lower width y, both of which are functions of x) *to make the hydraulic mean depth, $R = F \div w$, a maximum,* or $w \div F$ *a minimum.* F is constant.



FIG. 615.

From the figure we have

$$w = \overline{AB} + 2\overline{BC} = y + 2x \operatorname{cosec.} \theta, \quad . \quad . \quad . \quad (1)$$

and

$$F = yx + x^2 \cot. \theta;$$

whence

$$y = \frac{1}{x} . (F - x^2 \cot. \theta), \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

substituting which in (1) and dividing by F, noting that $2 \operatorname{cosec.} \theta - \cot. \theta = \dfrac{2 - \cos \theta}{\sin \theta}$, we have

$$\frac{w}{F} = \frac{1}{R} = \frac{1}{x} + \frac{2 - \cos \theta}{F \sin \theta} . x. \quad . \quad . \quad . \quad . \quad (3)$$

For a minimum w we put

$$\frac{d\left(\frac{w}{F}\right)}{dx} = 0; \quad \text{i.e.,} \quad -\frac{1}{x^2} + \frac{2 - \cos \theta}{F \sin \theta} = 0;$$

$$\therefore \ x (\text{for max. or min. } w) = \pm \sqrt{\frac{F \sin \theta}{2 - \cos \theta}}.$$

The + sign makes the second derivative positive, and hence for a min. w or max. R we have

$$x \text{ (call it } x') = x' = \frac{\sqrt{F \sin \theta}}{\sqrt{2 - \cos \theta}}, \quad . \quad . \quad . \quad (4)$$

while the corresponding values for the other dimensions are

$$y' = \frac{F}{x'} - x' \cot.\theta \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

and

$$z' = y' + 2x' \cot.\theta = \frac{F}{x'} + x' \cot.\theta. \quad . \quad . \quad . \quad (6)$$

For the corresponding hydraulic mean depth R' [see (3)], i.e., the max. R, we have

$$\frac{1}{R'} = \frac{1}{x'} + \frac{2 - \cos\theta}{F \sin\theta} x' = \frac{2}{x'}; \quad . \quad . \quad . \quad . \quad (7)$$

$$\therefore \; R' = \tfrac{1}{2}x' = \frac{1}{2}\sqrt{\frac{F \sin\theta}{2 - \cos\theta}}. \quad . \quad . \quad . \quad . \quad (8)$$

Equations (4), (5), . . . (8) hold good, then, for the trapezoidal section of least frictional resistance for a given angle θ.

(It may be proved that the two sloping sides and the bottom, of this trapezoid, *are all tangent to the semicircle, of radius* $= x'$, *described with its center in the middle of the upper base DC*; see p. 217, Hydraulic Motors.)

The following values of the angle θ should not be exceeded (Unwin):

For banks of planks or masonry,	90°	; or 0	horiz. to 1	vert.
" " " masonry or brick walls,	63° 20′	; or 0.5	" to 1	"
" " " stone pitching,	45°	; or 1	" to 1	"
" " " loose earth	23° 60′	; or 2	" to 1	"
	21° 48′	; or 2.5	" to 1	"
	18° 20′	; or 3	" to 1	"

Example.—Required the dimensions of the trapezoidal section of *minimum frictional resistance* for $\theta = 45°$, which with $h = 6$ in. fall in every 1200 feet, and $n = .025$, is to deliver $Q = 360$ cub. ft. of water per sec., with *uniform motion.*

Here we have $s = \frac{1}{2} \div 1200 = .000416$; $Q = 360$; $\theta = 45°$; and $n = .025$; and must find x', y', and z'. For simplicity, let F_0 denote $\frac{1}{100}F$; then, from $Q = Fv$, we have

$$F_0 v = 3.60; \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (9)$$

and from eq. (8), $R'^2 = 13.70 F_0$; . . . . . (10)

while $v = A\sqrt{R's}$ gives $v^4 = A^4 s^2 R'^2$; i.e.,

$$v^4 = 0.0000001725 A^4 R'^2. \quad . \quad . \quad . \quad . \quad (11)$$

Eliminating R' and F from (11), by aid of (9) and (10), we find $F_0^5 = 71{,}000{,}000 \div A^4$. . . . . (12)

We must now solve by trial, since A depends on the unknown R'. With the round number 100 for A, for first trial, we obtain $F_0^5 = 0.710$, i.e., $F_0 = 0.9338$ sq. ft.; for which [see eq. (10)], R' would be $= \sqrt{13.7 \times 0.9338} = 3.57$ ft. The table on p. 761 gives (for $R' = 3.57$ ft., $n = .025$, and $s = .000416$) the value 74 for A, which on being placed in eq. (12) furnishes a second approximation for F_0, viz.: $F_0 = 1.188$ sq. ft.; and from this, again, we find $R' = 4.03$ ft. from eq. (10), and a value of 76 for A from the table. With 76 for A, in eq. (12), we have finally (without need of further revision) $R' = 4.00$ ft.; and hence $x' = 8$ ft., $y' = 6.54$, and $z' = 22.54$ ft. [eqs. (5) and (6)]. [By the use of diagrams (see foot p. 759) a much briefer solution is possible.]

545. Variable Motion.—If a steady flow of water of a delivery $Q, = Fv, =$ constant, takes place in a straight open channel the slope of whose bed has not the proper value to maintain a "*uniform motion*," then "*variable motion*" ensues (the flow is still steady, however); i.e., although the mean velocity in any one transverse section remains fixed (with lapse of time), this velocity has different values for different sections; but as the eq. of continuity,

$$Q = Fv = F_1 v_1 = F_2 v_2, \text{ etc.},$$

still holds (since the flow is steady), the different sections have different areas. If, Fig. 616, a stream of water flows down an inclined trough without friction, the relation between the velocities v_0 and v_1 at any two sections 0 and 1 will be the same as for a material point sliding down a guide without friction (see § 79, latter part), viz.:



FIG. 616.

$$\frac{v_1^2}{2g} = \frac{v_0^2}{2g} + h, \quad \ldots \ldots \ldots \quad (1)$$

an equation of heads (really a case of Bernoulli's Theorem, § 492). But, considering friction on the bed, we must subtract the *mean friction-head* $f \frac{l}{R} \cdot \frac{v_m^2}{2g}$ [see eqs. (3) and (3'), § 542] lost between 0 and 1; this friction-head may also be written thus: $f \frac{l w_m}{F_m} \frac{v_m^2}{2g}$; and therefore eq. (1) becomes

$$\frac{v_1^2}{2g} = \frac{v_0^2}{2g} + h - \frac{f w_m}{F_m} l \cdot \frac{v_m^2}{2g}, \quad . \quad . \quad . \quad . \quad (2)$$

which is the formula for *variable motion;* and in it l is the length of the section considered, which should be taken short enough to consider the surface straight between the end-sections, and the latter should differ but slightly in area. The subscript m may be taken as referring to the section midway between the ends, so that $v_m^2 = \frac{1}{2}(v_0^2 + v_1^2)$. The wetted perimeter $w_m = \frac{1}{2}(w_0 + w_1)$, and $F_m = \frac{1}{2}(F_0 + F_1)$. Hence eq. (2) becomes

$$h = \frac{v_1^2}{2g} - \frac{v_0^2}{2g} + \frac{\frac{1}{2} f (w_0 + w_1) l}{F_0 + F_1} \cdot \frac{v_0^2 + v_1^2}{2g}; \quad . \quad . \quad (3)$$

and again, by putting $v_0 = Q \div F_0$, $v_1 = Q \div F_1$, we may write

$$h = \left[\frac{1}{F_1^2} - \frac{1}{F_0^2} + \frac{1}{2} \cdot \frac{f l (w_0 + w_1)}{F_0 + F_1} \left(\frac{1}{F_0^2} + \frac{1}{F_1^2} \right) \right] \frac{Q^2}{2g}; \quad . \quad (4)$$

whence

$$Q = \frac{\sqrt{2gh}}{\sqrt{\frac{1}{F_1^2} - \frac{1}{F_0^2} + \frac{1}{2} \cdot \frac{f l (w_0 + w_1)}{F_0 + F_1} \cdot \left[\frac{1}{F_0^2} + \frac{1}{F_1^2} \right]}}. \quad (5)$$

From eq. (4), having given the desired shapes, areas, etc., of the end-sections and the volume of water, Q, to be carried per unit of time, we may compute the necessary fall, h, of the surface, in length $= l$; while from eq. (5), having observed in an actual water-course the values of the sectional areas F_0 and F_1, the wetted perimeters w_0 and w_1, the length, $= l$, of the por-

tion considered, we may calculate Q and thus *gauge* the stream approximately, without making any velocity measurements.

As to the value of f, we compute it from eq. (6), § 542b, using for R a mean between the values of the hydraulic radii of the end-sections.

546. Bends in an Open Channel.—According to Humphreys and Abbot's researches on the Mississippi River the loss of head due to a bend may be put

$$h_r = \frac{v^2}{536}\frac{6\delta}{\pi}, \quad \ldots\ldots\ldots \quad (1)$$

in which v must be in *ft. per sec.*, and δ, the angle ABC, Fig. 617, must be in π-measure, i.e. in radians. The section F must be greater than 100 sq. ft., and the slope s less than .0008. v is the mean velocity of the water. Hence if a bend occurred in a portion of a stream of length l, eq. (3) of § 542 becomes



FIG. 617.

$$h = \frac{fl}{R}\frac{v^2}{2g} + \frac{6}{536}\frac{v^2\delta}{\pi} \text{ . . [ft. and sec.], . (2)}$$

while eq. (2) of § 545 for variable motion would then become

$$\frac{v_1^2}{2g} = \frac{v_0^2}{2g} + h - \frac{f w_m l}{F_m}\frac{v_m^2}{2g} - \frac{6}{536}\frac{v^2\delta}{\pi} \text{ . . (ft. and sec.). . (3)}$$

(v and δ as above.) (For "radian" see p. 544.)

547. Equations for Variable Motion, introducing the Depths.—Fig. 618. The slope of the bed being sin α (or simply α, π meas.), while that of the surface is different, viz.,

$$\sin\beta = s = h \div l,$$

we may write

$$h = d_0 + l\sin\alpha - d_1,$$



FIG. 618.

in which d_0 and d_1 are the depths at the end-sections of the portion considered (steady flow with variable motion). With these substitutions in eq. (4), § 545, we have, solving for l,

$$l = \frac{d_0 - d_1 - \left(\frac{1}{F_1^2} - \frac{1}{F_0^2}\right)\frac{Q^2}{2g}}{\frac{fw_m}{F_0 + F_1}\left(\frac{1}{F_0^2} + \frac{1}{F_1^2}\right)\frac{Q^2}{2g} - \sin\alpha}. \quad . \quad . \quad . \quad (6)$$

From which, knowing the slope of the bed and the shape and size of the end-sections, also the discharge Q, we may compute the length or distance, l, between two sections whose depths differ by an assigned amount $(d_0 - d_1)$. But we cannot compute the change of depth for an assigned length l from (6). However, if the *width* b of the stream is *constant*, and the same at all depths; i.e., if all sections are rectangles having a common width; eq. (6) may be much simplified by introducing some approximations, as follows: We may put

$$\left(\frac{1}{F_1^2} - \frac{1}{F_0^2}\right)\frac{Q^2}{2g} = \frac{F_0^2 - F_1^2}{F_1^2 F_0^2}\cdot\frac{Q^2}{2g} = \frac{(F_0 - F_1)(F_0 + F_1)}{F_1^2}\cdot\frac{v_0^2}{2g}$$

$$= \frac{(d_0 - d_1)(d_0 + d_1)}{d_1^2}\cdot\frac{v_0^2}{2g}, \text{ which approx.} = \frac{2(d_0 - d_1)}{d_0}\cdot\frac{v_0^2}{2g};$$

and, similarly,

$$\frac{w_m}{F_0 + F_1}\left(\frac{1}{F_0^2} + \frac{1}{F_1^2}\right)\frac{Q^2}{2g} = \frac{w_m(F_0^2 + F_1^2}{(F_0 + F_1)F_1^2}\cdot\frac{v_0^2}{2g}$$

$$\text{which approx.} = \frac{w_m}{d_0 b}\frac{v_0^2}{2g}.$$

Hence by substitution in eq. (6) we have

$$l = \frac{(d_0 - d_1)\left[1 - \frac{2}{d_0}\cdot\frac{v_0^2}{2g}\right]}{\frac{fw_m}{d_0 b}\frac{v_0^2}{2g} - \sin\alpha}. \quad . \quad . \quad . \quad . \quad (7)$$

547a. Backwater.*—Let us suppose that a steady flow has been proceeding with uniform motion (i.e., the surface parallel

* The subject of backwater is more fully treated in the author's "*Hydraulic Motors*," pp. 226–239.

to the bed) in an open channel of indefinite extent, and that a vertical wall is now set up across the stream. The water rises and flows over the edge of the wall, or weir, and after a time a steady flow is again established. The depth, y_0, of the water close to the weir on the up-stream side is greater than d_0, the original depth. We now have "variable motion" above the weir, and at any distance x up-stream from the weir the new depth y is greater than d_0. This increase of depth is called backwater, and, though decreasing up-stream, may be perceptible several miles above the weir. Let s be the slope of the original uniform motion (and also of present bed), and v the velocity of the original uniform motion, and let $k = \frac{v^2}{2g}$. Then, if the section of the stream is a shallow rectangle of constant width, we have the following relation (Rankine):

$$x = \frac{1}{s}\left[y_0 - y + (d_0 - 2k)(\phi - \phi_0)\right], \quad . \quad . \quad . \quad (1)$$

where ϕ is a function of $\frac{y}{d_0}$, as per following table:

For $\frac{y}{d_0} = 1.0$	1.10	1.20	1.30	1.40	1.50	1.60	1.70
$\phi = \infty$	.680	.480	.376	.304	.255	.218	.189
For $\frac{y}{d_0} = 1.80$	1.90	2.00	2.20	2.40	2.60	2.80	3.0
$\phi = .166$	.147	.132	.107	.089	.076	.065	.056

ϕ_0 is found from $\frac{y_0}{d_0}$, precisely as ϕ from $\frac{y}{d_0}$, by use of the table. With this table and eq. (1), therefore, we can find x, the distance ("amplitude of backwater") from the weir of the point where any assigned depth y (or "height of backwater," $y - d_0$) will be found.

For example, Prof. Bowser cites the case from D'Aubuisson's Hydraulics of the river Weser in Germany, where the erection of a weir increased the depth at the weir from 2.5 ft. to 10 ft., the flow having been originally "uniform" for 10 miles. Three miles above the dam the *increase* $(y - d_0)$ of depth was 1.25 ft., and even at four miles it was 0 75 ft.

CHAPTER VIII.

KINETICS OF GASEOUS FLUIDS.

548. Steady Flow of a Gas.—[N.B. The student should now review § 492 up to eq. (5).] The differential equation from which Bernoulli's Theorem was derived for any liquid, *without friction*, was [eq. (5), § 492]

$$\frac{1}{g}vdv + dz + \frac{1}{\gamma}dp = 0, \quad . \quad . \quad . \quad . \quad . \quad (A)$$

and is equally applicable to the steady flow of a gaseous fluid, but with this difference in subsequent work, that the heaviness, γ (§ 7), of the gas passing different sections of the pipe or stream-line is, or may be, different (though always the same at a given point or section, since the flow is steady). For the present we neglect friction and consider the flow from a large receiver, where the great body of the gas is practically at rest, through an orifice in a thin plate, or a short nozzle with a rounded entrance.

In the steady flow of a gas, since γ is different at different points, the *equation of continuity* takes the form

$$\textit{Flow of weight per time-unit} = F_1 v_1 \gamma_1 = F_2 v_2 \gamma_2 = \text{etc.}; \quad . \quad (a)$$

i.e., the *weight* of gas passing any section, of area F, per unit of time, is the same as for any other section, or $Fv\gamma = \text{constant}$, γ being the heaviness at the section, and v the velocity.

549. Flow through an Orifice—Remarks.—In Fig. 619 we have a large rigid receiver containing gas at some tension, p_n higher than that, p_m, of the (still) outside air (or gas), and at some absolute temperature T_n, and of some heaviness γ_n; that is, in a *state n*. The small orifice of area F being opened, the gas begins to escape, and if the receiver is very large, or if the supply is continually kept up (by a blowing-engine, e.g.), after

a very short time the flow becomes steady. Let nm represent any stream-line (§ 495) of the flow. According to the ideal subdivision of this stream-line into laminæ of equal mass or weight (not equal volume, necessarily) in establishing eq. (A) for any one lamina, each lamina in the lapse of time dt moves into the position just vacated by the lamina next in front, and *assumes precisely the same velocity, pressure, and volume* (*and therefore heaviness*) *as that front one had at the beginning of the* dt. In its progress toward the orifice it expands in volume, its tension diminishes, while its velocity, insensible at n, is gradually accelerated on account of the pressure from behind always being greater than that in front, until at m, in the "*throat*" of the jet, the velocity has become v_m, the pressure (i.e., tension) has fallen to a value p_m, and the heaviness has changed to γ_m. The temperature T_m (absolute) is less than T_n, since the expansion has been rapid, *and does not depend on the temperature of the outside air or gas into which efflux takes place*, though, of course, after the effluent gas is once free from the orifice it may change its temperature in time.



FIG. 619.

We assume the pressure p_m (in throat of jet) to be equal to that of the outside medium (as was done with flow of water), so long as that outside tension is greater than .527 p_n; but if it is less than .527 p_n and is even zero (a vacuum), experiment seems to show that p_m remains equal to 0.527 of the interior tension p_n: probably on account of the expansion of the effluent gas beyond the throat, Fig. 620, so that although the tension in the outer edge, at a, of the jet is equal to that of the outside medium, the tension at m is greater because of the centripetal and centrifugal forces developed in the curved filaments between a and m. (See § 553.)



FIG. 620.

550. Flow through an Orifice; Heaviness assumed Constant during Flow. The Water Formula.—If the inner tension p_n ex-

ceeds the outer, p_m, but slightly, we may assume that, like water, the gas remains of the same heaviness during flow. Then, for the simultaneous advance made by all the laminæ of a stream-line, Fig. 619, in the time dt, we may conceive an equation like eq. (A) written out for each lamina between n and m, and corresponding terms added; i.e.,

$$(For\ orifices)\ \ldots\ \frac{1}{g}\int_n^m v\,dv + \int_n^m dz + \int_n^m \frac{dp}{\gamma} = 0. \quad (E)$$

In general, γ is different in the different laminæ, but in the present case it is assumed to be the same in all; hence, with m as datum level and h = vertical distance from n to m, we have, from eq. (B),

$$\frac{v_m^2}{2g} - \frac{v_n^2}{2g} + 0 - h + \frac{p_m}{\gamma} - \frac{p_n}{\gamma} = 0. \quad \ldots \quad (1)$$

But we may put $v_n = 0$; while h, even if several feet, is small compared with $\frac{p_n}{\gamma} - \frac{p_m}{\gamma}$. E.g., with $p_m = 15$ lbs. per sq. in. and $p_n = 16$ lbs. per sq. in., we have for atmospheric air at freezing temperature, with $\gamma = (16 \div 14.7) \times .0807 = .0880$ lbs./cub. ft.,

$$\frac{p_n}{\gamma} - \frac{p_m}{\gamma} = \frac{16 \times 144}{.0880} - \frac{15 \times 144}{.0880} = 1636 \text{ ft.}$$

Hence, putting $v_n = 0$ and $h = 0$ in eq. (1), we have

$$\frac{v_m^2}{2g} = \frac{p_n - p_m}{\gamma_n} \quad \ldots \quad \left\{ \begin{array}{l} Water\ formula;\ for\ small \\ difference\ of\ pressures,\ only. \end{array} \right\} \quad \ldots \quad (2)$$

The interior absolute temperature T_n being known, the γ_n (interior heaviness) may be obtained from $\gamma_n = p_n \gamma_0 T_0 \div T_n p_0$ (§ 472), and the volume of flow per unit of time then obtained (first solving (2) for v_m) is

$$Q_m = F_m v_m, \quad \ldots \quad (3)$$

where F_m is the sectional area of the jet at m. If the mouth-piece or orifice has well-rounded interior edges, as in Fig. 541,

its sectional area F may be taken as the area F_m. But if it is an orifice in "thin plate," putting the coefficient of contraction $= C = 0.60$, we have

$$F_m = CF = 0.60\ F; \quad \text{and} \quad Q_m = 0.60\ Fv_m. \quad . \quad (4)$$

This volume, Q_m, is that occupied by the flow per time-unit when in *state* m, and we have assumed that $\gamma_m = \gamma_n$; hence the *weight of flow* per time-unit is

$$G = Q_m\gamma_m = F_m v_m \gamma_m = F_m v_m \gamma_n. \quad . \quad . \quad . \quad (5)$$

Example.—In the testing of a blowing-engine it is found capable of maintaining a pressure of 16 lbs. per sq. inch in a large receiver, from whose side a blast is steadily escaping through a "thin plate" orifice (circular) having an area $F = 4$ sq. inches. The interior temperature is 30° Cent. and the outside tension 15 lbs. per sq. in.

Required the discharge of air per second, both volume and weight. The data are: $p_n = 18$ lbs. per sq. in., $T_n = 303°$ Abs. Cent., $F = 4$ sq. inches, and $p_m = 15$ lbs. per sq. in. Use ft.-lb.-sec. system.

First, the heaviness in the receiver is

$$\gamma_n = \frac{p_n}{p_0} \cdot \frac{T_0}{T_n} \gamma_0 = \frac{16}{14.7} \cdot \frac{273}{303} \times .0807 = .079 \text{ lbs. per cub. ft.}$$

Then, from eq. (2),

$$v_m = \sqrt{2g\frac{p_n - p_m}{\gamma_n}} = \sqrt{\frac{2 \times 32.2[144 \times 16 - 144 \times 15]}{0.079}} = \left\{ \begin{matrix} 342.6 \\ \text{feet} \\ \text{per sec.} \end{matrix} \right.$$

(97 per cent of this would be more correct on account of friction.)

$$\therefore\ Q_m = F_m v_m = .6 F v_m = \tfrac{6}{10} \cdot \tfrac{4}{144} \times 342.6 = 5.71 \text{ cub. ft. per sec.}$$

at a tension of 15 lbs. per sq. in., and of heaviness (by hypothesis) $= .079$ lbs. per cub. ft. Hence weight

$$= G = 5.71 \times .079 = 0.451 \text{ lbs. per sec.}$$

The theoretical *power* of the air-compressor or blowing-engine to maintain this steady flow can be computed as in Example 3, § 483.

551. Flow through an Orifice on the Basis of Mariotte's Law; or Isothermal Efflux.—Since in reality the gas expands during flow through an orifice, and hence changes its heaviness (Fig. 619), we approximate more nearly to the truth in assuming this change of density to follow Mariotte's law, i.e., that the *heaviness varies directly as the pressure*, and thus imply that the *temperature remains unchanged during the flow.* We again integrate the terms of eq. (*B*), but take care to note that, *now*, γ is variable (i.e., different in different laminæ at the same instant), and hence express it in terms of the variable p (from eq. (2), § 475), thus:

$$\gamma = (\gamma_n \div p_n)p.$$

Therefore the term $\int_n^m \frac{dp}{\gamma}$ of eq. (*B*) becomes

$$\frac{p_n}{\gamma_n}\int_n^m \frac{dp}{p} = -\frac{p_n}{\gamma_n}\log_e \frac{p_n}{p_m}, \quad \ldots \quad (1)$$

and, integrating all the terms of eq. (*B*), neglecting h, and calling v_n zero, we have

$$\frac{v_m^2}{2g} = \frac{p_n}{\gamma_n}\log_e \frac{p_n}{p_m} \quad \ldots \quad \left\{\begin{array}{l}\textit{efflux by Mariotte's}\\ \textit{Law through orifice}\end{array}\right\} \ldots \quad (2)$$

As before, $\gamma_n = \frac{T_0}{T_n}\cdot\frac{p_n}{p_0}\gamma_0$, and the flow of volume per time-unit at m is

$$Q_m = F_m v_m; \quad \ldots \quad (3)$$

while if the orifice is in thin plate, F_m may be put $= .60\ F$, and the

$$\textit{weight of the flow per time-unit} = G = F_m v_m \gamma_m. \quad (4)$$

If the mouth-piece is rounded, $F_m = F =$ area of exit orifice of mouth-piece.

EXAMPLE.—Applying eq. (2) to the data of the example in § 550, where γ_n was found to be .079 lbs. per cub. ft., we have [ft., lbs., sec.]

$$v_m = \sqrt{2g\frac{p_n}{\gamma_n}\log_e\frac{p_n}{p_m}}$$

$$= \sqrt{2\times 32.2\times\frac{16\times 144}{.079}\times 2.3025\times\log_{10}\left[\frac{16}{15}\right]} \quad = 348.7 \text{ ft. p. sec.}$$

$$\therefore\ Q_m = F_m v_m = 0.60\times\tfrac{4}{144}\times 348.7 = 5.81 \text{ cub. ft. per sec.}$$

Since the heaviness at m is, from Mariotte's law,

$$\gamma_m = \frac{p_m}{p_n}\gamma_n = \frac{15}{16} \text{ of } .079, \quad \text{i.e.,} \quad \gamma_m = .0741 \text{ lbs. per cub. ft.,}$$

hence the weight of the discharge is

$$G = Q_m\gamma_m = 5.81\times .0741 = 0.430 \text{ lbs. per sec.,}$$

or about 4½ per cent less than that given by the "water formula." If the difference between the inner and outer tensions had been less, the discrepancy between the results of the two methods would have been smaller.

552. Adiabatic Efflux from an Orifice.—It is most logical to assume that the expansion of the gas approaching the orifice, being rapid, is *adiabatic* (§ 478). Hence especially when the difference btween the inner and outer tensions is considerable) it is more accurate to assume γ to vary according to *Poisson's Law*, eq. (1), p. 623; i.e., $(p \div p_n) = (\gamma \div \gamma_n)^{1.41}$; in integrating eq. (*B*) of p. 775. Then the term

$$\int_n^m \frac{dp}{\gamma} \text{ will } = \frac{p_n{}^{.71}}{\gamma_n}\int_n^m p^{-.71}dp = \frac{3.44p_n{}^{.71}}{\gamma_n}[p_m{}^{.29} - p_n{}^{.29}]$$

$$= \frac{3.44p_n}{\gamma_n}\left[1 - \left(\frac{p_m}{p_n}\right)^{.29}\right];$$

and eq. (B), neglecting h as before, and with $v_n = 0$, becomes (See Fig. 619)

$$\frac{v_m^2}{2g} = \frac{3.44 p_n}{\gamma_n}\left[1 - \left(\frac{p_m}{p_n}\right)^{.29}\right]. \text{ (\textit{Adiabatic flow; orifice.})} \quad (1)$$

Having observed p_n and T_n in the reservoir, we compute $\gamma_n = \frac{p_n \gamma_0 T_0}{T_n p_0}$ (from § 472). The gas at m, just leaving the orifice, having expanded adiabatically from the *state* n to the *state* m, has cooled to a temperature T_m (absolute) found thus (§ 478),

$$T_m = T_n \left(\frac{p_m}{p_n}\right)^{.29}, \quad \ldots\ldots\ldots \quad (2)$$

and is of a heaviness

$$\gamma_m = \gamma_n \left(\frac{p_m}{p_n}\right)^{.71}, \quad \ldots\ldots\ldots \quad (3)$$

and the flow per second occupies a volume (immediately on exit)

$$Q_m = F_m v_m, \quad \ldots\ldots\ldots \quad (4)$$

and weighs

$$G = F_m v_m \gamma_m. \quad \ldots\ldots\ldots \quad (5)$$

Example 1.—Let the interior conditions in the large reservoir of Fig. 619 be as follows (*state* n): $p_n = 22\frac{1}{2}$ lbs. per sq. in., and $T_n = 294°$ Abs. Cent. (i.e., 21° Cent.); while externally the tension is 15 lbs. per sq. inch, which may be taken as being $= p_m =$ tension at m, the throat of jet. The opening is a circular orifice in "thin plate" and of one inch diameter. Required the weight of the discharge per second [ft., lb., sec.; $g = 32.2$].

First, $\gamma_n = \frac{22.5 \times 144}{14.7 \times 144} \cdot \frac{273}{294} \times .0807 = 0.115$ lbs. per cub. ft.

Then, from (1),

$$v_m = \sqrt{2g \frac{3.44 p_n}{\gamma_n}\left[1 - \left(\frac{p_m}{p_n}\right)^{.29}\right]}$$

$$= \sqrt{\frac{2 \times 32.2 \times 3.44 \times 22.5 \times 144}{0.115}\left[1 - \left(\tfrac{2}{3}\right)^{.29}\right]} = 833 \text{ ft. per sec.}$$

Now $$F = \tfrac{1}{4}\pi(\tfrac{1}{12})^2 = .00546 \text{ sq. ft.}$$

$$\therefore\ Q_m = CFv_m = .60Fv_m = 0.60 \times .00546 \times 833 = 2.73$$

cub. ft. per sec., at a temperature of [eq. (2)]

$$T_m = 294(\tfrac{2}{3})^{.29} = 261° \text{ Abs. Cent.} = -12° \text{ Cent.}*$$

and of a heaviness [eq. (3)]

$$\gamma_m = 0.115(\tfrac{2}{3})^{.71} = 0.0862 \text{ lbs. per cub. ft.,}$$

so that the weight of flow per sec.

$$= G = Q_m\gamma_m = 2.73 \times .0862 = .235 \text{ lbs. per sec.}$$

EXAMPLE 2.—Let us treat the example already solved by the two preceding approximate methods (§§ 550 and 551) by the present more accurate equation of adiabatic flow, eq. (1).

The data were (Fig. 619):

$p_n = 16$ lbs. per sq. in.; $T_n = 303°$ Abs. Cent.;
$p_m = 15$ " " " ; and $F = 4$ sq. inches

[F being the area of orifice]. γ_n was found = .079 lbs. per cub. ft. in § 550; hence, from eq. (1),

$$v_m = \sqrt{\frac{2 \times 32.2 \times 3.44 \times 18 \times 144}{.079}\left[1 - (\tfrac{15}{16})^{.29}\right]} = 348.5 \text{ ft. per sec.}$$

From (4),

$$Q_m = F_m v_m = .6Fv_m = .6 \times \tfrac{4}{144} \times 348.5 = 5.81 \text{ cub. ft. per sec.;}$$

and since at m it is of a heaviness

$$\gamma_m = .079(\tfrac{15}{16})^{.71} = .0755 \text{ lbs. per cub. ft.,}$$

we have weight of flow per sec.

$$= G = Q_m\gamma_m = 5.81 \times .0755 = 0.439 \text{ lbs. per sec.}$$

* By the impact of the effluent air on the outside air, with extinction of velocity, the temperature rises again.

Comparing the three methods for this problem, we see that

By the "*water formula*," . . . $G=0.451$ lbs. per sec.
" *isothermal formula*, . . $G=0.430$ " "
" *adiabatic formula*, . . $G=0.439$ " "

553. Practical Notes. Theoretical Maximum Flow of Weight.—If in the equations of § 552 we write for brevity $p_m \div p_n = x$ we derive, by substitution from (1) and (3) in (5),

$$\left.\begin{matrix}\text{Weight of flow}\\ \text{per unit of time}\end{matrix}\right\} = G = Q_m \gamma_m = F_m \sqrt{6.88 g p_n \gamma_n}[1 - x^{.29}]\tfrac{1}{4} x^{.71}. \quad (1)$$

This function of x is of such a form as to be a maximum for

$$x = (p_m \div p_n) = (.830)^{3.44} = .527; \quad . \quad . \quad . \quad (2)$$

i.e., theoretically, if the *state* n inside the reservoir remains the same, while the outside tension (considered $= p_m$ of jet, Fig. 619) is made to assume lower and lower values (so that $x, = p_m \div p_n$, diminishes in the same ratio), the maximum flow of weight per unit of time will occur when $p_m = .527 p_n$, a little more than half the inside tension.

Prof. Cotterill says (p. 544 of his "Applied Mechanics"): "The diminution of the theoretical discharge on diminution of the external pressure below the limit just now given is an anomaly which had always been considered as requiring explanation, and M. St. Venant had already suggested that it could not actually occur. In 1866 Mr. R. D. Napier showed by experiment that the weight of steam of given pressure discharged from an orifice really is independent of the pressure of the medium into which efflux takes place*; and in 1872 Mr. Wilson confirmed this result by experiments on the reaction of steam issuing from an orifice."

"The explanation lies in the fact that the pressure in the

* When the difference between internal and external pressures is great,—should be added.

centre of the contracted jet is not the same as that of the surrounding medium. The jet after passing the contracted section suddenly expands, and the change of direction of the fluid particles gives rise to centrifugal forces" which cause the pressures to be greater in the centre of the contracted section than at the circumference; see Fig. 620.

Prof. Cotterill then advises the assumption that $p_m = .527 p_n$ (for air and perfect gases) as the mean tension in the jet at m (Fig. 619), *whenever the outside medium is at a tension less than* $.527 p_n$. He also says, "Contraction and friction must be allowed for by the use of a coefficient of discharge the value of which, however, is more variable than that of the corresponding coefficient for an incompressible fluid. Little is certainly known on this point." See §§ 549 and 554.

For air the velocity of this *maximum flow of weight* is

$$\textit{Vel. of max. } G = \left[997 \sqrt{\frac{T_n}{T_0}} \right] \text{ ft. per sec., } \quad . \quad (3)$$

where T_n = abs. temp. in reservoir, and T_0 = that of freezing point. Rankine's Applied Mechanics (p. 584) mentions experiments of Drs. Joule and Thomson, in which the circular orifices were in a thin plate of copper and of diameters 0.029 in., 0.053 in., and 0.084 in., while the outside tension was about one half of that inside. The results were 84 per cent of those demanded by theory, a discrepancy due mainly, as Rankine says, to the fact that the actual area of the orifice was used in computation instead of the contracted section; i.e., contraction was neglected.

554. Coefficients of Efflux by Experiment. For Orifices and Short Pipes. Small Difference of Tensions.—Since the discharge through an orifice or short pipe from a reservoir is affected not only by contraction, but by slight friction at the edges, even with a rounded entrance, the theoretical results for the volume and weight of flow per unit of time in preceding paragraphs should be multiplied both by a coefficient of velocity ϕ and one for contraction C, as in the case of water; i.e., by a *coefficient of efflux* $\mu = \phi C$. (Of course, when there is no

contraction, $C = 1.00$, and then $\mu = \phi$ as with a well-rounded mouth-piece, for instance, Fig. 541, and with short pipes.)

Hence for practical results, with orifices and short pipes, we should write for the *weight of flow per unit of time*

$$= G = \mu F v_m \gamma_m = \mu F \left(\frac{p}{p_n}\right)^{.71} \sqrt{2g3.44 p_n \gamma_n \left[1 - \left(\frac{p_m}{p_n}\right)^{.29}\right]}. \quad (1)$$

(from the equations of § 552 for adiabatic flow, as most accurate; $p_m \div p_n$ may range from $\frac{1}{2}$ to 1.00). F = area of orifice, or of discharging end of mouth-piece or short pipe. γ_n = heaviness of air in reservoir and $= T_0 p_n \gamma_0 \div T_n p_0$, eq. (13) of § 437; and μ = the experimental coefficient of efflux.

From his own experiments * and those of Koch, D'Aubuisson, and others, Weisbach recommends the following mean values of μ for various mouthpieces, when p_n is not more than $\frac{1}{7}$ larger than p_m (i.e., about 17 % larger), for use in eq. (1):

1. For an orifice in a thin plate, ... $\mu = 0.56$
2. For a short cylindrical pipe (inner corners not rounded), $\mu = 0.75$
3. For a well-rounded mouth-piece (like that in Fig. 541), $\mu = 0.98$
4. For a short conical convergent pipe (angle about 6°), $\mu = 0.92$

Example.—(Data from Weisbach's Mechanics.) "If the sum of the areas of two conical tuyères of a blowing-machine is $F = 3$ sq. inches, the temperature in the reservoir 15° Cent., the height of the attached (open) mercury manometer (see Fig. 464) 3 inches, and the height of the barometer in the external air 29 inches," we have (ft., lb., sec.)

$$\frac{p_m}{p_n} = \frac{29}{29+3} = \frac{29}{32}; \quad T_n = 288° \text{ Abs. Cent.};$$

$$p_n = (\tfrac{32}{30})\, 14.7 \times 144 \text{ lbs. per sq. ft.};$$

$$\gamma_n = \tfrac{273}{288} \cdot \tfrac{32}{30} \times 0.0807 = 0.0816 \text{ lbs. per cub. ft.},$$

while $F = \frac{3}{144}$ sq. ft. and (see above) $\mu = .92$; hence $G =$

$$.92(\tfrac{3}{144})(\tfrac{29}{32})^{.71} \sqrt{64.4 \times 3.44(\tfrac{32}{30}) \times 14.7 \times 144 \times .0816[1 - (\tfrac{29}{32})^{.29}]};$$

* See also the *Engineering Record* of Oct. 1901, p. 409, where an account is given of experiments on the flow of air through orifices made at the Mass. Inst. of Technology. Fliegner's researches are referred to by Ruehlmann in his *Hydromechanik*, p. 675.

i.e., $G = .606$ lbs. per second; which will occupy a volume

$$V_0 = G \div \gamma_0 = G \div .0807 = 7.51 \text{ cub. ft.}$$

at one atmosphere tension and freezing-point temperature, while at a temperature of $T_n = 288°$ Abs. Cent. and tension of $p_m = \frac{29}{30}$ of one atmosphere (i.e., in the state in which it was on entering the blowing-engine) it occupied a volume

$$V = \frac{288}{273} \cdot \frac{30}{29} \times 7.51 = 8.20 \text{ cub. ft.}$$

(This last is Weisbach's result, very nearly, obtained by an approximate formula.)

555. Coefficients of Efflux for Orifices and Short Pipes for a Large Difference of Tension.—For values $> \frac{7}{8}$ and < 2, of the ratio $p_n : p_m$, of internal to external tension, Weisbach's experiments with *circular orifices in thin plate*, of diameters ($= d$) from 0.4 inches to 0.8 inches, gave the following results:

$p_n : p_m$ =	1.05	1.09	1.40	1.65	1.90	2.00
for $d = .4^{\text{in.}}$; μ =	.55	.59	.69	.72	.76	.78
" $d = .8^{\text{in.}}$; μ =	.56	.57	.64	.68		.72

Whence it appears that μ increases somewhat with the ratio of p_n to p_m, and decreases slightly for increasing size of orifice.

With short cylindrical pipes, internal edges not rounded, and three times as long as wide, Weisbach obtained μ as follows:

$p_n : p_m$ =	1.05	1.10	1.30	1.40	1.70	1.74
diam. = $.4^{\text{in.}}$; μ =	.73	.77	.83			
" = $.6^{\text{in.}}$; μ =				81	. .82	
" = $1.0^{\text{in.}}$; μ =						.83

When the inner edges of the 0.4 in. pipe were slightly rounded, μ was found $= 0.93$; while a well-rounded mouthpiece of the form shown in Fig. 541 gave a value $\mu =$ from .965 to .968, for $p_n : p_m$ ranging from 1.25 to 2.00. These values of μ are for use in eq. (1), above.

556. To find the Discharge when the Internal Pressure is measured in a Small Reservoir or Pipe, not much larger than the

Orifice.--Fig. 621. If the internal pressure p_n, and temperature T_n, must be measured in a small reservoir or pipe, n, whose sectional area F_n is not very large compared with that of the orifice, F, (or of the jet, F_m,) the velocity v_n at n (velocity of approach) cannot be put = zero. Hence, in applying eq. (B), § 550, to the successive laminæ between n and m, and integrating, we shall have, for *adiabatic steady flow*,



FIG. 621.

$$\frac{v_m^2}{2g}-\frac{v_n^2}{2g}=\frac{3.44p_n}{\gamma_n}\left[1-\left(\frac{p_m}{p_n}\right)^{.29}\right] \quad . \quad . \quad . \quad . \quad (1)$$

instead of eq. (1) of § 552. But from the equation of continuity for steady flow of gases [eq. (a) of § 548], $F_n v_n \gamma_n = F\ v_m \gamma_m$; hence $v_n^2=\frac{F_m^2\gamma_m^2}{F_n^2\gamma_n^2}v_m^2$, while for an adiabatic change from n to m, $\frac{\gamma_m}{\gamma_n}=\left(\frac{p_m}{p_n}\right)^{.71}$; whence by substitution in (1), solving for v_m, we have

$$v_m=\frac{\sqrt{2g\cdot\frac{3.44p_n}{\gamma_n}\left[1-\left(\frac{p_m}{p_n}\right)^{.29}\right]}}{\sqrt{1-\left(\frac{F_m}{F_n}\right)^2\left(\frac{p_m}{p_n}\right)^{1.42}}} \quad . \quad . \quad . \quad (2)$$

As before, from §§ 472 and 478,

$$\gamma_n=\frac{p_n}{p_0}\frac{T_0}{T_n}\cdot\gamma_0 \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

and

$$\gamma_m=\left(\frac{p_m}{p_n}\right)^{.71}\gamma_n \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

Having observed p_n, p_m, and T_n, then, and knowing the area F of the orifice, we may compute γ_n, γ_m, and v_m, and finally the

$$\textit{Weight of flow per time-unit}=G=\mu F v_m \gamma_m, \quad . \quad . \quad . \quad (5)$$



by the friction on the sides of the pipe. Since the pipe is very long, and the change of pressure small, the mean velocity in the pipe, v', assumed to be nearly the same at all points along the pipe, will not be large; hence the difference between the velocity-heads at n and m will be neglected; a certain *mean heaviness* γ' will be assigned to all the gas in the pipe, as if a liquid.

Applying Bernoulli's Theorem, *with friction*, § 516, to the ends of the pipe, n and m, we have (as for a liquid)

$$\frac{v_m^2}{2g}+\frac{p_m}{\gamma'}+0=\frac{v_n^2}{2g}+\frac{p_n}{\gamma'}+0-4f\frac{l}{d}\frac{v'^2}{2g}. \quad . \quad (1)$$

Putting (as above mentioned) $v_m^2 - v_n^2 = 0$, we have, more simply,

$$\frac{p_n - p_m}{\gamma'} = 4f\frac{l}{d}\cdot\frac{v'^2}{2g}. \quad . \quad . \quad . \quad . \quad . \quad (2)$$

The value of f as *coefficient of friction for air in long pipes* is found to be somewhat smaller than for water; see next paragraph.

558. Transmission of Compressed Air.* Experiments in the St. Gothard Tunnel, 1878.—[See p. 96 of Vol. 24 (Feb. '81), Van Nostrand's Engineering Magazine.] In these experiments, the temperature and pressure of the flowing gas (air) were observed at each end of a long portion of the pipe which delivered the compressed air to the boring-machines three miles distant from the tunnel's mouth. The portion considered was selected at a distance from the entrance of the tunnel, to eliminate the fluctuating influence of the weather on the temperature of the flowing air. A *steady flow* being secured by proper regulation of the compressors and distributing tubes, observations were made of the internal pressure (p), internal temperature (T), as well as the external, at each end of the portion of pipe considered, and also at intermediate points; also of the *weight of flow per second* $G = Q_0\gamma_0$, measured at the compressors under standard conditions (0° Cent. and one atmos. tension). Then knowing the p and T at any section of the pipe, the

* For experiments at Paris in 1891 see Proc. Inst. Civ. Engineers, vol. 105, p. 180; and *Engineering News* of Dec. 1889, p. 556. See also foot-note on next page.

heaviness γ of the air passing that section can be computed $\left[\text{from } \frac{\gamma}{\gamma_0} = \frac{p}{p_0} \cdot \frac{T_0}{T}\right]$ and the velocity $v = G \div F\gamma$, F being the sectional area at that point. Hence the *mean velocity* v', and the *mean heaviness* γ', can be computed for this portion of the pipe whose diameter $= d$ and length $= l$. In the experiments cited it was found that at points not too near the tunnel-mouth the temperature inside the pipe was always about 3° Cent. lower than that of the tunnel. The values of f in the different experiments were then computed from eq. (2) of the last paragraph; i.e.,

$$\frac{p_n - p_m}{\gamma'} = 4f\frac{l}{d} \cdot \frac{v'^2}{2g}, \quad \ldots\ldots \quad (2)$$

all the other quantities having been either directly observed, or computed from observed quantities.

THE ST. GOTHARD EXPERIMENTS.

[*Concrete quantities reduced to English units.*]

No.	l (feet.)	d (ft.)	γ (lbs. cub. ft.)	Atmospheres. p_n	Atmospheres. p_m	$p_n - p_m$ lbs. sq. in.	v' ft. per sec.	mean temp. Cent.	f
1	15092	$\frac{3}{8}$	0.4058	5.60	5.24	5.29	19.32	21°	.0035
2	15092	$\frac{3}{8}$	0.3209	4.35	4.13	3.23	16.30	21°	.0038
3	15092	$\frac{3}{8}$	.2803	3.84	3.65	2.79	15.55	21°	.0041
4	1712	$\frac{1}{2}$	.3765	5.24	5.00	3.52	37.13	26.5	.0045
5	1712	$\frac{1}{2}$	.3009	4.13	4.06	1.03	30.82	26.5	.0024(?)
6	1712	$\frac{1}{2}$	.2641	3.65	3.54	1.54	29.34	26.5	.0045

In the article referred to (Van Nostrand's Mag.) f is not computed. The writer contents himself with showing that Weisbach's values (based on experiments with small pipes and high velocities) are much too great for the pipes in use in the tunnel.*

With small tubes an inch or less in diameter Weisbach found, for a velocity of about 80 ft. per second, $f = .0060$; for still higher velocities f was smaller, approximately, in accordance with the relation

$$f = \frac{.0542}{\sqrt{v'\,(\text{in ft. per sec.})}}$$

* See also experiments described in Engineering News, Nov. 3, 1904, p. 387. In that article the quantity called f is the f of this chapter divided by 64.4.

On p. 370, vol. xxiv, Van Nostrand's Mag., Prof. Robinson of Ohio mentions other experiments with large long pipes.

From the St. Gothard experiments a value of $f = .004$ may be inferred for approximate results with pipes from 3 to 8 in. in diameter.

Example.—It is required to transmit, in steady flow, a supply of $G = 6.456$ lbs. of atmospheric air per second through a pipe 30000 ft. in length (nearly six miles) from a reservoir where the tension is 6.0 atmos. to another where it is 5.8 atmos., the mean temperature in the pipe being 80° Fahr., = 24° Cent. (i.e. = 297° Abs. Cent.). Required the proper diameter of pipe; $d = ?$ The value $f = .00425$ will be used, and the ft.-lb.-sec. system of units. The mean volume passing per second in the pipe is

$$Q' = G \div \gamma' . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

The mean velocity may thus be written: $v' = \frac{Q'}{F} = \frac{Q'}{\frac{1}{4}\pi d^2}$. (4)

The mean heaviness of the flowing air, computed for a mean tension of 5.9 atmospheres, is, by § 472,

$$\gamma' = \frac{5.9 \times 14.7}{1 \times 14.7} \cdot \frac{273}{297} \times .0807 = 0.431 \text{ lbs. per cub. ft.};$$

and hence, see eq. (3),

$$Q' = \frac{G}{\gamma'} = \frac{6.456}{0.431} = 14.74 \text{ cub. ft.}$$

at tension of 5.9 atmos., and temperature 297° Abs. Cent.

Now, from eq. (2),

$$\frac{p_n - p_m}{\gamma'} = \frac{4f}{2g} \cdot \frac{l}{d} \cdot \left[\frac{Q'}{\frac{1}{4}\pi d^2}\right]^2;$$

whence

$$d^5 = \frac{4f}{(\frac{1}{4}\pi)^2} \cdot \frac{\gamma' l}{(p_n - p_m)} \cdot \frac{Q'^2}{2g}; \quad . \quad . \quad . \quad . \quad . \quad (5)$$

and hence, numerically,

$$d = \sqrt[5]{\frac{4 \times .00425 \times 0.431 \times 30000 \times (14.74)^2}{(.7854)^2[14.7 \times 144(6.00 - 5.80)]2 \times 32.2}} = 1.23 \text{ feet.}$$

559. (Case II of § 557) Long Pipe, with Considerable Difference of Pressure at Extremities of the Pipe. Flow Steady.—Fig. 623. If the difference between the end-tensions is comparatively *great*, we can no longer deal with the whole of the air



FIG. 623.

in the pipe at once, as regards ascribing to it a mean velocity and mean tension, but *must consider the separate laminæ*, such as AB (a short length of the air-stream) to which we may apply eq. (2) of § 55 ; A and B corresponding to the n and m of Fig. 622. Since the $p_n - p_m$, l, γ', and v' of § 557 correspond to the $-dp$, ds, γ, and v of the present case (short section or lamina), we may write

$$-\frac{dp}{\gamma} = 4f\frac{v^2}{d\,2g}\,ds. \quad \ldots\ldots \quad (1)$$

But if G = weight of flow per unit of time, we have at any section, $Fv\gamma = G$ (equation of continuity); i.e., $v = G \div F\gamma$, whence by substitution in eq. (1) we have

$$-\frac{dp}{\gamma} = \frac{4f}{2gd}\cdot\frac{G^2 ds}{F^2\gamma^2}; \quad \text{i.e.,} \quad -\gamma dp = \frac{4fG^2}{2gF^2 d}\,ds. \quad \ldots \quad (2)$$

Eq. (2) contains *three variables*, γ, p, and s (= distance of lamina from n'). As to the dependence of the heaviness γ on the tension p in different laminæ, experiment shows that in most cases a uniform temperature is found to exist all along the pipe, if properly buried, or shaded from the sun; the loss of heat by adiabatic expansion being in great part made up by the heat generated by the friction against the walls of the

pipe. This is due to the small loss of tension per unit of length of pipe as compared with that occurring in a short discharge pipe or nozzle. Hence we may treat the flow as *isothermal*, and write $p \div \gamma = p_{n'} \div \gamma_{n'}$ (§ 475, Mariotte's Law). Hence $\gamma = \frac{\gamma_{n'}}{p_{n'}} p$, which substituted in eq. (2) enables us to write:

$$-pdp = \left[\frac{4fG^2}{2gF^2d}\frac{p_{n'}}{\gamma_{n'}}\right]ds. \quad . \quad . \quad . \quad . \quad . \quad (3)'$$

$$\therefore \; -\int_{n'}^{m'} pdp = \left[\frac{4fG^2p_{n'}}{2gF^2\gamma_{n'}d}\right]\int_0^l ds. \quad . \quad . \quad . \quad . \quad (3)$$

Performing the integration, noting that at n' $p = p_{n'}$, $s = 0$, and at m' $p = p_{m'}$ and $s = l$, we have

$$\tfrac{1}{2}[p_{n'}^2 - p_{m'}^2] = \frac{4fl}{2gd} \cdot \frac{G^2}{F^2} \cdot \frac{p_{n'}}{\gamma_{n'}} \cdot \cdot \left\{\begin{matrix} \textit{isothermal flow} \\ \textit{in long pipes} \end{matrix}\right\} \cdot \cdot \; (4)$$

It is here assumed that the tension at the entrance of the pipe is practically equal to that in the head reservoir, and that at the end (m') to that of the receiving reservoir; which is not strictly true, especially when the corners are not rounded. It will be remembered also that in establishing eq. (2) of § 557 (the basis of the present paragraph), the "inertia" of the gas was neglected; i.e., the change of velocity in passing along the pipe. Hence eq. (4) should not be applied to cases where the pipe is so short, or the difference of end-tensions so great, as to create a considerable difference between the velocities at the two ends of the pipe. (See Addendum on p. 797.)

Example.—A well or reservoir supplies natural gas at a tension of $p_{n'} = 30$ lbs. per sq. inch. Its heaviness at 0° Cent. and one atmosphere tension is .0484 lbs. per cub. foot. In piping this gas along a level to a town two miles distant, a single four-inch pipe is to be employed, and the tension in the receiving reservoir (by proper regulation of the gas distributed from it) is to be kept equal to 16 lbs. per sq. in. (which would sustain a column of water about 2 ft. in height in an *open* water manometer, Fig. 465).

The mean temperature in the pipe being 17° Cent., required the amount (weight) of gas delivered per second, supposing leakage to be prevented (formerly a difficult matter in practice). Solve (4) for G, and we have

$$G = \tfrac{1}{4}\pi d^2 \sqrt{\frac{gd}{4fl} \cdot \frac{\gamma_{n'}}{p_{n'}} (p_{n'}^2 - p_{m'}^2)}. \quad . \quad . \quad . \quad (5)$$

First, from § 472, with $T_{n'} = T_{m'} = 290°$ Abs. Cent., we compute

$$\frac{p_{n'}}{\gamma_{n'}} = \frac{p_0}{\gamma_0} \cdot \frac{T_{n'}}{T_0} = \frac{14.7 \times 144}{.0484} \cdot \frac{290}{273} = 46454 \text{ feet.}$$

Hence with $f = .005$,

$$G = \tfrac{1}{4}\pi(\tfrac{4}{12})^2 \cdot \sqrt{\frac{32.2 \times \frac{4}{12}[(30 \times 144)^2 - (16 \times 144)^2]}{4 \times .005 \times 10560 \times 46454}}$$

$$= 0.337 \text{ lbs. per sec.}$$

(For compressed atmospheric air, under like conditions, we would have $G = 0.430$ lbs. per second.)

Of course the proper choice of the coefficient f has an important influence on the result.

From the above result ($G = 0.337$ lbs. per second) we can compute the volume occupied by this quantity of gas in the receiving reservoir, using the relation $Q_{m'} = \frac{G}{\gamma_{m'}}$.

The heaviness $\gamma_{m'}$ of the gas in the receiving reservoir is most easily found from the relation $\frac{p_{m'}}{\gamma_{m'}} = \frac{p_{n'}}{\gamma_{n'}}$, which holds good since the flow is *isothermal*. I.e., $\frac{p_{m'}}{\gamma_{m'}} = 46454$ ft.; whence $\gamma_{m'} = 0.049$ lbs. per cubic foot, $p_{m'}$ being 16×144 lbs. per sq. ft.

Hence

$$Q_{m'} = \frac{G}{\gamma_{m'}} = \frac{0.337}{0.049} = 6.794 \text{ cub. ft. per sec.}$$

It should be said that the pressure at the up-stream end of the pipe depends upon the rate of flow allowed to take place.

With no flow permitted, the pressure in the tube of a gas-well has in some cases reached the high figure of 500 or 600 lbs. per sq. in.

560. Rate of Decrease of Pressure along a Long Pipe.—Considering further the case of the last paragraph, that of a straight, long, level pipe of uniform diameter, delivering gas from a storage reservoir into a receiving reservoir, we note that if in eq. (4) we retain $p_{m'}$ to indicate the tension in the receiving reservoir, but let $p_{n'}$ denote in turn the tension at points in the pipe successively further and further (a distance x) from the receiving reservoir m', we may write x for l and obtain the equation (between two variables, $p_{n'}$ and x)

$$p_{n'}^2 - p_{m'}^2 = Const. \times x. \quad . \quad . \quad . \quad . \quad . \quad (6)$$

This can be used to bring out an interesting relation mentioned by a writer in the *Engineering News* of July 1887 (p. 71), viz., the fact that in the parts of the pipe more distant from the receiving end, m', the distance along the pipe in which a given loss of pressure occurs is much greater than near the receiving end.

To make a numerical illustration, let us suppose that the pipe is of such size, in connection with other circumstances, that the tension $p_{n'}$ at A, a distance $x =$ six miles from m', is two atmospheres, the tension in the receiving reservoir being one atmosphere; that is, that the loss of tension between A and m' is one atmosphere. If we express tensions in atmospheres and distances in miles, we have for the value of the constant in eq. (6), for this case,

$$\text{Const.} = (4 - 1) \div 6 = \tfrac{3}{6}; \quad (\textit{for assumed units.}) \quad . \quad . \quad (7)$$

Now let $p_{n'} =$ the tension at B, a point 18 miles from m', and we have, from eqs. (6) and (7), the tension at $B = 3.16$ atmospheres. Proceeding in this manner, the following set of values is obtained:

Point.	Total distance from m'.	Distance between consecutive points.	Tension at point.	Loss of tension in each interval.
F	126 miles.	36 miles.	8.00 atm.	1.22 atm.
E	90 "	30 "	6.78 "	1.22 "
D	60 "	24 "	5.56 "	1.21 "
C	36 "	18 "	4.35 "	1.19 "
B	18 "	12 "	3.16 "	1.16 "
A	6 "	6 "	2.00 "	1.00 "
m'	0 "	.....	1.00 "	.....

If the distances and tensions in the second and fourth columns be plotted as abscissæ and ordinates of a curve, the latter is a parabola with its axis following the axis of the pipe; its vertex is not at m', however.

561. Long Pipe of Variable Diameter.—Another way of stating the fact mentioned in the last paragraph is as follows: At the up-stream end of the pipe of *uniform diameter* the gas is of much greater density than at the other extremity (the heaviness is directly as the tension, the temperature being assumed the same throughout the pipe), and the velocity of its motion is smaller than at the discharging end (in the same ratio). It is true that the frictional resistance per unit of length of pipe varies directly as the heaviness [eq. (1), § 510], but also true that it varies as the *square* of the velocity; so that, for instance, if the pressure at a point A is double that at B in the pipe of constant diameter, it implies that the heaviness and velocity at A are double and half, respectively, those at B, and thus the gas at A is subjected to only half the frictional resisting force per foot of length as compared with that at B. Hence the relatively small diminution, per unit of length, in the tension at the up-stream end in the example of the last paragraph.

In the pipe of uniform diameter, as we have seen, the greater part of the length is subjected to a comparatively high tension, and is thus under a greater liability to loss by leakage than if the decrease of tension were more uniform. The total "*hoop-tension*" (§ 426) in a unit length of pipe, also, is proportional to the gas tension,* and thinner walls might be employed for the down-stream portions of the pipe if the gas

* Or, rather, to its *excess* over that of external air.

tension in those portions could be made smaller than as shown in the preceding example.

To secure a more rapid fall of pressure at the up-stream end of the pipe, and at the same time provide for the same delivery of gas as with a pipe of uniform diameter throughout, a pipe of *variable* diameter may be employed, that diameter being considerably smaller at the inlet than that of the uniform pipe but progressively enlarging down-stream. This will require the diameters of portions near the discharging end to be larger than in the uniform pipe, and if the same thickness of metal were necessary throughout, there would be no saving of metal, but rather the reverse, as will be seen; but the diminished thickness made practicable in those parts from a less total hoop tension than in the corresponding parts of the uniform pipe more than compensates for the extra metal due to increased circumference, aside from the diminished liability to leakage, which is of equal importance.

A simple numerical example will illustrate the foregoing. The pipe being circular, we may replace F by $\frac{1}{4}\pi d^2$ in equation (4), and finally derive, G being given,

$$d = Const. \times \left[\frac{l}{p_{n'}^2 - p_{m'}^2}\right]^{\frac{1}{5}} = C. \left[\frac{l}{p_{n'}^2 - p_{m'}^2}\right]^{\frac{1}{5}}. \quad . \quad (8)$$

Let A be the head reservoir, and m' the receiving reservoir, and B a point half-way between. At A the tension is 10 atmospheres; at m', 2 atmospheres. For transmitting a given weight of gas per unit-time, through a pipe of constant diamter throughout, that diameter must be (tensions in atmospheres; $2l_0$ being the length), by eq. (8),

$$d = Cl_0^{\frac{1}{5}}\left[\frac{2}{100 - 4}\right]^{\frac{1}{5}} = Cl_0^{\frac{1}{5}}(.0208)^{\frac{1}{5}} = 0.46\, Cl_0^{\frac{1}{5}}. \quad . \quad (8)_1$$

If we substitute for the pipe mentioned, another having a constant diameter d_1 from A to B, where we wish the tension to be 5 atmospheres, and a different constant diameter d_2 from B to m', we derive similarly

$$d_1 = Cl_0^{\frac{1}{5}}\left[\frac{1}{100 - 25}\right]^{\frac{1}{5}} = 0.42\, Cl_0^{\frac{1}{5}}$$

and

$$d_2 = Cl^{\frac{1}{5}}\left[\frac{1}{25-4}\right]^{\frac{1}{5}} = 0.54\ Cl^{\frac{1}{5}}$$

It is now to be noted that the sum of d_1 and d_2 is slightly greater than the double of d; so that if the same thickness of metal were used in both designs the compound pipe would require a little more material than the uniform pipe; but, from the reasoning given at the beginning of this paragraph, that thickness may be made considerably less in the down-stream part of the compound pipe, and thus economy secured.

[In case of a cessation of the flow, the gas tension in the whole pipe might rise to an equality with that of the head-reservoir were it not for the insertion, at intervals, of automatic regulators, each of which prevents the increase of tension on its down-stream side above a fixed value. To provide for changes of length due to rise and fall of temperature, the pipe is laid with slight undulations.]

It is a noteworthy t eoretical deduction that a given pipe of variable diameter connecting two reservoirs of gas at specified pressures will deliver the same weight of gas as before, *if turned end for end*. This follows from equation (3)′, § 559. With d variable, (3)′ becomes (with $F = \frac{1}{4}\pi d^2$)

$$\int_{n'}^{m'}(-pdp) = G^2 C'' \int_{n'}^{m'} \frac{ds}{d^5}; \quad \text{i.e.,} \quad G^2 = \frac{p_{n'}^2 - p_{m'}^2}{2C'' \int_{n'}^{m'} \frac{ds}{d^5}}. \quad . \quad (9)$$

(C'' is a constant.)

But $\int_{n'}^{m'} \frac{ds}{d^5}$ is evidently the same in value if the pipe be turned end for end. In commenting on this circumstance, we should remember (see § 559) that the loss of pressure along the pipe is ascribed *entirely to frictional resistance*, and in no degree to changes of velocity (inertia).

On p. 73 of the *Engineering News* of July 1887 are given the following dimensions of a compound pipe in actual use, and delivering natural gas. The pressure in the head-reservoir is 319 lbs. per sq. in.; that in the receiving reservoir, 65. For 2.84 miles from the head-reservoir the diameter of the pipe is

8 in.; throughout the next 2.75 miles, 10 in.; while in the remaining 3.84 miles the diameter is 12 in. At the two points of junction the pressures are stated to be 185 and 132 lbs. per sq. in., respectively, during the flow of gas under the conditions mentioned.

561a. Values of the Coefficient of Fluid Friction for Natural Gas.—In the Ohio Report on Economic Geology for 1888 may be found an article by Prof. S. W. Robinson of the University of that State describing a series of interesting experiments made by him on the flow of natural gas from orifices and through pipes.* By the insertion of Pitot tubes approximate measurements were made of the velocity of the stream of gas in a pipe. The following are some of the results of these experiments, $p_1 - p_2$ representing the loss of pressure (in lbs. per sq. inch) per mile of pipe-length, and f the coefficient of fluid friction, in experiments with a six-inch pipe:

$p_1 - p_2$	1.00	1.50	2.25	2.50	5.75	6.25
f	0.0025	0.0037	0.0052	0.0059	0.0070	0.0060

In the flow under observation Prof. Robinson concluded that f could be taken as approximately proportional to the fourth root of the cube of the velocity of flow; though calling attention to the fact that very reliable results could hardly be expected under the circumstances.

561b. [Addendum to § 559.] Isothermal Flow in a level pipe, with consideration of Inertia.—In eq. (1) of p. 697 neglect dz, put $w \div F = 4 \div d$, and divide through by v^2. In the second term put $G^2 \div F^2\gamma^2$ for v^2 and then $p\,(\gamma_m \div p_m)$ for γ. We now find the variables separated, and on integration for steady flow obtain (after putting $v_n \div v_m = F\gamma_m \div F\gamma_n = p_m \div p_n$),

$$\log_e\left(\frac{p_n}{p_m}\right) - \frac{g(p_n^2 - p_m^2)}{2} \cdot \frac{F^2}{G^2} \cdot \frac{\gamma_m}{p_m} = -\frac{2fl}{d}.$$

[Notation as in § 557 with $G = Fv\gamma$.]

* More recent experiments with the Pitot Tube, in measuring the velocity of gases in pipes, have been made in Chicago by Messrs. Dreffein and McBurney. See *Engineering News* of Dec. 21, 1905, p. 660.

CHAPTER IX.

IMPULSE AND RESISTANCE OF FLUIDS.

562. The so-called "Reaction" of a Jet of Water flowing from a Vessel.—In Fig. 624, if a frictionless but water-tight plug B be inserted in an orifice in the vertical side of a vessel mounted on wheels, the resultant action of the water on the rigid vessel (as a whole) consists of its weight G, and a force $P' = Fh\gamma$ (in which $F =$ the area of orifice) which is the excess of the horizontal hydrostatic pressures on the vessel wall toward the right ($\|$ to paper) over those toward the left, since the pressure $P, = Fh\gamma$, exerted on the plug is felt by the post C, and not by the vessel. Hence the post D receives a pressure



FIG. 624.

$$P' = Fh\gamma. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

Let the plug B be removed. A steady flow is then set up through the orifice, and now the pressure against the post D is $2Fh\gamma$ (as will be proved in the next paragraph); for not only is the pressure $Fh\gamma$ lacking on the left, because of the orifice, but the sum of all the horizontal components ($\|$ to paper) of the pressures of the liquid filaments against the vessel wall around the orifice is less than its value before the flow began, by an amount $Fh\gamma$. A resistance $R = 2Fh\gamma$ being provided, and the post removed, a slow uniform motion may be maintained toward the right, the working force being $2Fh\gamma = P''$

(see Fig. 625; R is not shown). If an insufficient resistance be furnished before removing the post D, the vessel will begin to move toward the right with an *acceleration*, which will disturb the surface of the water and change the value of the horizontal force. This force

$$P'' = 2Fh\gamma \quad . \quad . \quad . \quad (2).$$

is called the "*reaction*" of the water-jet; γ is the heaviness of the liquid (§ 7).



FIG. 625.

Of course, as the flow goes on, the water level sinks and the "reaction" diminishes accordingly. Looked upon as a motor, the vessel may be considered to be a piston-less and valve-less water-pressure engine, carrying its own reservoir with it.

In Case II of § 500 we have already had a treatment of the "Reaction-wheel" or "Barker's mill," which is a practical machine operating on this principle, and will be again considered in "Hydraulic Motors." *

563. "Reaction" of a Liquid Jet on the Vessel from which it Issues.—Instead of showing that the pressures on the vessel close to the orifice are less than they were when there was no flow by an amount $Fh\gamma$ (a rather lengthy demonstration), another method will be given, of greater simplicity but somewhat fanciful.

If a man standing on the rear platform of a car is to take up in succession, from a basket on the car, a number of balls of equal mass $= M$, and project each one in turn horizontally backward with an acceleration $= p$, he can accomplish this only by exerting against each ball a pressure $= Mp$, and in the opposite direction against the car an equal pressure $= Mp$. If this action is kept up continuously the car is subjected to a constant and continuous forward force of $P'' = Mp$.

Similarly, the backward projection of the jet of water in the case of the vessel at rest must occasion a forward force against the vessel of a value dependent on the fact that in each small interval of time Δt a small mass ΔM of liquid has its velocity changed from zero to a backward velocity of $v = \sqrt{2gh}$; that

* *Hydraulic Motors; with related subjects.* New York, 1905, John Wiley & Sons.

is, has been projected with a mean acceleration of $p = \frac{v - 0}{\Delta t}$, so that the forward force against the vessel is

$$P'' = \text{mass} \times \text{acc.} = \frac{\Delta M . v}{\Delta t}. \quad . \quad . \quad . \quad . \quad . \quad (3)$$

If $Q =$ the volume of water discharged per unit time, then $\Delta M = \frac{Q\gamma}{g} \Delta t$, and since also $Q = Fv = F\sqrt{2gh}$, eq. (3) becomes

$$\text{"}\textit{Reaction}\text{" of jet} = P'' = 2Fh\gamma. \quad . \quad . \quad . \quad (4)$$

(A similar proof, resulting in the same value for P'', is easily made if the vessel has a uniform motion with water surface horizontal.)

If the orifice is in "thin plate," we understand by F the area of the *contracted section*. Practically, we have $v = \phi\sqrt{2gh}$ (§ 495), and hence (4) reduces to

$$P'' = 2\phi^2 Fh\gamma. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

Weisbach mentions the experiments of Mr. Peter Ewart of Manchester, England, as giving the result $P'' = 1.73Fh\gamma$ with a well-rounded orifice as in Fig. 625. He also found $\phi = .94$ for the same orifice, so that by eq. (4) we should have

$$P'' = 2(.94)^2 Fh\gamma = 1.77Fh\gamma.$$

With an orifice in thin plate Mr. Ewart found $P'' = 1.14Fh\gamma$. As for a result from eq. (4), we must put, for F, the area of the contracted section $.64F$ (§ 495), which, with $\phi = .96$, gives

$$P'' = 2(.96)^2 . 64Fh\gamma = 1.18Fh\gamma. \quad . \quad . \quad . \quad (6)$$

Evidently both results agree well with experiment.

Experiments made by Prof. J. B. Webb at the Stevens Institute (see Journal of the Franklin Inst., Jan. '88, p. 35) also confirm the foregoing results. In these experiments the vessel was suspended on springs and the jet directly downward, so that the "reaction" consisted of a diminution of the tension of the springs during the flow.

564. Impulse of a Jet of Water on a Fixed Curved Vane (with Borders).—The jet passes tangentially upon the vane. Fig.

626. B is the stationary nozzle from which a jet of water of cross-section F (area) and velocity $= c$ impinges tangentially upon the vane, which has plane borders, parallel to paper, to prevent the lateral escape of the jet. The curve of the vane is not circular necessarily. The vane being smooth, the velocity of the water in its curved path remains $= c$ at all points along the curve. Conceive the curve divided into a great number of small lengths each $= ds$, and subtending some angle $= d\phi$ from its own centre of curvature, its radius of curvature being $= r$ (different for different ds's), which makes some angle $= \phi$ with the axis Y ($\perp$ to original straight jet BA). At any instant of time there is an arc of water AD in contact with the vane, exerting pressure upon it. The pressure dP of any ds of the vane against the small mass of water $Fds \cdot \gamma \div g$ then in contact with it is the "deviating" or "centripetal" force accountable for its motion in a curve of radius $= r$, and hence must have a value



FIG. 626.

$$dP = \frac{F\gamma ds}{g} \cdot \frac{c^2}{r}. \quad \ldots (\S\ 76) \ldots (1)$$

The opposite and equal of this force is the dP shown in Fig. 626, and is the impulse or pressure of this small mass against the vane. Its X-component is $dX = dP \sin \phi$. By making ϕ vary from 0 to α, and adding up the corresponding values of dX, we obtain the sum of the X-components of the small pressures exerted simultaneously against the vane by the arc of water then in contact with it; i.e., noting that $ds = r\,d\phi$,

$$\int_{\phi=0}^{\phi=\alpha} dX = \int_0^\alpha dP \cdot \sin\phi = \frac{F\gamma c^2}{g} \int_0^\alpha \frac{ds \cdot \sin\phi}{r}$$

$$= \frac{F\gamma c^2}{g} \int_0^\alpha [\sin\phi] d\phi = \frac{F\gamma c^2}{g} \Big[-\cos\phi \Big]_0^\alpha;$$

$$\left.\begin{matrix}\textit{hence the } X\textit{-impulse} \\ \textit{against fixed vane}\end{matrix}\right\} = \frac{F\gamma c^2}{g}[1-\cos\alpha] = \frac{Q\gamma c}{g}[1-\cos\alpha], \quad (2)$$

in which $Q = Fc$ = volume of water which passes through the nozzle (and also = that passing over the vane, in this case) per unit of time, and α = angle between the direction of the stream leaving the vane (i.e., at D) and its original direction (BA of the jet); i.e., α = *total angle of deviation*. Similarly, the sum of the Y-components of the dP's of Fig. 626 may be shown to be

$$Y\textit{-impulse on fixed vane} = \int_0^\alpha dP \cdot \cos\phi = \frac{Q\gamma c}{g}\sin\alpha \ldots (2)'$$

Hence the *resultant impulse* on the vane is a force

$$P'' = \sqrt{X^2+Y^2} = \frac{Q\gamma c}{g}\sqrt{2(1-\cos\alpha)}, \quad . \quad . \quad (3)$$

and makes such an angle α', Fig. 627, with the direction BA, that

$$\tan\alpha' = \frac{Y}{X} = \frac{\sin\alpha}{1-\cos\alpha} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$



FIG. 627.



FIG. 628.

That is, $\tan\alpha' = \cot.\frac{1}{2}\alpha$, or $\alpha' = 90° - \frac{1}{2}\alpha$; and the force P'' *bisects the angle between the original* (BA), *and the final direction of the jet.* For example, if $\alpha = 70°$, $\alpha' = 55°$; while if $\alpha = 180°$, Fig. 628, we have $\alpha' = 0°$ and hence P'' is parallel to BA, its value being (see eq. (3)),

$$P'' = 2Q\gamma\frac{c}{g}.$$

565. Impulse of a Jet on a Fixed Solid of Revolution whose Axis is Parallel to the Jet.—If the curved vane, with borders, of the preceding paragraph be replaced by a solid of revolution, Fig. 629, with its axis in line of the jet, the resultant pressure of the jet upon it will simply be the sum of the X-components (i.e., = to BA) of the pressures on all elements of the surface at a given instant; i.e.,



FIG. 629.

$$X = P'' = Q\gamma \frac{c}{g}(1 - \cos\alpha); \quad . \quad . \quad . \quad . \quad (5)$$

while the components ⊥ to X, all directed toward the axis of the solid, neutralize each other. For a *fixed plate*, then, Fig. 630, at right angles to the jet, we have for the force, or "impulse" (with $\alpha = 90°$),



FIG. 630.

$$P'' = \frac{Q\gamma}{g} c = \frac{Fc^2}{g}\gamma = 2F\frac{c^2}{2g}\gamma. \quad . \quad (6)$$

The experiments of Bidone, made in 1838, confirm the truth of eq. (6) quite closely, as do also those of two students of the University of Pennsylvania at Philadelphia (see Jour. of the Frank. Inst. for Oct. '87, p. 258).

We may apply eq. (6) to the theory of *Pitot's Tube* (§ 539), Fig. 631, assuming the current to act like a jet, with $\alpha = 90°$. The water in the tube is at rest, and its section at A (of area $= F$) may be treated as a flat vertical plate receiving not only the hydrostatic pressure $Fx\gamma$, due to the depth x below the surface, but a continuous impulse $P'' = Fc^2\gamma \div g$ [see eq. (6)].*



FIG. 631.

* This implies that the sectional area F of the "equivalent isolated jet" is equal to that of the extremity of tube and that α is 90°, an assumption which, though simple, is largely conjectural.

Hence, we write, for the equilibrium of the "plate" A,

$$Fx\gamma + \frac{Fc^2\gamma}{g} = Fx\gamma + Fh'\gamma; \quad \text{i.e.,} \quad h' = (2.0)\frac{c^2}{2g}. \quad . \quad (7)$$

But the assumed size of the "equivalent isolated jet" and of the angle α (see foot-note, p. 803) are both probably much too large; so that, for the factor 2.0 of eq. (7), we substitute some smaller number, or coefficient, k; and hence write

$$h' = k\frac{c^2}{2g} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (7a)$$

as a theoretical relation holding good for the Pitot Tube.

The value of k can only be determined by experiment. Pitot found $k = 1.5$ when the point of the tube was made flaring like a funnel; while Darcy, desiring that the end of the tube should occasion but little disturbance in the current itself, made the extremity small and conically convergent.* The latter found k practically $= 1.00$.



FIG. 632.

For other practical details see p. 750.

If the solid of revolution is made cup-shaped, as in Fig. 632, we have (as in Fig. 628) $\alpha = 180°$, and therefore, from eq. (5),

$$P'' = 2Q\gamma\frac{c}{g} = \frac{2Fc^2\gamma}{g} = 4F\left(\frac{c^2}{2g}\right)\gamma. \quad . \quad . \quad . \quad (8)$$

EXAMPLE.—Fig. 632. If $c = 30$ ft. per sec. and the jet (cylindrical) has a diameter of 1 inch, the liquid being water, so that $\gamma = 62.5$ lbs. per cub. ft., we have [ft., lb., sec.]

$$\text{the impulse (force)} = P'' = \frac{2\frac{\pi}{4}\left(\frac{1}{12}\right)^2 900 \times 62.5}{32.2} = 19.05 \text{ lbs.}$$

Experiment would probably show a smaller result.

* See p. 833 for Mr. Freeman's Experiments.

566. Impulse of a Liquid Jet upon a Moving Vane having Lateral Borders and Moving in the Direction of the Jet.—Fig. 633. The vane has a motion of translation (§ 108) in the same direction as the jet. Call this the axis X. It is moving with a velocity v *away from the jet* (or, if toward the jet, v is negative). We consider v constant, its acceleration being prevented by a proper resistance (such as a weight $= G$) to balance the X-components of the arc-pressures. Before coming in contact with the vane, which it does tangentially (to avoid *sudden* deviation), the absolute velocity (§ 83) of the water in the jet $= c$, while its velocity relatively to the vane at A is $= c - v$; and it will now be proved that the relative velocity along the vane is constant. See Fig. 634. Let $v =$ the velocity of the vane (of each point of it, since its motion is one of translation), and $u =$ the velocity of a water particle (or small mass of water of length $= ds$) relatively to the point of the vane which it is passing. Then w, the absolute velocity of the small mass, is the diagonal formed on u and v. Neglecting friction, the only actual force acting on the mass is P, the pressure of the vane against it, and this is normal to the curve. Now an imaginary system of forces, equivalent to this actual system of one force P, i.e., capable of producing the same motion in the mass, may be conceived of, consisting of the individual forces which would produce, separately, the separate motions of which the actual motion of this small mass M is compounded. These component motions are as follows:



FIG. 633.

1. A horizontal uniform motion of constant velocity $= v$; and

2. A motion in the arc of a circle of radius $= r$ and with a

velocity $= u$, which we shall consider variable until proved otherwise.

Motion 1 is of such a nature as to call for *no force* (by Newton's first law of motion), while motion 2 could be maintained by a system of two forces, one normal, $P_n, = \frac{Mu^2}{r}$, and the other tangential, $P_t = M\frac{du}{dt}$ [see eq. (5), p. 76]. This imaginary system of forces is shown at (II.), Fig. 634, and is equiv-



FIG. 634.

alent to the actual system at (I.). Therefore Σ(tang. compons.) in (I.) should be equal to Σ(tang. compons.) in (II.); whence we have

$$P_t = 0; \quad \text{i.e.,} \quad M\frac{du}{dt} = 0; \quad \text{or} \quad \frac{du}{dt} = 0; \quad . \quad . \quad (1)$$

i.e., u is constant along the vane and is equal to $c - v$ at every point. (The weight of the mass has been neglected since the height of the vane is small.) In Fig. 634 the symbol w_0 has been used instead of c, and the point 0 corresponds to A in Fig. 633.

[N.B. If the motion of the vane were *rotary*, about an axis $\perp$ to AB (or to c), this relative velocity would be different at different points. See p. 59 of *Hydraulic Motors*. If the radius of motion of the point A, however, is quite large compared with the projection of AD upon this radius, the relative velocity is approximately $= c - v$ at all parts of the vane, and will be taken $= c - v$ in treating the "Hurdy gurdy" in § 567.]

By putting Σ(normal compons.) of (I.) $= \Sigma$(normal compons.) in (II.) we have

$$P = P_n; \quad \text{i.e.,} \quad P = M\frac{u^2}{r} = \frac{M(c-v)^2}{r}; \quad . \quad . \quad . \quad (2)$$

so that to find the sum of the X-components of the pressures exerted against the vane simultaneously by all the small masses of water in contact with it at any instant, the analysis differs from that in § 564 only in replacing the c of that article by the $(c - v)$ of this. Therefore

$$\Sigma(X\text{-}pressures) = P_x = \frac{F\gamma}{g}(c-v)^2[1-\cos\alpha], \quad . \quad (3)$$

(where α is the angle of total deviation, relatively to vane, of the stream leaving the vane, from its original direction), and is seen to be proportional to the *square* of the relative velocity. F is the sectional area of jet, and γ the heaviness (§ 7) of the liquid. The Y-component (or P_Y) of the resultant impulse is counteracted by the support EF, Fig. 633. Hence, *for a uniform motion to be maintained*, with a given velocity $= v$, the weight G must be made $= P_x$ of eq. (3). (We here neglect friction and suppose the jet to preserve a practically horizontal direction for an indefinite distance before meeting the vane. If this uniform motion is to be *toward* the jet, v will be negative in eq. (3), making P_x (and $\therefore$ G) larger than for a positive v of same numerical value.

As to the *doing of work* [§§ 128, etc.], or exchange of energy, between the two bodies, jet and vane, during a uniform motion *away* from the jet, P_x exerts a *power* of

$$L = P_x v = \frac{F\gamma}{g}(c-v)^2 v[1-\cos\alpha], \quad . \quad . \quad . \quad (4)$$

in which L denotes the number of units of work done per unit of time by P_x; i.e., the *power* (§ 130) exerted by P_x.

If v is negative, call it $-v'$, and we have the

$$\left.\begin{matrix}\textit{Power expended}\\ \textit{by vane upon jet}\end{matrix}\right\} = P_x v' = \frac{F\gamma}{g}(c+v')^2 v'[1-\cos\alpha]. \quad . \quad (5$$

Of course, practically, we are more concerned with eq. (4) than with (5). The power L in (4) is a maximum for $v = \frac{1}{3}c$; but in practice, since a single moving vane or float cannot utilize the water of the jet as fast as it flows from the nozzle, let us conceive of a succession of vanes coming into position consecutively in front of the jet, all having the same velocity v; then the portion of jet intercepted between two vanes is at liberty to finish its work on the front vane, while additional work is being done on the hinder one; i.e., the water will be utilized as fast as it issues from the nozzle.

With such a *series of vanes*, then, we may put $Q' = F'c$, the volume of flow per unit of time from the nozzle, in place of $F(c - v)$ = the volume of flow per unit of time over the vane, in eq. (4); whence

$$\left.\begin{matrix}\textit{Power exerted on}\\ \textit{series of vanes}\end{matrix}\right\} = L' = \frac{Q'\gamma}{g}[1 - \cos\alpha](c - v)v. \quad . \quad (6)$$

Making v variable, and putting $dL' \div dv = 0$, whence $c - 2v = 0$, we find that for $v = \frac{1}{2}c$, L', the power, is a maximum. Assuming different values for α, we find that for $\alpha = 180°$, i.e., by the use of a semicircular vane, or of a hemispherical cup, Fig. 635, with a point in middle, $1 - \cos\alpha$ is a max., $= 2$; whence, with $v = \frac{1}{2}c$, we have, as the *maximum power*,



Fig. 635.

$$L'_{\max.} = \frac{Q'\gamma}{g} \cdot \frac{c^2}{2} = \frac{M'c^2}{2}; \left\{\begin{matrix}\alpha = 180°,\\ v = \frac{1}{2}c;\end{matrix}\right\} \quad . \quad (7)$$

in which M' denotes the mass of the flow per unit of time from the stationary nozzle. Now $\frac{M'c^2}{2}$ is the *entire kinetic energy* furnished per unit of time by the jet; hence the motor of Fig. 635 (*series* of cups) has a theoretical efficiency of unity, utilizing all the kinetic energy of the water. If this is true, the absolute velocity of the particles of liquid where they leave the cup, or vane, should be *zero*, which is seen to be true,

as follows: At H, or H', the velocity of the particles relatively to the vane is $= c - v =$ what it was at A, and hence is $= c - \frac{c}{2} = \frac{c}{2}$; hence at H the absolute velocity is $w =$ (rel. veloc. $\frac{c}{2}$ toward left) $-$ (veloc. $\frac{c}{2}$ of vane toward right) $= 0$; Q.E.D. For $v >$ or $< \frac{1}{2}c$ this efficiency will not be attained.

567. **The California "Hurdy-gurdy;" or Pelton Wheel.**—The efficiency of unity in the series of cups just mentioned is in practice reduced to 80 or 85 per cent from friction and lateral escape of water. The Pelton wheel or California "Hurdy-gurdy," shown (in principle only) in Fig. 636, is designed to utilize the mechanical relation just presented, and yields results confirming the above theory, viz., that with the linear velocity of the cup-centres regulated to equal $\frac{c}{2}$, and with $\alpha = 180°$, the efficiency approaches unity or 100 per cent. Each cup has a projecting sharp edge or rib along the middle, to split the jet; see Fig. 635. (See also p. 70, *Hydraulic Motors*.)



FIG. 636.

This wheel was invented to utilize small jets of very great velocities (c) in regions just deserted by "hydraulic mining" operators. Although c is great, still, by giving a large value to r, the radius of the wheel, the making of $v = \frac{c}{2}$ does not necessitate an inconveniently great speed of rotation (i.e., revolutions per unit of time). The plane of the wheel may be in any convenient position.

In the London *Engineer* of May '84, p. 397, is given an account of a test* made of a "Hurdy-gurdy," in which the motor

* See p. 834 for further details of this test and a perspective view of wheel

showed an efficiency of 87 per cent. The diameter of the wheel was only 6 ft., that of the jet 1.89 in., and the head of the supply reservoir 386 ft., the water being transmitted through a pipe of 22 inches diameter and 6900 ft. in length. 107 H. P. was developed by the wheel.

EXAMPLE.—If the jet in Fig. 636 has a velocity $c = 60$ ft. per second, and is delivered through a 2-inch nozzle, the total power due to the kinetic energy of the water is (ft., lb., sec.)

$$\frac{Q'\gamma}{g}\cdot\frac{c^2}{2}=\frac{1}{32.2}\cdot\frac{\pi}{4}\left(\frac{2}{12}\right)^2\times 60\times 62.5\times\tfrac{1}{2}\times 3600=4566.9\left\{\begin{matrix}\text{ft. lbs.}\\ \text{p. sec.,}\end{matrix}\right.$$

and if, by making the velocity of the cups $= \frac{c}{2} = 30$ ft. per sec., 85 per cent of this power can be utilized, the power of the wheel at this most advantageous velocity is

$$L = .85 \times 4566.9 = 3881 \text{ ft. lbs. per sec.} = 7.05 \text{ horse-power}$$

[since $3881 \div 550 = 7.05$] (§ 132). For a cup-velocity of 30 ft. per sec., if we make the radius, r, $= 10$ feet, the angular velocity of the wheel will be $\omega = v \div r = 3\,0$ *radians* per sec. (for radian see Example in § 428; for angular velocity, § 110), which nearly $= \pi$, thus implying nearly a half-revolution per sec.

568. Oblique Impact of a Jet on a Moving Plate having no Border.—The plate has a motion of translation with a uniform veloc. $= v$ in a direction parallel to jet whose velocity is $= c$. At O the filaments of liquid are deviated, so that in leaving the plate their particles are all found in the moving plane BB' of the plate surface, but the respective absolute velocities of these particles



FIG. 637.

depend on the location of the point of the plate where they leave it, being found by forming a diagonal on the relative veloc. $c - v$ and the velocity v of the plate. For example, at B the absolute velocity of a liquid particle is

$$w = BE = \sqrt{v^2 + (c-v)^2 + 2v(c-v)\cos\alpha},$$

while at B' it is

$$w' = B'E' = \sqrt{v^2 + (c-v)^2 - 2v(c-v)\cos\alpha};$$

but evidently the component $\perp$ to plate (the other component being parallel) of the absolute velocities of *all particles leaving* the plate, is the same and $= v \sin\alpha$. The skin-friction of the liquid on the plate being neglected, the resultant impulse of the jet against the plate must be *normal* to its surface, and its amount, P, is most readily found as follows:

Denoting by ΔM the mass of the liquid passing over the plate in a short time Δt, resolve the absolute velocities of all the liquid particles, before and after deviation, into components $\perp$ to the plate (call this direction Y) and $\parallel$ to the plate. Before meeting the plate the particles composing ΔM have a velocity in the direction of Y of $c_y = c \sin\alpha$; on leaving the plate a velocity in direction of Y of $v \sin\alpha$: they have therefore lost an amount of velocity in direction of $Y = (c - v) \sin\alpha$ in time Δt; i.e., they have suffered an average retardation (or negative acceleration) in a Y-direction of

$$p_y = \left\{ \begin{matrix} \text{neg. accelera-} \\ \text{tion } \parallel \text{ to } Y \end{matrix} \right\} = \frac{(c-v)\sin\alpha}{\Delta t} \quad . \quad . \quad . \quad (1)$$

Hence the resistance in direction of Y (i.e., the equal and opposite of P in figure) must be

$$P_Y = \text{mass} \times Y\text{-accel.} = \frac{\Delta M}{\Delta t}(c-v)\sin\alpha; \quad . \quad . \quad (2)$$

and therefore, since $\frac{\Delta M}{\Delta t} = M = \frac{Q\gamma}{g} =$ mass of liquid passing

over the plate per unit of time (not that issuing from nozzle), we have

$$\left.\begin{matrix}\textit{Impulse or pressure on plate}\end{matrix}\right\} = P = \frac{Q\gamma}{g}(c-v)\sin\alpha = \frac{F\gamma}{g}(c-v)^2\sin\alpha, \quad (3)$$

in which F = sectional area of jet before meeting plate.

[N.B. Since eq. (3) can also be written $P = Mc\sin\alpha - Mv\sin\alpha$, and $Mc\sin\alpha$ may be called the Y-momentum before contact, while $Mv\sin\alpha$ is the Y-momentum after contact (of the mass passing over plate per unit of time), this method may be said to be founded on the *principle of momentum* which is nothing more than the relation that the accelerating force in any direction = mass × acceleration in that direction; e.g., $P_x = Mp_x$; $P_y = Mp_y$; see § 74.]

If we resolve P, Fig. 637, into two components, one, P', ∥ to the direction of motion (v and c), and the other, P'', ⅂ to the same, we have

$$P' = P\sin\alpha = \frac{Q\gamma}{g}(c-v)\sin^2\alpha, \quad . \quad . \quad . \quad . \quad (4)$$

and

$$P'' = P\cos\alpha = \frac{Q\gamma}{g}(c-v)\sin\alpha\cos\alpha. \quad . \quad . \quad (5)$$

($Q = F(c-v)$ = volume passing over the *plate* per unit of time.) The force P'' does no work, while the former, P', does an amount of work $P'v$ per unit of time; i.e., exerts a *power* (one plate)

$$= L = P'v = \frac{Q\gamma}{g}(c-v)v\sin^2\alpha. \quad . \quad . \quad . \quad (6)$$

If, instead of a single plate, a *series of plates*, forming a regular succession, is employed, then, as in a previous paragraph, we may replace Q, $= F(c-v)$, by $Q' = Fc$, obtaining as the

$$\left.\begin{matrix}\textit{Power exerted by jet on series of plates}\end{matrix}\right\} = L' = \frac{Fc\gamma}{g}(c-v)v\sin^2\alpha. \quad . \quad (7)$$

For $v = \frac{c}{2}$ and $\alpha = 90°$ we have

$$L'_{\max.} = \frac{1}{2}\frac{Fc\gamma}{g}\frac{c^2}{2} = \frac{1}{2}\frac{M'c^2}{2} \quad . \quad . \quad . \quad . \quad . \quad (8)$$

= only half the kinetic energy (per time-unit) of the jet.

569. Rigid Plates Moving in a Fluid, Totally Submerged. Fluid Moving against a Fixed Plate. Impulse and Resistance.— If a thin flat rigid plate have a motion of uniform *translation* with velocity $= v$ through a fluid which completely surrounds it, Fig. 638, a resistance is encountered (which must be overcome by an equal and opposite force, not shown in figure, to preserve the uniform motion) consisting of a normal component N, ⊥ to plate, and a (small) tangential component, or skin-friction, T, ∥ to plate.



FIG. 638.

Unless the angle α, between the surface of plate and the direction of motion $O \ldots v$, is very small, i.e. unless the plate is moving nearly edgewise through the fluid, N is usually much greater than T. The skin-resistance between a solid and a fluid has already been spoken of in § 510.

When the plate and fluid are at rest the pressures on both sides are normal and balance each other, being ordinary static fluid pressures. When motion is in progress, however, the normal pressures on the front surface are increased by the components, normal to plate, of the centrifugal forces of the curved filaments (such as AB) or "stream-lines," while on the back surface, D, the fluid does not close in fast enough to produce a pressure equal to that (even) of rest. In fact, if the motion is sufficiently rapid, and the fluid is inelastic (a liquid), a *vacuum may be maintained behind the plate*, in which case there is evidently no pressure on that side of the plate.

Whatever pressure exists on the back acts, of course, to diminish the resultant resistance. The water on turning the sharp corners of the plate is broken up into eddies forming a

"wake" behind. From the accompaniment of these eddies, the resistance in this case (at least the component N normal to plate) is said to be due to "*eddy-making*;" though logically we should say, rather, that the body does not derive the assistance (or negative resistance) from behind which it would obtain if eddies were not formed; i.e., if the fluid could close in behind in smooth curved stream-lines symmetrical with those in front.

The *heat* corresponding to the change of temperature produced in the portion of fluid acted on, by the skin-friction and by the mutual friction of the particles in the eddies, is the equivalent of the work done (or energy spent) by the motive force in maintaining the uniform motion (§ 149). (Joule's experiments to determine the Mechanical Equivalent of Heat were made with paddles moving in water.)

If the fluid is *sea-water*, the results of Col. Beaufoy's experiments are applicable, viz.:

The resistance, per square foot of area, sustained by a submerged plate moving normally to itself [i.e., $\alpha = 90°$] *in sea-water with a velocity of* $v = 10$ *ft. per second is* 112 *lbs.* He also asserts that *for other velocities the resistance varies as the square of the velocity.* This latter fact we would be led to suspect from the results obtained in § 568 for the impulse of jets; also in § 565 [see eq. (6)]. Also, that when the plate moved obliquely to its normal (as in Fig. 638) *the resistance was nearly equal to (the resistance, at same velocity, when* $\alpha = 90°$*)* $\times$ *(the sine of the angle* α*); also, that the depth of submersion had no influence on the resistance.*

FIG. 639.

Confining our attention to a plate *moving normally to itself*, Fig. 639, let F = area of plate, γ = heaviness (§ 409) of the fluid, v = the uniform velocity of plate, and g = the acceleration of gravity (= 32.2 for the foot and second; = 9.81 for the metre and second). Then from the analogy of eq. (6), § 565, where velocity c of the jet against a stationary plate corresponds to the velocity v of the plate in the present case moving through a fluid at rest, we may write

$$\left.\begin{matrix}\textit{Resistance of fluid}\\ \textit{to moving plate}\end{matrix}\right\} = R = \zeta F \gamma \frac{v^2}{2g} \cdots \left\{\begin{matrix}v \text{ normal}\\ \text{to plate}\end{matrix}\right\} \cdots (1)$$

And similarly for the *impulse of an indefinite stream of fluid against a fixed plate* (⌝ to velocity of stream), v being the velocity of the current,

$$\left.\begin{matrix}\textit{Impulse of current}\\ \textit{upon fixed plate}\end{matrix}\right\} = P = \zeta' F \gamma \frac{v^2}{2g} \cdots \left\{\begin{matrix}v \text{ normal}\\ \text{to plate}\end{matrix}\right\} \cdots (2)$$

The $2g$ is introduced simply for convenience; since, having v given, we may easily find $v^2 \div 2g$ from a table of velocity-heads; and also (a ground of greater importance) since the coefficients ζ and ζ' which depend on experiment are evidently *abstract numbers* in the present form of these equations (for R and P are forces, and $F\gamma v^2 \div 2g$ is the weight (force) of an ideal prism of fluid; hence ζ and ζ' must be abstract numbers.)

From Col. Beaufoy's experiments (see above), we have for *sea-water* [ft., lb., sec.], putting $R = 112$ lbs., $F = 1$ sq. ft., $\gamma = 64$ lbs. per cub. ft., and $v = 10$ ft. per second,

$$\zeta = \frac{2 \times 32.2 \times 112}{1.0 \times 64 \times 10^2} = 1.13.$$

Hence in eq. (1) for sea-water, we may put $\zeta = 1.13$ (with $\gamma = 64$ lbs. per cub. ft.).

From the experiments of Dubuat and Thibault, Weisbach computes that for the plate of Fig. 639, moving through either water or air, $\zeta = 1.25$ for eq. (1), in which the γ for air must be computed from § 473; while for the impulse of water or air on fixed plates he obtains $\zeta' = 1.86$ for use in eq. (2). It is hardly reasonable to suppose that ζ and ζ' should not be identical in value, and Prof. Unwin thinks that the difference in the numbers just given must be due to errors of experiment.* The latter value, $\zeta' = 1.86$, agrees well with equation (6) below. For great velocities ζ and ζ' are greater for air than for water, since air, being compressible, is of greater heaviness in front of the plate than would be computed for

* Flamant thinks that this difference is due to the fact that the relative conditions are not identical in the two cases; since when a current of liquid impinges against a stationary plate there is much intricacy of internal motion among the particles of fluid, to which there is nothing to correspond when a plate is moved through stationary liquid.

the given temperature and barometric height for use in eqs. (1) and (2)

The experiments of Borda in 1763 led to the formula

$$P = [0.0031 + 0.00035c]Sv^2 \quad . \quad . \quad . \quad . \quad (3)$$

for the total pressure upon a plate moving through the air in a direction ⊓ to its own surface. P is the pressure in pounds, c the length of the contour of the plate in feet, and S its surface in square feet, while v is the velocity in miles per hour. Adopting the same form of formula, Hagen found, from experiments in 1873, the relation

$$P = [0.002894 + 0.00014c]Sv^2 \quad . \quad . \quad . \quad (4)$$

for the same case of fluid resistance.

Hagen's experiments were conducted with great care, but like Borda's were made with a "whirling machine," in which the plate was caused to revolve in a horizontal circle of only 7 or 8 feet radius at the end of a horizontal bar rotating about a vertical axis. Hagen's plates ranged from 4 to 40 sq. in. in area, and the velocities from 1 to 4 miles per hour.

The last result was quite closely confirmed by Mr. H. Allen Hazen at Washington in November 1886, the experiments being made with a whirling machine and plates of from 16 to 576 sq. in. area. (See the *American Journal of Science*, Oct. 1887, p. 245.)

In Thibault's experiments plates of areas 1.16 and 1.531 sq. ft. were exposed to direct wind-pressure, giving the formula

$$P = 0.00475Sv^2. \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

Recent experiments in France (see *R. R. and Eng. Journal*, Feb. '87), where flat boards were hung from the side of a railway train run at different velocities, gave the formula

$$P = 0.00535Sv^2. \quad . \quad . \quad . \quad . \quad . \quad . \quad (6)$$

The highest velocity was 44 miles per hour. The magnitude of the area did not seemingly affect the relation given.* More

* Langley found $P = 0.00327Sv^2$. See also Irminger's experiments (*Engineering News*, Feb. 1895, p. 109).

extended and elaborate experiments are needed in this field, those involving a motion of translation being considered the better, rather than with whirling machines, in which "centrifugal action" must have a disturbing influence.*

The notation and units for eqs. (4), (5), and (6) are the same as those given for (3).

It may be of interest to note that if equation (3) of § 568 be considered applicable to this case of the pressure of an unlimited stream of fluid against a plate placed at right-angles to the current, with F put equal to the area of the plate, we obtain, after reduction to the units prescribed above for the preceding equations and putting $\alpha = 90°$,

$$P = 0.0053 S v^2. \quad . \quad . \quad . \quad . \quad . \quad . \quad (7)$$

The value $\gamma = 0.0807$ lbs. per cub. ft. has been used in the substitution, corresponding to a temperature of freezing and a barometric height of 30 inches. At higher temperatures, of course, γ would be less, unless with very high barometer.

569a. **Example.**—Supposing each blade of the paddle-wheel of a steamer to have an area of 6 sq. ft., and that when in the lowest position its velocity [relatively to the water, not to the vessel] is 5 ft. per second; what resistance is it overcoming in salt water?

From eq. (1) of § 569, with $\zeta = 1.13$ and $\gamma = 64$ lbs. per cubic foot, we have (ft., lb., sec.)

$$R = \frac{1.13 \times 6 \times 64 \times 25}{2 \times 32.2} = 169.4 \text{ lbs.}$$

If on the average there may be considered to be three paddles always overcoming this resistance on each side of the boat, then the work lost (work of "*slip*") in overcoming these resistances per second (i.e., *power* lost) is

$L_1 = [6 \times 169.4]$ lbs. $\times$ 5 ft. per sec. $= 5082$ ft.-lbs. per sec.

or 9.24 Horse Power (since $5082 \div 550 = 9.24$).

* See Capt. Bixby's article on p. 175 *et seq.* of the *Engineering News*, March 1895.

If, further, the velocity of the boat is *uniform* and = 20 ft. per sec., the resistance of the water to the progress of the boat at this speed being 6×169.4, i.e. 1016.4 lbs., the power expended in actual propulsion is

$$L_2 = 1016.4 \times 20 = 20328 \text{ ft.-lbs. per sec.}$$

Hence the power expended in both ways (usefully in propulsion, uselessly in "slip") is

$$L_2 + L_1 = 25410 \text{ ft.-lbs. per sec.} = 46.2 \text{ H. P.}$$

Of this, 9.24 H. P., or about 20 per cent, is lost in "slip."



FIG. 640.

570. Wind-pressure on the surface of a roof inclined at an angle $= \alpha$ with the horizontal, i.e., with the direction of the wind, is usually estimated according to the empirical formula (Hutton's)

$$p = p' [\sin \alpha]^{[1.84 \cos \alpha - 1]}, \quad . \quad . \quad . \quad . \quad . \quad (1)$$

in which p' = pressure of wind per unit area against a *vertical* surface (⊓ to wind), and p = that against the inclined plane (*and normal to it*) at the same velocity. For a value of $p' = 40$ lbs. per square foot (as a maximum), we have the following values for p, computed from (1):

For $\alpha =$	5°	10°	15°	20°	25°	30°	35°	40°	45°	50°	55°	60°
$p =$(lbs. sq. ft.)	5.2	9.6	14	18.3	22.5	26.5	30.1	33.4	36.1	38.1	39.6	40.

Duchemin's formula for the normal pressure per unit-area is

$$p = p' \cdot \frac{2 \sin \alpha}{1 + \sin^2 \alpha}, \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

with the same notation as above. Some experimenters in London tested this latter formula by measuring the pressure on a metal plate supported in front of the blast-pipe of a blowing engine; the results were as follows:

$\alpha =$	15°	20°	60°	90°
p by experiment = (in lbs. per sq. ft.)	1.65	2.05	3.01	3.31
By Duchemin's formula $p =$	1.60	2.02	3.27	3.31

The scale of the Smithsonian Institution at Washington for the estimation and description of the velocity and pressure of the wind is as follows:

Grade.	Velocity in miles per hour.	Pressure per sq. foot in lbs.	Name.
0	0	0.00	Calm.
1	2	0.02	Very light breeze.
2	4	0.08	Gentle breeze.
3	12	0.75	Fresh wind.
4	25	3.00	Strong wind.
5	35	6	High wind.
6	45	10	Gale.
7	60	18	Strong gale.
8	75		Violent gale.
9	90		Hurricane.
10	100		Most violent hurricane.

571. Mechanics of the Sail-boat.—The action of the wind on a sail will be understood from the following. Let Fig. 641 represent the boat in horizontal projection and OS the sail, O being the mast. For simplicity we consider the sail to be a plane and to remain vertical. At this instant the boat is moving in the direction MB of its fore-and-aft line with a velocity $= c$, the wind having a velocity of the direction and magnitude represented by w (purposely taken at an angle $< 90°$ with the direction of motion of the boat). We are now to inquire the nature of the action of the wind on the boat, and whether



FIG. 641.

in the present position its tendency is to accelerate, or retard, the motion of the boat. If we form a parallelogram of which w is the diagonal and c one side, then the other side OK, making some angle α with BM, will be the velocity v of the wind *relatively to the boat* (and sail), and upon this (and not upon w) depends the action on the sail. The sail, being so placed that the angle θ is smaller than α, will experience pressure from the wind; that is, from the impact of the particles of air which strike the surface and glance along it. This pressure, P, is normal to the sail (considered smooth), and evidently, for the position of the parts in the figure, the component of P along MB points in the same direction as c, and hence if that component is greater than the water-resistance to the boat at this velocity, c will be accelerated; if less, c will be retarded. Any change in c, of course, gives a different form to the parallelogram of velocities, and thus the relative velocity v and the pressure P, for a given position of the sail, will both change. [The component of P ⊥ to MB tends, of course, to cause the boat to move laterally, but the great resistance to such movement at even a very slight lateral velocity will make the resulting motion insignificant.]

As c increases, α diminishes, for a given amount and position of w; and the sail must be drawn nearer to the line MB, i.e. θ must be made to decrease, to derive a wind-pressure having a *forward* fore-and-aft component; and that component becomes smaller and smaller. But if the craft is an ice-boat, this small component may still be of sufficient magnitude to exceed the resistance and continue the acceleration of c until c is larger than w; i.e., the boat may be caused to go as fast as, or faster than, the wind, and still be receiving from the latter a forward pressure which exceeds the resistance. And it is plain that there is nothing in the geometry of the figure to preclude such a relation (i.e., $c > w$, with $\theta < \alpha$ and > 0).

572. Resistance of Still Water to Moving Bodies, Completely Immersed.—This resistance depends on the shape, position, and velocity of the moving body, and also upon the roughness of its surface. If it is pointed at both ends (Fig. 642) with its

axis parallel to the velocity, v, of its *uniform* motion, the stream lines on closing together smoothly at the hinder extremity, or stern, B, exert normal pressures against the surface of the portion $CD...B$ whose longitudinal components approximately balance the corresponding components of the normal pressures on $CD \ldots A$; so that the resistance R, which must be overcome to maintain the uniform velocity v, is *mainly due to the "skin-friction"* alone, distributed along the external surface of the body; the resultant of these resistances is a force R acting in the line AB of symmetry (supposing the body symmetrical about the direction of motion).



FIG. 642.

If, however, Fig. 643, the stern, $E..B..F$ is too bluff, eddies are formed round the corners E and F, and the pressure on the surface $E \ldots F$ is much less than in Fig. 642; i.e., the water pressure from behind is less than the backward (longitudinal) pressures from in front, and thus the resultant resistance R is due partly to skin-friction and partly to "eddy-making" (§ 569).



FIG. 643.

[NOTE.—The diminished pressure on EF is analogous to the loss of pressure of water (flowing in a pipe) after passing a narrow section the enlargement from which to the original section is sudden. E.g., Fig. 644, supposing the velocity v and pressure p (per unit-area) to be the same respectively at A and A', in the two pipes shown, with diameter $AL = WK = A'L' = W'K'$; then the pressure at M is equal to that at A (disregarding skin-friction), whereas that at



FIG. 644.

that at M is considerably *less* than that at A' on account of the head lost in the sudden enlargement. (See also Fig. 575.)]

It is therefore evident that *bluffness of stern may be a large factor in the production of resistance.*

In any case experiment shows that for a given body symmetrical about an axis and moving through a fluid (not only water, but any fluid) in the direction of its axis with a uniform velocity $= v$, we may write approximately the resistance

$$R = (\textit{resistance at vel. } v) = \zeta F \gamma \frac{v^2}{2g}. \quad . \quad . \quad . \quad (1)$$

As in preceding paragraphs, F = area of the *greatest* section, ⊓ to axis, of the external *surface* of body (not of the substance; i.e., the sectional area of the circumscribing cylinder (cylinder in the most general sense) with elements parallel to the axis of the body. γ = the heaviness (§ 409) of the fluid, and v = velocity of motion; while ζ is an *abstract number* dependent on experiment.

According to Weisbach, who cites different experimenters, we can put for *spheres*, moving in water, ζ = about 0.55; for cannon-balls moving in water, $\zeta = .467$.

According to Robins and Hutton, for *spheres* in *air*, we have

For v in mets. per sec.	1	5	25	100	200	300	400	500	meters per sec.
$\zeta =$	.59	.63	.67	.71	.77	88	.99	1.04	

For musket-balls in the air, Piobert found

$$\zeta = 0.451\ (1 + 0.0023 \times \text{veloc. in metres per sec.}).$$

From Dubuat's experiments, for the resistance of water to a right prism moving endwise and of length $= l$,

For $(l : \sqrt{F}) =$	0	1	2	3
$\zeta =$	1.25	1.26	1.31	1.33

For a circular cylinder moving perpendicularly to its axis Borda claimed that ζ is one-half as much as for the circum-

scribing right parallelopiped moving with four faces parallel to direction of motion.

EXAMPLE.—The resistance of the air at a temperature of freezing and tension of one atmosphere to a musket-ball $\frac{1}{2}$ inch in diameter when moving with a velocity of 328 ft. per sec. is thus determined by Piobert's formula, above:

$$c = 0.451(1 + .0023 \times 100) = 0.554;$$

hence, from eq. (1),

$$R = 0.554 \times \frac{\pi}{4}\left(\frac{\frac{1}{2}}{12}\right)^2 \times .0807 \times \frac{(328)^2}{64.4} = 0.1018 \text{ lbs.}$$

572a. Deviation of a Spinning Ball from a Vertical Plane in Still Air.—It is a well-known fact in base-ball playing that if a rapid spinning motion is given to the ball about a vertical axis as well as a forward motion of translation, its path will not remain in its initial vertical plane, but curve out of that plane toward the side on which the absolute velocity of an external point of the ball's surface is least. Thus, if the ball is thrown from North to South, with a spin of such character as to appear "*clock-wise*" seen from above, the ball will curve *toward the West*, out of the vertical plane in which it started.

This could not occur if the surface of the ball were perfectly smooth (there being also no adhesion between that surface and the air particles), and is due to the fact that the cushion of compressed air which the ball piles up in front during its progress, and which would occupy a symmetrical position with respect to the direction of motion of the centre of the ball if there were no motion of rotation of the kind indicated, is now piled up somewhat on the East of the centre (in example above), creating constantly more obstruction on that side than on the right; the cause of this is that the absolute velocity of the surface-points, at the same level as the centre of ball, is greatest, and the friction greatest, at the instant when they are passing through their extreme Easterly positions; since then that velocity is the *sum* of the linear velocity of translation and that of rotation; whereas, in the position diametrically oppo-

site, on the West side, the absolute velocity is the *difference;* hence the greater accumulation of compressed air on the left (in the case above imagined, ball thrown from North to South, etc.).

573. Robinson's Cup-anemometer.—This instrument, named after Dr. T. R. Robinson of Armagh, Ireland, consists of four hemispherical cups set at equal intervals in a circle, all facing in the same direction round the circle, and so mounted on a light but rigid framework as to be capable of rotating with but little friction about a vertical axis. When in a current of air (or other fluid) the apparatus begins to rotate with an accelerated velocity on account of the pressure against the open mouth of a cup on one side being greater than the resistance met by the back of the cup diametrically opposite. Very soon, however, the motion becomes practically uniform, the cup-centre having a constant linear velocity v'' the ratio of which to the velocity, v', of the wind at the same instant must be found in some way, in order to deduce the value of the latter from the observed amount of the former in the practical use of the instrument. After sixteen experiments made by Dr. Robinson on stationary cups exposed to winds of varying intensities, from a gentle breeze to a hard gale, the conclusion was reached by him that with a given wind-velocity the total pressure on a cup with concave surface presented to the wind was very nearly four times as great as that exerted when the convex side was presented, whatever the velocity (see vol. XXII of *Transac. Irish Royal Acad., Part I*, p. 163).

Assuming this ratio to be exactly 4.0 and neglecting axle-friction, we have the data for obtaining an approximate value of m, the ratio of v' to the observed v'', when the instrument is in use. The influence of the wind on those cups the planes of whose mouths are for the instant $\parallel$ to its direction will also be neglected.

If, then, Fig. 645, we write the *impulse* on a cup when the hollow is presented to the wind [§ 572, eq. (1)]

$$P_h = \zeta_h F \gamma \frac{v_1^2}{2g}, \quad \ldots \ldots \quad (1)$$

and the *resistance* when the convex side is presented

$$P_c = \zeta_c F \gamma \frac{v_2^2}{2g}, \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

we may also put

$$\zeta_h = 4\zeta_c. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

In (1) and (2) v and v_2 are relative velocities.

Regarding only the two cups A and B, whose centres at a definite instant are moving in lines parallel to the direction of the wind, it is evident that the motion of the cups does not become uniform until the relative velocity $v' - v''$ of the wind and cup A (retreating before the wind) has become so small, and the relative velocity $v' + v''$ with which B advances to meet the air-particles has become so great, that the impulse of the wind on A *equals* the resistance encountered by B; i.e., these forces, P_h and P_c, must be equal, having equal lever-arms about the axis. Hence, for uniform rotary motion,



FIG. 645.

$$\zeta_h F \gamma \frac{(v' - v'')^2}{2g} = \zeta_c F \gamma \frac{(v' + v'')^2}{2g}; \quad . \quad . \quad . \quad (4)$$

i.e. [see eq. (3)],

$$4\left[\frac{v'}{v''} - 1\right]^2 = \left[\frac{v'}{v''} + 1\right]^2; \quad \text{or,} \quad 4(m-1)^2 = (m+1)^2. \quad . \quad (5)$$

Solving the quadratic for m, we obtain

$$m = 3.00. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (6)$$

That is, the velocity of the wind is about three times that of the cup-centre.

574. Experiments with Robinson's Cup-anemometer. –The ratio 3.00 just obtained is the one in common use in connection with this instrument in America. Experiments by Mr.

Hazen at Washington in 1886 (*Am. Jour. Science*, Oct. '87, p. 248) were made on a special type devised by Lieut. Gibbon. The anemometer was mounted on a whirling machine at the end of a 16-ft. horizontal arm, and values for m obtained, with velocities up to 12 miles per hour, from 2.84 to 3.06; average 2.94. The cups were 4 in. in diameter and the distance of their centres from the axis 6.72 in., these dimensions being those usually adopted in America. This instrument was nearly new and was well lubricated.

Dr. Robinson himself made an extensive series of experiments, with instruments of various sizes, of which an account may be found in the *Philos. Transac.* for 1878, p. 797 (see also the volume for 1880, p. 1055). Cups of 4 in. and also of 9 in. were employed, placed first at 24 and then at 12 in. from the axis. The cup-centres revolved in a (moving) vertical plane perpendicular to the horizontal arm of a whirling-machine; this arm, however, was only 9 ft. long. A friction-brake was attached to the axis of the instrument for testing the effect of increased friction on the value of m. At high speeds of 30 to 40 miles per hour (i.e., the speed of the centre of the instrument in its horizontal circle, representing an equal speed of wind for an instrument in actual use with axis stationary) the effect of friction was relatively less than at low velocities. That is, at high speeds with considerable friction the value of m was nearly the same as with little friction at low speeds. With the large 9 in. cups at a distance of either 24 or 12 in. from the axis the value of m at 30 miles per hour ranged generally from 2.3 to 2.6, with little or much friction; while with the minimum friction m rose slowly to about 2.9 as the velocity diminished to 10 miles per hour. At 5 miles per hour with minimum friction m was 3.5 for the 24 in. instrument and about 5.0 for the 12 in. The effect of considerable friction at low speeds was to increase m, making it as high as 8 or 10 in some cases. With the 4 in.-cups no value was obtained for m less than 3.3. On the whole, Dr. Robinson concluded that m is more likely to have a constant value at all velocities the larger the cups, the longer the arms, and the less the friction, of the anemometer. But few straight-line experi-

ments have been made with the cup-anemometer, the most noteworthy being mentioned on p. 308 of the *Engineering News* for October 1887. The instrument was placed on the front of the locomotive of a train running between Baltimore and Washington on a calm day. The actual distance is 40 miles between the two cities, while from the indications of the anemometer, assuming $m = 3.00$, it would have been in one trip 46 miles and in another 47. The velocity of the train was 20 miles per hour in one case and 40 in the other.

575 Other Anemometers.—Both Biram's and Castello's anemometers consist of a wheel furnished with radiating vanes set obliquely to the axis of the wheel, forming a small "windmill," somewhat resembling the current-meter for water shown in Fig. 604; having six or eight blades, however. The wheel revolves with but little friction, and is held in the current of air with its axis parallel to the direction of the latter, and very quickly assumes a steady motion of rotation. The number of revolutions in an observed time is read from a dial. The instruments must be rated by experiment, and are used chiefly in measuring the velocity of the currents of air in the galleries of mines, of draughts of air in flues and ventilating shafts, etc.

To quote from vol. v of the Report of the Geological Survey of Ohio, p. 370: "Approximate measurements (of the velocity of air) are made by miners by flashing gunpowder, and noting with a watch the speed with which the smoke moves along the air-way of the mine. A lighted lamp is sometimes used, the miner moving along the air-gallery, and keeping the light in a perfectly perpendicular position, noting the time required to pass to a given point."

Another kind makes use of the principle of Pitot's Tube (p. 751), and consists of a U-tube partially filled with water, one end of the tube being vertical and open, while the other turns horizontally, and is enlarged into a wide funnel, whose mouth receives the impulse of the current of air; the difference of level of the water in the two parts of the U is a measure of the velocity.

576. **Resistance of Ships.***—We shall first suppose the ship *to be towed* at a uniform speed; i.e., to be without means of self-propulsion (under water). This being the case, it is found that at moderate velocities (under six miles per hour), the ship being of "*fair*" form (i.e., the hull tapering both at bow and stern, under water) the resistance in still water is almost wholly due to *skin-friction*, "eddy-making" (see § 569) being done away with largely by avoiding a bluff stern.

When the velocity is greater than about six miles an hour the resistance is much larger than would be accounted for by skin-friction alone, and is found to be connected with the surface-disturbance or waves produced by the motion of the hull in (originally) still water. The recent experiments of Mr. Froude and his son at Torquay, England, with models, in a tank 300 feet long, have led to important rules (see Mr. White's *Naval Architecture* and "Hydromechanics" in the *Ency. Britann.*) of so proportioning not only the total length of a ship of given displacement, but the length of the *entrance* (forward tapering part of hull) and length of *run* (hinder tapering part of hull), as to secure a minimum "*wave-making resistance*," as this source of resistance is called.

To quote from Mr. White (p. 460 of his *Naval Architecture*, London, 1882): "Summing up the foregoing remarks, it appears:

"(1) That *frictional resistance*, depending upon the area of the immersed surface of a ship, its degree of roughness, its length, and (about) the square of its speed, is not sensibly affected by the forms and proportions of ships; unless there be some unwonted singularity of form, or want of fairness. For *moderate speeds* this element of resistance is by far the most important; for high speeds it also occupies an important position—from 50 to 60 per cent of the whole resistance, probably, in a very large number of classes, when the bottoms are *clean;* and a larger percentage when the bottoms become foul.

"(2) That *eddy-making resistance* is usually small, except in special cases, and amounts to 8 or 10 per cent of the frictional

* Not in canals, but in water of indefinite width and depth.

resistance. A defective form of stern causes largely increased eddy-making.

"(3) That *wave-making resistance* is the element of the total resistance which is most influenced by the forms and proportions of ships. Its ratio to the frictional resistance, as well as its absolute magnitude, depend on many circumstances; the most important being the forms and lengths of the entrance and run, in relation to the intended full speed of the ship. For every ship there is a limit of speed beyond which each small increase in speed is attended by a disproportionate increase in resistance; and this limit is fixed by the lengths of the entrance and run—the 'wave-making features' of a ship.

"The sum of these three elements constitutes the total resistance offered by the water to the motion of a ship towed through it, or propelled by sails; in a steamship there is an '*augment*' of resistance due to the action of the propellers."

In the case of a steamship driven by a screw propeller, this *augment* to the resistance varies from 20 to 45 per cent of the "tow-rope resistance," on account of the presence and action of the propeller itself; since its action relieves the stern of some of the *forward* hydrostatic pressure of the water closing in around it. Still, if the screw is placed far back of the stern, the augment is very much diminished; but such a position involves risks of various kinds and is rarely adopted.

We may compute approximately the resistance of the water to a ship propelled by steam at a uniform velocity v, in the following manner: Let L denote the power developed in the engine cylinder; whence, allowing 10 per cent of L for engine friction, and 15 per cent for "work of slip" of the propeller-blade, we have remaining $0.75L$, as expended in overcoming the resistance R through a distance $= v$ each unit of time; i.e.,

(*approx.*) $$0.75L = Rv. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

Example.—If 3000 indicated H. P. (§ 132) is exerted by the engines of a steamer at a uniform speed of 15 miles per hour

(= 22 ft. per sec.), we have (with above allowances for slip and engine friction) [foot-lb.-sec.]

$$\tfrac{3}{4} \times 3000 \times 550 = R \times 22; \quad \therefore \quad R = 56250 \text{ lbs.}$$

Further, since R varies (roughly) as the *square* of the velocity, and can therefore be written $R = (\text{Const.}) \times v^2$, we have from (1)

$$L = a \text{ constant} \times v^3 \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

as a roughly approximate relation between the speed and the power necessary to maintain it uniformly. In view of eq. (3) involving the *cube* of the velocity as it does, we can understand why a large increase of power is necessary to secure a proportionally small increase of speed.

577. **"Transporting Power," or Scouring Action, of a Current.**—The capacity or power of a current of water in an open channel to carry along with it loose particles, sand, gravel, pebbles, etc., lying upon its bed was investigated experimentally by Dubuat about a century ago, though on a rather small scale. His results are as follows:

The velocity of current must be at least

0.25	ft.	per	sec.,	to transport silt;
0.50	"	"	"	loam;
1.00	"	"	"	sand;
2.00	"	"	"	gravel;
3.5	"	"	"	pebbles 1 in. in diam.;
4.0	"	"	"	broken stone;
5.0	"	"	"	chalk, soft shale.

When a current holds "*silt*," (i.e., fine clay, sand, or mud) in suspension, the latter may be deposited if conditions of velocity, or of depth, change. According to Kennedy's observations on certain canals in India, silt will be deposited if the velocity falls below a certain critical value, *different for different depths of stream.* Some of these values, with the corresponding depths are here given (Bellasis, *Hydraulics*, p. 179):

For $d =$	1	2	3	4	5	6	7	8	9	10 ft.
$v =$	.84	1.3	1.7	2.04	2.35	2.64	2.92	3.18	3.43	3.67 ft./sec.

In case the particles move in filaments or stream-lines parallel to the axis of the stream the statement is sometimes made that *the "transporting power" varies as the sixth power*

of the velocity of the current, by which is meant, more definitely, the following: Fig. 646. Conceive a row of cubes (or other solids geometrically *similar* to each other) of many sizes, all of the same heaviness (§ 7), and similarly situated, to be placed on the horizontal bottom of a trough and there exposed to a current of water, being completely immersed. Suppose the coefficient of friction between the cubes and the trough-bottom to be the same for all. Then, as the current is given greater and greater velocity v, the impulse P_m (corresponding to a particular velocity v_m) against some one, m, of the cubes, will be just sufficient to move it, and at some higher velocity v_n the impulse P_n against some larger cube, n, will be just sufficient to move it, in turn. We are to prove that $P_m : P_n :: v_m^6 : v_n^6$.



FIG. 646.

Since, when a cube barely begins to move, the impulse is equal to the friction on its base, and the frictions under the cubes (when motion is impending) are proportional to their volumes (see above), we have therefore

$$\frac{P_m}{P_n} = \frac{x_m^3}{x_n^3} \quad \ldots \ldots \ldots \quad (1)$$

Also, the impulses on the cubes, whatever the velocity, are proportional to the face areas and to the squares of the velocities (nearly; see § 572); hence

$$\frac{P_m}{P_n} = \frac{v_m^2 x_m^2}{v_n^2 x_n^2} \quad \ldots \ldots \ldots \quad (2)$$

From (1) and (2) we have

$$\frac{v_m^2}{v_n^2} = \frac{x_m}{x_n}; \quad \text{i.e.,} \quad \frac{x_m^2}{x_n^2} = \frac{v_m^4}{v_n^4}; \quad \ldots \quad (3)$$

while from (3) and (2) we have, finally,

$$P_m : P_n :: v_m^6 : v_n^6. \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

Thus we see in a general way why it is that if the velocity of a stream is doubled its transporting power is increased about sixty-four-fold; i.e., it can now impel along the bottom pebbles that are sixty-four times as heavy as the heaviest which it could move before (of same shape and heaviness).

Though rocks are generally from two to three times as heavy as water, their loss of weight under water causes them to encounter less friction on the bottom than if not immersed.

578. Recent Experiments with Fire-hose, Nozzles, etc. (Addendum to § 520.)—The very full and careful investigations of Mr. J. R. Freeman, hydraulic engineer of Boston, Mass., in this line (see Transac. A. S. C. E., Nov. 1889) furnish the following results: By taking piezometer readings at the ends of a portion of fire-hose conducting a steady flow of water, the values of loss of pressure due to fluid friction per 100 feet of length could be computed; a careful measurement being also made of the diameter of the hose and of the volume of water transmitted in an observed time. The table here given presents results applicable to hose of exactly 2.5 inches diameter, for a delivery of water at the rate of 240 gallons per minute (that is, for a velocity in the hose of 15.68 ft. per sec.). (The value of f has been computed by the writer.)

Sample.	Description.	Loss of pressure, per 100 ft. of length, in lbs. per sq. in.	Coefficient f. (See § 520.)	Velocity of water in hose.
L	Unlined linen hose	33.2	0.01045	15.68
K	Woven cotton, rubber-lined, "Mill Hose"	25.5	0.00802	15.68
I	K. " cotton, rubber-lined, hose.	19.4	0.00610	15.68
E	Ditto, but interstices between threads well filled	16.0	0.00503	15.68
C	Woven cotton, rubber-lined, hose. So well filled with the rubber that the inner surface remained smooth under pressure	14.1	0.00443	15.68

It was found that with other rates of flow the friction-head varied nearly as the square of the velocity. The great importance of a smooth interior of hose is well shown by this table.

A short section of each kind of hose was filled with liquid plaster *under pressure*. After the setting of the plaster the hose was removed and photographs taken of the cast, thus conveying a definite idea of the degree of roughness of interior of hose.

As to nozzles, it was found that the plain conical nozzle gave the best results, jets from the ring-nozzles being slightly inferior in range.

By means of a very delicate form of Pitot's tube measurements were made of the velocity in different parts of the section of jets, near the nozzle, with the interesting result that in "about two-thirds the whole distance from centre to circumference the velocity remains the same as at centre," and that at $\frac{1}{8}$ inch from the wall of most of the orifices the velocity was only 5% less than at centre of jet. With a jet from a 5-foot length of brass tubing $1\frac{1}{8}$ inch in diameter and used as a nozzle the velocity fell off rapidly for filaments further from the centre; e.g., at half the distance from centre to circumference the velocity was 90% of that at the centre, and at the outside edge 60%. Most of the nozzles ranged from 1 in. to $1\frac{1}{4}$ in. in diameter of orifice.

By using these velocity measurements to "gauge" the flow it was found that the relation $h' = \frac{c^2}{2g}$ was quite closely borne out (within 1%) (see eq. (7)", p. 804). The point of the Pitot tube was conically convergent, its extremity being 0.017 in. in external diameter and containing an orifice of 0.006 in. diameter. A minute passage-way led from the orifice to a Bourdon gauge.

Based on his experiments, Mr. Freeman gives tables for the maximum vertical height, V, and also the maximum horizontal range, H, of "*good effective fire-streams*" delivered from smooth conical nozzles of various sizes and with different piezometer pressures p (in lbs. p. sq. in. above atmosphere) at the base of play-pipe, the gauge being at same level as nozzle. (The distances reached by the extreme drops are very much greater with the high pressures. V and H are in feet.)

The following is a brief synopsis of this table. d is the internal diameter of the extremity of nozzle. The maximum horizontal range was obtained at an angle of elevation of about 32°.

For p =	10		20		40		60		80		100	
	V	H	V	H	V	H	V	H	V	H	V	H
$d = \frac{3}{4}$ in.	17 ft.	19	33	29	60	44	72	54	79	62	83	68
$d = \frac{7}{8}$ "	18	21	34	33	62	49	77	61	85	70	90	76
$d = 1$ "	18	21	35	37	64	55	79	67	89	76	96	83
$d = 1\frac{1}{8}$ "	18	22	36	38	65	59	83	72	92	81	99	89
$d = 1\frac{1}{4}$ "	19	22	37	40	67	63	85	76	95	85	101	93
$d = 1\frac{3}{8}$ "	20	23	38	42	69	66	87	79	97	88	103	96

579. Addendum on the Pelton Water-wheel.—The annexed cut and additional details of the test alluded to on p. 810 are taken from circulars of the manufacturers, of San Francisco, Cal.



The water was measured over an iron weir ⅛″ thick and 3.042 feet long without end contraction.

The depth was measured by a Boyden hook gauge reading to .001″, and was .4146 foot. The quantity of water discharged was found to be 2.819 cubic feet per second—Fteley's formula. The head lost by friction in pipe was 1.8 feet, reducing the effective head to 384.7 feet.

The work done was measured by a Prony brake bearing vertically down upon a platform scale and which showed a weight of 200 pounds upon the scale-beam when the brake gear was suspended by a cord from a point immediately above the wheel-shaft. This made a constant minus correction of 200 pounds. The friction pulley had a face of 12″, and being kept wet by a jet of clear cold water, it developed very little heat and ran without much jumping. Thirteen tests were made showing very uniform results, the first four of which were as follows:

Tests.	Weight shown by scale	Net weight (—200 lbs.)	Rev. wheel-shaft per min.	
1	665	$G = 465$	$u = 254\frac{1}{4}$	$Gu = 118342$
2	665	465	255	118575
3	660	460	256	117760
4	660	460	$256\frac{1}{4}$	117990
			Totals 1022	472667
			Means $255\frac{1}{4}$	118167

The arm of the Prony brake was 4.775 feet from centre of wheel-shaft to point of contact on scale and hence described a circle with a circumference of 30 feet. The work done per minute was therefore $Gu(2\pi r) =$ (118167 × 30) or 3,545,000 foot-pounds, equal to 107.4 horse-power. The theoretical power of the water was (2.819 × 60 × 384.7 × 62.4) or 4,060,258 foot-pounds. The useful effect was therefore 87.3 per cent.

APPENDIX.

Note.—This appendix contains addenda and tables, and also several pages from a former edition of the book. In these last the numbering of the articles and of the figures has been left unchanged.

48a. Addendum to § 55. Mass.—In PHYSICS, the fundamental units are those of

SPACE, involving a unit of length (and thence of area and volume);
TIME, " a unit of time, usually the second;
MASS, " a unit of mass, which (by Government decree) may be the quantity of matter in a specified piece of platinum, or specified volume of water, etc. (a beam-balance being used to determine equal quantities of mass); while

FORCE involves a derived unit, being measured by its effect in accelerating the velocity of a moving mass, since it is proportional both to the mass and the acceleration. The unit force (called absolute unit) is the force necessary to produce unit acceleration in a unit of mass; so that to produce an acceleration $= p$ in a mass $= m$ requires a force $= F = mp$, and the force thus obtained is in absolute units. This is called the dynamic measure of a force.

Example.—In the C.G.S. system of units, required the constant force necessary to cause a mass of 400 grams to gain 200 velocity units in 2 sec; i.e., $p = 100$ centims. per sec., per sec. From $F = mp$ we have

$$F = 400 \times 100 = 40000 \text{ abs. units of force (or dynes, in C.G.S. system).}$$

In the ft.-lb.-sec. system the absolute unit is called a *poundal.*

In MECHANICS OF ENGINEERING, however, it is more convenient to regard the fundamental units to be those of

SPACE, as ft., metre, etc., area and volume corresponding;
TIME, as seconds, hours, etc.;
FORCE, as lbs., grams, kilograms, tons, etc., indicated by a *spring balance;* while for

MASS we assume a derived unit, a mode of measuring it being developed as follows:

If by experiment (block on smooth table, for instance) we find that a constant force P (lbs., tons, kilos.) will maintain an acceleration $= p$ in the rectilinear motion (in line of force) of a body whose weight (by previous trial with a spring balance) is G (lbs., tons, or other unit); and if in a second experiment, by allowing the force G to act on the same body in vacuo, a free vertical fall with acceleration $= g$ is the result,—we find that the proportion (Newton's 2d Law) $P : G :: p : g$ is verified. This may be written $P = \frac{G}{g} \cdot p$, and may then be read: Force = mass $\times$ acceleration, if we call the quotient $G \div g$ the MASS of the body whose weight (by spring balance) is $= G$ at a locality where the acceleration of gravity $= g$; for this quotient will be the same at all localities on the earth's surface.

Example (same as above).—If a body whose weight $G = 400$ grams (force) is to have its velocity increased, in 2 sec., from 300 centims. per sec. to 500 centims. per sec., at a uniform rate, we must provide a constant force

$$P = \frac{400}{981} \times 100 = \frac{40000}{981} = 40.77 \text{ grams; or } .040 \text{ kilos.}$$

This is called the *gravitation measure* of a force. Hence it is evident that to reduce absolute units (called *dynes* and *poundals*) in the C.G.S. and ft.-lb.-sec. systems, respectively) to ordinary practical units of force (lbs., tons, kilos., etc., of a spring balance), *we divide by the value of g proper to the system of units employed;* and *vice versâ.*

(Addendum to § 49a of page 49.) Numerical Example.—A set of light screens is set up at intervals of 100 feet apart in the horizontal path of a cannon-ball, with the object of determining its velocity, and also the rate of change (or negative acceleration) of that velocity, as due to the resistance of the air.

By electrical connection the time of passing each screen is noted, and the *intervals* of time are given in this diagram for four of the screens, *A*, *B*, *C*, and *D*.

From these data it is required to compute, as nearly as the circumstances allow, the velocity and acceleration (negative) of the ball at various points (the ball moves from left to right).

Solution.—In passing from *A* to *B* the ball has an *average* velocity of 1610 ft. per second, obtained by dividing the distance of 100 feet by the time of passage, 0.0621 second. Similarly we find the average velocity between *B* and *C* to be 1582 ft. per second, and that between *C* and *D* to be 1554 ft. per second.

As the velocity is not changing very rapidly, we may claim that the ball actually possesses the velocity $v_1 = 1610$ ft. per second at the point 1, midway between *A* and *B*, or very near that point; and similarly the velocity $v_2 = 1582$ ft. per second at point 2, midway between *B* and *C*; and $v_3 = 1554$ ft. per second at point 3, midway between *C* and *D*.

Hence the total gain of velocity from 1 to 2 is $1582 - 1610 = -28$ ft. per second; and the time in which this gain is made is one half of the 0.0621 second plus one half of the 0.0632 second, i.e., 0.0626 second. Therefore an approximate value for the *average* acceleration between points 1 and 2 is found by dividing the -28 ft. per second gain in velocity by the time 0.0626 second occupied in acquiring the gain. This gives -447 ft. per second per second *average* acceleration for portion 1...2 of path, and since screen *B* lies at the middle of this portion, the actual acceleration of the ball's motion as it passes the screen *B* is very nearly equal to this, viz.: -447 ft. per second per second (or "ft. per square second").

By a similar process the student may compute the acceleration at screen *C*. Of course the reason why these results are merely approximate is that the spaces and times concerned, though relatively small, are not infinitesimal.

[A recent English writer calls a unit of velocity a "*speed*;" and a unit of acceleration, a "*hurry*."]

TABLE OF HYPERBOLIC SINES AND COSINES (See p. 48).

u	cosh u	sinh u	u	cosh u	sinh u
0.00	1.0000	0			
0.05	1.0013	0.0500	2.05	3.9484	3.8196
.10	1.0050	.1002	2.10	4.1443	4.0219
.15	1.0112	.1506	2.15	4.3507	4.2342
.20	1.0201	.2013	2.20	4.5679	4.4571
.25	1.0314	.2526	2.25	4.7966	4.6912
0.30	1.0453	0.3045	2.30	5.0372	4.9369
.35	1.0619	.3572	2.35	5.2905	5.1952
.40	1.0811	.4108	2.40	5.5569	5.4662
.45	1.1030	.4653	2.45	5.8373	5.7510
.50	1.1276	.5211	2.50	6.1323	6.0502
0.55	1.1551	0.5782	2.55	6.4426	6.3645
.60	1.1855	.6367	2.60	6.7690	6.6947
.65	1.2188	.6967	2.65	7.1123	7.0417
.70	1.2552	.7586	2.70	7.4735	7.4063
.75	1.2947	.8223	2.75	7.8533	7.7894
0.80	1.3374	0.8881	2.80	8.2527	8.1919
.85	1.3835	0.9561	2.85	8.6728	8.6150
.90	1.4331	1.0265	2.90	9.1146	9.0596
.95	1.4862	1.0995	2.95	9.5791	9.5268
1.00	1.5431	1.1752	3.00	10.0677	10.0179
1.05	1.6038	1.2539	3.05	10.5814	10.5340
1.10	1.6685	1.3356	3.10	11.1215	11.0765
1.15	1.7374	1.4208	3.15	11.6895	11.6466
1.20	1.8107	1.5097	3.20	12.2866	12.2459
1.25	1.8884	1.6019	3.25	12.9146	12.8758
1.30	1.9709	1.6984	3.30	13.5748	13.5379
1.35	2.0583	1.7991	3.35	14.2689	14.2338
1.40	2.1509	1.9043	3.40	14.9987	14.9654
1.45	2.2488	2.0143	3.45	15.7661	15.7343
1.50	2.3524	2.1293	3.50	16.5728	16.5426
1.55	2.4619	2.2496	3.55	17.4210	17.3923
1.60	2.5775	2.3757	3.60	18.3128	18.2855
1.65	2.6995	2.5075	3.65	19.2503	19.2243
1.70	2.8283	2.6456	3.70	20.2360	20.2113
1.75	2.9642	2.7904	3.75	21.2723	21.2488
1.80	3.1075	2.9422	3.80	22.3618	22.3394
1.85	3.2583	3.1013	3.85	23.5072	23.4859
1.90	3.4177	3.2682	3.90	24.7113	24.6911
1.95	3.5855	3.4432	3.95	25.9773	25.9581
2.00	3.7622	3.6269	4.00	27.3082	27.2899

266. The Four x-Derivatives of the Ordinate of the Elastic Curve —If y = func. (x) is the equation of the elastic curve for any portion of a loaded beam, on which portion the load per unit of length of the beam is w = either zero, (Fig. 234) or = constant, (Fig. 235), or = a continuous func. (x) (as in the last §), we may prove, as follows, that w = the x-derivative of the shear. Fig. 269. Let N and N' be two consecutive cross-sections of a loaded beam, and let the block between them, bearing its portion, wdx, of a distributed load, be considered free. The elastic forces consist of the two stress-couples (tensions and compressions) and the two shears, J and $J + dJ$, dJ being the shear-increment consequent upon x receiving its increment dx. By putting Σ(vert. components) = 0 we have



FIG. 269.

$$J+dJ-wdx-J=0 \therefore w=\frac{dJ}{dx}$$

Q. E. D. But J itself = $dM \div dx$, (§ 240) and $M = [d^2y \div dx^2]\ EI$. By substitution, then, we have the following relations:

y = func.(x) = ordinate at any point of the elastic curve (1)

$\frac{dy}{dx} = a$ = slope at any point of the elastic curve . . (2)

$EI\ \frac{d^2y}{dx^2} = M$ = ordinate (to scale) of the moment curve (3)

$EI\ \frac{d^3y}{dx^3}$ = the shear, J = { the ordinate (to scale) of the shear diagram } . . (4)

$EI\ \frac{d^4y}{dx^4} = w$ = { the load per unit of length of beam = ordinate (to scale) of a curve of loading. } . (5)

If, then, the equation of the elastic curve (the neutral line of the beam itself; a reality, and not artificial like the

other curves spoken of) is given; we may by successive differentiation, for a prismatic and homogeneous beam so that both E and I are constant, find the other four quantities mentioned.

As to the converse process, (i.e. having given w as a function of x, to find expressions for J, M and y as functions of x) this is more difficult, since in taking the x-anti-derivative, an unknown constant must be added and determined. The problem just treated in § 264, however, offers a very simple case since w is the same function of x, *along the whole beam*, and there is therefore but one elastic curve to be determined.

We ∴ begin, numbering backward, with

$$EI\frac{d^4y}{dx^4} = -\gamma bx \quad \left\{\begin{array}{l}\text{since } w = \gamma bx, \text{ see}\\ \text{last § and Fig. 268}\end{array}\right\} \quad . \quad . \quad . \quad (5a)$$

[N. B.—This derivative $(dJ \div dx)$ is negative since dJ and dx have contrary signs.]

$$\therefore (shear =) E\,I\frac{d^3y}{dx^3} = -\gamma\, b\,\frac{x^2}{2} + Const.$$

But writing out this equation for $x=0$, *i.e.* for the point O, where the shear $= R_0$, we have $R_0 = 0 + Const.$ ∴ $Const. = R_0$, and hence write

$$EI\frac{d^3y}{dx^3} = -\gamma\, b\frac{x^2}{2} + R_0 \quad . \quad (Shear) \quad . \quad (4a)$$

Again taking the x-anti-derivative of both sides

$$(Moment =)\ E\,I\frac{d^2y}{dx^2} = -\gamma\, b\frac{x^3}{6} + R_0x + (Const. = 0) \quad . \quad (3a)$$

[At O, $x=0$ also M, ∴ $Const. = 0$]. Again,

$$EI\frac{dy}{dx} = -\gamma b\frac{x^4}{24} + R_0\frac{x^2}{2} + C'$$

At O, where $x=0$ $dy \div dx = a_0 =$ the unknown slope of the elastic line at O, and hence $C' = EI\,a_0$

$$\therefore EI\frac{dy}{dx} = -\gamma b\frac{x^4}{24} + R_0\frac{x^2}{2} + EI\,a_0 \quad . \quad . \quad . \quad (2a)$$

Passing now to y itself, and remembering that at O, both y and x are zero, so that the constant, if added, would= zero, we obtain (inserting the value of R_0 from last §)

$$EIy = -\gamma\, b \frac{x^5}{120} + \gamma\, b\, l^2 \frac{x^3}{36} + EIa_0 x \qquad . \quad (1a)$$

the equation of the elastic curve. This, however, contains the unknown constant a_0 = the slope at O. To determine a_0 write out eq. (1a) for the point B, Fig. 268, where x is known to be equal to l, and y to be = zero, solve for a_0, and insert its value both in (1a) and (2a). To find the point of max. y (i.e., of greatest deflection) in the elastic curve, write the slope, i.e. $dy \div dx$, = zero [see eq. 2a] and solve for x; four values will be obtained, of which the one lying between 0 and l is obviously the one to be taken. This value of x substituted in (1a) will give the maximum deflection. The location of this maximum deflection is neither at the centre of action of the load $\left(x = \frac{2}{3}\, l\right)$ nor at the section of max. moment ($x = l \div \sqrt{3}$.)

The qualities of the left hand members of equations (1) to (5) should be carefully noted. *E. g.*, in the inch-pound-second system of units we should have:

1. y (a linear quantity) = (so many) inches.
2. $dy \div dx$ (an abstract number) = (so many) abstract units.
3. M (a moment) = (so many) inch-pounds.
4. J (a shear, i.e., force) = (so many) pounds.
5. w (force per linear unit) = (so many) pounds per running inch of beam's length.

As to the quantities E, and I, individually, E is pounds per sq. in., and I has four linear dimensions, i.e. (so many) bi-quadratic inches.

287. Cantilevers of Uniform Strength.—Beams built in at one end, horizontally, and projecting from the wall without support at the other, should have the forms given below, for the given cases of loading, if all cross-sections are to be **Rectangular** and the weight of beam neglected. Sides of sections horizontal and vertical. Also, the sections are symmetrical about the axis of the piece. b and h are the dimensions at the wall. l= length. No proofs given.



Fig. 290.



Fig. 291.

Width constant. Vertical outline parabolic. Single end load. } Fig. 290, (*a*). $(\frac{1}{2}v)^2 = (\frac{1}{2}h)^2\frac{x}{l}$ (1)

Height constant. Single end load. Horizontal outline triangular. } Fig. 290, (*b*). $(\frac{1}{2}u) = (\frac{1}{2}b)\frac{x}{l}$. (2)

Constant ratio of height v to width u. Both outlines cubic parabolas. } Fig. 290. (*c*). $(\frac{1}{2}v)^3 = (\frac{1}{2}h)^3\frac{x}{l}$. (3)

$(\frac{1}{2}u)^3 = (\frac{1}{2}b)^3\frac{x}{l}$. (3′)

Uniform Load. Width constant. Vertical outline triangular.	Fig. 291, (*a*).	$(\frac{1}{2}v)=(\frac{1}{2}h)\frac{x}{l}$.	(4)
Uniform Load. Height constant. Horiz. outline is two parabolas meeting at *O* (vertex) with geomet. axes ‖ to wall.	Fig. 291, (*b*).	$\frac{1}{2}u=(\frac{1}{2}b)\frac{x^2}{l^2}$ . .	(5)
Uniform Load. Both outlines semi-cubic parabolas. Sections similar rectangles.	Fig. 291, (*c*).	$(\frac{1}{2}u)^3=(\frac{1}{2}b)^3\frac{x^3}{l^3}$	(6)
		$(\frac{1}{2}v)^3=(\frac{1}{2}h)^3\frac{x^3}{l^3}$	(6)′

289.—Beams and cantilevers of circular cross-sections may be dealt with similarly, and the proper longitudinal outline given, to constitute them "bodies of uniform strength." As a consequence of the possession of this property, with loading and mode of support of specified character, the following may be stated; that to find the equation of safe loading *any cross-section whatever may be employed.* This refers to tension and compression. As regards the shearing stresses in different parts of the beam the condition of "uniform strength" is not necessarily obtained at the same time with that for normal stress in the outer fibres.

DEFLECTION OF BEAMS OF UNIFORM STRENGTH.

290. Case of § 283, the double wedge, but symmetrical, i.e., $l_1=l_0=\frac{1}{2}l$, Fig. 292. Here we shall find the use of the



FIG. 292.

form $\frac{EI}{\rho}$ (of the three forms for the moment of the *stress couple*, see eqs. (5), (6) and (7), §§ 229 and 231) of the most direct service in determining the form of the elastic curve OB, which is symmetrical, and has a common tangent at B, with the curve BC. First to find the radius of curvature, ρ, at any section n, we have for the free body nO, $\Sigma(\text{moms.}_n=0)$, whence

$$-\frac{EI}{\rho}+\tfrac{1}{2}Px=0\,;\ \text{but}\ \left\{\begin{matrix}\text{from eq.}\\(3)\ \S\ 283\end{matrix}\right\}\ x=\frac{u}{b}\tfrac{1}{2}l\ \text{and}\ I=\tfrac{1}{12}uh^3$$

$$\text{we have}\ \tfrac{1}{12}\frac{E}{\rho}\,uh^3=\tfrac{1}{4}P\frac{ul}{b}\ \text{and}\ \therefore\ \rho=\tfrac{1}{3}\,\frac{bh^3}{l}\cdot\frac{E}{P}\qquad(1)$$

from which all variables have disappeared in the right hand member; i.e., ρ is constant, the same at all points of the elastic curve, hence the latter is the arc of a circle, having a horizontal tangent at B.

To find the deflection, d, at B, consider Fig. 292, (*b*) where $d=\overline{KB}$, and the full circle of radius $BH=\rho$ is drawn.

The triangle KOB is similar to YOB,
and $\therefore\ \overline{KB}:\overline{OB}::\overline{OB}:\overline{YB}$
But $OB=\frac{1}{2}l$, $KB=d$ and $YB=2\rho$

$$\therefore\ d=\frac{(\frac{1}{2}l)^2}{2\rho},\ \text{and}\ \therefore\ ,\ \text{from eq. (1)},\ d=\tfrac{3}{8}\cdot\frac{Pl^3}{bh^3E}\qquad(2)$$

From eq. (4) §233 we note that for a beam of the same material but *prismatic* (parallelopipedical in this case,) having the same dimensions, b and h, at all sections as at the middle, deflects an amount $=\frac{1}{48}\,\frac{Pl^3}{EI}=\frac{1}{4}\frac{Pl^3}{bh^3E}$ under a

load P in the middle of the span. Hence the tapering beam of the present § has only ⅔ the stiffness of the prismatic beam, for the same b, h, l, E, and P.

291. Case of § 281 (Parabolic Body), With $l_1 = l_0$, i.e., Symmetrical.—Fig. 293,(*a*). Required the equation of the neutral



Fig. 293.

line OB. For the free body nO, $\Sigma(\text{moms.}_n) = 0$ gives us

$$EI\frac{d^2y}{dx^2} = -\tfrac{1}{2}Px \quad . \quad . \quad . \quad (1)'$$

Fig. 293, (*b*), shows simply the geometrical relations of the problem, position of origin, axes, etc. OnB is the neutral line or elastic curve whose equation, and greatest ordinate d, are required. (The right hand member of eq. (1)′ is made negative because $d^2y \div dx^2$ is negative, the curve being concave to the axis X in this, the first quadrant.)

Now if the beam were prismatic, I, the "moment of inertia" of the cross-section would be constant, i.e., the same for all values of x, and we might proceed by taking the x-anti-derivative of each member of (1)′ and add a constant; but it is *variable* and is

$$= \tfrac{1}{12}bv^3 = \tfrac{1}{12}\cdot\frac{bh_1^3}{(\frac{1}{2}l)^{\frac{3}{2}}}\,x^{\frac{3}{2}}, \quad \text{(from eq. 3, § 281, putting } l_0 = \tfrac{1}{2}l\text{)}$$

hence (1)′ becomes

$$\tfrac{1}{12}E\frac{bh_1^3}{(\frac{1}{2}l)^{\frac{3}{2}}}\,x^{\frac{3}{2}}\cdot\frac{d^2y}{dx^2} = -\tfrac{1}{2}Px \quad . \quad . \quad . \quad . \quad . \quad (1)'$$

To put this into the form Const. $\times \dfrac{d^2y}{dx^2}$ = func. of (x), we need

only divide through by $x^{\frac{3}{2}}$, (and for brevity denote $\frac{1}{12} Eb{h_1}^3 \div (\frac{1}{2}l)^{\frac{3}{2}}$ by A) and obtain

$$A\frac{d^2y}{dx^2} = -\frac{1}{2}Px^{-\frac{1}{2}} \quad . \quad . \quad . \quad . \quad (1)$$

We can now take the x-anti-derivative of each member, and have

$$A\frac{dy}{dx} = -\frac{1}{2}P(2x^{+\frac{1}{2}}) + C \quad . \quad . \quad . \quad . \quad (2)'$$

To determine the constant C, we utilize the fact that at B, where $x = \frac{1}{2}l$, the slope $dy \div dx$ is zero, since the tangent line is there horizontal, whence from (2)'

$$0 = -P\sqrt{\tfrac{l}{2}} + C \quad \therefore C = P\sqrt{\tfrac{l}{2}}$$

$$\therefore (2)' \text{ becomes } A\frac{dy}{dx} = P[\sqrt{\tfrac{1}{2}l} - x^{\frac{1}{2}}] \quad . \quad . \quad . \quad . \quad . \quad (2)$$

$$\therefore \quad Ay = P\left[\sqrt{\tfrac{1}{2}l}.x - \tfrac{2}{3}x^{\frac{3}{2}}\right] + [C' = 0] \quad . \quad . \quad . \quad (3)$$

($C' = 0$ since for $x = 0$, $y = 0$). We may now find the deflection d (Fig. 293(b)) by writing $x = \frac{1}{2}l$ and $y = d$, whence, after restoring the value of the constant A,

$$d = \tfrac{1}{2}\frac{Pl^3}{Eb{h_1}^3} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (4)$$

and is twice as great [being $= 2.\ \frac{Pl^3}{4Eb{h_1}^3}$]* as if the girder

* See § 233, putting $I = \frac{1}{12}bh^3$ in eq. (4).

were parallelopipedical. In other words, the present girder is only half as stiff as the prismatic one.

292. Special Problem. (I.) The symmetrical beam in Fig. 294 is of rectangular cross-section and constant width $= b$,

but the height is constant only over the extreme quarter spans, being $=h_1=\frac{1}{2}h$, i. e., half the height h at mid-span. The convergence of the two truncated wedges forming the middle quarters of the beam is such that the prolongations



Fig. 294.

of the upper and lower surfaces *would meet over the supports* (as should be the case to make $h=2h_1$). Neglecting the weight of the beam, and placing a single load in middle, it is required to find the equation for safe loading; also the equations of the four elastic curves; and finally the deflection.

The solutions of this and the following problem are left to the student, as exercises. Of course the beam here given is not one of uniform strength.

293. Special Problem. (II). Fig. 295. Required the manner in which the width of the beam must vary, the height being constant, cross-sections rectangular, weight of beam



Fig. 295.

neglected, to be a beam of uniform strength, if the load is uniformly distributed?

Note.—The following five pages originally formed the concluding part of the chapter on "Arch-ribs" of this book; and gives a graphic treatment of straight girders considered as a particular case of curved beams (or arch ribs).

HORIZONTAL STRAIGHT GIRDERS.

389. Ends Free to Turn.—This corresponds to an arch-rib with hinged ends, but it must be understood that there is no hindrance to horizontal motion. (Fig. 439.) In



FIG. 439.

treating a straight beam, *slightly* bent under *vertical forces only* (as in this case with no horizontal constraint), as a

particular case of an arch-rib, it is evident that since the pole distance must be zero, the special equil. polygon will have all its segments vertical, and the corresponding force diagram reduces to a single vertical line (the load line). The first and last segments must pass through A and b (points of no moment) respectively, but being vertical will not intersect P_1 and P_2; i.e., the remainder of the special equilibrium polygon *lies at an infinite distance* above the span AB. Hence the actual spec. equil. pol. is useless.

However, knowing that the shear, J, and the moment M (of stress couple) are the only quantities pertaining to any section m (Fig. 439) which we wish to determine (since there is no thrust along the beam), and knowing that an imaginary force H', applied horizontally at each end of the beam, would have no influence in determining the shear and moment at m as due to the new system of forces, we may therefore obtain the shears and moments graphically from *this new system* (viz.: the loads P_1, etc., the vertical reactions V and V_n, and the two equal and opposite H''s). [Evidently, since H' has no moment about the neutral axis (or gravity axis here), of m, the moment at m will be unaffected by it; and since H'' has no component ⌐ to the beam at m, the shear at m is the same in the new system of forces, as in the old, before the introduction of the H''s.]

Hence, lay off the load-line 1 . . 2 . . 3, Fig. 439, and construct an equil. polyg. which shall pass through A and B and have any convenient arbitrary H'' (force) as a pole distance. This is done by first determining n' on the load-line, using the auxiliary polygon $A'a'B'$, to a pole O' (arbitrary), and drawing $O'n' \parallel$ to $A'B'$. Taking O'' on a horizontal through n', making $O''n' = H''$, we complete the force diagram, and equil. pol. AaB. Then, z *being the vertical intercept* between m and the equil. polygon, we have: **Moment at** $m = M = H''z$ (or $= H'z'$ also), and shear at m, or $J_m = 2 \ldots n'$, i.e., = projection of the proper ray R_2, or $O'' \ldots 2$, upon the vertical through m. Similarly we obtain M and J at any other section for the given load. (See

§§ 329, 337 and 367). The moment of inertia need not be constant in this case.

390. Straight Horizontal Prismatic Girder of Fixed Ends at Same Level.—No horizontal constraint, hence no thrust. I constant. Ends at same level, with end-tangents horizontal. We may consider the whole beam free (cutting close to the walls) putting in the unknown upward shears J_0 and J_n



Fig. 440.

and the two stress couples of unknown moments M_0 and M_n at these end sections. Also, as in § 388, an arbitrary H'' horizontal and in line of beam at each extremity. Now (See Fig. 33) the couple at O and the force H'' are equivalent to a single horizontal H'' at an unknown vertical distance c below O; similarly at the right hand end. The special polygon FG is to be determined for this new system, since the moment and shear will be the same at any section under this new system as under the real system. The conditions for determining it are as follows: Since the end-tangents are fixed, $\Sigma^{B}_{0} M\Delta s=0$ $\therefore$ $\Sigma^{B}_{0} z\Delta s=0$ and since

O's displacement relatively to B's tangent is zero we have $\Sigma Mx\Delta s=0$ $\therefore$ $\Sigma H''zx\Delta s=0$ $\therefore$ $\Sigma xz\Delta s=0$. See § 374. Hence for Equal Δs's, $\Sigma(z)=0$ and $\Sigma(xz)=0$. Now for any pole O''' draw an equil. pol. $F'''G'''$ and in it (by § 377; see Note) locate $v'''m'''$ so as to make $\Sigma(z''')=0$ and $\Sigma(xz''')=0$. Draw verticals through the intersections E''' and L''', to determine E and L on the beam, these are the points of inflection (i.e., of zero moment), and are points in the required special polygon FG.

Draw $O'''n''' \parallel$ to $v'''m'''$ to fix n''. Take a pole O'' on the horizontal through n'', making $\mathcal{O}''z''=H''$ (arbitrary), draw the force diagram O'' 1234 and a corresponding equilibrium polygon beginning at E. It should cut L, and will fulfil the two requirments $\Sigma_0^B(z)=0$ and $\Sigma_0^B(xz)=0$, with reference to the axis of the beam $O'B'$. The moment of the stress-couple at any section m will be $M=H''z$, and the shear J = the projection of the "proper ray" of the force diagram O'' . . 1, 2, etc., upon the vertical (not in the trial diagram O'''. . 1, 2, etc.). As far as the moment is concerned the trial polygon $F'''G'''$ will serve as well as the special polygon FG; i.e., $M=H'''z'''$ as well as $H''z$, H''' being the pole-distance of O'''; but for the shear we must use the rays of the final and not the trial diagram.

The peculiarity of this treatment of straight beams, considered as a particular case of curved beams, consists in the substitution of an imaginary system of forces involving the two equal and opposite, and *arbitrary* H's, for the real system in which there is no horizontal force and consequently no "special equilibrium polygon," and thus determining all that is desired, i.e., the moment and shear at any section.

In the polygon FG the student will recognize the "moment-diagram" of the problems in Chaps. III and IV.

He will also see why the shear is proportional to the slope $\frac{dM}{dx}$ of the moment curve in those chapters. For example, the "slope" of the second segment of the polygon FG, that segment being $\parallel$ to O'' 2, is

$$\text{tang. of angle } 2O''n''=\overline{2n''}\div\overline{O''n''}=\text{shear}\div H''$$

and similarly for any other segment; i.e., the tangent of the inclination of the "moment curve," or line, is proportional to the shear.

It is also interesting to notice with the present problem of a straight beam, that in the conditions

$$\Sigma(z\Delta s)=0 \text{ and } \Sigma(z\Delta s)x=0,$$

for locating the polygon FG, each Δs is ⊥ to its z, and that consequently each $z\Delta s$ is the area of a small vertical strip of area between the beam and the polygon, and $(z\Delta s)x$ is the "moment" of this strip of area about O' the origin of x. Hence these conditions imply; *first*, that the area EWL between the polygon and the axis of the beam on one side is equal to that $(O'FE+LB'G)$ on the other side, and, *secondly*, that the centre of gravity of EWL lies in the same vertical as that of $O'FE$ and $LB'G$ combined. Another way of stating the same thing is that, if we join FG, the area of the trapezoid $FO'B'G$ is equal to that of the figure $FEWLG$, and their centres of gravity lie in the same vertical. A corresponding statement may be made (if we join $F'''G'''$) for the trapezoid $F'''v'''m'''G'''$ and figure $F'''E'''W'''L'''G'''$,

N	0	1	2	3	4	5	6	7	8	9	Dif.
10	0000	0043	0086	0128	0170	0212	0253	0294	0334	0374	42
11	0414	0453	0492	0531	0569	0607	0645	0682	0719	0755	38
12	0792	0828	0864	0899	0934	0969	1004	1038	1072	1106	35
13	1139	1173	1206	1239	1271	1303	1335	1367	1399	1430	32
14	1461	1492	1523	1553	1584	1614	1644	1673	1703	1732	30
15	1761	1790	1818	1847	1875	1903	1931	1959	1987	2014	28
16	2041	2068	2095	2122	2148	2175	2201	2227	2253	2279	26
17	2304	2330	2355	2380	2405	2430	2455	2480	2504	2529	25
18	2553	2577	2601	2625	2648	2672	2695	2718	2742	2765	24
19	2788	2810	2833	2856	2878	2900	2923	2945	2967	2989	22
20	3010	3032	3054	3075	3096	3118	3139	3160	3181	3201	21
21	3222	3243	3263	3284	3304	3324	3345	3365	3385	3404	20
22	3424	3444	3464	3483	3502	3522	3541	3560	3579	3598	19
23	3617	3636	3655	3674	3692	3711	3729	3747	3766	3784	19
24	3802	3820	3838	3856	3874	3892	3909	3927	3945	3962	18
25	3979	3997	4014	4031	4048	4065	4082	4099	4116	4133	17
26	4150	4166	4183	4200	4216	4232	4249	4265	4281	4298	16
27	4314	4330	4346	4362	4378	4393	4409	4425	4440	4456	16
28	4472	4487	4502	4518	4533	4548	4564	4579	4594	4609	15
29	4624	4639	4654	4669	4683	4698	4713	4728	4742	4757	15
30	4771	4786	4800	4814	4829	4843	4857	4871	4886	4900	14
31	4914	4928	4942	4955	4969	4983	4997	5011	5024	5038	14
32	5051	5065	5079	5092	5105	5119	5132	5145	5159	5172	13
33	5185	5198	5211	5224	5237	5250	5263	5276	5289	5302	13
34	5315	5328	5340	5353	5366	5378	5391	5403	5416	5428	13
35	5441	5453	5465	5478	5490	5502	5514	5527	5539	5551	12
36	5563	5575	5587	5599	5611	5623	5635	5647	5658	5670	12
37	5682	5694	5705	5717	5729	5740	5752	5763	5775	5786	12
38	5798	5809	5821	5832	5843	5855	5866	5877	5888	5899	11
39	5911	5922	5933	5944	5955	5966	5977	5988	5999	6010	11
40	6021	6031	6042	6053	6064	6075	6085	6096	6107	6117	11
41	6128	6138	6149	6160	6170	6180	6191	6201	6212	6222	10
42	6232	6243	6253	6263	6274	6284	6294	6304	6314	6325	10
43	6335	6345	6355	6365	6375	6385	6395	6405	6415	6425	10
44	6435	6444	6454	6464	6474	6484	6493	6503	6513	6522	10
45	6532	6542	6551	6561	6571	6580	6590	6599	6609	6618	10
46	6628	6637	6646	6656	6665	6675	6684	6693	6702	6712	9
47	6721	6730	6739	6749	6758	6767	6776	6785	6794	6803	9
48	6812	6821	6830	6839	6848	6857	6866	6875	6884	6893	9
49	6902	6911	6920	6928	6937	6946	6955	6964	6972	6981	9
50	6990	6998	7007	7016	7024	7033	7042	7050	7059	7067	9
51	7076	7084	7093	7101	7110	7118	7126	7135	7143	7152	9
52	7160	7168	7177	7185	7193	7202	7210	7218	7226	7235	8
53	7243	7251	7259	7267	7275	7284	7292	7300	7308	7316	8
54	7324	7332	7340	7348	7356	7364	7372	7380	7388	7396	8

N. B.—Naperian log = Briggs' log × 2.302.
Base of Naperian system = e = 2.71828.

N	0	1	2	3	4	5	6	7	8	9	Dif.
55	7404	7412	7419	7427	7435	7443	7451	7459	7466	7474	8
56	7482	7490	7497	7505	7513	7520	7528	7536	7543	7551	8
57	7559	7566	7574	7582	7589	7597	7604	7612	7619	7627	8
58	7634	7642	7649	7657	7664	7672	7679	7686	7694	7701	7
59	7709	7716	7723	7731	7738	7745	7752	7760	7767	7774	7
60	7782	7789	7796	7803	7810	7818	7825	7832	7839	7846	7
61	7853	7860	7868	7875	7882	7889	7896	7903	7910	7917	7
62	7924	7931	7938	7945	7952	7959	7966	7973	7980	7987	7
63	7993	8000	8007	8014	8021	8028	8035	8041	8048	8055	7
64	8062	8069	8075	8082	8089	8096	8102	8109	8116	8122	7
65	8129	8136	8142	8149	8156	8162	8169	8176	8182	8189	7
66	8195	8202	8209	8215	8222	8228	8235	8241	8248	8254	7
67	8261	8267	8274	8280	8287	8293	8299	8306	8312	8319	6
68	8325	8331	8338	8344	8351	8357	8363	8370	8376	8382	6
69	8388	8395	8401	8407	8414	8420	8426	8432	8439	8445	6
70	8451	8457	8463	8470	8476	8482	8488	8494	8500	8506	6
71	8513	8519	8525	8531	8537	8543	8549	8555	8561	8567	6
72	8573	8579	8585	8591	8597	8603	8609	8615	8621	8627	6
73	8633	8639	8645	8651	8657	8663	8669	8675	8681	8686	6
74	8692	8698	8704	8710	8716	8722	8727	8733	8739	8745	6
75	8751	8756	8762	8768	8774	8779	8785	8791	8797	8802	6
76	8808	8814	8820	8825	8831	8837	8842	8848	8854	8859	6
77	8865	8871	8876	8882	8887	8893	8899	8904	8910	8915	6
78	8921	8927	8932	8938	8943	8949	8954	8960	8965	8971	6
79	8976	8982	8987	8993	8998	9004	9009	9015	9020	9025	5
80	9031	9036	9042	9047	9053	9058	9063	9069	9074	9079	5
81	9085	9090	9096	9101	9106	9112	9117	9122	9128	9133	5
82	9138	9143	9149	9154	9159	9165	9170	9175	9180	9186	5
83	9191	9196	9201	9206	9212	9217	9222	9227	9232	9238	5
84	9243	9248	9253	9258	9263	9269	9274	9279	9284	9289	5
85	9294	9299	9304	9309	9315	9320	9325	9330	9335	9340	5
86	9345	9350	9355	9360	9365	9370	9375	9380	9385	9390	5
87	9395	9400	9405	9410	9415	9420	9425	9430	9435	9440	5
88	9445	9450	9455	9460	9465	9469	9474	9479	9484	9489	5
89	9494	9499	9504	9509	9513	9518	9523	9528	9533	9538	5
90	9542	9547	9552	9557	9562	9566	9571	9576	9581	9586	5
91	9590	9595	9600	9605	9609	9614	9619	9624	9628	9633	5
92	9638	9643	9647	9652	9657	9661	9666	9671	9675	9680	5
93	9685	9689	9694	9699	9703	9708	9713	9717	9722	9727	5
94	9731	9736	9741	9745	9750	9754	9759	9763	9768	9773	5
95	9777	9782	9786	9791	9795	9800	9805	9809	9814	9818	5
96	9823	9827	9832	9836	9841	9845	9850	9854	9859	9863	4
97	9868	9872	9877	9881	9886	9890	9894	9899	9903	9908	4
98	9912	9917	9921	9926	9930	9934	9939	9943	9948	9952	4
99	9956	9961	9965	9969	9974	9978	9983	9987	9991	9996	4

N. B.—Naperian log = Briggs' log × 2.302.
Base of Naperian System = e = 2.71828.

Trigonometric Ratios (Natural); including "*arc*," by which is meant "radians," or "π-measure," or "circular measure;" e.g., arc $100° = 1.7453293$, $= \frac{100}{180}$ of π.

arc	degree	sin	cosec	tan	cotan	sec	cos		
0	0	0	infin.	0	infin.	1.0000	1.0000	90	1.5708
0.0175	1	0.0175	57.299	0.0175	57.290	1.0001	0.9998	89	1.5533
.0349	2	.0349	28.654	.0349	28.636	1.0006	.9994	88	1.5359
.0524	3	.0523	19.107	.0524	19.081	1.0014	.9986	87	1.5184
.0698	4	.0698	14.336	.0699	14.301	1.0024	.9976	86	1.5010
.0873	5	.0872	11.474	.0875	11.430	1.0038	.9962	85	1.4835
0.1047	6	0.1045	9.5668	0.1051	9.5144	1.0055	0.9945	84	1.4661
.1222	7	.1219	8.2055	.1228	8.1443	1.0075	.9925	83	1.4486
.1396	8	.1392	7.1853	.1405	7.1154	1.0098	.9903	82	1.4312
.1571	9	.1564	6.3925	.1584	6.3138	1.0125	.9877	81	1.4137
.1745	10	.1736	5.7588	.1763	5.6713	1.0154	.9848	80	1.3963
0.1920	11	0.1908	5.2408	0.1944	5.1446	1.0187	0.9816	79	1.3788
.2094	12	.2079	4.8097	.2126	4.7046	1.0223	.9781	78	1.3614
.2269	13	.2250	4.4454	.2309	4.3315	1.0263	.9744	77	1.3439
.2443	14	.2419	4.1336	.2493	4.0108	1.0306	.9703	76	1.3264
.2618	15	.2588	3.8637	.2679	3.7321	1.0353	.9659	75	1.3090
0.2793	16	0.2756	3.6280	0.2867	3.4874	1.0403	0.9613	74	1.2915
.2967	17	.2924	3.4203	.3057	3.2709	1.0457	.9563	73	1.2741
.3142	18	.3090	3.2361	.3249	3.0777	1.0515	.9511	72	1.2566
.3316	19	.3256	3.0716	.3443	2.9042	1.0576	.9455	71	1.2392
.3491	20	.3420	2.9238	.3640	2.7475	1.0642	.9397	70	1.2217
0.3665	21	0.3584	2.7904	0.3839	2.6051	1.0712	0.9336	69	1.2043
.3840	22	.3746	2.6695	.4040	2.4751	1.0785	.9272	68	1.1868
.4014	23	.3907	2.5593	.4245	2.3559	1.0864	.9205	67	1.1694
.4189	24	.4067	2.4586	.4452	2.2460	1.0946	.9135	66	1.1519
.4363	25	.4226	2.3662	.4663	2.1445	1.1034	.9063	65	1.1345
0.4538	26	0.4384	2.2812	0.4877	2.0503	1.1126	0.8988	64	1.1170
.4712	27	.4540	2.2027	.5095	1.9626	1.1223	.8910	63	1.0996
.4887	28	.4695	2.1301	.5317	1.8807	1.1326	.8829	62	1.0821
.5061	29	.4848	2.0627	.5543	1.8040	1.1434	.8746	61	1.0646
.5236	30	.5000	2.0000	.5774	1.7321	1.1547	.8660	60	1.0472
0.5411	31	0.5150	1.9416	0.6009	1.6643	1.1666	0.8572	59	1.0297
.5585	32	.5299	1.8871	.6249	1.6003	1.1792	.8480	58	1.0123
.5760	33	.5446	1.8361	.6494	1.5399	1.1924	.8387	57	0.9948
.5934	34	.5592	1.7883	.6745	1.4826	1.2062	.8290	56	0.9774
.6109	35	.5736	1.7435	.7002	1.4281	1.2208	.8192	55	0.9599
0.6283	36	0.5878	1.7013	0.7265	1.3764	1.2361	0.8090	54	0.9425
.6458	37	.6018	1.6616	.7536	1.3270	1.2521	.7986	53	0.9250
.6632	38	.6157	1.6243	.7813	1.2799	1.2690	.7880	52	0.9076
.6807	39	.6293	1.5890	.8098	1.2349	1.2868	.7771	51	0.8901
.6981	40	.6428	1.5557	.8391	1.1918	1.3054	.7660	50	0.8727
0.7156	41	0.6561	1.5243	0.8693	1.1504	1.3250	0.7547	49	0.8552
7330	42	.6691	1.4945	.9004	1.1106	1.3456	.7431	48	0.8378
7505	43	.6820	1.4663	.9325	1.0724	1.3673	.7314	47	0.8203
.7679	44	.6947	1.4396	.9657	1.0355	1.3902	.7193	46	0.8028
.7854	45	.7071	1.4142	1.0000	1.0000	1.4142	.7071	45	0.7854
		cos	sec	cotan	tan	cosec	sin	degree	arc

INDEX TO MECHANICS OF SOLIDS.

(For index to "Hydraulics" see p. xxii.)

PAGE

Aberration of Light 90
Absolute Velocity 89
Abutment-Line 414
Abutments of Arches 430, 435
Acceleration, Angular 109
Acceleration, Linear 49
Acceleration, Normal 75, 77
Acceleration of Gravity . . 51, 160, 179
Acceleration, Tangential 74, 80
Action and Reaction 1, 53
Angular, or Rotary Motion . . . 109
Angular Velocity 109
Anti-Derivative 253, 254, 256, 257, 322, 328, 839, 845
Anti-Resultant 402
Anti-Stress Resultant 411
Apparent Weight 78, 79
Arches, Linear 386, 396
Arches of Masonry 421, 437
Arch-Ribs 438, 483
Arch-Ribs, Classification of . . . 458
Arch-Rib of Three Hinges . 458, 460
Arch-Rib of Hinged Ends, 440, 458, 461
Arch-Rib of Fixed Ends . 439, 459, 465
Arch Truss, or Braced Arch . . . 478
Autographic Testing Machine . 240
Beams, Rectangular, Comparative Strength and Stiffness 272, 273, 277
Belting, Pressure of 181
Belting, Slip of 182
Bent Lever with Friction 173
Boat-Rowing 160
Bow's Notation 407
Box-Girder 275, 292
Braced Arch 438, 478
Brake, Pony 158
Brakes, Railroad 190
Bridges, Arch 430
Bridge-Pier 141
Bridge, Suspension 46
Bridge Truss, Warren 35
Buckling of Web-Plates 383
Built Beams, designing Sections of 295
Built Columns 378

PAGE

Burr, Prof., Citations from . 224, 229
Butt-Joint 226
Cantilevers 260, 276, 841
Cantilever, Oblique 352, 354
Catenary, Common 46
Catenary, Inverted 387
Catenary, Transformed 395
Cast Iron 220, 279
Centre of Gravity, 18, 19, etc. . . 336
Centre of Oscillation 119
Centre of Percussion of Rod . . 113
Centrifugal Action 125
Centrifugal Force 77, 78
Centripetal Force 77, 78, 79
Centrobaric Method 24
Cheval-Vapeur 136
Circle as Elastic Curve 262, 368
Circular Arc as Linear Arch . . 391
Clinometers, Torsion 241
Closing Line 414
Coblenz, Bridge at 459, 478
Columns, Long 360
Composition of Forces . . 4, 8, 31, 38
Compression of Short Blocks . . 218
Concrete-Steel Beams 339
Concurrent Forces 6, 8, 397
Cone of Friction 168
Conical Pendulum 78
Connecting-Rod 59, 69, 70
Conservation of Energy 156
Conservation of Momentum . . 66
Continuous Girders, by Analysis 320–332
Continuous Girders, by Geometric Method 485–506
Copying-Press 71
Cords, Flexible 42
Cords, Rigidity of 192
Couples 27, 30
Cover-Plates 226
Crane 357
Crank-Shaft, Strength of 314
Creeping of Belts 186
Crushing, Modulus of 219, 424
Curvilinear Motion 72
Cylinder, Thick Hollow 509
Dangerous Section 262, 332

(For index to "Hydraulics" see p. xxii.)

	PAGE
Dash-Pot	158
Deck-Beam	275
Deflections, (Flexure)	252–262, 488
Derived Quantities	2
Deviating Force	77
Diagrams, Strain	209, 241
Displacement of Point of Arch Rib	447
Dove-Tail Joint	269
Duchayla's Proof of the Parallelogram of Forces	4
Dynamometers	157, 158, 159
Eddy, Prof., Graphic Methods, (See Preface)	426
Elastic Curve a Circle	262, 368
Elastic Curves	245, 252–262, 362
Elastic Curves, the Four x-Derivatives of	838
Elasticity-Line	241
Elasticity, Modulus of	203, 227
Elastic Limit	202
Elevation of Outer Rail on Railroad Curves	78
Ellipse of Inertia	94
Ellipse of Stress	205
Ellipsoid of Inertia	104
Elliptical Beam	338
Elongation of Wrought-Iron Rod	207
Elongation Theory of Safety	508
Energy	137
Energy, Conservation of	156
Energy, Kinetic	137, 144, 147, 150
Energy, Potential	155
Equations, Homogeneous	2
Equator, Apparent Weight at the	78
Equilibrium	4, 33, 39
Equilibrium Polygon	401, 450
Equilibrium Polygon Through Three Points	418, 419
Equivalent Systems	7, 105, 145
Exaggeration of Vertical Dimensions in Arch-Ribs	470
Examples in Flexure	280–284
Examples in Shearing	231, 232
Examples in Tension and Compression	222, 223
Examples in Torsion	241–243
Experiments of an English Railroad Commission	314
Experiments of Prof. Lanza	280
Experiments on Building Stone	424
Experiments on Columns	366
Extrados	421
Euler's Formula for Columns	364
Factor of Safety	223
Falling of Bodies	51
Fatigue of Metals	224
Flexural Stiffness	250
Flexure	244–386
Flexure and Torsion Combined	314
Flexure, Beams of Uniform Strength	335
Flexure, Common Theory	244
Flexure, Eccentric Load	256, 301
Flexure, Elastic Curves in,	245, 251, 252–262
Flexure, Examples in	280–284
Flexure, Geometrical Treatment	485
Flexure, Moving Loads	298
Flexure, Non-Prismatic Beams,	332, 335
Flexure of Long Columns	363
Flexure of Prismatic Beams Under Oblique Forces	352
Flexure of Reinforced Concrete Beams	332
Flexure, Safe Loads in	262–284
Flexure, Safe Stress in	279
Flexure, Shearing Stress in,	284–295
Flexure, Special Problems in,	295–319
Flexure, Strength in	249
Flexure, the Elastic Forces	246
Flexure, the "Moment"	249
Flexure, the "Shear"	248
Flexure, Uniform Load	258, 267, 302, 305, 307, 324, 329, 340
Flow of Solids	212
Fly-Wheel	121, 151
Fly-Wheel, Stresses in	126, 127
Force	1
Force Diagram	400
Force Polygons	397
Forces, Concurrent	6, 8
Forces, Distributed	197
Forces, Non-Concurrent	6, 31
Forces, Parallel	13
Forces, Parallelogram of	4
Forces, Varieties of	7
Free Axes	129
Free-Body Method, the	11, 105
Friction	164–194, 422, 423
Frictional Gearing	172
Friction of Journals	192
Friction Axle	175
Friction Brake	158
Friction, Cone of	168
Friction in Machinery	191
Friction, Sliding	164–168
Friction of Pivots	179
Friction, Rolling	186
Friction-Wheels	177

(For index to "Hydraulics" see p. xxii.)

PAGE

Friction, Work Spent in 149
General Properties of Materials 204
Governor Ball 78
Graphic Representations of Uniformally Accelerated Motion. 57
Graphic Treatment of Arch ... 431
Gravity, Acceleration of, 51, 79, 160
Gravity, Centre of.....18, 336, 453
Gravity-Vertical 453
Graphical Statics, Elements of, 397–420
Graphical Statics of Vertical Forces 412–420
Guide Curve 83
Gyroscope 132
Harmonic Motion. 58, 81, 117
Heat Energy 156
Heaviness, Table, Etc 3
Height Due to Velocity 52, 84
Homogeneous Equations 2
Hooke's Law 201, 203, 207
Hooks, Strength of 356
Horizontal Straight Girders by Graphics 847
Horse-Power 136, 239, 242
Hyperbolic Functions 47, 837
I-Beam.....275, 292, 295
Ice-Boat, Speed of 90
Impact 63
Impact, Loss of Energy in ... 141
Inclined Beam 354
Inclined Plane, 83, 135, 151, 166, 169
Indicator 159
Inertia..... 53
Inertia of Piston-Rod 59
Instantaneous Rotation, Axis of 112
Intrados 421
Isochronal Axes..... 120
Isotropes..... 204
Kinetic Energy..137, 144, 147, 150
Kinetics, Definition 4
Kinetics of a Rigid Body..... 105
Kinetics of a Material Point .. 49
Knot, Fixed 43
Knot, Slip 43
Lanza, Experiments of Prof. .. 280
Lateral Contraction 211, 229
Lateral Security of Girders, 280, 298
Lever 18, 71
Lever, Bent, with Friction.173, 174
Linear Arches . . .386–396, 417, 425
Live Loads 298, 430
Load-Line..... 413
Locomotive on Arch 430
Locomotive on Girder 298
Locomotive, Parallel-Rod of .. 131

PAGE

Mass 2, 53
Material Point 3
Mechanical Equivalent of Heat 156
Mechanics, Definition of 1
Mechanics, Divisions of 4
Middle Third 423
Modulus of Elasticity.....203, 227
Modulus of Resilience..... 213
Modulus of Rupture (Flexure). 278
Modulus of Tenacity..... 212
Modulus, Young's 204
Moduli of Compression 219
Moment-Area 491
Moment of a Force 14
Moment-Diagram 263
Moment of Flexure . . 248, 348, 351
Moment of Inertia 91
Moment of Inertia by Graphics 454
Moment of Inertia of Box-Girder 276
Moment of Inertia of Built Beam..... 296
Moment of Inertia of Built Column 375
Moment of Inertia of Plane Figures. 91–98, 249, 274
Moment of Inertia of Rigid Bodies.....98, 103
Moment of Inertia of Truss ... 478
Moment of Torsion 236
Momentum 66
Mortar..... 422
Motion, Curvilinear..... 72
Motion, Rectilinear 50
Motion, Rotary 107
Moving Loads (Flexure) 298
Naperian Base 183, 357, 387
Naperian Lorarithms 47
Navier's Principle 422, 436
Neutral Axis 245, 247, 347, 355
Neutral Line (see Elastic Curve).
Newton's Laws 1, 53
Non-Concurrent Forces in a Plane 31, 399
Non-Concurrent Forces in Space 37
Normal Acceleration.....75, 76, 77
Normal Moment Diagram 494
Normal Stress 200
Oblique Section of Rod in Tension 200
Parabola as Linear Arch 391
Parabolic Cord..... 45
Parabolic Working-Beam..336, 844
Parallel Forces..... 13
Parallel-Rod of Locomotive .. 131
Parallelogram of Forces 4
Parallelogram of Motions..... 72
Parallelogram of Velocities ... 72

(For index to "Hydraulics" see p. xxii.)

PAGE

Pendulum, Compound 118
Pendulum, Conical 78
Pendulum, Cycloidal 80
Pendulum, Simple Circular. . . 81
Phœnix Columns 374
Pier Reactions 404
Piers of Arches 430, 435
Pile-Driving 140
Pillars (see Columns).
"Pin-and-Square" Columns . . 361
Planet, Velocity of 82
Plates 310
Poisson's Ratio 507
Polar Moment of Inertia . . .97, 238
Pole (in Graphics) 401
Pole-Distance 416, 417
Practical Notes 223
Potential Energy 155
Power 134
Power of Motors. 153, 157, 158
Power, Transmission of, by Belting 184
Power, Transmission of, by Shafts 238, 318
Principal Axes 104, 129
Projectile in Vacuo 83, 84–87
Prony Friction Brake 158
Pulley 43, 103
Punching Rivet Holes 229
Quantity, Kinds of 1
Quantities, Derived 2
Radius of Curvature .75, 76, 250, 843
Radius of Gyration, 91, 92, 115, 313, 372
Rankine's Formula for Columns 369
Rays of Force Diagram 401
Reaction 1, 18, 36, 53, 404
Reduced Load-Contour 429
Regulation of Machines 153
Reinforced Concrete Beams... 339
Relative and Absolute Velocities 89
Resilience ..204, 213, 237, 251, 313
Resultant of Parallel Forces, 13, 15
Resultant of Two or More Forces 4, 6
Rigid Body 4
Rigidity of Ropes 192
Riveting of Built Beams 292
Rivets and Riveted Plates, 225, 292
Rod in Tension 198, 200
Rolling Friction 186
Rolling Motion 130
Roof Truss 37, 405
Rotary Motion 68, 107, 129
Rotation and Translation Combined 130, 150

PAGE

Rupture 202
Safe Limit in Stress 202
Safe Loads in Flexure 262, 284
St. Louis Bridge. 459, 467, 478
Schiele's "Anti-Friction" Pivots 181
Set, Permanent, 202, 209, 208, 241
Shafts 233–239
Shafts, Non-Circular 239
Shear Diagram (Flexure) 265
Shearing 225–232
Shearing Distortion 227
Shear, Distribution of in Flexure 287
Shearing Forces 7, 225
Shearing Stress, 7, 200, 201, 225, 234, 284
Shear, the First x-Derivative of Moment (Flexure) 264
Skidding 190
Slip (of Oar, etc.) 161
Slope (in Flexure) 253
Soffit 421
Spandrel 421
Special Equilibrium Polygon, 409, 424, 440
Specific Gravity 3
Sphere, Thick Hollow 513
Statics, Definition of 4
Statics, Graphical 397–420
Statics of a Material Point . . . 8
Statics of a Rigid Body 27
Statics of Flexible Cords 42
Steam Engine Problems, 59, 61, 69, 70, 121, 131, 151
Steam Hammer 138
Stiffening of Web-Plates 383
Stone, Strength of 221, 424
Stress Diagrams for Arch-Ribs 471
Stresses due to Rib Shortening 476
Strain Diagrams 209, 241
Strains, two kinds only 196
Stress 197, 198
Stress and Strain, Relation Between 201
Stress-Couple 253, 348
Stress, Normal and Shearing .. 200
Strength of Materials 195
Stretching of a Prism Under its Own Weight 215
"Sudden" Application of a Load . . .:.....214, 255
Summation of Products by Graphics 451
Suspension Bridge 46
Table for Flexure 279
Table for Shearing 228

(For index to "Hydraulics" see p. xxii.)

PAGE

Tables for Tension and Compression 221
Tackle 43
Temperature Stresses, 217, 222, 473
Tenacity, Moduli of 212
Testing Machine, Autographic. 240
Theorem of Three Moments . . . 497
Thrust (in Flexure) 348, 350
Torsion 233–243
Torsion, Angle of 233
Torsion Clinometers 241
Torsion, Helix Angle in 233
Torsion, Moment of 236
Torsional Resilience 237
Torsional Stiffness 236
Torsional Strength 235
Tractrix, The 181
Transformed Catenary 395
Transmission of Power by Belting 184
Transmission of Power by Shafting 238, 318
Translation, Motion of, 68, 107, 133, 137
Uniformly Accelerated Motion, 54, 107
Uniform Motion 48, 107, 129

PAGE

Uniform Strength, Beams of . . 335
Uniform Strength, Solid of, in Tension 216
Units, Proper Use . . . . see § 6, p. 2
Velocity, Absolute 89
Velocity, Angular 109
Velocity, Linear 49
Velocity, Relative 89
Virtual Moment 67
Virtual Velocities 67
Voussoir 386, 421
Warren Bridge Truss 35
Water, Jets of 87
Web of I-Beam 274
Web of I-Beam, Buckling of . . 383
Web of I-Beam, Shear in 290
Wedge, with Friction 171
Weight 2, 3, 7, 79
Weight, Apparent 78, 79
Wind, and Sail-Boat 89, 90
Work . . . . . 133, 134, etc.
Work and Energy in Machines, 146, 147, etc.
Working-Beam 336, 344
Working Strength 202
Yield-Point 210
Young's Modulus 204

INDEX TO HYDRAULICS.

(For index to "Mechanics of Solids" see p. xvii.)

PAGE

Absolute Temperature 606
Absolute Zero 606
Accumulator, Hydraulic 700
Adiabatic Change, 621, 629, 631, 636
Adiabatic Expansion in Compressed-air Engine 631
Adiabatic Flow of Gases from an Orifice 778
Air Collecting in Water-pipes, 731, 736
Air, Compressed, Transmission of 786–790
Air-compressor 636
Air-profile 749
Air-pump, Sprengel's 656
Air-thermometer 604
Amplitude of Backwater 772
Anemometer, Biram's 827
Anemometer, Castello's 827
Anemometer, Robinson's . .824, 826
Angle of Repose 572
Angular Stability of Ships 597
Atkinson Gas-engine 642, 643
Atmosphere as a Unit Pressure 519
Augment of Resistance of Screw Propeller 829
Backwater 771
Ball, Spinning, Deviation from Vertical Plane 823
Balloon 644
Barker's Mill 672
Barometers 530
Barometric Levelling 619
Bazin, Experiments 688
Beaufoy's Experiments 814
Bellinger, Capt., Experiments with Elbows 729
Bends, Loss of Head due to . . 728
Bends in Open Channels 770
Bent Tube, Liquids in 529
Bernoulli's Theorem and the Conservation of Energy 717
Bernoulli's Theorem for Gases, 773
Bernoulli's Theorem, General Form 706
Bernoulli's Theorem, Steady Flow without Friction . .652, 654

PAGE

Bernoulli's Theorem with Friction 696
Bidone, Experiments on Jets . . 803
Blowing-engine, Test 776
Borda's Formula 722
Bourdon Steam-gauge 532
Boyle's Law 615
Bramah Press 526
Branching Pipes 736
Buoyant Effort 586
Buoyant Effort of the Atmosphere 644
Canal Lock, Time of Filling, 739,740
Centigrade Scale 605
Centre of Buoyancy 586
Centre of Pressure 546
Change of State of Gas 610
Chézy's Formula 714
Chézy's Formula for Open Channels 758
Church and Fteley, Report on Quaker Bridge Dam, 558, 563, 564
Clearance 627
Closed Air-manometer 614
Coal Consumption 643
Coal, Heat of Combustion 643
Coefficient of Contraction 659
Coefficients of Efflux, 661, 676, 712, 734, 738, 784
Coefficient of Fluid Friction, 707, 797
Coefficient of Resistance 704
Coefficient of Roughness . . 759, 760
Coefficient of Velocity, 661, 689, 704, 712, 723, 734
Collapse of Tubes 538
Communicating Prismatic Vessels 739
Complete and Perfect Contraction 676
Component of Fluid Pressure . 525
Compressed-air Engine 631
Compressed Air, Transmission of 786
Compressibility of Water 516
Conical Short Tubes 692
Conservation of Energy and Bernoulli's Theorem 717

(For index to "Mechanics of Solids" see p. xvii.)

PAGE

Contraction 659
Contraction, Perfect 676
Cooling in Sudden Expansion of Gas 622
Critical Temperature of a Vapor 608
Croton Aqueduct, Slope 749
Cunningham, Experiments on the River Ganges 759
Cup-anemometer 824, 826
Cups, Impulse of Jet on . . . 804, 808
Current, Transporting Power of, 830
Current-meters 750
Curved Dams 562
Cylinders, Thin Hollow, Strength 538
Dams, High Masonry 562
Darcy, Experiments with Pitot's Tube 804
Darcy and Bazin, Experiments with Open Channels 758
Decrease of Tension of Gas along a Pipe 793
Depth of Flotation 592
Deviation of Spinning Ball from Vertical Plane 823
Diaphragm in a Pipe, Loss of Head 724
Diesel Oil-engine 642, 643
Differential Manometer 533
Displacement of a Ship 596
Divergent Tubes, Flow through 692
Dividing Surface of Two Fluids 528
Diving-bell 617
Double Floats 750
Draught of Ships 596
Dubuat's Experiments, 707, 815, 822, 830
Duchemin's Formula for Wind-pressure 818
Duty of Pumping-engines 644
Earth Pressure 572
Earthwork Dam 566
Eddy-making Resistance . . 814, 828
Efficiency 637, 642
Efflux of Gases 773–797
Efflux from Steam-boiler 664
Efflux from Vessel in Motion . . 670
Efflux into Condenser 665
Efflux under Water 669
Egg-shaped Section for Sewers . 765
Elastic Fluids 516
Elbows, Loss of Head due to, 727, 729
Emptying Vessels, Time of, 737–746
Engine, Gas- 641
Engine, Hot-air 639
Engine, Oil- 641
Engine, Steam- 624

PAGE

Enlargement, Sudden, in Pipe . 721
Equal Transmission of Fluid Pressure 524
Equation of Continuity, 648, 737, 756
Equation of Continuity for Gases 773
Equation of Continuity for Open Channels 756
Equilibrium of Flotation 590
Ericsson's Hot-air Engine 640
Ewart's Experiments on Jets . 800
Expanding Steam 625
Fahrenheit Scale 605
Fairbairn's Experiments on Collapse of Tubes 538
Fanning, Table of Coefficients of Fluid Friction 709
Feet and Meters, Table 677
Fire-engine Hose, Friction in . . 832
Fire-streams 833
Floating Staff 750
Flood-gate 553
Flotation 590
Flow in Plane Layers 648, 652
Flow in Open Channels 749
Flow of Gas in Pipes 786, 790
Fluid Friction 695, 797, 828
Fluid Friction, Coefficient for Natural Gas 797
Fluid Pressure, Equal Transmission of 524
Force-pump 667
Francis' Formula for Overfalls . 687
Free Surface of Liquid at Rest . 528
Free Surface a Paraboloid 544
Fresh Water, Heaviness, Table 518
Friction-head in Open Channels 757
Friction-head in Pipes 699
Friction, Fluid 695, 797, 828
Froude's Experiments on Fluid Friction 696
Froude's Experiments on Gradual Enlargement in Pipes . . . 725
Froude's Experiments with Piezometers 720
Fteley and Stearn's Experiments on Overfalls 687
Fteley and Stearn's Experiments with Open Channels . . 758
Gas and Vapor 607
Gas-engines 641
Gaseous Fluids 604–645
Gas, Flow through Orifices . 773–784
Gas, Flow through Short Pipes 784
Gas, Illuminating 517, 533
Gas, Natural, Flow in Pipes, 786, 790

(For index to "Mechanics of Solids" see p. xvii.)

PAGE

Gas, Steady Flow 773
Gas, Velocity of Approach ... 784
Gases, Definition 515
Gauging of Streams 755
Gay-Lussac's Law 609
Gradual Enlargement in Pipe . 725
Granular Materials 725
Graphic Representation of Change of State of Gas 628
Haskell's Current-meter 751
Head of Water 530
Heat-engines, Efficiency 642
Heaviness of Fluids 517
Heaviness of Fresh Water at Different Temperatures 518
Height Due to Velocity 649
Height of the Homogeneous Atmosphere 320
Herschel's Venturi Water-meter 726
High Masonry Dams 562
Hoop-tension 537
Hose, Rubber-lined and Unlined, Linen; Friction in ... 832
Hot-air Engines 639
Humphreys and Abbot's Survey of the Mississippi River, 754, 759
Hurdy-gurdy, California 809
Hutton's Formula for Wind-pressure 818
Hydraulic Grade-line 715
Hydraulic Mean Depth, 698, 757, 764
Hydraulic Press 526
Hydraulic Radius 698
Hydraulic Radius for Minimum Friction 764
Hydraulics, Definition 518
Hydrokinetics 518, 646–832
Hydrometers 591
Hydrostatic Pressure 522
Hydrostatics, Definition 518
Ice-making Machine 624
Illuminating Gas 517
Immersion of Rigid Bodies .. 586
Imperfect Contraction 680, 684
Impulse and Resistance of Fluids 797–832
Impulse of Jet on Vanes .. 801, 805
Inclined Short Tubes, Efflux through 691
Incomplete Contraction ...679, 684
Inelastic Fluids 516
Irregular Shape, Emptying of Vessels of 746
Isothermal Change ...615, 629, 639
Isothermal Expansion 624, 635

PAGE

Isothermal Flow of Gas in Pipes 790
Isothermal Flow of Gases through Orifices 777
Jacket of Hot Water 635
Jet from Force-pump 667
Jets, Impulse of 800, 803, 810
Jets of Water 660, 662, 833
Joule, Experiment on Flow of Gas 782
Kansas City Water-works; Siphon 731, 736
Kinetic Energy 672, 718
Kinetic Energy of Jet 672, 808
Kinetic Theory of Gases 516, 606, 622
Kinetics of Gaseous Fluids, 773, 797
Kutter's Formula 759
Kutter's Hydraulic Tables ... 761
Laminated Flow 648, 652
Land-ties 585
Law of Charles 609
Levelling, Barometric 619
Liquefaction of Oxygen 609
Liquid, Definition 515
Long Pipes, Flow of Water through 710–716
Loss of Head....698, 703, 721, etc.
Loss of Head due to Bends ... 728
Loss of Head due to Elbows, 727, 729
Loss of Head due to Throttle-valves 730
Loss of Head due to Valve-gates 730
Manometer, Differential 533
Manometers 530
Mariotte's Law 615, 777
Mechanics of the Sail-boat ... 819
Mendelejeff's Device for Specula 544
Metacentre of a Ship 599
Metres and Feet, Table 677
Mill, Barker's 672
Minimum Frictional Resistance in Open Channel 764, 766
Mississippi River, Hydraulic Survey 754, 759, 770
Mixture of Gases 618
Momentum, Principle of 812
Moving Pistons 524
Moving Vane, Impulse of Jet on 805
Napier on Flow of Steam 781
Natural Gas, Flow in Pipes, 791, 797
Natural Slope, of Earth 573
Non-planar Pistons 526
Notch, Rectangular, Efflux from 683, 741

(For index to "Mechanics of Solids" see p. xvii.)

PAGE

Obelisk-shaped Vessel; Time of Emptying 744
Oblique Impact of Jet on Plate, 810
Oil-engines, ...641, 642
Open Channels, Flow in ...749–797
Orifices in Thin Plate.....658, 773
Otto Gas-engine 641, 643
Overfall, Emptying Reservoir through 741
Overfall Weirs . .677, 683, 688, 756
Overfall Weirs, Actual Discharge 683
Paddle-wheel of a Steamer . . . 817
Paraboloid as Free Surface . . . 544
Paraboloidal Vessel..... 742
Parallelopipedical Reservoir Walls 555
Pelton Wheel or Hurdy-gurdy. 809
Perfect Fluid, Definition 515
Permanent Gases 605, 608
Petroleum-engine 641
Petroleum Pumping 708
Piezometer 649, 657, 700
Pipes, of Various Surfaces 708
Pipes, Foul 707
Pipes, Riveted Steel 708
Pipes, Thickness of, for Strength 538
Piston Pressures 523
Pistons, Moving..... 524
Pistons, Non-planar 526
Pitot's Tube 751, 797, 804, 827
Plate between Two Levels of Water 568, 569
Plates, Impulse of Jets on, 801, 805, 810
Plates, Moving in a Fluid 813
Plates, Resistance in Sea-water 814
Pneumatics, Definition 518
Poisson's Law 621
Poncelet's Experiments with Overfalls 677
Power Required to Propel Ships 830
Pressure, Centre of 546
Pressure-energy 717
Pressure-head 650
Pressure on Bottom of a Vessel 545
Pressure on Curved Surfaces .. 569
Pressure on Sluice-gates..... 551
Pressure per Unit-area 519
Principle of Momentum 812
Pyramidal Vessel, Emptying of 743
Quaker Bridge Dam, Proposed 564
Radian, Definition 544
Reaction of a Water-jet 798
Rectangular Orifices.....672, 676
Refrigerator of Hot-air Engine 640

PAGE

Regenerator of Hot-air Engine 640
Relative Equilibrium of a Liquid 540
Reservoir of Irregular Shape, Emptying of 746
Reservoir Walls 554–567
Resistance, Eddy-making..814, 828
Resistance, Wave-making 828
Resistance of Fluid to Moving Bodies 820
Resistance of Fluid to Moving Plates 814
Resistance of Ships 828
Resistance of Still Water to Moving Solids 820
Retaining Walls 572–580
Righting Couple, of Floating Body 597
Ritchie-Haskell Direction Current-meter 750
Rivers, Flow in 749
Robinson, Prof., Experiments on Flow of Natural Gas 797
Robinson's Anemometer.. 824, 826
Rounded Orifice 663
Safety-valves 534
Sail-boat, Mechanics of the ... 819
Sail-boat Moving Faster than the Wind 820
Saturated Steam, Heaviness .. 628
Saturated Vapor 607
Scouring Action of a Current.. 830
Screw Propeller, Augment of.. 829
Sewers, Flow in 761, 765
Ships, Resistance of 828
Ships, Stability of.....597, 599
Short Cylindrical Pipes, Efflux through 689, 704
Short Pipe, Minimum Head for Full Discharge 724
Short Pipes 722, 723
Simpson's Rule.....603, 747, 748
Siphons 735
Skin-friction 695, 828
"Slip" 829
Slope, in Open Channels 749
Smithsonian Scale of Wind-pressures 819
Solid of Revolution, Impulse of Jet on 803
Specific Gravity..... 589
Sprengel's Air-pump 656
St. Gothard Tunnel, Experiments in 787
Stability of Rectangular Wall. 554
Stability of Ships 597
State of Permanency of Flow . 647
Steady Flow, Definition 647

* Corthell's Allowable Pressure on Deep Foundations 12mo, 1 25
Freitag's Architectural Engineering 8vo 3 50
Fireproofing of Steel Buildings 8vo, 2 50
French and Ives's Stereotomy 8vo, 2 50
Gerhard's Guide to Sanitary House-Inspection 16mo, 1 00
* Modern Baths and Bath Houses 8vo, 3 00
Sanitation of Public Buildings 12mo, 1 50
Theatre Fires and Panics 12mo, 1 50
Holley and Ladd's Analysis of Mixed Paints, Color Pigments, and Varnishes Large 12mo, 2 50
Johnson's Statics by Algebraic and Graphic Methods 8vo, 2 00
Kellaway's How to Lay Out Suburban Home Grounds 8vo, 2 00
Kidder's Architects' and Builders' Pocket-book ..... 16mo, mor., 5 00
Maire's Modern Pigments and their Vehicles 12mo, 2 00
Merrill's Non-metallic Minerals: Their Occurrence and Uses 8vo, 4 00
Stones for Building and Decoration 8vo, 5 00
Monckton's Stair-building 4to, 4 00
Patton's Practical Treatise on Foundations 8vo, 5 00
Peabody's Naval Architecture 8vo, 7 50
Rice's Concrete-block Manufacture 8vo, 2 00
Richey's Handbook for Superintendents of Construction ..... 16mo, mor., 4 00
* Building Mechanics' Ready Reference Book:
* Building Foreman's Pocket Book and Ready Reference. (In Preparation).
* Carpenters' and Woodworkers' Edition ..... 16mo, mor. 1 50
* Cement Workers and Plasterer's Edition ..... 16mo, mor. 1 50
* Plumbers', Steam-Filters', and Tinners' Edition ..... 16mo, mor. 1 50
* Stone- and Brick-masons' Edition ..... 16mo, mor. 1 50
Sabin's Industrial and Artistic Technology of Paints and Varnish 8vo, 3 00
Siebert and Biggin's Modern Stone-cutting and Masonry 8vo, 1 50
Snow's Principal Species of Wood 8vo, 3 50
Towne's Locks and Builders' Hardware ..... 18mo, mor. 3 00
Wait's Engineering and Architectural Jurisprudence 8vo, 6 00
Sheep, 6 50
Law of Contracts 8vo, 3 00
Law of Operations Preliminary to Construction in Engineering and Architecture 8vo, 5 00
Sheep, 5 50
Wilson's Air Conditioning 12mo, 1 50
Worcester and Atkinson's Small Hospitals, Establishment and Maintenance, Suggestions for Hospital Architecture, with Plans for a Small Hospital. 12mo, 1 25

ARMY AND NAVY.

Bernadou's Smokeless Powder, Nitro-cellulose, and the Theory of the Cellulose Molecule 12mo, 2 50
Chase's Art of Pattern Making 12mo, 2 50
Screw Propellers and Marine Propulsion 8vo, 3 00
Cloke's Gunner's Examiner 8vo, 1 50
Craig's Azimuth 4to, 3 50
Crehore and Squier's Polarizing Photo-chronograph 8vo, 3 00
* Davis's Elements of Law 8vo, 2 50
* Treatise on the Military Law of United States 8vo, 7 00
Sheep, 7 50
De Brack's Cavalry Outpost Duties. (Carr.) ..... 24mo, mor. 2 00
* Dudley's Military Law and the Procedure of Courts-martial ..... Large 12mo, 2 50
Durand's Resistance and Propulsion of Ships 8vo, 5 00

* Dyer's Handbook of Light Artillery	12mo,	3 00
Eissler's Modern High Explosives	8vo,	4 00
* Fiebeger's Text-book on Field Fortification	Large 12mo,	2 00
Hamilton and Bond's The Gunner's Catechism	18mo,	1 00
* Hoff's Elementary Naval Tactics	8vo,	1 50
Ingalls's Handbook of Problems in Direct Fire	8vo,	4 00
* Lissak's Ordnance and Gunnery	8vo,	6 00
* Ludlow's Logarithmic and Trigonometric Tables	8vo,	1 00
* Lyons's Treatise on Electromagnetic Phenomena. Vols. I. and II.	8vo, each,	6 00
* Mahan's Permanent Fortifications. (Mercur.)	8vo, half mor.	7 50
Manual for Courts-martial	16mo, mor.	1 50
* Mercur's Attack of Fortified Places	12mo,	2 00
* Elements of the Art of War	8vo,	4 00
Metcalf's Cost of Manufactures—And the Administration of Workshops	8vo,	5 00
* Ordnance and Gunnery. 2 vols.	Text 12mo, Plates atlas form	5 00
Nixon's Adjutants' Manual	24mo,	1 00
Peabody's Naval Architecture	8vo,	7 50
* Phelps's Practical Marine Surveying	8vo,	2 50
Powell's Army Officer's Examiner	12mo,	4 00
Sharpe's Art of Subsisting Armies in War	18mo, mor.	1 50
* Tupes and Poole's Manual of Bayonet Exercises and Musketry Fencing	24mo, leather,	50
* Weaver's Military Explosives	8vo,	3 00
Woodhull's Notes on Military Hygiene	16mo,	1 50

ASSAYING.

Betts's Lead Refining by Electrolysis	8vo,	4 00
Fletcher's Practical Instructions in Quantitative Assaying with the Blowpipe	16mo, mor.	1 50
Furman's Manual of Practical Assaying	8vo,	3 00
Lodge's Notes on Assaying and Metallurgical Laboratory Experiments	8vo,	3 00
Low's Technical Methods of Ore Analysis	8vo,	3 00
Miller's Cyanide Process	12mo,	1 00
Manual of Assaying	12mo,	1 00
Minet's Production of Aluminum and its Industrial Use. (Waldo.)	12mo,	2 50
O'Driscoll's Notes on the Treatment of Gold Ores	8vo,	2 00
Ricketts and Miller's Notes on Assaying	8vo,	3 00
Robine and Lenglen's Cyanide Industry. (Le Clerc.)	8vo,	4 00
Ulke's Modern Electrolytic Copper Refining	8vo,	3 00
Wilson's Chlorination Process	12mo,	1 50
Cyanide Processes	12mo,	1 50

ASTRONOMY.

Comstock's Field Astronomy for Engineers	8vo,	2 50
Craig's Azimuth	4to,	3 50
Crandall's Text-book on Geodesy and Least Squares	8vo,	3 00
Doolittle's Treatise on Practical Astronomy	8vo,	4 00
Gore's Elements of Geodesy	8vo,	2 50
Hayford's Text-book of Geodetic Astronomy	8vo,	3 00
Merriman's Elements of Precise Surveying and Geodesy	8vo,	2 50
* Michie and Harlow's Practical Astronomy	8vo,	3 00
Rust's Ex-meridian Altitude, Azimuth and Star-Finding Tables. (In Press.)		
* White's Elements of Theoretical and Descriptive Astronomy	12mo,	2 00

Abderhalden's Physiological Chemistry in Thirty Lectures. (Hall and Defren). (In Press.)

* Abegg's Theory of Electrolytic Dissociation. (von Ende.) 12mo, 1 25
Adriance's Laboratory Calculations and Specific Gravity Tables 12mo, 1 25
Alexeyeff's General Principles of Organic Syntheses. (Matthews.) 8vo, 3 00
Allen's Tables for Iron Analysis 8vo, 3 00
Arnold's Compendium of Chemistry. (Mandel.) ..... Large 12mo, 3 50
Association of State and National Food and Dairy Departments, Hartford Meeting, 1906 ..... 8vo, 3 00
Jamestown Meeting, 1907 ..... 8vo, 3 00
Austen's Notes for Chemical Students 12mo, 1 50
Baskerville's Chemical Elements. (In Preparation).
Bernadou's Smokeless Powder.—Nitro-cellulose, and Theory of the Cellulose Molecule 12mo, 2 50
* Blanchard's Synthetic Inorganic Chemistry 12mo, 1 00
* Browning's Introduction to the Rarer Elements 8vo, 1 50
Brush and Penfield's Manual of Determinative Mineralogy 8vo, 4 00
* Claassen's Beet-sugar Manufacture. (Hall and Rolfe.) 8vo, 3 00
Classen's Quantitative Chemical Analysis by Electrolysis. (Boltwood.) 8vo, 3 00
Cohn's Indicators and Test-papers 12mo, 2 00
Tests and Reagents 8vo, 3 00
* Danneel's Electrochemistry. (Merriam.) 12mo, 1 25
Duhem's Thermodynamics and Chemistry. (Burgess.) 8vo, 4 00
Eakle's Mineral Tables for the Determination of Minerals by their Physical Properties 8vo, 1 25
Eissler's Modern High Explosives 8vo, 4 00
Effront's Enzymes and their Applications. (Prescott.) 8vo, 3 00
Erdmann's Introduction to Chemical Preparations. (Dunlap.) 12mo, 1 25
* Fischer's Physiology of Alimentation ..... Large 12mo, 2 00
Fletcher's Practical Instructions in Quantitative Assaying with the Blowpipe. 12mo, mor. 1 50
Fowler's Sewage Works Analyses 12mo, 2 00
Fresenius's Manual of Qualitative Chemical Analysis. (Wells.) 8vo, 5 00
Manual of Qualitative Chemical Analysis. Part I. Descriptive. (Wells.) 8vo, 3 00
Quantitative Chemical Analysis. (Cohn.) 2 vols 8vo, 12 50
When Sold Separately, Vol. I, $6. Vol. II, $8.
Fuertes's Water and Public Health 12mo, 1 50
Furman's Manual of Practical Assaying 8vo, 3 00
* Getman's Exercises in Physical Chemistry 12mo, 2 00
Gill's Gas and Fuel Analysis for Engineers 12mo, 1 25
* Gooch and Browning's Outlines of Qualitative Chemical Analysis. Large 12mo, 1 25
Grotenfelt's Principles of Modern Dairy Practice. (Woll.) 12mo, 2 00
Groth's Introduction to Chemical Crystallography (Marshall) 12mo, 1 25
Hammarsten's Text-book of Physiological Chemistry. (Mandel.) 8vo, 4 00
Hanausek's Microscopy of Technical Products. (Winton.) 8vo, 5 00
* Haskins and Macleod's Organic Chemistry 12mo, 2 00
Helm's Principles of Mathematical Chemistry. (Morgan.) 12mo, 1 50
Hering's Ready Reference Tables (Conversion Factors) ..... 16mo, mor. 2 50
* Herrick's Denatured or Industrial Alcohol 8vo, 4 00
Hinds's Inorganic Chemistry 8vo, 3 00
* Laboratory Manual for Students 12mo, 1 00
* Holleman's Laboratory Manual of Organic Chemistry for Beginners. (Walker.) 12mo, 1 00
Text-book of Inorganic Chemistry. (Cooper.) 8vo, 2 50
Text-book of Organic Chemistry. (Walker and Mott.) 8vo, 2 50
Holley and Ladd's Analysis of Mixed Paints, Color Pigments, and Varnishes. Large 12mo 2 50

Hopkins's Oil-chemists' Handbook.....8vo, 3 00
Iddings's Rock Minerals.....8vo, 5 00
Jackson's Directions for Laboratory Work in Physiological Chemistry..8vo, 1 25
Johannsen's Determination of Rock-forming Minerals in Thin Sections...8vo, 4 00
Keep's Cast Iron.....8vo, 2 50
Ladd's Manual of Quantitative Chemical Analysis.....12mo, 1 00
Landauer's Spectrum Analysis. (Tingle.).....8vo, 3 00
* Langworthy and Austen's Occurrence of Aluminium in Vegetable Products, Animal Products, and Natural Waters.....8vo, 2 00
Lassar-Cohn's Application of Some General Reactions to Investigations in Organic Chemistry. (Tingle.).....12mo, 1 00
Leach's Inspection and Analysis of Food with Special Reference to State Control.....8vo, 7 50
Löb's Electrochemistry of Organic Compounds. (Lorenz.).....8vo, 3 00
Lodge's Notes on Assaying and Metallurgical Laboratory Experiments...8vo, 3 00
Low's Technical Method of Ore Analysis.....8vo, 3 00
Lunge's Techno-chemical Analysis. (Cohn.).....12mo 1 00
* McKay and Larsen's Principles and Practice of Butter-making.....8vo, 1 50
Maire's Modern Pigments and their Vehicles.....12mo, 2 00
Mandel's Handbook for Bio-chemical Laboratory.....12mo, 1 50
* Martin's Laboratory Guide to Qualitative Analysis with the Blowpipe..12mo, 60
Mason's Examination of Water. (Chemical and Bacteriological.)....12mo, 1 25
Water-supply. (Considered Principally from a Sanitary Standpoint.) 8vo, 4 00
Matthews's The Textile Fibres. 2d Edition, Rewritten.....8vo, 4 00
Meyer's Determination of Radicles in Carbon Compounds. (Tingle.)..12mo, 1 00
Miller's Cyanide Process.....12mo, 1 00
Manual of Assaying.....12mo, 1 00
Minet's Production of Aluminum and its Industrial Use. (Waldo.)....12mo, 2 50
Mixter's Elementary Text-book of Chemistry.....12mo, 1 50
Morgan's Elements of Physical Chemistry.....12mo, 3 00
Outline of the Theory of Solutions and its Results.....12mo, 1 00
* Physical Chemistry for Electrical Engineers.....12mo, 1 50
Morse's Calculations used in Cane-sugar Factories.....16mo, mor. 1 50
* Muir's History of Chemical Theories and Laws.....8vo, 4 00
Mulliken's General Method for the Identification of Pure Organic Compounds. Vol. I.....Large 8vo, 5 00
O'Driscoll's Notes on the Treatment of Gold Ores.....8vo, 2 00
Ostwald's Conversations on Chemistry. Part One. (Ramsey.).....12mo, 1 50
" " " " Part Two. (Turnbull.).....12mo, 2 00
* Palmer's Practical Test Book of Chemistry.....12mo, 1 00
* Pauli's Physical Chemistry in the Service of Medicine. (Fischer.)....12mo, 1 25
* Penfield's Notes on Determinative Mineralogy and Record of Mineral Tests. 8vo, paper, 50
Tables of Minerals, Including the Use of Minerals and Statistics of Domestic Production.....8vo, 1 00
Pictet's Alkaloids and their Chemical Constitution. (Biddle.).....8vo, 5 00
Poole's Calorific Power of Fuels.....8vo, 3 00
Prescott and Winslow's Elements of Water Bacteriology, with Special Reference to Sanitary Water Analysis.....12mo, 1 50
* Reisig's Guide to Piece-dyeing.....8vo, 25 00
Richards and Woodman's Air, Water, and Food from a Sanitary Standpoint..8vo, 2 00
Ricketts and Miller's Notes on Assaying.....8vo, 3 00
Rideal's Disinfection and the Preservation of Food.....8vo, 4 00
Sewage and the Bacterial Purification of Sewage.....8vo, 4 00
Riggs's Elementary Manual for the Chemical Laboratory.....8vo, 1 25
Robine and Lenglen's Cyanide Industry. (Le Clerc.).....8vo, 4 00
Ruddiman's Incompatibilities in Prescriptions.....8vo, 2 00
Whys in Pharmacy.....12mo, 1 00

Ruer's Elements of Metallography. (Mathewson). (In Preparation.)
Sabin's Industrial and Artistic Technology of Paints and Varnish. 8vo, 3 00
Salkowski's Physiological and Pathological Chemistry. (Orndorff.). 8vo, 2 50
Schimpf's Essentials of Volumetric Analysis. 12mo, 1 25
* Qualitative Chemical Analysis 8vo, 1 25
Text-book of Volumetric Analysis. 12mo, 2 50
Smith's Lecture Notes on Chemistry for Dental Students. 8vo, 2 50
Spencer's Handbook for Cane Sugar Manufacturers. ..... 16mo, mor. 3 00
Handbook for Chemists of Beet-sugar Houses ..... 16mo, mor. 3 00
Stockbridge's Rocks and Soils. 8vo, 2 50
*. Tillman's Descriptive General Chemistry. 8vo, 3 00
* Elementary Lessons in Heat 8vo, 1 50
Treadwell's Qualitative Analysis. (Hall.). 8vo, 3 00
Quantitative Analysis. (Hall.). 8vo, 4 00
Turneaure and Russell's Public Water-supplies 8vo, 5 00
Van Deventer's Physical Chemistry for Beginners. (Boltwood.) 12mo, 1 50
Venable's Methods and Devices for Bacterial Treatment of Sewage 8vo, 3 00
Ward and Whipple's Freshwater Biology. (In Press.)
Ware's Beet-sugar Manufacture and Refining. Vol. I. ..... Small 8vo, 4 00
" " " " " Vol. II. ..... Small 8vo, 5 00
Washington's Manual of the Chemical Analysis of Rocks. 8vo, 2 00
* Weaver's Military Explosives. 8vo, 3 00
Wells's Laboratory Guide in Qualitative Chemical Analysis. 8vo, 1 50
Short Course in Inorganic Qualitative Chemical Analysis for Engineering Students. 12mo, 1 50
Text-book of Chemical Arithmetic 12mo, 1 25
Whipple's Microscopy of Drinking-water. 8vo, 3 50
Wilson's Chlorination Process. 12mo 1 50
Cyanide Processes 12mo 1 50
Winton's Microscopy of Vegetable Foods 8vo 7 50

CIVIL ENGINEERING.

BRIDGES AND ROOFS. HYDRAULICS. MATERIALS OF ENGINEERING. RAILWAY ENGINEERING.

Baker's Engineers' Surveying Instruments. 12mo, 3 00
Bixby's Graphical Computing Table. ..... Paper 19½ × 24¼ inches. 25
Breed and Hosmer's Principles and Practice of Surveying 8vo, 3 00
* Burr's Ancient and Modern Engineering and the Isthmian Canal 8vo, 3 50
Comstock's Field Astronomy for Engineers. 8vo, 2 50
* Corthell's Allowable Pressures on Deep Foundations 12mo, 1 25
Crandall's Text-book on Geodesy and Least Squares 8vo, 3 00
Davis's Elevation and Stadia Tables. 8vo, 1 00
Elliott's Engineering for Land Drainage. 12mo, 1 50
Practical Farm Drainage. 12mo, 1 00
*Fiebeger's Treatise on Civil Engineering. 8vo, 5 00
Flemer's Phototopographic Methods and Instruments. 8vo, 5 00
Folwell's Sewerage. (Designing and Maintenance.). 8vo, 3 00
Freitag's Architectural Engineering. 8vo, 3 50
French and Ives's Stereotomy 8vo, 2 50
Goodhue's Municipal Improvements. 12mo, 1 50
Gore's Elements of Geodesy. 8vo, 2 50
* Hauch and Rice's Tables of Quantities for Preliminary Estimates. 12mo, 1 25
Hayford's Text-book of Geodetic Astronomy. 8vo, 3 00
Hering's Ready Reference Tables (Conversion Factors). ..... 16mo, mor. 2 50
Howe's Retaining Walls for Earth. 12mo, 1 25

* Ives's Adjustments of the Engineer's Transit and Level. . . . . 16mo, Bds. 25
Ives and Hilts's Problems in Surveying . . . . . 16mo, mor. 1 50
Johnson's (J. B.) Theory and Practice of Surveying. . . . . Small 8vo, 4 00
Johnson's (L. J.) Statics by Algebraic and Graphic Methods. 8vo, 2 00
Kinnicutt, Winslow and Pratt's Purification of Sewage. (In Preparation).
Laplace's Philosophical Essay on Probabilities. (Truscott and Emory.)
12mo, 2 00
Mahan's Descriptive Geometry. 8vo, 1 50
Treatise on Civil Engineering. (1873.) (Wood.). 8vo, 5 00
Merriman's Elements of Precise Surveying and Geodesy. 8vo, 2 50
Merriman and Brooks's Handbook for Surveyors. . . . . 16mo, mor. 2 00
Morrison's Elements of Highway Engineering. (In Press.)
Nugent's Plane Surveying. 8vo, 3 50
Ogden's Sewer Design. 12mo, 2 00
Parsons's Disposal of Municipal Refuse. 8vo, 2 00
Patton's Treatise on Civil Engineering. . . . . 8vo, half leather, 7 50
Reed's Topographical Drawing and Sketching 4to, 5 00
Rideal's Sewage and the Bacterial Purification of Sewage. 8vo, 4 00
Riemer's Shaft-sinking under Difficult Conditions. (Corning and Peele.). . 8vo, 3 00
Siebert and Biggin's Modern Stone-cutting and Masonry. 8vo, 1 50
Smith's Manual of Topographical Drawing. (McMillan.). 8vo, 2 50
Soper's Air and Ventilation of Subways. (In Press.)
Tracy's Plane Surveying. . . . . 16mo, mor. 3 00
* Trautwine's Civil Engineer's Pocket-book. . . . . 16mo, mor. 5 00
Venable's Garbage Crematories in America. 8vo, 2 00
Methods and Devices for Bacterial Treatment of Sewage. 8vo, 3 00
Wait's Engineering and Architectural Jurisprudence. 8vo, 6 00
Sheep, 6 50
Law of Contracts. 8vo, 3 00
Law of Operations Preliminary to Construction in Engineering and Architecture. 8vo, 5 00
Sheep, 5 50
Warren's Stereotomy—Problems in Stone-cutting. 8vo, 2 50
* Waterbury's Vest-Pocket Hand-book of Mathematics for Engineers.
$2\frac{1}{2} \times 5\frac{3}{8}$ inches, mor. 1 00
Webb's Problems in the Use and Adjustment of Engineering Instruments.
16mo, mor. 1 25
Wilson's Topographic Surveying. 8vo, 3 50

BRIDGES AND ROOFS.

Boller's Practical Treatise on the Construction of Iron Highway Bridges. . 8vo, 2 00
Burr and Falk's Design and Construction of Metallic Bridges 8vo, 5 00
Influence Lines for Bridge and Roof Computations. 8vo, 3 00
Du Bois's Mechanics of Engineering. Vol. II. . . . . Small 4to, 10 00
Foster's Treatise on Wooden Trestle Bridges. 4to, 5 00
Fowler's Ordinary Foundations 8vo, 3 50
French and Ives's Stereotomy. 8vo, 2 50
Greene's Arches in Wood, Iron, and Stone. 8vo, 2 50
Bridge Trusses. 8vo, 2 50
Roof Trusses. 8vo, 1 25
Grimm's Secondary Stresses in Bridge Trusses. 8vo, 2 50
Heller's Stresses in Structures and the Accompanying Deformations. 8vo,
Howe's Design of Simple Roof-trusses in Wood and Steel. 8vo, 2 00
Symmetrical Masonry Arches. 8vo, 2 50
Treatise on Arches. 8vo, 4 00
Johnson, Bryan, and Turneaure's Theory and Practice in the Designing of Modern Framed Structures. . . . . Small 4to, 10 00

Merriman and Jacoby's Text-book on Roofs and Bridges:
Part I. Stresses in Simple Trusses....8vo, 2 50
Part II. Graphic Statics....8vo, 2 50
Part III. Bridge Design....8vo, 2 50
Part IV. Higher Structures....8vo, 2 50
Morison's Memphis Bridge....Oblong 4to, 10 00
Sondericker's Graphic Statics, with Applications to Trusses, Beams, and Arches. 8vo, 2 00
Waddell's De Pontibus, Pocket-book for Bridge Engineers....16mo, mor, 2 00
* Specifications for Steel Bridges....12mo, 50
Waddell and Harrington's Bridge Engineering. (In Preparation.)
Wright's Designing of Draw-spans. Two parts in one volume....8vo, 3 50

HYDRAULICS.

Barnes's Ice Formation....8vo, 3 00
Bazin's Experiments upon the Contraction of the Liquid Vein Issuing from an Orifice. (Trautwine.)....8vo, 2 00
Bovey's Treatise on Hydraulics....8vo, 5 00
Church's Diagrams of Mean Velocity of Water in Open Channels. Oblong 4to, paper, 1 50
Hydraulic Motors....8vo, 2 00
Mechanics of Engineering....8vo, 6 00
Coffin's Graphical Solution of Hydraulic Problems....16mo, morocco, 2 50
Flather's Dynamometers, and the Measurement of Power....12mo, 3 00
Folwell's Water-supply Engineering....8vo, 4 00
Frizell's Water-power....8vo, 5 00
Fuertes's Water and Public Health....12mo, 1 50
Water-filtration Works....12mo, 2 50
Ganguillet and Kutter's General Formula for the Uniform Flow of Water in Rivers and Other Channels. (Hering and Trautwine.)....8vo, 4 00
Hazen's Clean Water and How to Get It....Large 12mo, 1 50
Filtration of Public Water-supplies....8vo, 3 00
Hazlehurst's Towers and Tanks for Water-works....8vo, 2 50
Herschel's 115 Experiments on the Carrying Capacity of Large, Riveted, Metal Conduits....8vo, 2 00
Hoyt and Grover's River Discharge....8vo, 2 00
Hubbard and Kiersted's Water-works Management and Maintenance....8vo, 4 00
* Lyndon's Development and Electrical Distribution of Water Power....8vo, 3 00
Mason's Water-supply. (Considered Principally from a Sanitary Standpoint.) 8vo, 4 00
Merriman's Treatise on Hydraulics....8vo, 5 00
* Michie's Elements of Analytical Mechanics....8vo, 4 00
Molitor's Hydraulics of Rivers, Weirs and Sluices. (In Press.)
Schuyler's Reservoirs for Irrigation, Water-power, and Domestic Water-supply....Large 8vo, 5 00
* Thomas and Watt's Improvement of Rivers....4to, 6 00
Turneaure and Russell's Public Water-supplies....8vo, 5 00
Wegmann's Design and Construction of Dams. 5th Ed., enlarged....4to, 6 00
Water-supply of the City of New York from 1658 to 1895....4to, 10 00
Whipple's Value of Pure Water....Large 12mo, 1 00
Williams and Hazen's Hydraulic Tables....8vo, 1 50
Wilson's Irrigation Engineering....Small 8vo, 4 00
Wolff's Windmill as a Prime Mover....8vo, 3 00
Wood's Elements of Analytical Mechanics....8vo, 3 00
Turbines....8vo, 2 50

MATERIALS OF ENGINEERING.

Baker's Roads and Pavements.....8vo, 5 00
Treatise on Masonry Construction.....8vo, 5 00
Birkmire's Architectural Iron and Steel.....8vo, 3 50
Compound Riveted Girders as Applied in Buildings.....8vo, 2 00
Black's United States Public Works.....Oblong 4to, 5 00
Bleininger's Manufacture of Hydraulic Cement. (In Preparation.)
* Bovey's Strength of Materials and Theory of Structures.....8vo, 7 50
Burr's Elasticity and Resistance of the Materials of Engineering.....8vo, 7 50
Byrne's Highway Construction.....8vo, 5 00
Inspection of the Materials and Workmanship Employed in Construction. 16mo, 3 00
Church's Mechanics of Engineering.....8vo, 6 00
Du Bois's Mechanics of Engineering.
Vol. I. Kinematics, Statics, Kinetics.....Small 4to, 7 50
Vol. II. The Stresses in Framed Structures, Strength of Materials and Theory of Flexures.....Small 4to, 10 00
*Eckel's Cements, Limes, and Plasters.....8vo, 6 00
Stone and Clay Products used in Engineering. (In Preparation.)
Fowler's Ordinary Foundations.....8vo, 3 50
Graves's Forest Mensuration.....8vo, 4 00
Green's Principles of American Forestry.....12mo, 1 50
* Greene's Structural Mechanics.....8vo, 2 50
Holly and Ladd's Analysis of Mixed Paints, Color Pigments and Varnishes Large 12mo, 2 50
Johnson's Materials of Construction.....Large 8vo, 6 00
Keep's Cast Iron.....8vo, 2 50
Kidder's Architects and Builders' Pocket-book.....16mo, 5 00
Lanza's Applied Mechanics.....8vo, 7 50
Maire's Modern Pigments and their Vehicles.....12mo, 2 00
Martens's Handbook on Testing Materials. (Henning.) 2 vols.....8vo, 7 50
Maurer's Technical Mechanics.....8vo, 4 00
Merrill's Stones for Building and Decoration.....8vo, 5 00
Merriman's Mechanics of Materials.....8vo, 5 00
* Strength of Materials.....12mo, 1 00
Metcalf's Steel. A Manual for Steel-users.....12mo, 2 00
Patton's Practical Treatise on Foundations.....8vo, 5 00
Rice's Concrete Block Manufacture.....8vo, 2 00
Richardson's Modern Asphalt Pavements.....8vo, 3 00
Richey's Handbook for Superintendents of Construction.....16mo, mor., 4 00
* Ries's Clays: Their Occurrence, Properties, and Uses.....8vo, 5 00
Sabin's Industrial and Artistic Technology of Paints and Varnish.....8vo, 3 00
* Schwarz's Longleaf Pine in Virgin Forest.....12mo, 1 25
Snow's Principal Species of Wood.....8vo, 3 50
Spalding's Hydraulic Cement.....12mo, 2 00
Text-book on Roads and Pavements.....12mo, 2 00
Taylor and Thompson's Treatise on Concrete, Plain and Reinforced.....8vo, 5 00
Thurston's Materials of Engineering. In Three Parts.....8vo, 8 00
Part I. Non-metallic Materials of Engineering and Metallurgy.....8vo, 2 00
Part II. Iron and Steel.....8vo, 3 50
Part III. A Treatise on Brasses, Bronzes, and Other Alloys and their Constituents.....8vo, 2 50
Tillson's Street Pavements and Paving Materials.....8vo, 4 00
Turneaure and Maurer's Principles of Reinforced Concrete Construction.....8vo, 3 00
Wood's (De V.) Treatise on the Resistance of Materials, and an Appendix on the Preservation of Timber.....8vo, 2 00
Wood's (M. P.) Rustless Coatings: Corrosion and Electrolysis of Iron and Steel.....8vo, 4 00

RAILWAY ENGINEERING.

Andrews's Handbook for Street Railway Engineers.....3x5 inches, mor. 1 25
Berg's Buildings and Structures of American Railroads.....4to, 5 00
Brooks's Handbook of Street Railroad Location.....16mo, mor. 1 50
Butt's Civil Engineer's Field-book.....16mo, mor. 2 50
Crandall's Railway and Other Earthwork Tables.....8vo, 1 50
Transition Curve.....16mo, mor. 1 50
* Crockett's Methods for Earthwork Computations.....8vo, 1 50
Dawson's "Engineering" and Electric Traction Pocket-book.....16mo, mor. 5 00
Dredge's History of the Pennsylvania Railroad: (1879).....Paper, 5 00
Fisher's Table of Cubic Yards.....Cardboard, 25
Godwin's Railroad Engineers' Field-book and Explorers' Guide...16mo, mor. 2 50
Hudson's Tables for Calculating the Cubic Contents of Excavations and Embankments.....8vo, 1 00
Ives and Hilts's Problems in Surveying, Railroad Surveying and Geodesy 16mo, mor. 1 50
Molitor and Beard's Manual for Resident Engineers.....16mo, 1 00
Nagle's Field Manual for Railroad Engineers.....16mo, mor. 3 00
Philbrick's Field Manual for Engineers.....16mo, mor. 3 00
Raymond's Railroad Engineering. 3 volumes.
Vol. I. Railroad Field Geometry. (In Preparation.)
Vol. II. Elements of Railroad Engineering.....8vo, 3 50
Vol III. Railroad Engineer's Field Book. (In Preparation.)
Searles's Field Engineering.....16mo, mor. 3 00
Railroad Spiral.....16mo, mor. 1 50
Taylor's Prismoidal Formulæ and Earthwork.....8vo, 1 50
* Trautwine's Field Practice of Laying Out Circular Curves for Railroads. 12mo. mor, 2 50
* Method of Calculating the Cubic Contents of Excavations and Embankments by the Aid of Diagrams.....8vo, 2 00
Webb's Economics of Railroad Construction.....Large 12mo, 2 50
Railroad Construction.....16mo, mor. 5 00
Wellington's Economic Theory of the Location of Railways.....Small 8vo, 5 00

DRAWING.

Barr's Kinematics of Machinery.....8vo, 2 50
* Bartlett's Mechanical Drawing.....8vo, 3 00
* " " " Abridged Ed.....8vo, 1 50
Coolidge's Manual of Drawing.....8vo, paper, 1 00
Coolidge and Freeman's Elements of General Drafting for Mechanical Engineers.....Oblong 4to, 2 50
Durley's Kinematics of Machines.....8vo, 4 00
Emch's Introduction to Projective Geometry and its Applications.....8vo, 2 50
Hill's Text-book on Shades and Shadows, and Perspective.....8vo, 2 00
Jamison's Advanced Mechanical Drawing.....8vo, 2 00
Elements of Mechanical Drawing.....8vo, 2 50
Jones's Machine Design:
Part I. Kinematics of Machinery.....8vo, 1 50
Part II. Form, Strength, and Proportions of Parts.....8vo, 3 00
MacCord's Elements of Descriptive Geometry.....8vo, 3 00
Kinematics; or, Practical Mechanism.....8vo, 5 00
Mechanical Drawing.....4to, 4 00
Velocity Diagrams.....8vo, 1 50
McLeod's Descriptive Geometry.....Large 12mo, 1 50
* Mahan's Descriptive Geometry and Stone-cutting.....8vo, 1 50
Industrial Drawing. (Thompson.).....8vo, 3 50

Moyer's Descriptive Geometry. 8vo, 2 00
Reed's Topographical Drawing and Sketching. 4to, 5 00
Reid's Course in Mechanical Drawing. 8vo, 2 00
Text-book of Mechanical Drawing and Elementary Machine Design. 8vo, 3 00
Robinson's Principles of Mechanism. 8vo, 3 00
Schwamb and Merrill's Elements of Mechanism. 8vo, 3 00
Smith's (R. S.) Manual of Topographical Drawing. (McMillan.). 8vo, 2 50
Smith (A. W.) and Marx's Machine Design. 8vo, 3 00
* Titsworth's Elements of Mechanical Drawing . . . . . Oblong 8vo, 1 25
Warren's Drafting Instruments and Operations. 12mo, 1 25
Elements of Descriptive Geometry, Shadows, and Perspective. 8vo, 3 50
Elements of Machine Construction and Drawing. 8vo, 7 50
Elements of Plane and Solid Free-hand Geometrical Drawing. . . . 12mo, 1 00
General Problems of Shades and Shadows 8vo, 3 00
Manual of Elementary Problems in the Linear Perspective of Form and Shadow. 12mo, 1 00
Manual of Elementary Projection Drawing. 12mo, 1 50
Plane Problems in Elementary Geometry. 12mo, 1 25
Problems, Theorems, and Examples in Descriptive Geometry. 8vo, 2 50
Weisbach's Kinematics and Power of Transmission. (Hermann and Klein.). 8vo, 5 00
Wilson's (H. M.) Topographic Surveying. 8vo, 3 50
Wilson's (V. T.) Free-hand Lettering. 8vo, 1 00
Free-hand Perspective. 8vo, 2 50
Woolf's Elementary Course in Descriptive Geometry. . . . . Large 8vo, 3 00

ELECTRICITY AND PHYSICS.

* Abegg's Theory of Electrolytic Dissociation. (von Ende.) 12mo, 1 25
Andrews's Hand-Book for Street Railway Engineering. . . . . 3×5 inches, mor., 1 25
Anthony and Brackett's Text-book of Physics. (Magie.). . . . . Large 12mo, 3 00
Anthony's Lecture-notes on the Theory of Electrical Measurements. . . . 12mo, 1 00
Benjamin's History of Electricity. 8vo, 3 00
Voltaic Cell. 8vo, 3 00
Betts's Lead Refining and Electrolysis 8vo, 4 00
Classen's Quantitative Chemical Analysis by Electrolysis. (Boltwood.). 8vo, 3 00
* Collins's Manual of Wireless Telegraphy. 12mo, 1 50
Mor. 2 00
Crehore and Squier's Polarizing Photo-chronograph. 8vo, 3 00
* Danneel's Electrochemistry. (Merriam.). 12mo, 1 25
Dawson's "Engineering" and Electric Traction Pocket-book. . . . . 16mo, mor 5 00
Dolezalek's Theory of the Lead Accumulator (Storage Battery). (von Ende.) 12mo, 2 50
Duhem's Thermodynamics and Chemistry. (Burgess.). 8vo, 4 00
Flather's Dynamometers, and the Measurement of Power. 12mo, 3 00
Gilbert's De Magnete. (Mottelay.). 8vo, 2 50
* Hanchett's Alternating Currents 12mo, 1 00
Hering's Ready Reference Tables (Conversion Factors). . . . . 16mo, mor. 2 50
Hobart and Ellis's High-speed Dynamo Electric Machinery. (In Press.)
Holman's Precision of Measurements. 8vo, 2 00
Telescopic Mirror-scale Method, Adjustments, and Tests. . . . Large 8vo, 75
* Karapetoff's Experimental Electrical Engineering. 8vo, 6 00
Kinzbrunner's Testing of Continuous-current Machines. 8vo, 2 00
Landauer's Spectrum Analysis. (Tingle.). 8vo, 3 00
Le Chatelier's High-temperature Measurements. (Boudouard—Burgess.) 12mo, 3 00
Löb's Electrochemistry of Organic Compounds. (Lorenz.). 8vo, 3 00
* Lyndon's Development and Electrical Distribution of Water Power . . . 8vo, 3 00
* Lyons's Treatise on Electromagnetic Phenomena. Vols. I. and II. 8vo, each, 6 00
* Michie's Elements of Wave Motion Relating to Sound and Light. 8vo, 4 00

Morgan's Outline of the Theory of Solution and its Results.....12mo, 1 00
* Physical Chemistry for Electrical Engineers.....12mo, 1 50
Niaudet's Elementary Treatise on Electric Batteries. (Fishback)....12mo. 2 50
* Norris's Introduction to the Study of Electrical Engineering.....8vo, 2 50
* Parshall and Hobart's Electric Machine Design.....4to, half morocco, 12 50
Reagan's Locomotives: Simple, Compound, and Electric. New Edition.
Large 12mo, 3 50
* Rosenberg's Electrical Engineering. (Haldane Gee—Kinzbrunner.)...8vo, 2 00
Ryan, Norris, and Hoxie's Electrical Machinery. Vol. I.....8vo, 2 50
Schapper's Laboratory Guide for Students in Physical Chemistry.....12mo, 1 00
Thurston's Stationary Steam-engines.....8vo, 2 50
* Tillman's Elementary Lessons in Heat.....8vo, 1 50
Tory and Pitcher's Manual of Laboratory Physics.....Large 12mo, 2 00
Ulke's Modern Electrolytic Copper Refining.....8vo, 3 00

LAW.

* Davis's Elements of Law.....8vo, 2 50
* Treatise on the Military Law of United States.....8vo, 7 00
* Sheep, 7 50
* Dudley's Military Law and the Procedure of Courts-martial....Large 12mo, 2 50
Manual for Courts-martial.....16mo, mor. 1 50
Wait's Engineering and Architectural Jurisprudence.....8vo, 6 00
Sheep, 6 50
Law of Contracts.....8vo, 3 00
Law of Operations Preliminary to Construction in Engineering and Architecture.....8vo 5 00
Sheep, 5 50

MATHEMATICS.

Baker's Elliptic Functions.....8vo, 1 50
Briggs's Elements of Plane Analytic Geometry. (Bôcher).....12mo, 1 00
* Buchanan's Plane and Spherical Trigonometry.....8vo, 1 00
Byerley's Harmonic Functions.....8vo, 1 00
Chandler's Elements of the Infinitesimal Calculus.....12mo, 2 00
Compton's Manual of Logarithmic Computations.....12mo, 1 50
Davis's Introduction to the Logic of Algebra.....8vo, 1 50
* Dickson's College Algebra.....Large 12mo, 1 50
* Introduction to the Theory of Algebraic Equations.....Large 12mo, 1 25
Emch's Introduction to Projective Geometry and its Applications.....8vo, 2 50
Fiske's Functions of a Complex Variable.....8vo, 1 00
Halsted's Elementary Synthetic Geometry.....8vo, 1 50
Elements of Geometry.....8vo, 1 75
* Rational Geometry.....12mo, 1 50
Hyde's Grassmann's Space Analysis.....8vo, 1 00
* Jonnson's (J. B.) Three-place Logarithmic Tables: Vest-pocket size, paper, 15
100 copies, 5 00
* Mounted on heavy cardboard, 8 × 10 inches, 25
10 copies, 2 00
Johnson's (W. W.) Abridged Editions of Differential and Integral Calculus
Large 12mo, 1 vol. 2 50
Curve Tracing in Cartesian Co-ordinates.....12mo, 1 00
Differential Equations.....8vo, 1 00
Elementary Treatise on Differential Calculus. (In Press.)
Elementary Treatise on the Integral Calculus.....Large 12mo, 1 50
* Theoretical Mechanics.....12mo, 3 00
Theory of Errors and the Method of Least Squares.....12mo, 1 50
Treatise on Differential Calculus.....Large 12mo, 3 00
Treatise on the Integral Calculus.....Large 12mo, 3 00
Treatise on Ordinary and Partial Differential Equations..Large 12mo, 3 50

Laplace's Philosophical Essay on Probabilities. (Truscott and Emory.).12mo, 2 00
* Ludlow and Bass's Elements of Trigonometry and Logarithmic and Other Tables 8vo, 3 00
Trigonometry and Tables published separately .....Each, 2 00
* Ludlow's Logarithmic and Trigonometric Tables 8vo, 1 00
Macfarlane's Vector Analysis and Quaternions 8vo, 1 00
McMahon's Hyperbolic Functions 8vo, 1 00
Manning's Irrational Numbers and their Representation by Sequences and Series 12mo, 1 25
Mathematical Monographs. Edited by Mansfield Merriman and Robert S. Woodward .....Octavo, each 1 00
No. 1. History of Modern Mathematics, by David Eugene Smith. No. 2. Synthetic Projective Geometry, by George Bruce Halsted. No. 3. Determinants, by Laenas Gifford Weld. No. 4. Hyperbolic Functions, by James McMahon. No. 5. Harmonic Functions, by William E. Byerly. No. 6. Grassmann's Space Analysis, by Edward W. Hyde. No. 7. Probability and Theory of Errors, by Robert S. Woodward. No. 8. Vector Analysis and Quaternions, by Alexander Macfarlane. No. 9. Differential Equations, by William Woolsey Johnson. No. 10. The Solution of Equations, by Mansfield Merriman. No. 11. Functions of a Complex Variable, by Thomas S. Fiske.
Maurer's Technical Mechanics 8vo, 4 00
Merriman's Method of Least Squares 8vo, 2 00
Solution of Equations 8vo, 1 00
Rice and Johnson's Differential and Integral Calculus. 2 vols. in one. Large 12mo, 1 50
Elementary Treatise on the Differential Calculus .....Large 12mo, 3 00
Smith's History of Modern Mathematics 8vo, 1 00
* Veblen and Lennes's Introduction to the Real Infinitesimal Analysis of One Variable 8vo, 2 00
* Waterbury's Vest Pocket Hand-Book of Mathematics for Engineers. $2\frac{7}{8} \times 5\frac{3}{8}$ inches, mor., 1 00
Weld's Determinations 8vo, 1 00
Wood's Elements of Co-ordinate Geometry 8vo, 2 00
Woodward's Probability and Theory of Errors 8vo, 1 00

MECHANICAL ENGINEERING.

MATERIALS OF ENGINEERING, STEAM-ENGINES AND BOILERS.

Bacon's Forge Practice 12mo, 1 50
Baldwin's Steam Heating for Buildings 12mo, 2 50
Barr's Kinematics of Machinery 8vo, 2 50
* Bartlett's Mechanical Drawing 8vo, 3 00
* " " " Abridged Ed. 8vo, 1 50
Benjamin's Wrinkles and Recipes 12mo, 2 00
* Burr's Ancient and Modern Engineering and the Isthmian Canal 8vo, 3 50
Carpenter's Experimental Engineering 8vo, 6 00
Heating and Ventilating Buildings 8vo, 4 00
Clerk's Gas and Oil Engine .....Large 12mo, 4 00
Compton's First Lessons in Metal Working 12mo, 1 50
Compton and De Groodt's Speed Lathe 12mo, 1 50
Coolidge's Manual of Drawing .....8vo, paper, 1 00
Coolidge and Freeman's Elements of General Drafting for Mechanical Engineers .....Oblong 4to, 2 50
Cromwell's Treatise on Belts and Pulleys 12mo, 1 50
Treatise on Toothed Gearing 12mo, 1 50
Durley's Kinematics of Machines 8vo, 4 00

Flather's Dynamometers and the Measurement of Power.....12mo, 3 00
Rope Driving.....12mo, 2 00
Gill's Gas and Fuel Analysis for Engineers.....12mo, 1 25
Goss's Locomotive Sparks.....8vo, 2 00
Hall's Car Lubrication.....12mo, 1 00
Hering's Ready Reference Tables (Conversion Factors).....16mo, mor., 2 50
Hobart and Ellis's High Speed Dynamo Electric Machinery. (In Press.)
Hutton's Gas Engine.....8vo, 5 00
Jamison's Advanced Mechanical Drawing.....8vo, 2 00
Elements of Mechanical Drawing.....8vo, 2 50
Jones's Machine Design:
Part I. Kinematics of Machinery.....8vo, 1 50
Part II. Form, Strength, and Proportions of Parts.....8vo, 3 00
Kent's Mechanical Engineers' Pocket-book.....16mo, mor, 5 00
Kerr's Power and Power Transmission.....8vo, 2 00
Leonard's Machine Shop Tools and Methods.....8vo, 4 00
* Lorenz's Modern Refrigerating Machinery. (Pope, Haven, and Dean.)..8vo, 4 00
MacCord's Kinematics; or, Practical Mechanism.....8vo, 5 00
Mechanical Drawing.....4to, 4 00
Velocity Diagrams.....8vo, 1 50
MacFarland's Standard Reduction Factors for Gases.....8vo, 1 50
Mahan's Industrial Drawing. (Thompson.).....8vo, 3 50
* Parshall and Hobart's Electric Machine Design.....Small 4to, half leather, 12 50
Peele's Compressed Air Plant for Mines. (In Press.)
Poole's Calorific Power of Fuels.....8vo, 3 00
* Porter's Engineering Reminiscences, 1855 to 1882.....8vo, 3 00
Reid's Course in Mechanical Drawing.....8vo, 2 00
Text-book of Mechanical Drawing and Elementary Machine Design.8vo, 3 00
Richard's Compressed Air.....12mo, 1 50
Robinson's Principles of Mechanism.....8vo, 3 00
Schwamb and Merrill's Elements of Mechanism.....8vo, 3 00
Smith's (O.) Press-working of Metals.....8vo, 3 00
Smith (A. W.) and Marx's Machine Design.....8vo, 3 00
Thurston's Animal as a Machine and Prime Motor, and the Laws of Energetics.
12mo, 1 00
Treatise on Friction and Lost Work in Machinery and Mill Work...8vo, 3 00
Tillson's Complete Automobile Instructor.....16mo, 1 50
mor., 2 00
* Titsworth's Elements of Mechanical Drawing.....Oblong 8vo, 1 25
Warren's Elements of Machine Construction and Drawing.....8vo, 7 50
* Waterbury's Vest Pocket Hand Book of Mathematics for Engineers.
$2\frac{7}{8} \times 5\frac{3}{8}$ inches, mor., 1 00
Weisbach's Kinematics and the Power of Transmission. (Herrmann—Klein.).....8vo, 5 00
Machinery of Transmission and Governors. (Herrmann—Klein.)..8vo, 5 00
Wolff's Windmill as a Prime Mover.....8vo, 3 00
Wood's Turbines.....8vo, 2 50

MATERIALS OF ENGINEERING.

* Bovey's Strength of Materials and Theory of Structures.....8vo, 7 50
Burr's Elasticity and Resistance of the Materials of Engineering.....8vo, 7 50
Church's Mechanics of Engineering.....8vo, 6 00
* Greene's Structural Mechanics.....8vo, 2 50
Holley and Ladd's Analysis of Mixed Paints, Color Pigments, and Varnishes.
Large 12mo, 2 50
Johnson's Materials of Construction.....8vo, 6 00
Keep's Cast Iron.....8vo, 2 50
Lanza's Applied Mechanics.....8vo, 7 50

Maire's Modern Pigments and their Vehicles 12mo, 2 00
Martens's Handbook on Testing Materials. (Henning.) 8vo, 7 50
Maurer's Technical Mechanics 8vo, 4 00
Merriman's Mechanics of Materials 8vo, 5 00
* Strength of Materials 12mo, 1 00
Metcalf's Steel. A Manual for Steel-users 12mo, 2 00
Sabin's Industrial and Artistic Technology of Paints and Varnish 8vo, 3 00
Smith's Materials of Machines 12mo, 1 00
Thurston's Materials of Engineering ..... 3 vols., 8vo, 8 00
Part I. Non-metallic Materials of Engineering, see Civil Engineering, page 9.
Part II. Iron and Steel 8vo, 3 50
Part III. A Treatise on Brasses, Bronzes, and Other Alloys and their Constituents 8vo, 2 50
Wood's (De V.) Elements of Analytical Mechanics 8vo, 3 00
Treatise on the Resistance of Materials and an Appendix on the Preservation of Timber 8vo, 2 00
Wood's (M. P.) Rustless Coatings: Corrosion and Electrolysis of Iron and Steel 8vo, 4 00

STEAM-ENGINES AND BOILERS.

Berry's Temperature-entropy Diagram 12mo, 1 25
Carnot's Reflections on the Motive Power of Heat. (Thurston.) 12mo, 1 50
Chase's Art of Pattern Making 12mo, 2 50
Creighton's Steam-engine and other Heat-motors 8vo, 5 00
Dawson's "Engineering" and Electric Traction Pocket-book ..... 16mo, mor., 5 00
Ford's Boiler Making for Boiler Makers 18mo, 1 00
Goss's Locomotive Performance 8vo, 5 00
Hemenway's Indicator Practice and Steam-engine Economy 12mo, 2 00
Hutton's Heat and Heat-engines 8vo, 5 00
Mechanical Engineering of Power Plants 8vo, 5 00
Kent's Steam boiler Economy 8vo, 4 00
Kneass's Practice and Theory of the Injector 8vo, 1 50
MacCord's Slide-valves 8vo, 2 00
Meyer's Modern Locomotive Construction 4to, 10 00
Moyer's Steam Turbines. (In Press.)
Peabody's Manual of the Steam-engine Indicator 12mo, 1 50
Tables of the Properties of Saturated Steam and Other Vapors 8vo, 1 00
Thermodynamics of the Steam-engine and Other Heat-engines 8vo, 5 00
Valve-gears for Steam-engines 8vo, 2 50
Peabody and Miller's Steam-boilers 8vo, 4 00
Pray's Twenty Years with the Indicator ..... Large 8vo, 2 50
Pupin's Thermodynamics of Reversible Cycles in Gases and Saturated Vapors. (Osterberg.) 12mo, 1 25
Reagan's Locomotives: Simple, Compound, and Electric. New Edition. Large 12mo, 3 50
Sinclair's Locomotive Engine Running and Management 12mo, 2 00
Smart's Handbook of Engineering Laboratory Practice 12mo, 2 50
Snow's Steam-boiler Practice 8vo, 3 00
Spangler's Notes on Thermodynamics 12mo, 1 00
Valve-gears 8vo, 2 50
Spangler, Greene, and Marshall's Elements of Steam-engineering 8vo, 3 00
Thomas's Steam-turbines 8vo, 4 00
Thurston's Handbook of Engine and Boiler Trials, and the Use of the Indicator and the Prony Brake 8vo, 5 00
Handy Tables 8vo, 1 50
Manual of Steam-boilers, their Designs, Construction, and Operation 8vo, 5 00

Thurston's Manual of the Steam-engine.....2 vols., 8vo, 10 00
Part I. History, Structure, and Theory.....8vo, 6 00
Part II. Design, Construction, and Operation.....8vo, 6 00
Stationary Steam-engines.....8vo, 2 50
Steam-boiler Explosions in Theory and in Practice.....12mo, 1 50
Wehrenfenning's Analysis and Softening of Boiler Feed-water (Patterson) 8vo, 4 00
Weisbach's Heat, Steam, and Steam-engines. (Du Bois.).....8vo, 5 00
Whitham's Steam-engine Design.....8vo, 5 00
Wood's Thermodynamics, Heat Motors, and Refrigerating Machines...8vo, 4 00

MECHANICS PURE AND APPLIED.

Church's Mechanics of Engineering.....8vo, 6 00
Notes and Examples in Mechanics.....8vo, 2 00
Dana's Text-book of Elementary Mechanics for Colleges and Schools..12mo, 1 50
Du Bois's Elementary Principles of Mechanics:
Vol. I. Kinematics.....8vo, 3 50
Vol. II. Statics.....8vo, 4 00
Mechanics of Engineering. Vol. I.....Small 4to, 7 50
Vol. II.....Small 4to, 10 00
* Greene's Structural Mechanics.....8vo, 2 50
James's Kinematics of a Point and the Rational Mechanics of a Particle. Large 12mo, 2 00
* Johnson's (W. W.) Theoretical Mechanics.....12mo, 3 00
Lanza's Applied Mechanics.....8vo, 7 50
* Martin's Text Book on Mechanics, Vol. I, Statics.....12mo, 1 25
* Vol. 2, Kinematics and Kinetics..12mo, 1 50
Maurer's Technical Mechanics.....8vo, 4 00
* Merriman's Elements of Mechanics.....12mo, 1 00
Mechanics of Materials.....8vo, 5 00
* Michie's Elements of Analytical Mechanics.....8vo, 4 00
Robinson's Principles of Mechanism.....8vo, 3 00
Sanborn's Mechanics Problems.....Large 12mo, 1 50
Schwamb and Merrill's Elements of Mechanism.....8vo, 3 00
Wood's Elements of Analytical Mechanics.....8vo, 3 00
Principles of Elementary Mechanics.....12mo, 1 25

MEDICAL.

Abderhalden's Physiological Chemistry in Thirty Lectures. (Hall and Defren). (In Press).
von Behring's Suppression of Tuberculosis. (Bolduan.).....12mo, 1 00
* Bolduan's Immune Sera.....12mo, 1 50
Davenport's Statistical Methods with Special Reference to Biological Variations.....16mo, mor., 1 50
Ehrlich's Collected Studies on Immunity. (Bolduan.).....8vo, 6 00
* Fischer's Physiology of Alimentation.....Large 12mo, cloth, 2 00
de Fursac's Manual of Psychiatry. (Rosanoff and Collins.).....Large 12mo, 2 50
Hammarsten's Text-book on Physiological Chemistry. (Mandel.).....8vo, 4 00
Jackson's Directions for Laboratory Work in Physiological Chemistry..8vo, 1 25
Lassar-Cohn's Practical Urinary Analysis. (Lorenz.).....12mo, 1 00
Mandel's Hand Book for the Bio-Chemical Laboratory.....12mo, 1 50
* Pauli's Physical Chemistry in the Service of Medicine. (Fischer.)....12mo, 1 25
* Pozzi-Escot's Toxins and Venoms and their Antibodies. (Cohn.).....12mo, 1 00
Rostoski's Serum Diagnosis. (Bolduan.).....12mo, 1 00
Ruddiman's Incompatibilities in Prescriptions.....8vo, 2 00
Whys in Pharmacy.....12mo, 1 00
Salkowski's Physiological and Pathological Chemistry. (Orndorff.).....8vo, 2 50
* Satterlee's Outlines of Human Embryology.....12mo, 1 25
Smith's Lecture Notes on Chemistry for Dental Students.....8vo, 2 50

Steel's Treatise on the Diseases of the Dog. 8vo, 3 50
* Whipple's Typhoid Fever ..... Large 12mo, 3 00
Woodhull's Notes on Military Hygiene 16mo, 1 50
* Personal Hygiene 12mo, 1 00
Worcester and Atkinson's Small Hospitals Establishment and Maintenance, and Suggestions for Hospital Architecture, with Plans for a Small Hospital 12mo, 1 25

METALLURGY.

Betts's Lead Refining by Electrolysis 8vo. 4 00
Bolland's Encyclopedia of Founding and Dictionary of Foundry Terms Used in the Practice of Moulding 12mo, 3 00
Iron Founder 12mo. 2 50
" " Supplement 12mo, 2 50
Douglas's Untechnical Addresses on Technical Subjects 12mo, 1 00
Goesel's Minerals and Metals: A Reference Book ..... 16mo, mor. 3 00
* Iles's Lead-smelting 12mo, 2 50
Keep's Cast Iron 8vo, 2 50
Le Chatelier's High-temperature Measurements. (Boudouard—Burgess.) 12mo, 3 00
Metcalf's Steel. A Manual for Steel-users 12mo, 2 00
Miller's Cyanide Process 12mo 1 00
Minet's Production of Aluminum and its Industrial Use. (Waldo.) 12mo, 2 50
Robine and Lenglen's Cyanide Industry. (Le Clerc.) 8vo, 4 00
Ruer's Elements of Metallography. (Mathewson). (In Press.)
Smith's Materials of Machines 12mo, 1 00
Thurston's Materials of Engineering. In Three Parts 8vo, 8 00
Part I. Non-metallic Materials of Engineering, see Civil Engineering, page 9.
Part II. Iron and Steel 8vo, 3 50
Part III. A Treatise on Brasses, Bronzes, and Other Alloys and their Constituents 8vo, 2 50
Ulke's Modern Electrolytic Copper Refining 8vo, 3 00
West's American Foundry Practice 12mo, 2 50
Moulders Text Book 12mo, 2 50
Wilson's Chlorination Process 12mo, 1 50
Cyanide Processes 12mo, 1 50

MINERALOGY.

Barringer's Description of Minerals of Commercial Value. Oblong, morocco, 2 50
Boyd's Resources of Southwest Virginia 8vo 3 00
Boyd's Map of Southwest Virginia ..... Pocket-book form. 2 00
* Browning's Introduction to the Rarer Elements 8vo, 1 50
Brush's Manual of Determinative Mineralogy. (Penfield.) 8vo, 4 00
Butler's Pocket Hand-Book of Minerals ..... 16mo, mor. 3 00
Chester's Catalogue of Minerals ..... 8vo, paper, 1 00
Cloth, 1 25
Crane's Gold and Silver. (In Press.)
Dana's First Appendix to Dana's New "System of Mineralogy." ..... Large 8vo, 1 00
Manual of Mineralogy and Petrography 12mo 2 00
Minerals and How to Study Them 12mo, 1 50
System of Mineralogy ..... Large 8vo, half leather, 12 50
Text-book of Mineralogy 8vo, 4 00
Douglas's Untechnical Addresses on Technical Subjects 12mo, 1 00
Eakle's Mineral Tables 8vo, 1 25
Stone and Clay Products Used in Engineering. (In Preparation).
Egleston's Catalogue of Minerals and Synonyms 8vo, 2 50
Goesel's Minerals and Metals: A Reference Book ..... 16mo, mor. 3 00
Groth's Introduction to Chemical Crystallography (Marshall) 12mo, 1 25

* Iddings's Rock Minerals 8vo, 5 00
Johannsen's Determination of Rock-forming Minerals in Thin Sections 8vo, 4 00
* Martin's Laboratory Guide to Qualitative Analysis with the Blowpipe. 12mo, 60
Merrill's Non-metallic Minerals: Their Occurrence and Uses 8vo, 4 00
Stones for Building and Decoration 8vo, 5 00
* Penfield's Notes on Determinative Mineralogy and Record of Mineral Tests. 8vo, paper, 50
Tables of Minerals, Including the Use of Minerals and Statistics of Domestic Production 8vo, 1 00
Pirsson's Rocks and Rock Minerals. (In Press.)
* Richards's Synopsis of Mineral Characters ..... 12mo, mor. 1 25
* Ries's Clays: Their Occurrence, Properties, and Uses 8vo, 5 00
* Tillman's Text-book of Important Minerals and Rocks 8vo, 2 00

MINING.

* Beard's Mine Gases and Explosions ..... Large 12mo, 3 00
Boyd's Map of Southwest Virginia ..... Pocket-book form, 2 00
Resources of Southwest Virginia 8vo, 3 00
Crane's Gold and Silver. (In Press.)
Douglas's Untechnical Addresses on Technical Subjects 12mo, 1 00
Eissler's Modern High Explosives 8vo 4 00
Goesel's Minerals and Metals: A Reference Book ..... 16mo, mor. 3 00
Ihlseng's Manual of Mining 8vo, 5 00
* Iles's Lead-smelting 12mo, 2 50
Miller's Cyanide Process 12mo, 1 00
O'Driscoll's Notes on the Treatment of Gold Ores 8vo, 2 00
Peele's Compressed Air Plant for Mines. (In Press.)
Riemer's Shaft Sinking Under Difficult Conditions. (Corning and Peele) ... 8vo, 3 00
Robine and Lenglen's Cyanide Industry. (Le Clerc.) 8vo, 4 00
* Weaver's Military Explosives 8vo, 3 00
Wilson's Chlorination Process 12mo, 1 50
Cyanide Processes 12mo, 1 50
Hydraulic and Placer Mining. 2d edition, rewritten 12mo, 2 50
Treatise on Practical and Theoretical Mine Ventilation 12mo, 1 25

SANITARY SCIENCE.

Association of State and National Food and Dairy Departments, Hartford Meeting, 1906 ..... 8vo, 3 00
Jamestown Meeting, 1907 ..... 8vo, 3 00
* Bashore's Outlines of Practical Sanitation 12mo, 1 25
Sanitation of a Country House 12mo, 1 00
Sanitation of Recreation Camps and Parks 12mo, 1 00
Folwell's Sewerage. (Designing, Construction, and Maintenance.) 8vo, 3 00
Water-supply Engineering 8vo, 4 00
Fowler's Sewage Works Analyses 12mo, 2 00
Fuertes's Water-filtration Works 12mo, 2 50
Water and Public Health 12mo, 1 50
Gerhard's Guide to Sanitary House-inspection 16mo, 1 00
* Modern Baths and Bath Houses 8vo, 3 00
Sanitation of Public Buildings 12mo, 1 50
Hazen's Clean Water and How to Get It ..... Large 12mo, 1 50
Filtration of Public Water-supplies 8vo, 3 00
Kinnicut, Winslow and Pratt's Purification of Sewage. (In Press.)
Leach's Inspection and Analysis of Food with Special Reference to State Control 8vo, 7 00
Mason's Examination of Water. (Chemical and Bacteriological) 12mo, 1 25
Water-supply. (Considered principally from a Sanitary Standpoint) .. 8vo, 4 00

* Merriman's Elements of Sanitary Engineering	8vo,	2 00
Ogden's Sewer Design	12mo,	2 00
Parsons's Disposal of Municipal Refuse	8vo,	2 00
Prescott and Winslow's Elements of Water Bacteriology, with Special Reference to Sanitary Water Analysis	12mo,	1 50
* Price's Handbook on Sanitation	12mo,	1 50
Richards's Cost of Food. A Study in Dietaries	12mo,	1 00
Cost of Living as Modified by Sanitary Science	12mo,	1 00
Cost of Shelter	12mo,	1 00
* Richards and Williams's Dietary Computer	8vo,	1 50
Richards and Woodman's Air, Water, and Food from a Sanitary Standpoint	8vo,	2 00
Rideal's Disinfection and the Preservation of Food	8vo,	4 00
Sewage and Bacterial Purification of Sewage	8vo,	4 00
Soper's Air and Ventilation of Subways. (In Press.)		
Turneaure and Russell's Public Water-supplies	8vo,	5 00
Venable's Garbage Crematories in America	8vo,	2 00
Method and Devices for Bacterial Treatment of Sewage	8vo,	3 00
Ward and Whipple's Freshwater Biology. (In Press.)		
Whipple's Microscopy of Drinking-water	8vo,	3 50
* Typhod Fever	Large 12mo,	3 00
Value of Pure Water	Large 12mo,	1 00
Winton's Microscopy of Vegetable Foods	8vo,	7 50

MISCELLANEOUS.

Emmons's Geological Guide-book of the Rocky Mountain Excursion of the International Congress of Geologists	Large 8vo,	1 50
Ferrel's Popular Treatise on the Winds	8vo,	4 00
Fitzgerald's Boston Machinist	18mo,	1 00
Gannett's Statistical Abstract of the World	24mo,	75
Haines's American Railway Management	12mo,	2 50
* Hanusek's The Microscopy of Technical Products. (Winton)	8vo,	5 00
Ricketts's History of Rensselaer Polytechnic Institute 1824–1894	Large 12mo,	3 00
Rotherham's Emphasized New Testament	Large 8vo,	2 00
Standage's Decoration of Wood, Glass, Metal, etc	12mo,	2 00
Thome's Structural and Physiological Botany. (Bennett)	16mo,	2 25
Westermaier's Compendium of General Botany. (Schneider)	8vo,	2 00
Winslow's Elements of Applied Microscopy	12mo,	1 50

HEBREW AND CHALDEE TEXT-BOOKS.

Green's Elementary Hebrew Grammar	12mo,	1 25
Gesenius's Hebrew and Chaldee Lexicon to the Old Testament Scriptures. (Tregelles)	Small 4to, half morocco,	5 00

532
C56m

532.C56M

a39001 006969383b